PETROLEUM REPORT SERIES

PR3216

Title Ahuroa South B-1; Ahuroa South B-1 ST-1, Tawn Area New Zealand

Operator Swift Energy New Zealand Ltd

Author Swift Energy New Zealand Ltd

Date 2005

This report has been compiled form material submitted to the New Zealand Government under legislation or voluntarily by exploration companies. An acknowledgement of this work in the following bibliographic format would be appreciated:


Author/Operator; Date; Title; Ministry of Economic Development New Zealand Unpublished Petroleum Report____

686422

SWIFT ENERGY
NEW ZEALAND LTD

AHUROA SOUTH B-1/ST1
Well Completion Report

PML 38139, Taranaki Basin, New Zealand



Permit: PML-38139

Operator: Swift Energy New Zealand Ltd

Authors: Roger Brash, Carey Davis, Rod van Koughnet, Tracey Hunter, Lana Klenner, Donald MacFarlan

Date: October 2007

MED Report no. PR 3216

Filename: PR3216**,** Ahuroa South B-1/ST1 Well Completion Report.pdf

1.0 EXECUTIVE SUMMARY AND WELL CARD 6
2.0 INTRODUCTION 11
2.1 REASONS FOR DRILLING AND PROSPECT DEFINITION 11
2.2 OPERATIONAL SUMMARY 11
2.3 RESULTS OF THE WELL 11
3.0 GENERAL DATA 12
3.1 WELL SUMMARY 12
3.2 LOCATION 13
4.0 GEOLOGY, GEOPHYSICS, FORMATION SAMPLING AND EVALUATION . 13
4.1 GEOLOGY AND GEOPHYSICS 13
4.1.1 TARANAKI BASIN OVERVIEW 13
4.1.2 AHUROA SOUTH PROSPECT (PRE-DRILL) 16
4.1.3 AHUROA SOUTH PROSPECT (POST-DRILL) 16
4.2 STRATIGRAPHY 16
4.2.1 LITHOLOGICAL SUMMARY: 16
4.2.2 RESERVOIR SEAL ASSESSMENT 21
4.2.3 PALYNOLOGY / PALEONTOLOGY 21
4.2.4 MUD LOGGING 21
4.3 DITCH CUTTINGS 22
4.4 HYDROCARBON SHOW SUMMARY 23
4.5 SIDEWALL CORES 23
4.6 CONVENTIONAL CORES 23
4.7 WIRELINE LOGGING 23
4.8 MWD LOGGING 23
4.9 GEOTHERMAL GRADIENT 24
4.10 VELOCITY SURVEY 24
4.11 PETROPHYSICS 24
5.0 DRILLING OPERATIONS 26
5.1 GENERAL DATA 26
5.2 CONTRACTORS 27
5.3 TIME VS. DEPTH CHART FOR DRILLING: PROGNOSED VS. ACTUAL 27
5.4 WELL DRILLING REPORTS (INCLUDING WELL COST SUMMARY) 27
5.5 MUD SUMMARY REPORT 27
5.6 BIT SUMMARY REPORT 27
5.7 CASING REPORT 27
5.8 CEMENTING REPORT 27
5.9 DIRECTIONAL SURVEY 27
5.10 BHA REPORT 28

5.11 RIG EQUIPMENT INVENTORY 28
6.0 TESTING AND RESERVOIR EVALUATION 28
6.1 SUMMARY OF TESTING 28
6.2 RESERVOIR FLUID ANALYSIS 28
7.0 REFERENCES 28

FIGURES:

FIGURE 1 PML 38139 Location Map 9
FIGURE 2 Ahuroa South B-1 Location Map 10
FIGURE 3 Generalised Stratigraphy, Taranaki Basin, New Zealand 15

TABLES:

TABLE 1 Formation Tops AHUROA SOUTH B-1 / ST1 8
TABLE 2 Well Summary AHUROA SOUTH B-1 12
TABLE 3 Hydrocarbon Show Summary AHUROA SOUTH B-1 23
TABLE 4 Wireline Logs AHUROA SOUTH B-1 23
TABLE 5 General Data AHUROA SOUTH B-1 / ST1 26
TABLE 6 Contractors AHUROA SOUTH B-1 / ST1 27

ENCLOSURES:

ENCLOSURE 1 Seismic Line
ENCLOSURE 2 Structure Map
ENCLOSURE 3 Formation Evaluation Log
ENCLOSURE 4 Drill Plot
ENCLOSURE 5 Composite Well Log
ENCLOSURE 6 Cross Section

AHUROA SOUTH B-1/ B-1 ST1

APPENDIX

I.	**Contractors Well Reports**	
		a. Baker Hughes Inteq
		b. Sperry Sun
II.	**Paleontology IGNS Reports**	
III.	**Charts**	**a. Drilling Time vs Depth**
		b. Cost vs Depth
		c. Well Elevation View
		d. Well Plan View
IV.	**Drilling Reports**	**a. Well Summary Report**
		b. Well Information Report
		c. Borehole Schematic
		d. Well Costs Summary Report
		e. Daily Drilling Reports
V.	**Geological Reports**	**a. Daily Geological Reports**
		b. Sample Descriptions
VI.	**Petrophysics Reports**	
VII.	**Mud Summary Report**	
VIII.	**Bit Summary Reports**	
IX.	**Casing Reports**	
X.	**Cementing Reports**	
XI.	**Directional Surveys**	
XII.	**BHA Reports**	
XIII.	**Rig Equipment Inventory**	
XIV.	**Operations Activity Summary & Time Analysis**	
XV.	**Drilling Fluids Recap**	

1.0 EXECUTIVE SUMMARY AND WELL CARD

The Ahuroa South B-1 well was designed as a directional appraisal well to test the hydrocarbon potential of the McKee Sand reservoir in a position approximately 825 m southeast of the Ahuroa pad. The well was planned to test a downdip location structurally equivalent to that drilled in the Piakau North A-2 location. The well was drilled from the existing Ahuroa B well site.

In the proposal the McKee Sand was to be intersected at 3180 m MD and the well was proposed to reach a TD of 3430 m. The McKee Sands were actually encountered at 3230 m MD, 59 m deep TVDSS to prognosis. This put the McKee Sands penetrated in this location below the estimated water contact for the field. A TD was called at 3370 m MD and wireline logs were run confirming that the McKee Sands were not hydrocarbon bearing in this location. The well was sidetracked from 2400 m MD to try and intersect the McKee Sands at an updip location; however, in Ahuroa South B-1 ST1, the McKee Sands were not developed.

The well was spudded on 5 October 2005 and the rig released on 28 November 2005.

WELL CARD	AHUROA SOUTH B-1 / ST1		
LATITUDE	39° 16' 01.196" S		
LONGITUDE	174° 20' 25.375" E		
GRID CO-ORDS:	2625724.00 m E 6214665.80 m N		
SEISMIC	2D Line WH85-28 & WH85-18		
ELEVATION	201.80 RKB		
PERMIT	PML 38139		
SPUDDED	5 October 2005		
REACHED TD	Ahuroa South B-1 7 November 2005 Ahuroa South B-1 ST1 24 November 2005		
RIG RELEASED	28 November 2005		
COMPLETION DETAILS	Plugged & Abandoned		
STRUCTURE TYPE	Thrust faulted structure		
RIG	Parker Rig #252		
TOTAL DEPTH ("TD") (m)			
DRILLER	Ahuroa South B-1 3370 m MD Ahuroa South B-1 ST1 3085 m MD		
LOGGER	Ahuroa South B-1 3370 m MD Ahuroa South B-1 ST1 3085 m MD		
HOLE SIZE (in.)	**12 ¼"**	**8 ½"**	**6"**
DEPTH (m) Ahuroa South B-1	659	2403	3370
Ahuroa South B-1 ST1	659	2403	3085
CASING DETAIL (in.)	**13 3/8"**	**9 5/8"**	**7"**
DEPTH (m)			
Ahuroa South B-1	50	653	2395
Ahuroa South B-1 ST1	50	653	2395
PARTICIPATING INTERESTS	*SWIFT ENERGY NEW ZEALAND LIMITED* ***100%***		

TABLE 1 Formation Tops AHUROA SOUTH B-1 / ST1

FORMATION/ UNIT	AGE	PROGNOSED DEPTH		DEPTH (mMD)		Basis of Pick
		m MD	m TVDSS	m MD	m TVDSS	
AHUROA SOUTH B-1						
Urenui	Upper Miocene			653.0	451.0	Logs
Mt Messenger	Mid – upper Miocene	1230	1000	1229.8	1002.4	Logs
Tikorangi Limestone	Oligocene	1940	1660	1902.0	1635.0	Logs
Otaraoa Fm (upper)	Oligocene	2100	1810	2014.0	1741.0	Logs
Tariki SS	Oligocene	2765	2440	2714.0	2400.4	Logs
Otaraoa Fm (Lower)	Oligocene			3145.0	2804.2	Logs
McKee Fm	Eocene	3180	2825	3230.0	2884.1	Logs
Mangahewa Fm	Eocene	3215	2860	3244.8	2898.1	Logs
AHUROA THRUST						
Sub-thrust Manganui	Mid Miocene	3360	3000	3300.0	2950.4	Logs
TD		3430	3060	3370.0	3016.6	
AHUROA SOUTH B-1 ST1						
Otaraoa Fm (upper)	Oligocene			2014.0	1741.0	Logs
Tariki SS	Oligocene			2669.0	2365.2	Logs
Otaraoa Fm (Lower)	Oligocene			2929.0	2623.1	Logs
McKee Fm	Eocene			2972.0	2665.8	Logs
Mangahewa Fm	Eocene			2985.0	2678.7	Logs
AHUROA THRUST						
Sub-thrust Manganui	Mid Miocene			3030.0	2723.2	Logs
TD				3085.0	2777.7	

FIGURE 1 PML 38139 Location Map





FIGURE 2 Ahuroa South B-1 Location Map



2.0 INTRODUCTION

2.1 REASONS FOR DRILLING AND PROSPECT DEFINITION

The Ahuroa South B-1 well was designed as a directional appraisal well to test the hydrocarbon potential of the McKee Sand reservoir in a position approximately 825 m south-east of the Ahuroa pad. The well was designed to test a down dip location structurally equivalent to that drilled in the Piakau North A-2 location (2800 m TVDSS). This well was to test the theory of a deeper OWC (2825 m TVDSS).

The McKee Sand was to be intersected at 3180 m MD and the well was proposed to reach a TD of 3430 m.

2.2 OPERATIONAL SUMMARY

The well was spudded on 5 October 2005 and a 12 ¼" hole was drilled from 50 to 659 m. 13 3/8" casing was set with the casing shoe at 653. The 8 ½" hole was drilled to 2403 m. Wireline logs were run and then 7" casing was run and cemented with the casing shoe set at 2395 m.

A 6" hole was drilled through the Tariki Sand and down through the McKee Sand. At 3340 m, the well drilled through the main thrust into the younger Manganui Formation. The well was drilled to a TD of 3370 m MD and then logged. A side-track, Ahuroa South B-1 ST1 was drilled with a 6" hole from the kick-off point (2400 m) to a final TD of 3085 m MD. After wireline logs were run, the well was plugged and abandoned.

The rig was released on 28 November 2005.

2.3 RESULTS OF THE WELL

(Note: All depths are quoted as MD, measured by wireline logs below the rotary table ("RT"), sometimes kelly bushing ("KB"), unless otherwise specified. TVDSS denotes true vertical depth below mean sea level in metres)

The well was spudded on 5 October 2005. The McKee Sands were encountered at 3230 m MD (2884.1 m TVDSS), 59 m TVDSS deep to prognosis (2825 m TVDSS), and below the oil-water contact. The well failed to meet the primary objective of penetrating a hydrocarbon bearing McKee Sand section. The well was drilled to a total depth of 3370 m MD and wireline logs were run. These logs confirming that the McKee Sands were not hydrocarbon bearing at this location.

The well was side-tracked from 2400 m MD to intersect the McKee Sands at an up-dip location, but on Ahuroa South B-1 ST1 the McKee Sands were not developed. The final TD was at 3085 m MD after drilling into the Mangahewa from 2981 m MD. The well was plugged and abandoned and the rig moved to the Kauri F-2 site.

3.0 GENERAL DATA

3.1 WELL SUMMARY

TABLE 2 Well Summary AHUROA SOUTH B-1

Designation	Appraisal		
Permit	PML 38139		
Basin	Taranaki, New Zealand		
Operator	Swift Energy New Zealand Limited		
Permitees	Swift Energy New Zealand Limited		
Rig	Parker Rig # 252		
RT Elevation	201.84 m		
Ground Level Elevation	196.3 m		
LATITUDE	39° 16' 01.196" S		
LONGITUDE	174° 20' 25.375" E		
GRID CO-ORDS:	2625724.00 m E 6214665.80 m N		
SEISMIC	2D Line WH85-28 & WH85-18		
ELEVATION	201.80 RKB		
PERMIT	PML 38139		
SPUDDED	5 October 2005		
REACHED TD	Ahuroa South B-1 7 November 2005 Ahuroa South B-1 ST1 24 November 2005		
RIG RELEASED	28 November 2005		
COMPLETION DETAILS	Plugged & Abandoned		
STRUCTURE TYPE	Thrust faulted structure		
RIG	Parker Rig #252		
TOTAL DEPTH ("TD") (m)			
DRILLER	Ahuroa South B-1 3370 m MD Ahuroa South B-1 ST1 3085 m MD		
LOGGER	Ahuroa South B-1 3370 m MD Ahuroa South B-1 ST1 3085 m MD		
HOLE SIZE (in.)	**12 ¼"**	**8 ½"**	**6"**
DEPTH (m) Ahuroa South B-1	659	2403	3370
Ahuroa South B-1 ST1	659	2403	3085
CASING DETAIL (in.)	**13 3/8"**	**9 5/8"**	**7"**
DEPTH (m)			
Ahuroa South B-1	50	653	2395
Ahuroa South B-1 ST1	50	653	2395
PARTICIPATING INTERESTS	*SWIFT ENERGY NEW ZEALAND LIMITED* ***100%***		

3.2 LOCATION

The final coordinates for the AHUROA SOUTH B-1 well are given below.

Grid Coordinates NZ Grid Map	**Geographical Coordinates** (degrees/mins/secs) (NZGD1949)	**Geographical Coordinates** (degrees/decimals)
2625724.00 m E	174° 20' 25.375" E	174.340382°
6214665.80 m N	39° 16' 01.196" S	39.266999°

4.0 GEOLOGY, GEOPHYSICS, FORMATION SAMPLING AND EVALUATION

4.1 GEOLOGY AND GEOPHYSICS

4.1.1 TARANAKI BASIN OVERVIEW

The structurally diverse Taranaki Basin lies along the west coast of New Zealand's North Island, south of Auckland and northwest of Wellington, and also along the northwest coast of the South Island, northwest of Nelson. Located at the convergent boundary between the Australian Plate (west New Zealand) and the Pacific Plate (east New Zealand), the Taranaki Basin is a product of several phases of basin evolution. It covers approximately 100,000 square kilometers (38,610 square miles), of which about 90% is offshore.

The Taranaki Basin is elongated in a north-south direction and is principally a subsurface feature, the onshore portion of which lies beneath a surficial cover of Quaternary volcanic and alluvial deposits. Sediments in the basin are up to nine kilometers thick and range in age from Cretaceous to Recent. The buried Taranaki Fault bounds the basin on the east, while the western boundary of the basin is effectively the deep-water platform Challenger Plateau.

The northern and southern limits of the basin are not as well defined. In the south, the Taranaki Basin is today topographically emergent and is evident on the northwest coast of the South Island in the form of Cretaceous cored ridges and sub-basins. To the north, the Taranaki Basin merges with the predominantly offshore Northland Basin and the abyssal New Caledonia Basin.

The Taranaki Basin can be readily divided between the Eastern Mobile Belt (Taranaki Graben) and the Western Stable Platform. All proved hydrocarbon accumulations lie either within or at the flank of the Eastern Mobile Belt. Maui Field, the largest in New Zealand, is at the boundary between these two provinces.

The Eastern Mobile Belt can be divided into a number of sub-provinces: Northern Graben, Central Graben, Tarata/Taranaki Fault Trend, and the Southern Inversion Zone.

The Northern Graben, which is entirely offshore north and northwest of the Taranaki Peninsula, is an area of late Miocene to Pliocene extension bounded on the west by the Cape Egmont Fault Zone and on the east by the Turi Fault Zone. The Cape Egmont Fault Zone marks the western limit of deformation of the overriding Australian Plate.

The Central Graben area, manifested both onshore and offshore, lies to the south of the Northern Graben area, but is slightly younger and represents the southward migration of the extension related to the complex interrelationships of the Australian and Pacific Plate boundaries. As with the Northern Graben region, the Central Graben region is bounded on the west by the Cape Egmont Fault Zone and on the east by a system of normal faults that trend northeast-southwest.

The Tarata/Taranaki Fault Trend lies immediately to the west of the Patea-Tongaporutu High basement block complex, along the eastern margin of the basin. The Taranaki Fault Zone is a major reverse fault that offsets the basement by more than 5 kilometers (3.1 miles). This westward directed fault was active throughout much of the Miocene. Sediments of late Miocene and younger cover the upthrust Patea-Tongaporutu High basement block east of the Taranaki Fault. This sediment cover continues eastward into the North and South Wanganui Basins.The Tarata Fault Zone, a region of generally thin-skinned thrust faults, is immediately west of, and associated with, the Taranaki Fault Zone. The Tarata Fault Zone is comprised of generally west directed faults that were active during the early Miocene. McKee, Waihapa, Tariki, and Ngaere are examples of Tarata Fault trend fieldsThe Southern Inversion Zone covers the southern reaches of the basin. This is an area of large-scale structural inversion of former rift half-grabens. The Southern Inversion Zone contains a number of reverse fault bounded inverted anticlines. The large Kapuni Field and the Kupe South Field along the Manaia anticline are examples of productive structures within this region. The latter two sub-provinces cover PML 38139 and contain the majority of the fields found to date.

The Western Stable Platform is largely unexplored and results to date have been discouraging. This area has been relatively tectonically inactive since the Paleocene, showing little evidence of deformation except for flexure to the east caused by sediment loading.

The Taranaki Basin is filled with sediment ranging in age from late Cretaceous to Recent. The entire sedimentary sequence may be summarized as an overall major transgressive cycle beginning in the late Cretaceous and continuing to the early Miocene. This was followed by an overall regressive phase, which continues today. The majority of reservoirs within the basin are clastic, aside from the fractured Tikorangi Limestone, which produces at Waihapa/Ngaere.

Oil has been produced in the Taranaki Basin since 1865 at the shallow Moturoa Field near New Plymouth. In this field, the oil reservoir is in the Miocene-Pliocene shelf sands of the Matemateaonga Formation. This remained the only producing area in the Taranaki Basin until the discovery in 1959 of the onshore Kapuni Field which produces gas-condensate from the Eocene level sands. Hydrocarbon reserves have been found within all major chronostratigraphic levels except the Cretaceous. The lack of Cretaceous age reservoirs may simply be a function of a lack of wells penetrating to this level.

The oldest proven reservoir in the Taranaki is the Paleocene Farewell Formation. This unit produces at the Kupe South Field and the Maui Field. The major reservoirs in the basin occur in the Eocene to early Miocene interval. The older reservoirs (Eocene and older) in the western portion of the basin (e.g., in the Maui Field and the Kapuni Field) tend to be gas-condensate, whereas those along the eastern flank of the basin in younger age rocks, latest Eocene and younger (e.g., in the McKee Field and Waihapa Field), are often oil bearing. The estimated known total remaining reserves in the Taranaki Basin are 54.5 MMBO and 1320.6 BCF with 0.8 MM tonnes LPG (Crown Minerals Data, 2002).

The major source for the hydrocarbons produced in the Taranaki Basin are the coals and carbonaceous shales deposited in the coastal plains and swamps of the Late Cretaceous Pakawau group and Paleocene-Eocene Kapuni groups. It is estimated that only about 1% of the hydrocarbons generated by the Rakopi Formation (Pakawau group) in the eastern region of the Taranaki Basin have been discovered to date.

FIGURE 3 Generalised Stratigraphy, Taranaki Basin, New Zealand




Figure 3: Generalised Stratigraphy, Taranaki Basin, New Zealand

4.1.2 AHUROA SOUTH PROSPECT (PRE-DRILL)

The Ahuroa South B-1 well was designed as a directional appraisal well to test the hydrocarbon potential of the McKee Sand reservoir in a position approximately 825 m south-east of the Ahuroa pad. The well was designed to test a down dip location structurally equivalent to that drilled in the Piakau North A-2 location.

The well was to be drilled from the existing Ahuroa B well-site. The McKee Sand was to be intersected at 3180 m MD. The well was proposed to reach a TD of 3430 m.

4.1.3 AHUROA SOUTH PROSPECT (POST-DRILL)

Tariki sands were water-wet in both Ahuroa South B-1 and ST1, as expected. McKee sands were encountered 59 m deep to prognosis in Ahuroa South B-1, well below the oil-water contact, and were water-wet. McKee sands were not developed in Ahuroa South B-1 ST1.

A revised geological picture would therefore suggest that the McKee Sand both thins to the north and to the west in the Ahuroa South area. The sand likely thickens in the direction of the Manutahi Pub.

4.2 STRATIGRAPHY

The stratigraphy in Ahuroa South B-1 and ST1 was similar to that seen in other wells in Ahuroa Field.

4.2.1 LITHOLOGICAL SUMMARY:

The following is a generalized description on formations drilled along with any fluorescence descriptions for Ahuroa South B-1 / ST1.

AHUROA SOUTH B-1

URENUI FORMATION: 653 – 1229 m MD

The Urenui Formation is predominantly claystone with siltstone, sandstone and limestone beds.

CLAYSTONE: The claystone is greenish grey to dark greenish grey, light bluish grey, medium grey and olive grey. The cuttings are predominantly very soft to soft, although they range from very soft to firm. They are largely amorphous to blocky. The claystone is generally non calcareous but is slightly to very calcareous in parts. Accessories include a trace to minor presence of shell fragments in parts, trace to common very fine lower to fine upper quartz sand grains in parts and minor to common glauconite pellets. This claystone has an arenaceous nature in parts.

SILTSTONE: The siltstone is olive grey in colour. The cuttings are soft and were amorphous to sub-blocky. The siltstone is non calcareous and grades to sandstone.

SANDSTONE: The sandstone is mainly unconsolidated, transparent to translucent, quartz grains, with aggregates that are predominantly coloured light olive grey to greenish grey and medium bluish grey in parts. The aggregates are mostly firm to hard, although they range from soft to hard. The grain size ranges from very fine lower to medium lower, predominantly very fine upper to fine upper. They are sub-angular to sub-rounded in shape and are moderately to well sorted. The sandstone has an argillaceous cement in some parts and calcite cement in others, and is moderately to very calcareous in parts. Accessories include minor to common levels of glauconite, traces of shell fragments, and traces of mica. The sandstone has poor inferred porosity.

LIMESTONE: The limestone is predominantly white to light grey. The aggregates are firm to hard and are sub-blocky in shape. The limestone is arenaceous and the grains are very fine upper to fine lower in size. There is a minor component of shell fragments. The limestone grades to sandstone.

MT MESSENGER FORMATION: 1229 – 1902 m MD

The Mt Messenger Formation is predominantly claystone inter-bedded with sandstone, siltstone and limestone.

CLAYSTONE: The claystone is predominantly light olive grey to olive grey, though it is greenish grey to dark greenish grey, medium bluish grey, and medium dark grey in parts. The cuttings are very soft to firm and sub-blocky to blocky in form. There is an arenaceous component to the claystone, with traces of quartz sand grains ranging in size from very fine lower to very fine upper. The claystone is slightly to very calcareous in parts and grades to siltstone.

SILTSTONE: The colour of the siltstone in this formation is greenish grey to dark greenish grey, and light olive grey to olive black. The cuttings are firm to hard and are sub-blocky to blocky in form. The claystone is moderately to very calcareous, and grades to claystone.

SANDSTONE: The sandstone is predominantly unconsolidated, transparent to translucent quartz, with light to dark grey aggregates. The aggregates are firm to hard and the grains range in size from very fine lower to coarse lower, though are predominantly fine upper to medium upper. The grains are sub-angular to sub-rounded in shape and range from poorly to well sorted. The aggregates are calcite cemented. The sandstone has no visible porosity; however, have moderate inferred porosity in parts determined by the size, shape and rounding of the unconsolidated grains.

LIMESTONE: The colour of the limestone is light olive grey. The cuttings are firm to hard and are sub-blocky in shape. There is an arenaceous component to the limestone. The limestone grades to claystone.

TIKORANGI FORMATION: 1902 – 2014 m MD

The Tikorangi Formation is primarily limestone with siltstone interbeds.

LIMESTONE: The limestone has a range in colour from white to light grey and olive grey. The limestone is arenaceous in nature. The cuttings are generally very soft to firm, but are hard in parts and are sub-blocky to blocky in form. Traces of pyrite are present at the top of the formation. The limestone grades to siltstone, and also grades to claystone at the top of the section.

SILTSTONE: The siltstone ranges in colour from medium grey, medium bluish grey, olive grey, and greenish grey to dark greenish grey. The cuttings are soft to hard and are sub-blocky to blocky in form. The siltstone is moderately to very calcareous. There are minor amounts of carbonaceous material in parts. It grades to claystone and limestone in parts.

OTARAOA FORMATION: 2014 – 2714 m MD

The Upper Otaraoa Formation consists of siltstone at the top of the section becoming mainly claystone towards the base of the section, with limestone inter-beds.

CLAYSTONE: The claystone is light olive grey to olive black, dark greenish grey and medium grey. The cuttings range from soft to hard, though predominantly soft to firm. They are sub-blocky to blocky in shape. There is a trace to common component of calcite veins, and the claystone is slightly to very calcareous, though predominantly moderately calcareous. The claystone grades to siltstone in parts.

SILTSTONE: The colour of the siltstone is predominantly light olive grey to olive grey, although it is greenish grey to dark greenish grey and bluish grey in parts. The cuttings are soft to firm though they are hard in parts. They are sub-blocky to blocky in form. The siltstone is argillaceous in parts, and also has a minor component of carbonaceous material in parts. The siltstone is moderately to very calcareous throughout the section, however it gradually becomes less calcareous towards the base of the section. The siltstone grades to claystone and limestone in parts.

LIMESTONE: The limestone is olive grey to medium grey in colour. The cuttings are very soft to hard and are sub-blocky to blocky in form. The limestone is arenaceous and grades to siltstone.

TARIKI SANDSTONE: 2714 – 3145 m MD

The Tariki Sandstone is sandstone with siltstone, claystone and limestone beds.

SANDSTONE: The sandstone is predominantly transparent to translucent quartz, with some white to dark grey, and yellowish grey aggregates. It is mostly unconsolidated, with a minor amount of soft to very hard aggregates. The grains range in size from very fine lower to coarse upper, and are sub-angular to rounded. The grains are predominantly moderately to well sorted, although there are some poorly sorted examples. The cement is calcareous and there are trace amounts of glauconite, coal and carbonaceous material present in parts. Rock flour is also common in the cuttings. There is poor to good inferred porosity.

SILTSTONE: The siltstone is olive grey to olive black, and light to dark grey in parts. The cuttings are firm and are sub-blocky to blocky in shape. The siltstone has a slightly to moderately calcareous character and grades to claystone in parts.

CLAYSTONE: The claystone is light olive grey to olive grey, and is dark grey in parts. Cuttings range from very soft to hard although are mainly soft to firm. The cuttings are predominantly sub-blocky to blocky in form, although amorphous in parts. The claystone ranges from non calcareous to moderately calcareous and grades to siltstone in parts.

LIMESTONE: The limestone is white to light grey. Cuttings range from soft to firm and are sub-blocky to blocky. The limestone is arenaceous in parts and has minor to common amounts of very fine upper to medium upper quartz grains. The limestone grades to very calcareous sandstone.

OTARAOA FORMATION (Lower): 3145 – 3230 m MD

The Lower Otaraoa Formation consists of interbedded claystone and siltstone with minor amounts of sandstone.

CLAYSTONE: The claystone is light olive grey to olive grey in colour. The cuttings are soft to firm, with occasional very hard cuttings in parts. Their form is sub-blocky to blocky. The claystone is slightly to moderately calcareous, and grades to limestone at the top of the section. It also grades to siltstone in parts.

SILTSTONE: The siltstone is coloured dark greenish grey to greenish black. The cuttings range from soft to firm and are sub-blocky to blocky in form. Glauconite is common in the siltstone. The siltstone is very calcareous, and grades to claystone.

SANDSTONE: The sandstone is loose transparent to translucent quartz. The grains range in size from very fine lower to fine upper, are sub-rounded and moderately sorted. There is fair inferred porosity in the sandstone.

MCKEE FORMATION: 3230 – 3244.8 m MD

The McKee Formation consists of interbedded sandstone and siltstone.

SANDSTONE: The sandstone is light grey to yellow grey aggregates. The cuttings are friable. The grains range in size from very fine lower to fine lower. The grains are sub-angular to sub-rounded in shape and moderately well sorted. There is abundant silty matrix present and traces of loose transparent to translucent quartz. There is poor visible porosity observed.

SILTSTONE: The siltstone is mostly white to yellowish grey, but is also dark greenish grey to greenish black. The cuttings are sub-blocky to blocky in shape and are soft to firm. Glauconite is common with the lighter siltstone. The darker siltstone is very calcareous, and the lighter is slightly calcareous in parts. The siltstone grades to sandstone.

MANGAHEWA FORMATION: 3244.8 – 3300 m MD

The Mangahewa Formation is comprised primarily of claystone, interbedded with minor layers of siltstone, sandstone and coal seams. The lower contact of this formation is marked by the Ahuroa Thrust system.

CLAYSTONE: The claystone varies in colour from brownish grey to brownish black and light olive grey to olive grey. The cuttings are firm to moderately hard and are sub-blocky to blocky in form. The claystone is non-calcareous to moderately calcareous, becoming more calcareous towards the base of the section. The claystone grades to siltstone in parts.

SILTSTONE: The siltstone is light olive grey to brownish grey and brownish black. The cuttings are firm to moderately hard and sub-fissile to blocky in shape. The siltstone is very carbonaceous in parts and has coal laminae. There are traces of very fine quartz grains in parts. The siltstone grades to claystone.

SANDSTONE: The sandstone is light grey to yellow grey aggregates. The aggregates are friable. The grain size ranges from very fine lower to fine lower. The grains are sub-angular to rounded and moderately sorted. A silty matrix is abundant in the sandstone. There is poor visible porosity.

COAL SEAM: The coal is black in colour and brittle to firm. The cuttings are sub-fissile to blocky in structure and have a hackly fracture pattern. The coal has an earthy to vitreous lustre and is argillaceous in part.

MANGANUI FORMATION: 3300 – 3370 m MD TD

The section of the Manganui Formation observed (the lower contact was not reached) was entirely claystone.

CLAYSTONE: The claystone is olive grey to olive black at the top of the section, grading to dark grey to olive black by the bottom of the section. The cuttings are firm to moderately hard and are sub-blocky to blocky in structure. There are traces of calcite veins in parts. The claystone is slightly calcareous at the top of the section and is non calcareous by the bottom.

AHUROA SOUTH B-1 ST1

OTARAOA FORMATION: 2400 (KOP)- 2669 m MD *AHUROA SOUTH B-1 ST1*

The Upper Otaraoa Formation consists of siltstone at the top of the section becoming mainly claystone towards the base of the section.

CLAYSTONE: The claystone Is light olive grey to olive black, brownish grey and medium grey are also commonly observed. The cuttings range from soft to hard, though predominantly soft to firm and are sub-blocky to blocky in shape. There is a trace to common component of calcite veins and the claystone Is slightly to very calcareous, though predominantly moderately calcareous. The claystone grades to siltstone in parts.

SILTSTONE: The colour of the siltstone is predominantly light olive grey to olive grey, although it is greenish grey to dark greenish grey and bluish grey in parts. The cuttings are soft to firm though they are hard in parts and are sub-blocky to blocky in form. The siltstone is argillaceous in parts and in places has a minor component of carbonaceous material. The siltstone is moderately to very calcareous throughout the section, but gradually becomes less calcareous towards the base. On occasion the siltstone grades to the above claystone.

TARIKI SANDSTONE: 2669 – 2929 m MD *AHUROA SOUTH B-1 ST1*

The Tariki Sandstone consists of sandstone with siltstone and claystone interbeds.

SANDSTONE: The sandstone is predominantly transparent to translucent quartz, with some white to dark grey, and yellowish grey aggregates. It is mostly unconsolidated, with a minor amount of soft to very hard aggregates. The grains range in size from very fine lower to coarse upper, and are sub-angular to rounded. The grains are predominantly moderately to well sorted, although there are some poorly sorted examples. The cement is calcareous and there are trace amounts of glauconite, coal and carbonaceous material present in parts. There is poor to good inferred porosity.

SILTSTONE: The siltstone is olive grey to olive black, and light to dark grey in parts. The cuttings are firm and are sub-blocky to blocky in shape. The siltstone is slightly to moderately calcareous and grades to claystone in parts.

CLAYSTONE: The claystone is light olive grey to olive grey and dark grey in parts. Cuttings range from very soft to hard although are mainly soft to firm. The cuttings are predominantly sub-blocky to blocky in form, although are amorphous in parts. The claystone ranges from non to moderately calcareous and grades to siltstone in parts.

OTARAOA FORMATION: 2929 – 2972 m MD AHUROA SOUTH B-1 ST1

The Lower Otaraoa Formation consists of interbedded claystone and siltstone with minor amounts of sandstone.

CLAYSTONE: The claystone is light olive grey to olive grey in colour. The cuttings are soft to firm, with occasional very hard cuttings in parts. Their form is sub-blocky to blocky. The claystone is slightly to moderately calcareous, and grades to limestone at the top of the section. It also grades to siltstone in parts.

SILTSTONE: The siltstone is coloured dark greenish grey to greenish black. The cuttings range from soft to firm and are sub-blocky to blocky in form. Glauconite is common in the siltstone. The siltstone is very calcareous, and grades to claystone.

SANDSTONE: The sandstone is loose transparent to translucent quartz. The grains range in size from very fine lower to fine upper, are sub-rounded and moderately sorted. There is fair inferred porosity in the sandstone.

MCKEE FORMATION: 2972 – 2985 m MD *AHUROA SOUTH B-1 ST1*

The McKee Formation is represented by a thin sequence of claystone and siltstone with minor sandstone. The McKee Sands are not developed.

CLAYSTONE: Olive grey, light olive grey, soft – firm, amorphous – subblocky, moderately calcareous.

SILTSTONE: Dark greenish grey – greyish black, soft – firm, blocky, moderately calcareous, abundant glauconite. Light grey, yellowish grey, soft – firm, blocky, moderately calcareous, trace very fine quartz grains, trace glauconite

SANDSTONE: Yellowish grey, friable, very fine lower – medium upper, predominantly fine lower, moderately sorted, subangular – rounded, trace calcareous cement, trace glauconite, abundant silty matrix, grades to siltstone, poor – fair porosity, no show

MANGAHEWA FORMATION: 2985 – 3030 m MD *AHUROA SOUTH B-1 ST1*

The Mangahewa Formation is comprised primarily of claystone, interbedded with minor layers of siltstone, sandstone and coal seams.

CLAYSTONE: The claystone varies in colour from brownish grey to brownish black and light olive grey to olive grey. The cuttings are firm to moderately hard and are sub-blocky to blocky in form. The claystone is non to moderately calcareous, becoming more calcareous towards the base of the section. The claystone grades to siltstone in parts.

SILTSTONE: The siltstone is light olive grey to brownish grey and brownish black. The cuttings are firm to moderately hard and sub-fissile to blocky in form. The siltstone is very carbonaceous in parts with coal laminae observed. There are trace amounts of very fine quartz grains in parts. The siltstone in part grades to claystone and sandstone.

SANDSTONE: The sandstone is light grey to yellow grey friable aggregates. The grain size ranges from very fine lower to fine lower. The grains are sub-angular to rounded, and are moderately sorted. Silty matrix is abundant in the sandstone. There is poor visible porosity.

COAL SEAM: The coal is black in colour and brittle to firm. The cuttings are sub-fissile to blocky in structure and have a hackly fracture pattern. The coal has an earthy to vitreous lustre and is argillaceous in part.

MANGANUI FORMATION: 3030– 3085 m MD TD ***AHUROA SOUTH B-1 ST1***

The section of the Manganui Formation observed (the lower contact was not reached) is entirely claystone.

CLAYSTONE: The claystone is olive grey to olive black at the top of the section, then changes abruptly to medium grey to dark grey in colour, giving a clear indication of the change in the Manganui Formation. The claystone is blocky in structure with trace amounts of calcite veins noted in parts. The claystone is very slightly to slightly calcareous at the top of the section becoming non-calcareous with depth

4.2.2 RESERVOIR SEAL ASSESSMENT

Seals in the Taranaki Basin generally consist of marine mudstones, which form top seals and internal seals to hydrocarbon bearing reservoirs. In the Ahuroa/Piakau area, the reservoir sands are juxtaposed against Manganui mudstones along the main thrust to the west.

4.2.3 PALYNOLOGY / PALEONTOLOGY

A paleontologist from GNS was on-site to evaluate samples obtained while drilling. The relatively short stratigraphic sections of Ahuroa South B-1 and Ahuroa South B-1 ST1 were examined, mainly to confirm that the well had penetrated the main thrust fault. Samples from the interval 3185 to 3245 m Ahuroa South B-1 were examined on-site. The remaining samples from Ahuroa South B-1 and all samples from Ahuroa South B-1 ST1 were examined at GNS.

Paleontology confirmed that both well bores penetrated the major thrust fault (Ahuroa Thrust). In the Ahuroa South B-1, 9 samples spanning the interval from 3185 - 3370 m TD, were examined. The section consists of upper Whaingaroan sediments of the Otaraoa and Tariki Formations, resting unconformably on un-dated, but probably upper Arnold Series, Kapuni Group sediments, which are, in turn, in fault contact with middle Altonian Manganui Formation (footwall).

Ahuroa South B-1 ST1 samples were taken from intervals 2970 - 3085 m (TD). The section consists of upper Whaingaroan sediments of the Otaraoa and Tariki Formations, resting unconformably on un-dated, but probably upper Arnold Series, Kapuni Group sediments, which are in turn, in fault contact with middle Altonian to possibly lower Southland Series Manganui Formation.

For the full report, see Appendix II.

4.2.4 MUD LOGGING

Continuous 24-hour mud logging service was supplied by Baker Hughes Inteq. Mud logging commenced at surface casing (659 m) and continued to TD (3370 m/ 3085 m MD ST1). The following services were provided:

(a) Gas Detection:
- Total gas detection
- Chromatographic gas analysis (C_1-C_5) and
- H_2S concentration.
- CO2 concentration.

(b) Monitoring of Drilling Parameters:
- Measured depth
- Rate of penetration
- Weight on bit

- RT speed
- Torque
- Hook load
- Mud pump stroke rate
- Standpipe pressure
- Mud pit volumes
- Mud volume in
- Mud temperature in and out

(c) Formation Sampling and Analysis:

- Routine description and compilation of samples
- Routine fluorescence detection in cuttings and mud
- Formation pressure analysis and prediction

4.3 DITCH CUTTINGS

Formation evaluation logging of Ahuroa South B-1 commenced at 659 m. Samples were collected, washed and logged as follows:

Sets A,B,C,D and E. Set F: 5 m intervals from 3200 – 3370 m (GNS)

Ahuroa South B-1

660-2720 m every 10 m

2720-2920 m every 5 m

2920-2960 m every 10 m

2960-3370 every 5 m

Ahuroa South B-1 ST1

2400-2670 m every 10 m

2670-2760 m every 5 m

2760-3000 m every 10 m

3000-3085 m (TD) every 5 m

Spot samples were also taken at drill breaks / gas peaks, or on request from Geologist.

Distribution of cuttings samples was as follows:

Ministry of Economic Development: 1 set Washed and air-dried cuttings samples (Set E). Two (2) sets Unwashed and air-dried cuttings samples. (Sets A & B)

Swift Energy New Zealand Limited: 1 set Washed and oven-dried cuttings samples (Set D). One (1) set Unwashed and air-dried cuttings samples (Set C).

Samples were described in the Formation Evaluation Log using standard Baker Hughes Inteq abbreviations. A Geological Society of America colour chart with Munsell colour chips was used for colour descriptions. Colour comparison was done on samples washed in oil base .

Washed cuttings samples were viewed under ultra-violet light for indications of hydrocarbon shows and described accordingly. Hydrocarbon shows are described on the mud log.

4.4 HYDROCARBON SHOW SUMMARY

TABLE 3 Hydrocarbon Show Summary AHUROA SOUTH B-1

DEPTH INTERVAL (m MD)	FORMATION	LITHOLOGY	SHOW DESCRIPTION
1410 - 1700	Mt Messenger	Claystone	Patchy, poor quality. Traces to 10% yellowish white direct fluorescence, slow blooming bluish white cut fluorescence, thick blue residue ring.

4.5 SIDEWALL CORES

There were no side-wall cores taken in Ahuroa South B-1 or ST1

4.6 CONVENTIONAL CORES

No conventional core was cut on Ahuroa South B-1 or ST1

4.7 WIRELINE LOGGING

Wireline logs were obtained by Schlumberger Logging Services NZ Limited.

TABLE 4 Wireline Logs AHUROA SOUTH B-1

SCHLUMBERGER RUN	LOGGING OPERATION #	TOOL STRING	INTERVAL (m MD)	BHT (°C)/Time Since Circ.	COMMENTS
1	1	PEX/HRLA/ BHC	2398 - 655	12hrs35 min/66 **°C**	Ahuroa South B-1 19/10/05
2	1	PEX/AIT/ BHC	3374-2402	11hrs00 min/89 **°C**	Ahuroa South B-1 07/11/05
3	1	PEX/AIT/ BHC	3085-2402	10hrs35 min/82 **°C**	Ahuroa South B-1 ST1 25/11/05
	2	UBIT	3088 - 2700	17hrs55 min/82 **°C**	Ahuroa South B-1 ST1 25/11/05

4.8 MWD LOGGING

Sperry Sun provided MWD/Surveys in the 8 ½" and 6" hole sections from 659 m down to 3370 m (TD) and 3085 m (TD in ST1).

4.9 GEOTHERMAL GRADIENT

Bottom hole temperatures were recorded during logging. Using the wireline logs, a bottom hole temperature of 88°C was recorded at 3218.4 m TVD (3374 m MD). Assuming an ambient surface temperature of 20°C, the geothermal gradient for the section penetrated is 21.13°C/km.

4.10 VELOCITY SURVEY

No check shots were run in Ahuroa South B-1 / ST1

4.11 PETROPHYSICS

Detailed petrophysical analysis was carried out over the target zones.

Petrophysical Evaluation

Ahuroa South B-1

Tariki Sand – 8 ½" hole

Drilled with OBM

OH Logged (Schlumberger)

Tariki Sand was encountered at 2714.0 m – 3002.0 m MD (Upper Tariki) and 3017.0 – 3131.0 m MD (Lower Tariki). A petrophysical analysis was not run on the Tariki sand given the results of the Piakau North A-1 well-bores. Wireline logs clearly showing wet Tariki sands with possible high residual hydrocarbon saturations, made difficult to quantify due to effects of OBM. It was noted however, that the Tariki sand had thickened substantially in this northerly direction relative to Piakau North.

McKee Sand (Kapuni Group)

Drilled with OBM

OH Logged (Schlumberger)

McKee Sand was encountered at 3231.0 – 3245.0 m MD. Unfortunately the McKee sand had thinned dramatically in this location and wire-line logs depicted a wet sand signature. A petrophysical analysis confirmed this, with zero netpay being interpreted.

The result from this well, added further weight to the local OWC existing at -2777 m TVDSS. As a result Ahuroa South B-1 was sidetracked in an updip location hoping to find a thickened McKee sand section and above the OWC.

Parameters:

a = 1.00; m = 2.00; n = 1.90 (averaged regional data)

Rw = 0.11 ohm-m (averaged regional data)

Equations Used:

Water Saturation – Archie

VShale – Gamma Ray

Effective Porosity – Density-Neutron

Ahuroa South B-1 ST-1

Tariki Sand – 8 ½" hole

Drilled with OBM

OH Logged (Schlumberger)

Tariki Sand was encountered at 2669.0 – 2929.0 m MD (Entire Tariki). A petrophysical analysis was not run on the Tariki sand given the results of the Piakau North A-1 well-bores and Ahuroa South B-1. Wireline logs clearly showing wet Tariki sands with possible high residual hydrocarbon saturations, made difficult to quantify due to effects of OBM.

McKee Sand (Kapuni Group)

Unfortunately as a result of side-tracking in an updip location the McKee sand was not penetrated at all.

A revised geological picture suggests that the McKee sand both thins to the north and to the west in the Ahuroa South area.

5.0 DRILLING OPERATIONS

5.1 GENERAL DATA

TABLE 5 General Data AHUROA SOUTH B-1 / ST1

DESIGNATION	Appraisal		
PERMIT	PML 38139		
BASIN	Taranaki, New Zealand		
OPERATOR	Swift Energy New Zealand Limited		
PERMITEES	Swift Energy New Zealand Limited		
RIG	Parker Rig# 252		
RT ELEVATION	201.84 m		
GROUND LEVEL ELEVATION	196.3 m		
LATITUDE	39° 16' 01.196" S		
LONGITUDE	174° 20' 25.375" E		
GRID CO-ORDS:	2625724.00 m E 6214665.80 m N		
SEISMIC	2D Line WH85-28 & WH85-18		
ELEVATION	201.80 RKB		
PERMIT	PML 38139		
SPUDDED	5 October 2005, Kick-off 11 November 2005		
REACHED TD	Ahuroa South B-1 7 November 2005 Ahuroa South B-1 ST1 24 November 2005		
RIG RELEASED	28 November 2005		
COMPLETION DETAILS	Plugged & Abandoned		
STRUCTURE TYPE	Thrust faulted structure		
RIG	Parker Rig #252		
DRILLER Total Depth (TD)	Ahuroa South B-1 3370 m MD Ahuroa South B-1 ST1 3085 m MD		
LOGGER Total Depth (TD)	Ahuroa South B-1 3370 m MD Ahuroa South B-1 ST1 3085 m MD		
HOLE SIZE (in.)	**12 ¼"**	**8 ½"**	**6"**
DEPTH (m) Ahuroa South B-1	659	2403	3370
Ahuroa South B-1 ST1	659	2403	3085
CASING DETAIL (in.)	**13 3/8"**	**9 5/8"**	**7"**
DEPTH (m)			
Ahuroa South B-1	50	653	2395
Ahuroa South B-1 ST1	50	653	2395
PARTICIPATING INTERESTS	*SWIFT ENERGY NEW ZEALAND LIMITED* ***100%***		

5.2 CONTRACTORS

TABLE 6 Contractors AHUROA SOUTH B-1 / ST1

Drilling	Parker Drilling
Rig Positioning	BTW Surveyors Ltd.
Fuel	Challenge
Supply Base	New Plymouth
Cementing	Halliburton Australia Pty. Ltd.
Mud Engineering	Baroid
Geologist	K&S Oil Field Consulting Limited
Mud Logging	Baker Hughes Inteq
Coring	N/A
Electric Logging	Schlumberger
Testing	Vause
Communications	Telecom NZ Ltd.
Casing Services	Austoil Drilling Services
Casing Cutting	N/A
Road Transport Services	Hookers Trucking, Burrough's Trucking

5.3 TIME VS. DEPTH CHART FOR DRILLING: PROGNOSED VS. ACTUAL

(See Appendix III)

5.4 WELL DRILLING REPORTS (INCLUDING WELL COST SUMMARY)

(See Appendix IV)

5.5 MUD SUMMARY REPORT

(See Appendix VII)

5.6 BIT SUMMARY REPORT

(See Appendix VIII)

5.7 CASING REPORT

(See Appendix IX)

5.8 CEMENTING REPORT

(See Appendix X)

5.9 DIRECTIONAL SURVEY

(See Appendix XI)

5.10 BHA REPORT

(See Appendix XII)

5.11 RIG EQUIPMENT INVENTORY

(See Appendix XVIII)

6.0 TESTING AND RESERVOIR EVALUATION

6.1 SUMMARY OF TESTING

No well testing.

6.2 RESERVOIR FLUID ANALYSIS

No fluid analysis.

7.0 REFERENCES

King, P.R. and G.P. Thrasher, 1996, Cretaceous-Cenozoic Geology and Petroleum Systems of the Taranaki Basin, New Zealand: Institute of Geological and Nuclear Sciences Monograph 13, Lower Hutt, New Zealand.

King, P.R., 1994, The Habitat of Oil and Gas in Taranaki Basin: New Zealand Petroleum Conference Proceedings, p. 180 – 202.

Thrasher, G. P., 1989, Tectonics of the Taranaki Rift: New Zealand Oil Exploration Conference, Vol. 1, p. 124 –133.

END OF WELL REPORT

SWIFT ENERGY NEW ZEALAND LTD

AHUROA SOUTH B-1

5th October 2005 – 10th November 2005

by

BAKER HUGHES INTEQ

The information, interpretations, recommendations, or opinions contained herein are advisory only and may be rejected. Consultant does not warrant their accuracy or correctness. Nothing contained herein shall be deemed to be inconsistent with, nor expand, modify or alter Consultants obligation of performance as provided for in a written agreement between the parties, or, if none, in Consultant's most recent price list.

Ahuroa South B-1

End of Well Report

SECTION 1 Well Data Summary

SECTION 2 Drilling and Engineering
- 2.1 Well Overview
- 2.2 Bit Run Summaries
- 2.3 Casing and Cementing

SECTION 3 Formation Evaluation and Sampling
- 3.1 Formation Evaluation
- 3.2 Sampling Summary
- 3.3 Geology and Shows

TABLES
- Bit Table
- Hydraulics Table
- Time Depth Curve

APPENDICES

Formation Evaluation Log	1: 500
Drilling Data Plot	1: 2500
Gas Ratio Plot	1: 500

CD Contents

ASCII

Ahuroa South B-1_Comments.xls	Excel file of Comments on the Mudlog
Ahuroa South B-1_Descriptions.xls	Excel file of Descriptions on the Mudlog
Ahuroa South B-1_Drill_Gas_Ascii.xls	Excel file of Drilling and Gas Data
Ahuroa South B-1_InterpretedLithAscii.xls	Excel file of Interpreted Lithology Data
Ahuroa South B-1_PercentLithAscii.xls	Excel file of Cuttings Percentage Lithology Data

FIVE SECOND DATA Five Second Data in Excel format

FWR

Ahuroa South B-1_End_of_Well_Report.pdf PDF file of End of Well Report

LOGS

Ahuroa South B-1_Drilling_Data_Plot.pdf	PDF file of Drilling Data Plot
Ahuroa South B-1_Gas_Ratio_Plot.pdf	PDF file of Gas Ratio Plot
Ahuroa South B-1_Mudlog.pdf	PDF file of Mudlog

MORNING_REPORTS Directory of Morning Reports

SECTION 1

WELL DATA SUMMARY

1. WELL DATA SUMMARY

Rig Name:	Parker Drilling Company Rig 252
Rig Type:	Ingersol Rand Truck Mounted Land Rig
Drilling Contractor:	Parker Drilling Company
Drilling Datum:	Rotary Kelly Bushing
Rotary Kelly Bushing Elevation:	201.41m AMSL
Ground Level Elevation:	196.20m AMSL
New Zealand Map Grid (Surface):	2625724.00 mE 6214665.80 mN
New Zealand Geodetic Datum (NZGD 1949)	Lat: 39° 16' 01.20" South Long: 174° 20' 25.438" East
Permit No:	PEP 38719
Well Type:	Exploration
Spud Date:	5th October 2005
Total Depth:	3370m (3219.00m TVD RKB)
TD Date:	7th November 2005
Primary Objective:	McKee Sands
Secondary Objectives:	Tariki Sands
Well Status:	Completed
Baker Hughes INTEQ Crew:	G. Ammundsen, G. Minarno, R. Farmer G. Lindsay, D. Barrel, B Berger

SECTION 2

DRILLING & ENGINEERING

2. DRILLING AND ENGINEERING

2.1 WELL OVERVIEW

Ahuroa South B-1 was spudded from 30m at 14:00 hrs on the 5th of October 2005 and was drilled to a total depth (TD) of 3370m with five drill bits. A Kelly system mounted on an Ingersol Rand Truck was used to drill this well. Unless otherwise stated, all depths in this report are measured in meters along hole below the Rotary Kelly Bushing (BRKB).

12.25" Hole Section: Prior to drilling the 12.25" hole section, independent contractors had set the 13.375" Conductor at 30m. One bit was used to drill the 12.25" section in one bit run.

NB-1 was run in and drilled from 30m to 659m. The 9.625" Casing was run in and cemented with the casing shoe set at 652m. Blow out preventers were installed and pressure tested. The mudlogging unit was rigged up and was online from 659m for the 8.5" Hole section.

8.5" Hole Section:

NB3 a REED DSX104HG drilled out the cement, float and 3m of new formation. After conditioning the mud and performing a leak off test new hole was drilled with regular sliding required to build angle. NB3 drilled without incident to the 7"casing point at 2399m. Wiper trips were carried out at 1280m and 1826m. The bit was pulled out of hole and the following Schlumberger wireline logs run;

Run 1: PEX, HRLA, BHC; was run to a depth of 2398m

RR3 with a stripped down BHA was run into hole for hole cleaning prior to running the 7" casing. Once on bottom it was decided to drill another 4m. Then the BHA was pulled in preparation for running the 7" casing.

6" Hole Section:

NB4 a Reed DSX516M-B1PDC bit was run in and drilled 6" hole from 2403m. After drilling out the 7" shoe and 3m of new hole, the mud was circulated and conditioned before an FIT test performed to an EMW of 10.5ppg at 2395m. New hole was then drilled, sliding and rotating as required. At 2787m a wiper trip was made back to the shoe. The hole was found to be in good condition when running back in. Rotary drilling continued with several slides and at regular intervals LCM sweeps pumped. NB4 drilled to 2903m where it was pulled due to poor penetration rates and problems sliding.

NB5 a Reed DSX516M-B1 PDC bit was run in along with a new mud motor and MWD probe. However due to MWD failure, the assembly was pulled out of hole and was re-run with a replacement MWD probe. Drilling alternated between sliding and rotating until 3006m after which there was no sliding as the reservoir section was approaching. A 17 stand wiper trip was made at 3182m. At 3296m a 1m coal stringer caused tight hole, the assembly was pulled to remove the motor and MWD tool due to the risk of further problems with possible coal lithologies.

NB6 a Reed DSX413M-A2 PDC bit was run in at 3296m and drilled to 3370m TD. The well was circulated clean and a four stand wiper trip performed before NB6 was pulled out of the hole.

A single wireline logging suite was then run:

Run 1: PEX-AIT-BHC was run to TD

After the wire line logging was completed a mule shoe and 2-7/8" tubing assembly was run-in on 3.5" drill pipe. Upon reaching the shoe, the Kelly was attached and the hole was slowly circulated, running in then continued to 2526m. The borehole was conditioned at this depth, by circulating the mud while reciprocating the pipe. Halliburton Cementing Unit was then lined up to the hole and a cement plug was set as per instructions. The mule shoe was pulled up to 2242m and the mud circulated, there were no cement returns. The Cement stinger was pulled out of hole and the excess 3-1/2" drillpipe laid out. Pulling out of hole continued, racking back the remaining drillpipe in the derrick. An assembly was run to drill out the cement and polish the plug before kicking off Ahuroa South B-1 ST-1.

2.2 BIT RUN SUMMARIES

8.5" PHASE: 11th Oct – 19th Oct 2005

Note: The BHI unit and crew were on line from 659m during the 8.5" hole section.

Bit Run No. 1 Summary

BIT No.:	NB3
BIT SIZE:	8.5"
BIT TYPE:	Reed DSX104HG
S/N:	111856
JETS:	5x14
DEPTH IN:	659 m
DEPTH OUT:	2399 m
DRILLED:	1740 m
HOURS:	113 hr
AVG ROP:	15.4 m/hr
TBR:	1218.1k rev
ROT. HRS:	149.5 hr
API CONDITION	Bit not graded

DRILLING PARAMETERS:


WOB:	1 – 25 klb
RPM:	78- 250
TORQUE:	0 – 18.9 kft lb
PRESSURE:	640 – 2345 psi
FLOW IN:	170- 635 gpm

MUD:

KCl Polymer	8.7 – 9.35 ppg

LITHOLOGY:
Sandstone, Claystone, Limestone, Siltstone

DRILLING SUMMARY:
After running casing, nippling up and testing the BOP's NB3 was made up and run in the hole. The MWD tool was shallow tested before running in continued. The top of cement was tagged at 634m. The cement, float collar, shoe track, shoe, and rat hole were drilled out to 639m. After drilling 3m of new formation the mud was circulated and conditioned prior to performing a leak off test to an EMW of 11.5ppg. Drilling proceeded with regular sliding required to build angle. A wiper trip was carried out at 1280m, with the hole found to be in good condition. Drilling continued without incident to 1826m, where another wiper trip was carried out, 2m of fill was encountered once back on bottom and a trip gas of 0.22% over a 0.06% background was observed. Drilling continued to the 7" casing point at 2399m. After circulating bottoms up and conducting a wiper trip, NB3 was pulled to surface.



Bit Run No. 2 Summary

BIT No.:	3RR
BIT SIZE:	8.5"
BIT TYPE:	Reed DSX104HG
S/N:	111856
JETS:	5x4
DEPTH IN:	2399 m
DEPTH OUT:	2403 m
DRILLED:	4 m
HOURS:	0.3 hr
AVG ROP:	13.3 m/hr
TBR:	3.04k rev
ROT. HRS:	0.33 hr
API CONDITION	1-3-CT-T-X-1-WT-CP

DRILLING PARAMETERS:


WOB:	4-6 klb
RPM:	85-97
TORQUE:	8.9-91 kft lb
PRESSURE:	1390-1420 psi
FLOW IN:	505-510 gpm

MUD:
KCl Polymer 9.30 ppg

LITHOLOGY:
Claystone, Siltstone

DRILLING SUMMARY:
3RR a clean up BHA was made up and run in the hole to 2378m. From here the bit was reamed to bottom. After drilling 4m of new formation a 20bbl sweep was pumped and the hole circulated clean. 3RR was pulled out of hole side ways and the 4½ DP laid out.

BHA No. 2 192.76 m



6.0" PHASE: 22nd Oct – 7 Nov 2005

Bit Run No. 3 Summary

BIT No.:	NB4
BIT SIZE:	6.0"
BIT TYPE:	Reed DSX516M-B1
S/N:	113097
JETS:	5x13
DEPTH IN:	2403 m
DEPTH OUT:	2903 m
DRILLED:	500 m
HOURS:	93.5 hr
AVG ROP:	5.35 m/hr
TBR:	890.1k rev
ROT. HRS:	117.5 hr
API CONDITION	3-6-WT-S-X-1-CT-PR


DRILLING PARAMETERS:

WOB:	1 - 15 klb
RPM:	105- 220
TORQUE:	0 – 9.89 kft lb
PRESSURE:	1955 - 3125 psi
FLOW IN:	175 - 425 gpm

MUD:
SBM 8.5 – 8.7 ppg

LITHOLOGY:
Claystone, Siltstone, Sandstone

DRILLING SUMMARY:
After the 7" casing had been run in and cemented and the BOPs tested, the mud system was changed to synthetic based mud. NB4 was made up and run in the hole picking up singles of 3.5" drill pipe. The MWD tool was shallow tested on entering the hole. The assembly was tripped in without incident tagging the float collar at 2395m. Cement, the shoe track, shoe and rat hole were drilled out to 2398m. The SBM mud was then circulated and conditioned prior to a leak off test (the water based mud was displaced to SBM during the cementing of the 7" casing). When the SBM had been weighted up to 8.5ppg, Howco were rigged up and performed a leak off test to an EMW of 11.5ppg. Drilling of the 6.0" section then proceeded, with 5bbl sweeps pumped at regular intervals. At 2787m bottoms up was circulated, the well was flow checked (static) then a slug pumped and a wiper trip was made back to the shoe. The hole was found to be in good condition when running back in. Bottoms up was circulated prior to drilling ahead. Rotary drilling continued with some short slides to maintain angle. 5 to 10bbl sweeps were pumped every third joint drilled. At 2903m the decision made to pull out of hole for a change of bit due to poor ROP and difficulty in sliding. A sweep was pumped and circulated out before pumping a slug and pulling out of the hole. Once at the shoe at 2382m the well was flowchecked (static), and the assembly was tripped out of the hole. At surface the bit, motor and MWD were changed out and the Stabilizer was removed from the BHA before running in the hole with NB5.



Bit Run No. 4 Summary

BIT No.:	NB5
BIT SIZE:	6.0"
BIT TYPE:	Reed DSX516M-B1
S/N:	113096
JETS:	3x13, 2x15
DEPTH IN:	2903 m
DEPTH OUT:	3296 m
DRILLED:	393 m
HOURS:	123.8 hr
AVG ROP:	3.2 m/hr
TBR:	1439k rev
ROT. HRS:	150.1 hr
API CONDITION	2-6-WT-S-X-1-WT-FM

DRILLING PARAMETERS:

WOB:	1 - 14 klb
RPM:	112 - 225
TORQUE:	0 – 9.14 kft lb
PRESSURE:	1410 - 3100 psi
FLOW IN:	195 - 245 gpm


MUD:

SBM	8.5 – 8.8 ppg

LITHOLOGY:
Claystone, Siltstone, Sandstone, Coal

DRILLING SUMMARY:
NB5 was made up and run in the hole, the MWD was shallow tested before running in continued, filling the pipe every 30 stands. The assembly was pulled out of hole before drilling any formation due to MWD tool failure (1.83hrs circtime/220gpm). The assembly was re-run with a new MWD tool. The MWD tool was shallow tested before running in continued without incident to bottom. Drilling proceeded from 2903m with several slides required to maintain azimuth. At 3155m a rig service was carried out before drilling continued to 3182m. Bottoms up was circulated and a 17 stand wiper trip carried out. The bit was run back in the hole without incident and the last stand reamed to bottom. Once drilling had resumed, 5bbl sweeps were pumped at regular intervals. New hole was drilled to 3296m where after drilling a 1m coal stringer tight hole problems were encountered. The pipe was worked and after reaming and pumping a slug the assembly was pulled in order to remove the motor and MWD tool.

BHA No. 5 215.87 m



Bit Run No. 5 Summary

BIT No.:	NB6
BIT SIZE:	6.0"
BIT TYPE:	Reed DSX413M-A2
S/N:	113215
JETS:	4x15
DEPTH IN:	3296 m
DEPTH OUT:	3370 m
DRILLED:	74 m
HOURS:	8.9 hr
AVG ROP:	8.3 m/hr
TBR:	44k rev
ROT. HRS:	11.9 hr
API CONDITION	1-1-NO-A-X-I-NO-TD

DRILLING PARAMETERS:


WOB:	2 - 13 klb
RPM:	33 - 99
TORQUE:	3.64 – 8.50 kft lb
PRESSURE:	1445 - 1935 psi
FLOW IN:	180 - 205 gpm

MUD:
SBM 8.8 ppg

LITHOLOGY:
Claystone

DRILLING SUMMARY:
NB6 was made up and run in the hole, filling the pipe every 25 stands, the last 3 joints were washed down to tag bottom. Bottoms up was circulated and a 5.17% trip gas recorded. New hole was drilled with 2 to 13klb on the bit. At 3327m a 5bbl sweep was pumped. Drilling continued to TD at 3370m without incident Bottoms up was circulated, a 15bbl low vis sweep pumped, followed by a 15bbl high vis sweep. A four stand wiper trip was then carried out, once the bit had been run back in, the hole was circulated clean and a 10bbl pill spotted on the bottom before pulling five stands wet, pumping a slug and continuing to pull to surface.

BHA No. 6 224.33 m



2.3 Casing & Cementing
20 October 2005

Note: BHI not online until 8.5" Hole Section

HOLE: SIZE: 8 1/2"
DEPTH: 2403m

CASING: 1 x Shoe Joint
1 x Float Collar Joint
204 Joints


OD	7"
ID	6.184"
Weight	29 lb/ft
Grade	L-80
Shoe Depth	2395m

CEMENT DETAIL:

Lead
TYPE: Class A
VOLUME: 88 bbl
200 sx
WEIGHT: 11.8 ppg
MIXSOLUTION: 5.15 gal/sx
YIELD: 1.17 cu-ft/sx (surface)

Tail
TYPE: Class A
VOLUME: 178 bbl
850 sx
WEIGHT: 15.6 ppg
MIXSOLUTION: 5.65 gal/sx
YIELD: 5.65 cu-ft/sx (surface)

REMARKS:
204 joints of 7" casing were run in the hole open ended to reduce losses. Losses during the trip in amounted to 60bbl. A Circ Swedge was made up on the last joint, however tight hole was encountered at 2397m. While circulating, the pipe was worked in an attempt to work it free without success. The Circ Swedge was removed with difficulty and the cement head rigged up. Howco were lined up and the surface lines were pressure tested to 4000psi. After pumping a 38bbl water spacer the bottom plug was dropped, this was followed by 26bbl of water. 88bbl of 11.8ppg Lead cement slurry was pumped, followed by 178bbl of 15.6ppg tail. After dropping the top plug the cement was displaced with 20bbl of water and 280bbl synthetic mud. The plugs were bumped with 2200psi maintained for 10 minutes.



9th November 2005


HOLE: SIZE: 6.0”
DEPTH: 3370m

LINER: N/A, Cement plug job

CEMENT DETAIL:

TYPE:	Class G	
VOLUME:	21.3 bbl	
	93 sx	
WEIGHT:	17.3 ppg	
MIXSOLUTION:	29.6 gal/sx	
YIELD:	0.98 cu-ft/sx (surface)	
ADDITIVES:	SCR/100L	0.6gal/sx
	NF-6	6.5gal/10bbl
	CFR-3	0.5%

REMARKS:
A mule shoe and tubing were run in the hole on 3.5” drillpipe to 2526m. The hole was circulated clean and the mud conditioned prior to performing the cementing job. A 30bbl spacer was pumped, followed by 21.3bbls of 17.3ppg cement and a 7bbl spacer. The mule shoe was pulled up to 2380m where bottoms up was circulated. There were no losses noted during cementing.



SECTION 3

FORMATION EVALUATION AND SAMPLING

3. FORMATION EVALUATION AND SAMPLING

3.1 FORMATION EVALUATION

Formation Evaluation of Ahuroa South B-1 commenced after the 9.625" casing shoe. Samples were collected in the 8.5" section (659m to 2403m) and also in the 6" section (2403m to 3370m). A Geological Society of America colour chart with Munsell colour chips was used for descriptions. The samples are described in the Mud Log using the standard abbreviations of Baker Hughes Inteq (N.Z. Ltd)

Flame Ionisation Total Gas and Chromatograph Detectors were used for gas analyses. During the course of the well, all gas equipment was calibrated regularly and spot samples were taken as required for more precise lithological evaluation.

3.2 SAMPLING

Three sets of 500g unwashed samples (Sets A, B, and C) and two sets of 100g washed samples (Sets D and E) were taken while drilling. An additional set of 500g unwashed samples (set F) was also taken (from 3200m to 3370m) for palaeontological analysis. The following intervals were sampled:

Sets A, B, C, D, and E:

10m interval from 660m to 2720m
5m interval from 2720m to 2920m
10m interval from 2920m to 2960m
5m interval from 2960m to 3370m (T.D.)

Set F:

5m intervals from 3200m to 3370m (T.D.)

Cuttings sample distribution is as follows:

Swift Energy New Zealand Ltd
1 set of Washed Cuttings samples (Set E)
1 set of Unwashed Cuttings samples (Set C)

Crown Minerals
1 set of Washed Cuttings samples (Set D)
2 sets of Unwashed Cuttings samples (Sets A & B)

Institute of Geological and Nuclear Sciences
1 set of unwashed Cuttings samples (Set F)

3.3 GEOLOGY AND SHOWS

The lithologies intersected in Ahuroa South B-1 are summarized below. All depths are in mAHRT unless otherwise stated. For more detailed descriptions, see Appendix 1, Formation Evaluation Log.

The formation tops were picked on the basis of drilling data and samples.

Ahuroa South B-1 was drilled with KCl water based mud from 653m to 2403m then with 80% SBM from 2403m to 3370m TD.

URENUI FORMATION: **653m – 1200m (653m – 1176m TVD)**

The Urenui Formation was predominantly Claystone with Siltstone, Sandstone and Limestone beds.

CLAYSTONE: The Claystone was greenish grey to dark greenish grey, light bluish grey, medium grey and olive grey. The cuttings were predominantly very soft to soft, although they ranged from very soft to firm. They were largely amorphous to blocky. The Claystone was generally non calcareous but was slightly to very calcareous in parts. Accessories included a trace to minor presence of shell fragments in parts, trace to common very fine lower to fine upper quartz sand grains in parts, and minor to common glauconite pellets. This Claystone had an arenaceous nature in parts.

SILTSTONE: The Siltstone was olive grey in colour. The cuttings were soft and were amorphous to sub-blocky. The Siltstone was non calcareous and graded to Sandstone.

SANDSTONE: The Sandstone was mainly unconsolidated, transparent to translucent, quartz grains, with aggregates that were predominantly coloured light olive grey to greenish grey and medium bluish grey in parts. The aggregates were mostly firm to hard, although they ranged from soft to hard. The grain size ranged from very fine lower to medium lower, predominantly very fine upper to fine upper. They were sub-angular to sub-rounded in shape, and were moderately to well sorted. The Sandstone had an argillaceous cement in some parts and calcite cement in others, and was moderately to very calcareous in parts. Accessories included minor to common levels of glauconite, traces of shell fragments, and traces of mica. The Sandstone had poor inferred porosity.

LIMESTONE: The Limestone was predominantly white to light grey. The cuttings were firm to hard and sub-blocky in shape. The Limestone was arenaceous and the grains were very fine upper to fine lower in size. There was a minor component of shell fragments. The Limestone graded to Sandstone.

Table 1.1 Summary of ROP statistics for the Urenui:

ROP m/hr		
Min.	Max.	Avg.
0.93	98.49	37.30

Total gas ranged from: 0.00%-0.28%.

No significant Gas Peaks were observed.

MT MESSENGER FORMATION: **1200m-1911m (1176m-1845m TVD)**

The Mt Messenger Formation was predominantly Claystone inter-bedded with Sandstone, Siltstone and Limestone.

CLAYSTONE: The Claystone was predominantly light olive grey to olive grey, though it was greenish grey to dark greenish grey, medium bluish grey, and medium dark grey in parts. It was very soft to firm, and the cuttings were sub-blocky to blocky in form. There was an arenaceous component to the Claystone, with traces of quartz sand grains ranging in size from very fine lower to very fine upper. The Claystone was slightly to very calcareous in parts and graded to Siltstone.

FLUORESCENCE: in Claystone at 1410m, 10% yellowish white direct fluorescence, slow blooming cut fluorescence, poor show.

FLUORESCENCE: in Claystone at 1540-1560m, 5% yellowish white direct fluorescence, slow blooming bluish white cut fluorescence, thick blue residue ring.

TRACE FLUORESCENCE: in Claystone at 1590-1610m, yellowish white direct fluorescence, no cut fluorescence.

FLUORESCENCE: in Claystone at 1610-1620m, 5% yellowish white direct fluorescence, very slow blooming bluish white cut fluorescence, trace residue ring.

FLUORESCENCE: in Claystone at 1637-1640m, trace yellowish white direct fluorescence, no cut fluorescence.

FLUORESCENCE: in Claystone at 1650-1680m, trace yellowish white direct fluorescence, no cut fluorescence.

SILTSTONE: The colour of the Siltstone in this formation was greenish grey to dark greenish grey, and light olive grey to olive black. The cuttings were firm to hard and sub-blocky to blocky in form. The Siltstone was moderately to very calcareous and graded to Claystone.

SANDSTONE: The Sandstone was predominantly unconsolidated, transparent to translucent Quartz, with light to dark grey aggregates. The aggregates were firm to hard and the grains ranged in size from very fine lower to coarse lower, though were predominantly fine upper to medium upper. The grains were sub-angular to sub-rounded and ranged from poorly to well sorted. The aggregates were calcite cemented. The Sandstone had no visible porosity, however had moderate inferred porosity in parts determined by the size, shape and rounding of the unconsolidated grains.

LIMESTONE: The colour of the Limestone was light olive grey. The cuttings were firm to hard and were sub-blocky in shape. There was an arenaceous component to the limestone. The Limestone graded to Claystone.

Table 2.1 Summary of ROP statistics for the Mount Messenger formation:

ROP m/hr		
Min.	Max.	Avg.
0.87	47.73	17.84

Total gas ranged from: 0.04%-0.33%. Background gas 0.05%

Table 2.2 Gas peaks observed:

Depth M	Total Gas %	C1 %	C2 %	C3 %	IC4 %	NC4 %	IC5 %	NC5 %
1414	0.074	0.053	-	-	-	-	-	-
1421	0.103	0.087	-	-	-	-	-	-

TIKORANGI FORMATION: 1911-2010m (1845m-1939m TVD)

The Tikorangi Formation was primarily Limestone with Siltstone interbeds.

LIMESTONE: The Limestone ranged in colour from white to light grey and olive grey. The Limestone was arenaceous in nature. The cuttings were generally very soft to firm, but were hard in parts and were sub-blocky to blocky in form. Traces of pyrite were present at the top of the formation. The Limestone graded to Siltstone, and also graded to Claystone at the top of the section.

SILTSTONE: The Siltstone ranged in colour from medium grey, medium bluish grey, olive grey, and greenish grey to dark greenish grey. The cuttings were soft to hard and were sub-blocky to blocky in form. The Siltstone was moderately to very calcareous. There were minor amounts of carbonaceous material in parts. It graded to Claystone and Limestone in parts.

Table 3.1 Summary of ROP statistics for the Tikorangi Formation:

ROP m/hr		
Min.	Max.	Avg.
3.79	18.13	11.06

Total gas ranged from: 0.05%-0.10%.

No significant gas peaks were observed.

OTARAOA FORMATION: 2010m-2710m (1939m-2598m TVD)

For the purpose of this of this log the Otaraoa Formation has been split into three parts; thus enabling a distinct description of the Tariki Sandstone Member. These parts are: Upper Otaraoa, Tariki Member, and Lower Otaraoa.

UPPER OTARAOA: 2010m-2710m (1939m-2598m TVD)

The Upper Otaraoa Formation consists of Siltstone at the top of the section becoming mainly Claystone towards the base of the section, with Limestone inter-beds.

CLAYSTONE: The Claystone was light olive grey to olive black, dark greenish grey and medium grey. The cuttings ranged from soft to hard, though predominantly soft to firm. They were sub-blocky to blocky in shape. There was a trace to common component of calcite veins, and the Claystone was slightly to very calcareous, though predominantly moderately calcareous. The Claystone graded to Siltstone in parts.

SILTSTONE: The colour of the Siltstone was predominantly light olive grey to olive grey, although it was greenish grey to dark greenish grey and bluish grey in parts. The cuttings were soft to firm although they were hard in parts. They were sub-blocky to blocky in form. The Siltstone was argillaceous in parts, and also had a minor component of carbonaceous material in parts. The Siltstone was moderately to very calcareous throughout the section, however it gradually became less calcareous towards the base of the section. The Siltstone graded to Claystone and Limestone in parts.

LIMESTONE: The Limestone was olive grey to medium grey in colour. The cuttings were very soft to hard and were sub-blocky to blocky in form. The Limestone was arenaceous and graded to Siltstone.

Table 4.1 Summary of ROP statistics for the Upper Otaraoa (8.5" section):

ROP m/hr		
Min.	Max.	Avg.
3.65	34.76	19.67

Table 4.2 Summary of ROP statistics for the Upper Otaraoa (6" section)

ROP m/hr		
Min.	Max.	Avg.
0.68	29.30	15.87

Total gas ranged from: 0.04%-0.34%.

No significant gas peaks were observed.

TARIKI MEMBER: **2710m-3130m (2598m-2992m TVD)**

The Tariki Formation was Sandstone with Siltstone, Claystone and Limestone beds.

SANDSTONE: The Sandstone was predominantly transparent to translucent quartz, with some white to dark grey, and yellowish grey aggregates. It was mostly unconsolidated, with a minor amount of soft to very hard aggregates. The grains ranged in size from very fine lower to coarse upper, and were sub-angular to rounded in shape. The grains were predominantly moderately to well sorted, although there were some poorly sorted examples. The cement was calcareous and there were trace amounts of glauconite, coal and carbonaceous material present in parts. Rock flour was also common in the cuttings. The Sandstone had poor to good inferred porosity.

SILTSTONE: The Siltstone was olive grey to olive black, and light to dark grey in parts. The cuttings were firm and sub-blocky to blocky in shape. The Siltstone had a slightly to moderately calcareous character and graded to Claystone in parts.

CLAYSTONE: The Claystone was light olive grey to olive grey, and was dark grey in parts. The cuttings ranged from very soft to hard although were mainly soft to firm. Cuttings were predominantly sub-blocky to blocky in form, although amorphous in parts. The Claystone ranged from non calcareous to moderately calcareous and graded to Siltstone in parts.

LIMESTONE: The Limestone was white to light grey. The cuttings ranged from soft to firm and were sub-blocky to blocky. The Limestone was arenaceous in parts, and had minor to common amounts of very fine upper to medium upper quartz grains. The Limestone graded to very calcareous Sandstone.

Table 5.1 Summary of ROP statistics for the Tariki Member:

ROP m/hr		
Min.	Max.	Avg.
0.83	34.79	6.53

Total gas ranged from: 0.10% - 0.85%. Background gas: 0.21%-0.40%.

Table 5.2 Gas peaks observed:

Depth M	Total Gas %	C1 %	C2 %	C3 %	IC4 %	NC4 %	IC5 %	NC5 %
2710	0.25	0.05	0.01	0.003	0.005	0.009	-	-
2718	0.44	0.26	0.02	0.009	0.005	0.006	-	-
2804	0.43	0.06	0.01	0.004	0.001	0.002	-	-
2809	0.55	0.18	0.02	0.009	0.002	0.003	-	-
2822	0.44	0.18	0.01	0.009	0.003	0.006	-	-
2845	0.67	0.28	0.03	0.014	0.003	0.002	-	-
2871	0.49	0.27	0.02	0.010	0.004	0.002	-	-
2918	0.51	0.25	0.02	0.011	0.004	0.005	0.002	0.002
2930	0.68	0.39	0.03	0.014	0.004	0.004	0.002	-
2935	0.77	0.45	0.05	0.023	0.005	0.006	0.002	-
2948	0.55	0.34	0.02	0.011	0.004	0.005	0.002	-
2959	0.72	0.42	0.03	0.015	0.004	0.003	0.001	-
2982	0.58	0.39	0.03	0.010	-	-	-	-
3038	0.55	0.28	0.02	0.012	0.003	0.003	0.001	-
3058	0.61	0.43	-	0.016	0.005	0.005	0.003	-
3063	0.63	0.28	0.03	0.013	0.005	0.009	0.005	-
3065	0.66	0.30	0.03	0.015	0.004	0.006	0.002	0.001
3074	0.85	0.45	0.04	0.022	0.004	0.005	0.001	0.001

LOWER OTARAOA: **3130m-3226m (2992m-3082m TVD)**

The Lower Otaraoa consisted of interbedded Claystone and Siltstone with minor amounts of Sandstone.

CLAYSTONE: The Claystone was light olive grey to olive grey in colour. The cuttings were soft to firm, with occasional very hard cuttings in parts. Their form was sub-blocky to blocky. The Claystone was slightly to moderately calcareous, and graded to Limestone at the top of the section. The Claystone also graded to Siltstone in parts.

SILTSTONE: The Siltstone was coloured dark greenish grey to greenish black. The cuttings ranged from soft to firm and were sub-blocky to blocky in form. Glauconite was common in the Siltstone. It was very calcareous, and graded to Claystone.

SANDSTONE: The Sandstone was loose transparent to translucent Quartz. The grains ranged in size from very fine lower to fine upper, were sub rounded and were moderately sorted. There was fair inferred porosity in the Sandstone.

Table 6.1 Summary of ROP statistics for the Lower Otaraoa:

ROP m/hr		
Min.	Max.	Avg.
0.45	8.31	2.85

Total gas ranged from: 0.16%-0.47%.

No significant Gas Peaks were observed.

MCKEE FORMATION: 3226m-3245m (3082m-3100m TVD)

The McKee Formation consisted of interbedded Sandstone and Siltstone.

SANDSTONE: The Sandstone was light grey to yellow grey friable aggregates. The grains ranged in size from very fine lower to fine lower. The grains were sub-angular to sub-rounded in shape and moderately well sorted. There was abundant silty matrix present, and traces of loose transparent to translucent quartz. There was poor visible porosity observed.

SILTSTONE: The Siltstone was mostly white to yellowish grey, but was also dark greenish grey to greenish black. The cuttings were sub-blocky to blocky in shape and soft to firm. Glauconite was common with the lighter Siltstone. The darker Siltstone was very calcareous, and the lighter was slightly calcareous in parts. The Siltstone graded to Sandstone.

Table 7.1 Summary of ROP statistics for the McKee Formation:

ROP m/hr		
Min.	Max.	Avg.
2.20	13.54	6.54

Total gas ranged from: 0.24%-0.27%.

No significant Gas peaks were observed.

MANGAHEWA FORMATION: 3245m-3320 (3100m-3171m TVD)

The Mangahewa formation is comprised primarily of Claystone, interbedded with minor layers of Siltstone. Sandstone and Coal seams. The lower contact of this formation is marked by the Ahuroa Thrust system.

CLAYSTONE: The Claystone varied in colour from brownish grey to brownish black and light olive grey to olive grey. The cuttings were firm to moderately hard and were sub-blocky to blocky in form. The Claystone was non-calcareous to moderately calcareous, becoming more calcareous towards the base of the section. The Claystone graded to Siltstone in parts.

SILTSTONE: The Siltstone was light olive grey to brownish grey and brownish black. The cuttings were firm to moderately hard and sub-fissile to blocky in shape. The Siltstone was very carbonaceous in parts and had coal laminae. There were also traces of very fine quartz grains in parts. The siltstone graded to Claystone.

SANDSTONE: The Sandstone was light grey to yellow grey aggregates. The aggregates were friable. The grain size ranged from very fine lower to fine lower. The grains were sub-angular to rounded and moderately sorted. Silty matrix was abundant in the Sandstone. The Sandstone had poor visible porosity.

COAL SEAM: The coal was black in colour and brittle to firm. The cuttings were sub-fissile to blocky in structure and had a hackly fracture pattern. The Coal had an earthy to vitreous lustre and was argillaceous in part.

Table 8.1 Summary of ROP statistics for the Mangahewa Formation:

ROP m/hr		
Min.	Max.	Avg.
1.20	12.28	6.05

Total gas ranged from: 0.25%-0.90%. Background gas: 0.30%-0.55%.

Table 8.2 Gas peaks observed:

Depth M	Total Gas %	C1 %	C2 %	C3 %	IC4 %	NC4 %	IC5 %	NC5 %
3257	0.85	0.53	0.03	0.012	0.003	0.003	0.001	-
3262	0.93	0.55	0.033	0.015	0.003	0.002	-	-
3296	0.83	0.59	0.03	0.015	0.003	0.002	-	-
3297	0.62	0.29	0.02	0.012	0.004	0.002	-	-

MANGANUI FORMATION: **3320m-3370m TD (3171m-3219m TVD)**

The section of the Manganui Formation observed (the lower contact was not reached) was entirely Claystone.

CLAYSTONE: the Claystone was olive grey to olive black at the top of the section, grading to dark grey to olive black by the bottom of the section. The cuttings were firm to moderately hard and sub-blocky to blocky in structure. There were traces of calcite veins in parts. The Claystone was slightly calcareous in at the top of the section and was non calcareous by the bottom.

Table 9.1 Summary of ROP statistics for the Manganui Formation:

ROP m/hr		
Min.	Max.	Avg.
6.58	18.23	10.77

Total gas ranged from: 0.27%-0.34%.

No significant Gas Peaks were observed.

TABLES

BAKER HUGHES INTEQ

LOCATION / WELL NAME
PEP 38719 Ahuroa South B-1

OPERATOR
Swift Energy New Zealand Ltd

CONTRACTOR / RIG
Parker Drilling / Rig 252

Rotary Type

RKB - Rotary Kelly Bushing

Mud Type

WBM /SBM

Geology

Sd : Sand
Sst : Sandstone
Lst : Limestone
Slt : Silt
Sltst : Siltstone
Cl : Clay
Clst:Claystone
Volc: Volcanics
Sh : Shale
Dol : Dolomite
Ms : Metasediment

Dull Grade & Reason Pulled

A - All Rows
BC - Broken Cone
BHA - Bottomhole Assembly
BU - Balled Up Bit
CM - Condition Mud
CP - Casing Point
DMF - Down Hole Motor Failure
DP - Drill Plug
DSF - String Failiure
DTF - Down Hole Tool Failure
E - Seals Effective
F - Seals Failed
FC - Flat Crested Wear
G - Gauge Rows
H - Heel
HP - Hole Problems
HR - Hours on Bit
I - In Gauge
PR - Penetration rate
RG - Rounded Gauge
SD - Shirt Tail Damage
TD - Total / Csg Depth
TQ - Torque
TW - Twist Off
WC - Weather Condition
WT - Worn Teeth
RO - Ring Out
JD - Junk Damage
LIH - Left In Hole
LOG - Run Logs
LT - Lost Teeth
M - Middle Rows
MH - Mid Heel
NO - No Dull Wear
O - Out of Gauge
PP - Pump Pressure
BT - Broken Teeth

BHA No.	Bit No.	Vendor	Type	Serial Number	Size (in)	IADC	Nozzles (x 1/32")	Depth In	Depth Out	Drilled m	Drilled hr	ROP (m/hr)	WOB (klb)	RPM (at bit)	TORQ. (kftlb)	TBR (krev)	RT (hr)	Pump Pr (psi)	Flow Rate (gpm)	Dev (deg)	Geology Formation	W ppg	Mud Type	PV/YP	IADC Dull Grade (G in 1/16") I	O	D	L	B	G	O	R
12.25" Hole Section: 50m - 659m. Note: BHI not online during the 12.25" Hole section																																
	NB1				12 1/4	-		50	659	609													WBM									
8.5" Hole Section: 659m - 2403m.																																
1	NB3	REED	DSX 104HG	JT8871	8 1/2	-	5 x 14	659	2399	1740	113.0	15.4	1-25	79-250	0-18.9	1218.1	71.9	640-2345	170-635	20.0	Clst,Sst,Sltst,Lst	9.3	WBM	14/26								
2	RR3	REED	DSX 104HG	JT8871	8 1/2	-	5 x 14	2399	2403	4	0.3	13.3	5-6	90-100	8.0-9.0	3.0	0.3	1400-1415	505-510	20.0	Sltst,Clst	9.3	WBM	15/24	1	3	CT	T	X	1	WT	CP
6" Hole Section: 2403m - 3370m.																																
4	NB4	REED	DSX516M-B1	113097	6	-	5 x 13	2403	2903	500	93.5	5.3	1-15	105-220	0-9.9	890.1	117.5	1955-3125	175-425	19.2	Clst,Sst,Sltst	8.5-8.7	SBM	18/25	3	6	WT	S	X	I	CT	PR
5	NB5	REED	DSX516M-B1	113096	6	-	3x13 2x15	2903	3296	393	123.8	3.2	1-14	112-225	0-9.1	1439.0	150.1	1410-3100	195-245	19.5	Clst,Sst,Sltst,Coal	8.5-8.8	SBM	29/18	2	6	WT	S	X	1	WT	FM
6	NB6	REED	DSX413M-A2	113215	6	-	4x15	3296	3370	74	8.9	8.3	2-13	33-90	3.6-8.5	44.0	11.9	1445-1935	180-205	19.5	Clst	8.8	SBM	30/20	1	1	NO	A	X	I	NO	TD

BAKER HUGHES INTEQ

OPERATOR	WELL NAME	LOCATION	CONTRACTOR	RIG
SWIFT ENERGY NEW ZEALAND LTD	AHUROA SOUTH B-1	PEP 38719	Parker Drilling Company	Parker Rig 252

Drillstring Abbreviations 0

N	Normal	**T**	Turbine	**P**	Positive Displacement Motor
M	MWD	**C**	Core		

Hydraulics Models

Power Law Model used for drilling with Mud

Bingham Model used for coring and drilling with sea water

Bit No.	Depth (m)	Hole Size in	Calc'd Hole Size in	JETS x 1/32"	Drill String Type	Mud Density ppg	Mud Type	PV / YP	Flow Rate gpm	ECD shoe ppg	ECD TD ppg	Annular Velocities DP Max Dia m/min	Annular Velocities DP OH m/min	Annular Velocities DC OH m/min	Jet Vel m/sec	HHP (bit) hp	HSI hp/sq in	Impact Force lbf	Bit Pressure Loss psi	% Bit Loss	Theoretical Pressure Loss psi	Actual Pressure Loss psi
8½" HOLE SECTION				**659-2403m (Note: BHI not online for 12.25" Hole Section)**																		
NB3	2399	8.5	8.5	5x14	M	9.30	KCl Polymer	14/26	445	9.62	9.87	46.0	64.0	92.0	62.3	67.5	1.21	7.2	260	12.0	2172	1785
RR3	2403	8.5	8.5	5x14	M	9.30	KCl Polymer	15/24	510	9.64	9.87	53.0	73.0	127.0	71.4	101.8	1.82	9.4	342	23.6	1447	1415
6" HOLE SECTION				**2403-3470m**																		
NB4	2903	6	6	5x13	M	8.65	SBM	18/25	200	10.35	10.56	50.0	63.0	111.0	32.5	8.5	0.31	3.5	73	3.3	2181	2715
NB5	3296	6	6	3X13,2X15	M	8.80	SBM	2918	200	9.46	9.67	50.0	63.0	111.0	28.7	6.1	0.22	2.8	52	2.1	2524	2415
NB6	3370	6	6	4x15	N	8.80	SBM	30/20	200	9.53	9.75	50.0	63.0	111.0	30.5	6.9	0.25	3.0	59	2.8	2134	1905


BAKER HUGHES INTEQ

TIME / DEPTH PLOT

SWIFT ENERGY NEW ZEALAND LTD

Ahuroa South B-1

SWIFT ENERGY COMPANY



APPENDICES

FORMATION EVALUATION LOG

1:500

DRILLING DATA PLOT

1:2500

GAS RATIO PLOT

1:500

END OF WELL REPORT

SWIFT ENERGY NEW ZEALAND LTD

AHUROA SOUTH B-1 ST-1

11th November 2005 – 27th November 2005

By

BAKER HUGHES INTEQ

The information, interpretations, recommendations, or opinions contained herein are advisory only and may be rejected. Consultant does not warrant their accuracy or correctness. Nothing contained herein shall be deemed to be inconsistent with, nor expand, modify or alter Consultants obligation of performance as provided for in a written agreement between the parties, or, if none, in Consultant's most recent price list.

Ahuroa South B-1 ST-1

End of Well Report

SECTION 1 Well Data Summary

SECTION 2 Drilling and Engineering
- 2.1 Well Overview
- 2.2 Bit Run Summaries
- 2.3 Casing and Cementing

SECTION 3 Formation Evaluations and Sampling
- 3.1 Formation Evaluation
- 3.2 Sampling Summary
- 3.3 Geology and Shows

TABLES
- Bit Table
- Hydraulics Table
- Time Depth Curve

APPENDICES

Formation Evaluation Log	1: 500
Drilling Data Plot	1: 2500
Gas Ratio Plot	1: 500

CD Contents

ASCII

Ahuroa South B-1 ST-1_Comments.xls	Excel file of Comments on the Mudlog
Ahuroa South B-1 ST-1_Descriptions.xls	Excel file of Descriptions on the Mudlog
Ahuroa South B-1 ST-1_Drill_Gas_Ascii.xls	Excel file of Drilling and Gas Data
Ahuroa South B-1 ST-1_InterpretedLithAscii.xls	Excel file of Interpreted Lithology Data
Ahuroa South B-1 ST-1_PercentLithAscii.xls	Excel file of Cuttings Percentage Lithology Data

FIVE SECOND DATA Five Second Data in Excel format

FWR

Ahuroa South B-1ST-1_End_of_Well_Report.pdf PDF file of End of Well Report

LOGS

Ahuroa South B-1ST-1_Drilling_Data_Plot.pdf	PDF file of Drilling Data Plot
Ahuroa South B-1 ST-1_Gas_Ratio_Plot.pdf	PDF file of Gas Ratio Plot
Ahuroa South B-1 ST-1_Mudlog.pdf	PDF file of Mudlog

MORNING REPORTS Directory of Morning Reports

SECTION 1

WELL DATA SUMMARY

1. WELL DATA SUMMARY

Rig Name:	Parker Drilling Company Rig 252
Rig Type:	Ingersol Rand Truck Mounted Land Rig
Drilling Contractor:	Parker Drilling Company
Drilling Datum:	Rotary Kelly Bushing (RKB)
Rotary Kelly Bushing Elevation:	201.41m AMSL
Ground Level Elevation:	196.20m AMSL
New Zealand Map Grid (Surface):	2625724.00 mE 6214665.80 mN
New Zealand Geodetic Datum (NZGD 1949)	Lat: 39° 16' 01.20" South Long: 174° 20' 25.438" East
Permit No:	PEP 38719
Well Type:	Exploration
Kick-Off Date:	11th November 2005
Total Depth:	3085m (2979.5m TVD RKB)
TD Date:	24th November 2005
Primary Objective:	McKee Sands
Secondary Objectives:	Tariki Sands
Well Status:	Plugged and Abandoned (P & A)
Baker Hughes INTEQ Crew:	G. Ammundsen, R. Farmer, R. Villarosa, R. Rolfe G. Lindsay, D. Barrel, B Berger

SECTION 2

DRILLING & ENGINEERING

2. DRILLING AND ENGINEERING

2.1 WELL OVERVIEW

After setting a cement plug in Ahuroa South B-1 from 2526 to 2356m and dressing the cement to 2400m, Ahuroa South B-1 ST-1 was kicked off at 18:00hrs on the 11th of November 2005 and drilled to a total depth of 3085m in three bit runs. 8.5ppg – 8.7ppg synthetic based mud system was used to drill Ahuroa South B-1 ST-1. All depths in this report are in meters unless otherwise specified, measured along hole below the Rotary Kelly Bushing (BRKB).

6" Hole Section: This section was drilled with four bits in four bit runs.

NB8 a new Smith XR+ rock bit was run in to dress the top of the cement plug and kicked off the sidetrack at 2400m, using synthetic based mud initially weighed at 8.5ppg. At 2433m depth however, the bit was pulled due to poor penetration rates and inaccurate MWD surveys (it was determined that the directional probe high side correction had been entered incorrectly).

NB9, a Reed PDC bit was made up on the same steerable assembly as previous. Drilling the 6" sidetrack hole continued rotating and sliding, steering the bit through the desired wellpath. Hi-Vis sweeps were pumped and circulated at regular intervals for borehole cleaning. A six stand wiper trip was conducted at 2742m, with no overpull or drag recorded, indicating the hole to be in good condition. The mud weight was increased to 8.7ppg as the background gas and volume of liberated gases increased. **NB9** was pulled at 2874m in order to change the bit.

NB10, a 6" Smith GeoDiamond bit was picked up along with a new mudmotor and MWD tool. The bit was run in to 2414m where the bit took weight. The Kelly was picked up and the minor tight spots encountered were worked through to 2430m. The trip in continued without incident. Drilling continued with regular 5bbl Hi-Vis sweeps pumped. At 2993m the drillstring became momentarily stuck prior to making a pipe connection. The pipe was able to be worked free (20klbs overpull recorded). After adding Barablok to the system, the bit was slowly pulled back to 2986m and then reamed back to 2993m. Drilling continued from 2993m with a short wiper trip carried out from 3031m to 2868m. Ahuroa South B-1 ST-1 reached TD at 3085m. After conducting a wiper trip and ensuring that the hole was clean, the bit was pulled to surface.

Schlumberger were rigged up and the following Wireline logs run;

1. PEX – AIT – BHC
2. UBI

Preparations were then made to plug and abandon the well. A mule shoe and 15 joints of 2 7/8" tubing were picked up and run in hole to 2430m. A balance cement plug was then set from 2445m to 2345m. Vause Wireline Services was rigged up and CBL log was conducted from 1500m to 500m. 3 1/2" drillpipe were then run in to tag the top of the cement without success.

A second cement job with ESZV packer assembly was planned. 21 joints of 2 7/8" tubing were picked up and made up with ESZV packer assembly. The packer was run in the hole and set at 2365m. HowCo were rigged up and pumped 12bbls of 15.8ppg Class G cement slurry. After displacing the cement with SBM, the ESZV was engaged (sting) and 6bbls of cement pumped below it. The 2 7/8" tubing was then pulled back to 2235m. The SBM in the hole was then displaced to brine.

The wear bushing was retrieved and a test plug installed in the tubing spool. Rig down of BOP followed After removing the BOP, the test plug was pulled out and the appropriate adapter flange and master valve installed. The casing and wellhead was pressure tested to 3000psi. Preparations were then made to move the rig.

2.2 BIT RUN SUMMARIES
6" PHASE: 11th Nov – 13th Nov 2005

Bit Run No. 1 Summary

BIT No.:	NB8
BIT SIZE:	6"
BIT TYPE:	Smith XR+
S/N:	PC7092
JETS:	3 x 18
DEPTH IN:	2400 m
DEPTH OUT:	2433 m
DRILLED:	33 meters
HOURS:	31.6 hr
AVG ROP:	1 m/hr
TBR:	241 k rev
ROT. HRS:	38.7 hrs
API CONDITION	not graded

DRILLING PARAMETERS:


WOB:	0.6 - 11.2 klb
BIT RPM:	112 - 212
TORQUE:	0 – 8.7 kft lb
PRESSURE:	1933 – 2956 psi
FLOW IN:	200 - 248 gpm

MUD:

SBM	8.5 – 8.55 ppg

LITHOLOGY:
Claystone, Siltstone

DRILLING SUMMARY:
NB8 was made up on a directional assembly and run in the hole. After a failed test of the MWD tool, the bit was pulled to surface and the MWD replaced. The bit was then run in hole, with the last single washed to bottom. Ahuroa south B-1 ST1 was kicked off at 2400m, drilling proceeded to 2433m where it was decided to pull out of hole due to the poor penetration rates and the inaccurate surveys caused by the incorrect entry of the directional probe high side correction. There was no significant gas recorded whilst drilling.



Bit Run No. 2 Summary

BIT No.:	NB9
BIT SIZE:	6"
BIT TYPE:	Reed DSX519S-A3
S/N:	211111
JETS:	5x14
DEPTH IN:	2433 m
DEPTH OUT:	2874 m
DRILLED:	441 meters
HOURS:	100.2 hrs
AVG ROP:	4.4 m/hr
TBR:	949k rev
ROT. HRS:	124.9 hrs
API CONDITION	3-4-WT-S-X-I-NO-PR

DRILLING PARAMETERS:

WOB:	1 - 12 klb
BIT RPM:	112 - 225
TORQUE:	0.0 – 8.0 kft-lb
PRESSURE:	1880 - 2850 psi
FLOW IN:	101 - 244 gpm


MUD:

SBM	8.5 - 8.7 ppg

LITHOLOGY:
Claystone, Sandstone, Siltstone

DRILLING SUMMARY:
NB9 was made up on the same assembly as previous and run in hole to just above the kick-off depth. The well was monitored on the trip tank (static) while the drilling line was slipped and cut. The bit was then run to bottom and drilling resumed, sliding and rotating as required. The mud weight was increased from 8.5ppg to 8.7ppg due to the slight increase in background gas. 5bbl Hi-Vis sweeps were pumped at regular intervals to aid hole cleaning. At 2742m a six stand wiper trip was carried out, the borehole was found to be in good condition with no overpull or drag encountered. The bit was run back to bottom and drilling continued with reducing penetration rates.
At 2874m, NB9 was pulled out after drilling 441m in 100.2 on-bottom drilling hours. The subsequent trip indicated good borehole condition, with no overpull encountered and correct pipe displacement recorded for the trip out.

BHA No. 12 217.90m



Bit Run No. 3 Summary

BIT No.:	NB10
BIT SIZE:	6.0"
BIT TYPE:	GEO M516LYPX
S/N:	JW3280
JETS:	1x16 1x15 3x13
DEPTH IN:	2874 m
DEPTH OUT:	3085 m
DRILLED:	211 meters
HOURS:	80.0 hrs
AVG ROP:	2.6 m/hr
TBR:	906k rev
ROT. HRS:	111.5 hr
API CONDITION	1-4-WT-S-X-1-WT-TD

DRILLING PARAMETERS:

WOB:	1 - 13 klb
BIT RPM:	109 - 209
TORQUE:	0.0 – 6.0 kft-lb
PRESSURE:	1139 - 2752 psi
FLOW IN:	129 - 214 gpm


MUD:

SBM	8.5 – 8.7 ppg

LITHOLOGY:
Claystone, Siltstone, Sandstone

DRILLING SUMMARY:
NB10 was made up on a new BHA with a new mudmotor and MWD tool. The bit was run in until above kick-off point where the drilling line was slipped and cut. The trip in continued with the bit encountering a tight spot from 2414m to 2430m which had to be worked through. The bit was run in without incident and the last single washed down to bottom. Driling proceeded from 2874m to 2993m where the drillstring became stuck momentarily prior to making a connection (coal interbeds earlier encountered around 2985m were the likely cause). After freeing the pipe, circulation was carried out with pipe rotation while adding Barablok to the active pits. A 10bbl Lo-Vis sweep was pumped followed by a 10bbl Hi-Vis sweep and circulated before drilling continued. Ahuroa South B-1 ST-1 reached TD at 3085m without intersecting major or significant hydrocarbon shows. NB10 drilled 211m with controlled parameters in 80 on-bottom drilling hours.

BHA No. 13 216.82m



2.3 Casing & Cementing

26th November 2005


HOLE SIZE: 6.0”
DEPTH: 3085m

LINER: N/A (Cement plug for Plugged & Abandon operation)

CEMENT DETAIL:

TYPE:	Class G	
VOLUME:	11.3 bbl	
	323 sx	
WEIGHT:	17.3 ppg	
MIXSOLUTION:	5.09 gal/sx	
YIELD:	1.16 cu-ft/sx (surface)	
ADDITIVES:	Latex 2000	1gal/sx
	Halad 322	1.0%
	HR-5	0.20%
	NF-6	0.05gal/sx
	Gas Con 469	0.08gal/sx
	Stabilizer 434c	0.2gal/sx

REMARKS:
A cement stinger made up of 2 7/8” mule shoe and 15 joints tubing was run on 3 1/2” drillpipe to 2430m. A balance cement plug was set from 2430m to 2345m. After circulating the hole clean, the cementing head was rigged up. A 10bbl spacer was pumped and the cement lines were pressure tested to 3000psi. A 20bbl spacer then pumped followed by 11bbls of cement slurry. The slurry was chased with 6bbls of spacer before displacing with 44bbls SBM. The stinger was pulled to 2283m where the well was circulated to 5024 strokes with the rig pumps before slugging the pipe and pulling out of hole.




26th November 2005

HOLE SIZE: 6.0”
DEPTH: 3085m

CEMENT DETAIL:

TYPE:	Class G	
VOLUME:	12 bbls	
	325 sx	
WEIGHT:	15.8 ppg	
MIXSOLUTION:	5.1gal/sx	
YIELD:	1.16 cu. ft/sx (surface)	
ADDITIVES:	Latex 2000	1gal/sx
	Halad 322	1.0%
	HR-5	0.20%
	NF-6	0.05gal/sx
	Gas Con 469	0.08gal/sx
	Stabilizer 434c	0.2gal/sx

REMARKS:
After a CBL log of the cased hole, drillpipes were run in an attempt to tag cement. The cement was not tagged. The drillpipe was pulled out of the hole and a second cement job carried out. A ESZV Packer assembly was made up to 2 7/8” tubings and run in hole on 3 1/2” drillpipe to 2365m where the packer was set. The Howco cementing unit was lined and after pumping a 5bbl spacer, surface lines were pressure tested to 3000psi. An 8bbl spacer was pumped, followed by 12bbl of 15.8ppg class G cement. The slurry was chased by a 1.3bbl spacer and displaced with 32.7bbls SBM. 6bbls of the cement slurry was pumped below the packer and displaced with 4.3bbls SBM. The cementing tubings were pulled to 2235m and the casing pressure tested. The hole was displaced to brine.



SECTION 3

FORMATION EVALUATION AND SAMPLES

3. FORMATION EVALUATION AND SAMPLING

3.1 FORMATION EVALUATION

Formation Evaluation of Ahuroa South B-1 ST-1 commenced from kick-off depth. Samples were collected 2400m to 3085m. A Geological Society of America colour chart with Munsell colour chips was used for descriptions. The samples are described in the Mud Log using the standard abbreviations of Baker Hughes Inteq (N.Z. Ltd). As required, spot samples were also taken for more precise lithological evaluation.

Flame Ionisation Total Gas and Chromatograph Detectors were used for gas analyses. During the course of the well, gas equipment was regularly calibrated.

3.2 SAMPLING

Three sets of 500g unwashed samples (Sets A, B, and C) and two sets of 100g washed samples (Sets D and E) were taken while drilling. An additional set of 500g unwashed samples (set F) were also taken (from 2970m to 3040m) for palaeontological analysis. The following intervals were sampled:

Sets A, B, C, D, and E:

10m interval from 2400m to 2670m
5m interval from 2670m to 2760m
10m interval from 2760m to 3000m
5m interval from 3000m to 3085m (T.D)

Set F:

10m intervals from 2970m to 2990m and 3030m to 3040m

Cuttings sample distribution is as follows:

Swift Energy New Zealand Ltd
1 set of Washed Cuttings samples (Set E)
1 set of Unwashed Cuttings samples (Set C)

Crown Minerals
1 set of Washed Cuttings samples (Set D)
2 sets of Unwashed Cuttings samples (Sets A & B)

Institute of Geological and Nuclear Sciences
1 set of unwashed Cuttings samples (Set F)

3.3 GEOLOGY AND SHOWS

The lithologies intersected in the sidetrack borehole Ahuroa South B-1 ST-1 are summarized below. For more detailed descriptions, see Appendix 1, Formation Evaluation Log.

The formation tops were picked on the basis of drilling data and samples.

Ahuroa South B-1 ST-1 was drilled with 8.5ppg to 8.7ppg synthetic based mud (SBM) from kick-off at 2400m to final depth at 3085m.

OTARAOA FORMATION: 2010m-2983m (1939m-2878m TVD)

For the purpose of this of this log the Otaraoa Formation has been split into two parts, enabling a distinct description of the Tariki Sandstone Member. These parts are; Upper Otaraoa, and the Tariki Member.

UPPER OTARAOA: 2010m-2665m (1939m-2598m TVD)

The Upper Otaraoa Formation consists of Siltstone at the top of the section becoming mainly Claystone towards the base of the section.

CLAYSTONE: The Claystone was light olive grey to olive black, brownish grey and medium grey were also commonly observed. The cuttings ranged from soft to hard, though predominantly soft to firm and were sub-blocky to blocky in shape. There was a trace to common component of calcite veins and the Claystone was slightly to very calcareous, though predominantly moderately calcareous. The Claystone graded to Siltstone in parts.

SILTSTONE: The colour of the Siltstone was predominantly light olive grey to olive grey, although it was greenish grey to dark greenish grey and bluish grey in parts. The cuttings were soft to firm though they were hard in parts and were sub-blocky to blocky in form. The Siltstone was argillaceous in parts and also had a minor component of carbonaceous material in parts. The Siltstone was moderately to very calcareous throughout the section, however it gradually became less calcareous towards the base of the section. On occasion the Siltstone graded to the above Claystone.

Table 4.2 Summary of ROP statistics for the Upper Otaraoa (6" section)

ROP m/hr		
Min.	Max.	Avg.
0.68	29.30	16.38

Total gas ranged from: 0.09%-0.34%.

No significant gas peaks were observed.

TARIKI MEMBER: 2665m-2983m (2563m-2878m TVD)

The Tariki Formation was Sandstone with Siltstone and Claystone inter beds.

SANDSTONE: The Sandstone was predominantly transparent to translucent quartz, with some white to dark grey, and yellowish grey aggregates. It was mostly unconsolidated, with a minor amount of soft to very hard aggregates. The grains ranged in size from very fine lower to coarse upper, and were sub-angular to rounded. The grains were predominantly moderately to well sorted, although there were some poorly sorted examples. The cement was calcareous and there were trace amounts of glauconite, coal and carbonaceous material present in parts. There was poor to good inferred porosity.

SILTSTONE: The Siltstone was olive grey to olive black, and light to dark grey in parts. The cuttings were firm and were sub-blocky to blocky in shape. The Siltstone was slightly to moderately calcareous and graded to Claystone in parts.

CLAYSTONE: The Claystone was light olive grey to olive grey and dark grey in parts. Cuttings ranged from very soft to hard although were mainly soft to firm. The cuttings were predominantly sub-blocky to blocky in form, although were amorphous in parts. The Claystone ranged from non to moderately calcareous and graded to Siltstone in parts.

Table 5.1 Summary of ROP statistics for the Tariki Member:

ROP m/hr		
Min.	Max.	Avg.
0.45	34.79	6.62

Total gas ranged from: 0.09% - 0.80%. Background gas: 0.12%-0.65%.

Table 5.2 Gas peaks observed:

Depth, m	Total Gas %	C1 %	C2 %	C3 %	IC4 %	NC4 %	IC5 %	NC5 %
2666	0.7	0.653	0.031	0.012	0.003	-	-	-
2669	1.21	1.274	0.69	0.025	0.0042	-	0.0042	-
2705	0.64	0.533	0.0365	0.0175	0.0039	-	0.0025	-
2709	0.66	0.6084	0.0362	0.0174	0.0033	-	0.0024	-
2720	0.47	0.498	0.026	0.014	0.003	-	0.001	-
2728	0.59	0.462	0.02	0.011	0.004	-	-	-
2736	0.75	0.592	0.031	0.016	0.003	-	0.001	-
2739	0.81	0.756	0.037	0.018	0.003	-	0.001	-
2749	0.75	0.81	0.04	0.02	0.004	-	0.002	-
2751	0.57	0.6	0.03	0.015	0.003	-	0.002	-
2757	0.59	0.654	0.028	0.017	0.004	-	0.002	-
2768	0.62	0.61	0.029	0.016	0.004	-	0.001	-
2771	0.63	0.59	0.027	0.014	0.004	-	0.001	-
2778	1.3	1.148	0.069	0.032	0.004	-	0.001	-
2791	1.87	1.585	0.106	0.046	0.006	-	0.002	-
2794	1.12	0.845	0.062	0.03	0.004	-	0.001	-
2795	1.22	0.926	0.069	0.032	0.004	-	0.001	-
2807	1.56	1.38	0.09	0.04	0.01	-	-	-
2913	0.55	0.224	0.019	0.008	0.004	0.004	0.004	-

MANGAHEWA FORMATION: 2983m-3034m (2878m-2929m TVD)

The Mangahewa formation was comprised primarily of Claystone, interbedded with minor layers of Siltstone Sandstone and Coal seams. The lower contact of this formation is marked by the Ahuroa Thrust system.

CLAYSTONE: The Claystone varied in colour from brownish grey to brownish black and light olive grey to olive grey. The cuttings were firm to moderately hard and were sub-blocky to blocky in form. The Claystone was non to moderately calcareous, becoming more calcareous towards the base of the section. The Claystone graded to Siltstone in parts.

SILTSTONE: The Siltstone was light olive grey to brownish grey and brownish black. The cuttings were firm to moderately hard and sub-fissile to blocky in form. The Siltstone was very carbonaceous in parts with coal laminae observed. There were trace amounts of very fine quartz grains in parts. The Siltstone in part graded to Claystone and Sandstone.

SANDSTONE: The Sandstone was light grey to yellow grey friable aggregates. The grain size ranged from very fine lower to fine lower. The grains were sub-angular to rounded, and were moderately sorted. Silty matrix was abundant in the Sandstone. There was poor visible porosity.

COAL SEAM: The coal was black in colour and brittle to firm. The cuttings were sub-fissile to blocky in structure and had a hackly fracture pattern. The Coal had an earthy to vitreous lustre and was argillaceous in part.

Table 8.1 Summary of ROP statistics for the Mangahewa Formation:

ROP m/hr		
Min.	Max.	Avg.
1.18	22.56	5.45

Total gas ranged from: 0.27%-0.54%. Background gas: 0.13%-0.58%.

Table 8.2 Gas peaks observed:

Depth M	Total Gas %	C1 %	C2 %	C3 %	IC4 %	NC4 %	IC5 %	NC5 %
2987	0.58	0.3598	0.015	0.004	0.001	0.001	-	-

MANGANUI FORMATION: 3034m-3085m TD (2929m-2979m TVD)

The section of the Manganui Formation observed (the lower contact was not reached) was entirely Claystone.

CLAYSTONE: The Claystone was olive grey to olive black at the top of the section, then changed abruptly to medium grey to dark grey in colour, giving a clear indication of the change in the Manganui formation. The Claystone was blocky in structure with trace amounts of calcite veins noted in parts. The Claystone was very slightly to slightly calcareous at the top of the section becoming non calcareous with depth

Table 9.1 Summary of ROP statistics for the Manganui Formation:

ROP m/hr		
Min.	Max.	Avg.
1.09	12.39	4.95

Total gas ranged from: 0.22%-0.78%.

No significant Gas Peaks were observed.

TABLES

BAKER HUGHES INTEQ

LOCATION / WELL NAME
PEP 38719 Ahuroa South B-1 ST-1

OPERATOR
Swift Energy New Zealand Ltd

CONTRACTOR / RIG
Parker Drilling / Rig 252

Rotary Type
RKB - Rotary Kelly Bushing

Mud Type
SBM

Geology
Sd : Sand
Sst : Sandstone
Lst : Limestone
Slt : Silt
Sltst : Siltstone
Cl : Clay
Clst:Claystone
Volc: Volcanics
Sh : Shale
Dol : Dolomite
Ms : Metasediment

Dull Grade & Reason Pulled Abbreviations

A - All Rows
BC - Broken Cone
BHA - Bottomhole Assembl
BU - Balled Up Bit
CM - Condition Mud
CP - Casing Point
DMF - Down Hole Motor Failure
DP - Drill Plug
DSF - String Failiure
DTF - Down Hole Tool Failure
E - Seals Effective
F - Seals Failed
FC - Flat Crested Wear
G - Gauge Rows
H - Heel
HP - Hole Problems
HR - Hours on Bit
I - In Gauge
PR - Penetration rate
RG - Rounded Gauge
SD - Shirt Tail Damage
TD - Total / Csg Depth
TQ - Torque
TW - Twist Off
WC - Weather Condition
WT - Worn Teeth
RO - Ring Out
JD - Junk Damage
LIH - Left In Hole
LOG - Run Logs
LT - Lost Teeth
M - Middle Rows
MH - Mid Heel
NO - No Dull Wear
O - Out of Gauge
PP - Pump Pressure
BT - Broken Teeth

BHA No.	Bit No.	Vendor	Type	Serial Number	Size (in)	IADC	Nozzles (x 1/32")	Depth In	Depth Out	Drilled m	Drilled hr	ROP (m/hr)	WOB (klb)	RPM (at bit)	TORQ. (kftlb)	TBR (krev)	RT (hr)	Pump Pr (psi)	Flow Rate (gpm)	Dev (deg)	Geology Formation	MW ppg	Mud Type	PV/YP	IADC Dull Grade (G in 1/16") I	O	D	L	B	G	O	R
6" Hole Section: 2400m - 3085.																																
11	NB8	Smith	XR+	PC7092	6	-	3x18	2400	2433	33	31.6	1.0	0.6-11	112-212	0-8.7	241.0	38.7	1933-2956	200-248	22.9	Clst,Sltst	8.5	SBM	23/19	-	-	-	-	-	-	-	PR
12	NB9	HyCalog	DSX519S-A3	211111	6	-	5x14	2433	2874	441	100.2	4.4	1-12	112-225	0-8.0	949.0	124.9	1880-2850	101-244	7.9	Clst,Sst,Sltst	8.5-8.7	SBM	26/15	3	4	WT	S	X	I	NO	PR
13	NB10	SmithGeo	M516LYPX	JW3280	6	-	16,15, 3x13	2874	3085	211	80.0	2.6	1-13	109-209	0-6.0	906.0	111.5	1139-2752	129-214	8.3	CLst, Sst, Slst, Coal	8.5-8.7	SBM	26/16	1	4	WT	S	X	I	WT	TD

BAKER HUGHES INTEQ

OPERATOR	WELL NAME	LOCATION	CONTRACTOR	RIG
SWIFT ENERGY NEW ZEALAND LTD	**AHUROA SOUTH B-1 ST-1**	**PEP 38719**	**Parker Drilling Company**	**Parker Rig 252**

Drillstring Abbreviations 0

N Normal **T** Turbine **P** Positive Displacement Motor
M MWD **C** Core


Hydraulics Models
Power Law Model used for drilling with Mud
Bingham Model used for coring and drilling with sea water

Bit No.	Depth (m)	Hole Size in	Calc'd Hole Size in	JETS x 1/32"	Drill String Type	Mud Density ppg	Mud Type	PV / YP	Flow Rate gpm	ECD shoe ppg	ECD TD ppg	Annular Velocities DP Max Dia m/min	Annular Velocities DP OH m/min	Annular Velocities DC OH m/min	Jet Vel m/sec	HHP (bit) hp	HSI hp/sq in	Impact Force lbf	Bit Pressure Loss psi	% Bit Loss	Theoretical Pressure Loss psi	Actual Pressure Loss psi
6" HOLE SECTION				**2400-3085m**																		
NB8	2433	6	6	3x18	M	8.55	SBM	23/20	202	9.23	9.25	50.0	63.0	111.0	28.3	5.7	0.21	2.7	49	2.6	2181	2715
NB9	2874	6	6	5X14	M	8.70	SBM	26/15	220	9.30	9.35	55.0	69.0	117.0	30.8	7.7	0.27	3.3	60	2.5	2382	2480
NB10	3085	6	6	1x16,1x15,3x13	M	8.70	SBM	26/17	9	9.30	9.40	62.0	67.0	110.0	26.0	6.4	0.21	2.6	47	2.0	2380	2390

BAKER HUGHES INTEQ

TIME- DEPTH PLOT
SWIFT ENERGY
AHUROA SOUTH B1 ST1

SWIFT ENERGY COMPANY



APPENDICES

FORMATION EVALUATION LOG

1:500

DRILLING DATA PLOT

1:2500

GAS RATIO PLOT

1:500

POST WELL ANALYSIS

AHUROA SOUTH B-1

CUSTOMER : SWIFT ENERGY NZ LTD.

WELL : AHUROA SOUTH B-1

RIG : PARKER RIG 252

LOCATION : AHUROA

DIRECTIONAL DRILLING PERSONNEL

B. LYE
W. McLENNAN

Sperry Drilling Services

HALLIBURTON

Table of Contents

1. Job Objectives/Summary
2. Proposal Data & Plot
3. Directional Drilling Record / Daily Reports
4. BHA Reports
5. Definitive Survey and Plot

SECTION 1

JOB OBJECTIVES / SUMMARY

Customer : Swift Energy NZ Ltd

Well : Ahuroa South B-1

Job Objectives:

Drill 12 1/4" hole to 650m and set 9 5/8" casing.
Drill out with 8 1/2" directional assembly then build at 3°/30m to 19.6 degrees on 136 degrees azimuth by 850m, then hold to 7" casing point @ 2600m (later changed to 2400m) .
Drill out 7" casing with 6" directional assembly and hold to TD @ 3600m, intersecting Target at 3027mTVD.

Summary of Results:

12 1/4" Section:

Due to the proximity of another producing well, it was considered necessary to run a steerable assembly in the 12 1/4" section. The well was spudded at with a conventional rotary assembly, with W/L surveys taken every 50m to track deviation, and this was used to 200m where it was pulled and replaced with a steerable assembly. No problems were encountered on this section and the well was drilled to 659m with minimal slide/corrections to keep it on line.

8 1/2" Section:

The build and turn was achieved as per the plan with an average dogleg of 2.6°/30m. Inclination and azimuth was then held in the tangent section through to the 7" casing point at 2395m MD. Due to the nature of the formations in this area it was dificult to ascertain the rotary Bld / walk trend but toward the last 200m it appeared to have a slight Drop and Right walk althought this could have been attributed to the considerable wear to the shoulder/gauge row of cutters on the bit.

6" Section:

BHA #4 performed well despite a strong 0.5°/30m drop and -1.0°/30m Right walk, in the rotary mode. The situation was made more difficult when the customer advised (300m from target) that they only wanted to be in the top 1/2 of the target and they wanted to follow the line after the target through to TD. This assembly was pulled due to poor penetration rate at 2903m.

BHA #5 was run in but the MWD failed to respond when pumping commenced. At surface the impeller/stator was found to be plugged with LCM. From this depth on a screen was used in the drill string. This assembly at first had a rotary build rate of 0.3°/30m and a right walk of 0.7°/30m until 3050m MD, where the rotary tendancy was to turn right at an average of between 1 - 3°/30m and drop between 0.5 - 1.0°/30m . It was necessary to wait for sections of faster ROP to slide in (due to the aggressive nature of the bit) & sliding results varied between 0.8 - 1.0°/30m after a 5-8m slide.
From 3100m onward no further corrections were attempted (at operator's request) as the well path was within projected boundaries.

Rotary drilling continued to 3297m where some tight hole was experienced on a connection, after drilling some stringers of coal, and it was decided to lay our directional tools out and proceed with a conventional rotary assembly.

Discussion:

BHA #	Bit #	Motor Run #	Hole Size (in)	MD In (m)	MD Out (m)	TVD In (m)	TVD Out (m)	Inc In (deg)	Inc Out (deg)	Azi In (deg)	Azi Out (deg)	Drlg hrs	Circ hrs
2	1rr1	1	12.250	0	659	0	659	0.0	2.0	0	112	31	1
3	2	2	8.500	659	2403	659	2308	2.0	20.0	112	142	155	10
4	3	3	6.000	2403	2903	2308	2781	20.0	20.5	142	130	117	7
5	4	4	6.000	2903	3297	2781	3150	20.5	17.3	130	160	155	5
6	?		6.000	3297		3150	0	17.3	0.0	160	0	0	0

Table 1 - BHA Summary


Motor Run #	Manufacturer	Type	Lobe	OD (in)	Gauge (in)	Bend (deg)	Adj	DLS (Ori) (°/30m)	ROP (Ori) (m/hr)	ROP (Rot) (m/hr)
1	SSDS	SperryDrill	6/7	8.000	12.000	1.15	Y		27	17
2	SSDS	SperryDrill	6/7	6.750	8.125	1.50	Y		13	11
3	SSDS	SperryDrill	7/8	4.750	5.813	1.15	Y	0.80	2	5
4	SSDS	SperryDrill	7/8	4.750	5.813	1.15	Y		1	3

Table 2 - Motor Run Summary


Bit #	Manufacturer	Style	OD (in)	Gge Len (in)	Nozzles (/32's)	TFA (in²)	Dull Grades I O D L B G O R	Ftge (m)	Drlg hrs	ROP (m/hr)
1rr1	Sec	XLC1	12.250		3x20	0.920	1-1-NO-A -G-I-NO-TD	659	31.25	21
2	Hycalog	DSX104HG	8.500	2.000	5x13	0.648	2-6-BT-G -X-I-WT-TD	1744	155.00	11
3	Reed Hycalog	DSX516	6.000		5x13	0.648	3-6-WT-A -X-I-CT-PR	500	117.25	4
4	Reed Hycalog	DSX516M-B1	6.000	2.500	3x13, 2x15	0.734		394	155.00	3
?	Reed Hycalog	DSX413M-A2	6.000	2.500	3x13, 2x15	0.734			0.00	

Table 3 - Bit Run Summary


Hours by Operation Summary




Hours per BHA Breakdown




Days vs. Depth



Average Rate of Penetration per BHA




Footage per BHA



Sperry-Sun Drilling Services

Swift Energy NZ Ltd
Ahuroa South B-1
Parker 252

Ahuroa
B-1
NZ-DD-0003978048



SECTION 2

PROPOSAL DATA AND PLOT

Swift Energy NZ Ltd.

Ahuroa
Ahuroa South
Ahuroa South B-1
Ahuroa South B-1

Plan: Ahuroa South B-1 rev7

Sperry Drilling Services

Proposal Report

04 October, 2005

Well Coordinates: 6,214,665.80 N, 2,625,724.00 E (39° 16' 01.20" S, 174° 20' 25.38" E)
Ground Level: 196.30 m

Local Coordinate Origin:	Centered on Well Ahuroa South B-1
Viewing Datum:	RKB @ 201.84m (Rig 252)
TVDs to System:	N
North Reference:	Grid
Unit System:	SI - Modified

Version: 2003.14 Build: 57

HALLIBURTON

Plan Report for Ahuroa South B-1 - Ahuroa South B-1 - Ahuroa South B-1 rev7

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)	Toolface Azimuth (°)
0.00	0.00	136.09	201.84	0.00	0.00	0.00	0.000	0.000	0.000	0.00
30.00	0.00	136.09	171.84	0.00	0.00	0.00	0.000	0.000	0.000	136.09
60.00	0.00	136.09	141.84	0.00	0.00	0.00	0.000	0.000	0.000	136.09
90.00	0.00	136.09	111.84	0.00	0.00	0.00	0.000	0.000	0.000	136.09
120.00	0.00	136.09	81.84	0.00	0.00	0.00	0.000	0.000	0.000	136.09
150.00	0.00	136.09	51.84	0.00	0.00	0.00	0.000	0.000	0.000	136.09
180.00	0.00	136.09	21.84	0.00	0.00	0.00	0.000	0.000	0.000	136.09
210.00	0.00	136.09	-8.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
240.00	0.00	136.09	-38.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
270.00	0.00	136.09	-68.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
300.00	0.00	136.09	-98.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
330.00	0.00	136.09	-128.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
360.00	0.00	136.09	-158.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
390.00	0.00	136.09	-188.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
420.00	0.00	136.09	-218.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
450.00	0.00	136.09	-248.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
480.00	0.00	136.09	-278.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
510.00	0.00	136.09	-308.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
540.00	0.00	136.09	-338.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
570.00	0.00	136.09	-368.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
600.00	0.00	136.09	-398.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
630.00	0.00	136.09	-428.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
650.00	0.00	136.09	-448.16	0.00	0.00	0.00	0.000	0.000	0.000	136.09
Start Build 3.000										
660.00	1.00	136.09	-458.16	-0.06	0.06	0.09	3.000	3.000	0.000	136.09
690.00	4.00	136.09	-488.13	-1.01	0.97	1.40	3.000	3.000	0.000	0.00
720.00	7.00	136.09	-517.99	-3.08	2.96	4.27	3.000	3.000	0.000	0.00
750.00	10.00	136.09	-547.65	-6.27	6.04	8.70	3.000	3.000	0.000	0.00
780.00	13.00	136.09	-577.05	-10.58	10.19	14.68	3.000	3.000	0.000	0.00
810.00	16.00	136.09	-606.09	-15.99	15.39	22.20	3.000	3.000	0.000	0.00
840.00	19.00	136.09	-634.70	-22.49	21.65	31.22	3.000	3.000	0.000	0.00
846.48	19.65	136.09	-640.81	-24.03	23.14	33.36	3.000	3.000	0.000	0.00
Start 2319.22 hold at 846.48 MD										
870.00	19.65	136.09	-662.96	-29.73	28.62	41.27	0.000	0.000	0.000	0.00
900.00	19.65	136.09	-691.22	-37.00	35.62	51.36	0.000	0.000	0.000	0.00
930.00	19.65	136.09	-719.47	-44.26	42.62	61.44	0.000	0.000	0.000	0.00
960.00	19.65	136.09	-747.72	-51.53	49.61	71.53	0.000	0.000	0.000	0.00
990.00	19.65	136.09	-775.98	-58.80	56.61	81.62	0.000	0.000	0.000	0.00
1,020.00	19.65	136.09	-804.23	-66.06	63.60	91.70	0.000	0.000	0.000	0.00
1,050.00	19.65	136.09	-832.48	-73.33	70.60	101.79	0.000	0.000	0.000	0.00
1,080.00	19.65	136.09	-860.74	-80.60	77.60	111.88	0.000	0.000	0.000	0.00
1,110.00	19.65	136.09	-888.99	-87.86	84.59	121.97	0.000	0.000	0.000	0.00
1,140.00	19.65	136.09	-917.24	-95.13	91.59	132.05	0.000	0.000	0.000	0.00
1,170.00	19.65	136.09	-945.50	-102.40	98.59	142.14	0.000	0.000	0.000	0.00
1,200.00	19.65	136.09	-973.75	-109.66	105.58	152.23	0.000	0.000	0.000	0.00
1,230.00	19.65	136.09	-1,002.00	-116.93	112.58	162.31	0.000	0.000	0.000	0.00
1,260.00	19.65	136.09	-1,030.25	-124.20	119.57	172.40	0.000	0.000	0.000	0.00
1,290.00	19.65	136.09	-1,058.51	-131.46	126.57	182.49	0.000	0.000	0.000	0.00
1,320.00	19.65	136.09	-1,086.76	-138.73	133.57	192.58	0.000	0.000	0.000	0.00
1,350.00	19.65	136.09	-1,115.01	-146.00	140.56	202.66	0.000	0.000	0.000	0.00
1,380.00	19.65	136.09	-1,143.27	-153.26	147.56	212.75	0.000	0.000	0.000	0.00
1,410.00	19.65	136.09	-1,171.52	-160.53	154.56	222.84	0.000	0.000	0.000	0.00
1,440.00	19.65	136.09	-1,199.77	-167.80	161.55	232.93	0.000	0.000	0.000	0.00
1,470.00	19.65	136.09	-1,228.03	-175.06	168.55	243.01	0.000	0.000	0.000	0.00
1,500.00	19.65	136.09	-1,256.28	-182.33	175.54	253.10	0.000	0.000	0.000	0.00
1,530.00	19.65	136.09	-1,284.53	-189.60	182.54	263.19	0.000	0.000	0.000	0.00
1,560.00	19.65	136.09	-1,312.79	-196.86	189.54	273.27	0.000	0.000	0.000	0.00
1,590.00	19.65	136.09	-1,341.04	-204.13	196.53	283.36	0.000	0.000	0.000	0.00

Plan Report for Ahuroa South B-1 - Ahuroa South B-1 - Ahuroa South B-1 rev7

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)	Toolface Azimuth (°)
1,620.00	19.65	136.09	-1,369.29	-211.40	203.53	293.45	0.000	0.000	0.000	0.00
1,650.00	19.65	136.09	-1,397.55	-218.66	210.53	303.54	0.000	0.000	0.000	0.00
1,680.00	19.65	136.09	-1,425.80	-225.93	217.52	313.62	0.000	0.000	0.000	0.00
1,710.00	19.65	136.09	-1,454.05	-233.20	224.52	323.71	0.000	0.000	0.000	0.00
1,740.00	19.65	136.09	-1,482.31	-240.46	231.51	333.80	0.000	0.000	0.000	0.00
1,770.00	19.65	136.09	-1,510.56	-247.73	238.51	343.89	0.000	0.000	0.000	0.00
1,800.00	19.65	136.09	-1,538.81	-255.00	245.51	353.97	0.000	0.000	0.000	0.00
1,830.00	19.65	136.09	-1,567.07	-262.26	252.50	364.06	0.000	0.000	0.000	0.00
1,860.00	19.65	136.09	-1,595.32	-269.53	259.50	374.15	0.000	0.000	0.000	0.00
1,890.00	19.65	136.09	-1,623.57	-276.80	266.50	384.23	0.000	0.000	0.000	0.00
1,920.00	19.65	136.09	-1,651.83	-284.06	273.49	394.32	0.000	0.000	0.000	0.00
1,950.00	19.65	136.09	-1,680.08	-291.33	280.49	404.41	0.000	0.000	0.000	0.00
1,980.00	19.65	136.09	-1,708.33	-298.60	287.48	414.50	0.000	0.000	0.000	0.00
2,010.00	19.65	136.09	-1,736.59	-305.86	294.48	424.58	0.000	0.000	0.000	0.00
2,040.00	19.65	136.09	-1,764.84	-313.13	301.48	434.67	0.000	0.000	0.000	0.00
2,070.00	19.65	136.09	-1,793.09	-320.40	308.47	444.76	0.000	0.000	0.000	0.00
2,100.00	19.65	136.09	-1,821.35	-327.66	315.47	454.84	0.000	0.000	0.000	0.00
2,130.00	19.65	136.09	-1,849.60	-334.93	322.47	464.93	0.000	0.000	0.000	0.00
2,160.00	19.65	136.09	-1,877.85	-342.20	329.46	475.02	0.000	0.000	0.000	0.00
2,190.00	19.65	136.09	-1,906.11	-349.46	336.46	485.11	0.000	0.000	0.000	0.00
2,220.00	19.65	136.09	-1,934.36	-356.73	343.45	495.19	0.000	0.000	0.000	0.00
2,250.00	19.65	136.09	-1,962.61	-364.00	350.45	505.28	0.000	0.000	0.000	0.00
2,280.00	19.65	136.09	-1,990.87	-371.26	357.45	515.37	0.000	0.000	0.000	0.00
2,310.00	19.65	136.09	-2,019.12	-378.53	364.44	525.46	0.000	0.000	0.000	0.00
2,340.00	19.65	136.09	-2,047.37	-385.80	371.44	535.54	0.000	0.000	0.000	0.00
2,370.00	19.65	136.09	-2,075.63	-393.06	378.44	545.63	0.000	0.000	0.000	0.00
2,400.00	19.65	136.09	-2,103.88	-400.33	385.43	555.72	0.000	0.000	0.000	0.00
2,430.00	19.65	136.09	-2,132.13	-407.60	392.43	565.80	0.000	0.000	0.000	0.00
2,460.00	19.65	136.09	-2,160.39	-414.86	399.42	575.89	0.000	0.000	0.000	0.00
2,490.00	19.65	136.09	-2,188.64	-422.13	406.42	585.98	0.000	0.000	0.000	0.00
2,520.00	19.65	136.09	-2,216.89	-429.40	413.42	596.07	0.000	0.000	0.000	0.00
2,550.00	19.65	136.09	-2,245.15	-436.66	420.41	606.15	0.000	0.000	0.000	0.00
2,580.00	19.65	136.09	-2,273.40	-443.93	427.41	616.24	0.000	0.000	0.000	0.00
2,610.00	19.65	136.09	-2,301.65	-451.20	434.41	626.33	0.000	0.000	0.000	0.00
2,640.00	19.65	136.09	-2,329.91	-458.46	441.40	636.41	0.000	0.000	0.000	0.00
2,670.00	19.65	136.09	-2,358.16	-465.73	448.40	646.50	0.000	0.000	0.000	0.00
2,700.00	19.65	136.09	-2,386.41	-473.00	455.39	656.59	0.000	0.000	0.000	0.00
2,730.00	19.65	136.09	-2,414.67	-480.26	462.39	666.68	0.000	0.000	0.000	0.00
2,760.00	19.65	136.09	-2,442.92	-487.53	469.39	676.76	0.000	0.000	0.000	0.00
2,790.00	19.65	136.09	-2,471.17	-494.80	476.38	686.85	0.000	0.000	0.000	0.00
2,820.00	19.65	136.09	-2,499.43	-502.06	483.38	696.94	0.000	0.000	0.000	0.00
2,850.00	19.65	136.09	-2,527.68	-509.33	490.38	707.03	0.000	0.000	0.000	0.00
2,880.00	19.65	136.09	-2,555.93	-516.60	497.37	717.11	0.000	0.000	0.000	0.00
2,910.00	19.65	136.09	-2,584.19	-523.86	504.37	727.20	0.000	0.000	0.000	0.00
2,940.00	19.65	136.09	-2,612.44	-531.13	511.36	737.29	0.000	0.000	0.000	0.00
2,970.00	19.65	136.09	-2,640.69	-538.40	518.36	747.37	0.000	0.000	0.000	0.00
3,000.00	19.65	136.09	-2,668.95	-545.66	525.36	757.46	0.000	0.000	0.000	0.00
3,030.00	19.65	136.09	-2,697.20	-552.93	532.35	767.55	0.000	0.000	0.000	0.00
3,060.00	19.65	136.09	-2,725.45	-560.20	539.35	777.64	0.000	0.000	0.000	0.00
3,090.00	19.65	136.09	-2,753.70	-567.46	546.35	787.72	0.000	0.000	0.000	0.00
3,120.00	19.65	136.09	-2,781.96	-574.73	553.34	797.81	0.000	0.000	0.000	0.00
3,150.00	19.65	136.09	-2,810.21	-582.00	560.34	807.90	0.000	0.000	0.000	0.00
3,165.70	19.65	136.09	-2,825.00	-585.80	564.00	813.18	0.000	0.000	0.000	0.00
Start 459.30 hold at 3165.70 MD - McKee - Target - Ahuroa South B-1 rev7										
3,180.00	19.65	136.09	-2,838.46	-589.26	567.33	817.98	0.000	0.000	0.000	0.00
3,210.00	19.65	136.09	-2,866.72	-596.53	574.33	828.07	0.000	0.000	0.000	0.00
3,240.00	19.65	136.09	-2,894.97	-603.80	581.33	838.16	0.000	0.000	0.000	0.00
3,270.00	19.65	136.09	-2,923.22	-611.06	588.32	848.25	0.000	0.000	0.000	0.00
3,300.00	19.65	136.09	-2,951.48	-618.33	595.32	858.33	0.000	0.000	0.000	0.00
3,330.00	19.65	136.09	-2,979.73	-625.60	602.32	868.42	0.000	0.000	0.000	0.00

Plan Report for Ahuroa South B-1 - Ahuroa South B-1 - Ahuroa South B-1 rev7

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)	Toolface Azimuth (°)
3,360.00	19.65	136.09	-3,007.98	-632.86	609.31	878.51	0.000	0.000	0.000	0.00
3,390.00	19.65	136.09	-3,036.24	-640.13	616.31	888.60	0.000	0.000	0.000	0.00
3,420.00	19.65	136.09	-3,064.49	-647.40	623.30	898.68	0.000	0.000	0.000	0.00
3,450.00	19.65	136.09	-3,092.74	-654.66	630.30	908.77	0.000	0.000	0.000	0.00
3,480.00	19.65	136.09	-3,121.00	-661.93	637.30	918.86	0.000	0.000	0.000	0.00
3,510.00	19.65	136.09	-3,149.25	-669.20	644.29	928.94	0.000	0.000	0.000	0.00
3,540.00	19.65	136.09	-3,177.50	-676.46	651.29	939.03	0.000	0.000	0.000	0.00
3,570.00	19.65	136.09	-3,205.76	-683.73	658.29	949.12	0.000	0.000	0.000	0.00
3,600.00	19.65	136.09	-3,234.01	-691.00	665.28	959.21	0.000	0.000	0.000	0.00
3,625.00	19.65	136.09	-3,257.56	-697.05	671.11	967.61	0.000	0.000	0.000	0.00
TD at 3625.00										

Plan Annotations

Measured Depth (m)	Vertical Depth (m)	Local Coordinates +N/-S (m)	Local Coordinates +E/-W (m)	Comment
650.00	650.00	0.00	0.00	Start Build 3.000
846.48	842.65	-24.03	23.14	Start 2319.22 hold at 846.48 MD
3,165.70	3,026.84	-585.80	564.00	Start 459.30 hold at 3165.70 MD
3,625.00	3,459.40	-697.05	671.11	TD at 3625.00

Vertical Section Information

Angle Type	Target	Azimuth (°)	Origin Type	Origin +N/_S (m)	Origin +E/-W (m)	Start TVD (m)
Target	Target - Ahuroa South B-1 rev7	136.09	Slot	0.00	0.00	0.00

Targets associated with this wellbore

Target Name	TVD (m)	+N/-S (m)	+E/-W (m)	Shape
Target - Ahuroa South B-1 rev4	3,101.84	-435.80	521.00	Circle
Target - Ahuroa South B-1 rev3	2,901.84	-432.80	316.00	Circle
Target - Ahuroa South B-1 rev5	2,826.84	-435.80	240.00	Circle
Target - Ahuroa South B-1 rev7	3,026.84	-585.80	564.00	Circle

North Reference Sheet for Ahuroa South - Ahuroa South B-1 - Ahuroa South B-1


All data is in Meters unless otherwise stated. Directions and Coordinates are relative to Grid North Reference.
Vertical Depths are relative to RKB @ 201.84m (Rig 252). Northing and Easting are relative to Ahuroa South B-1
Coordinate System is New Zealand Map Grid, New Zealand Map Grid using datum Geodetic Datum 1949, ellipsoid International 1924

Projection method is New Zealand Map Grid
Central Meridian is 0.00°, Longitude Origin:173° 0' 0.000 E°, Latitude Origin:41° 0' 0.000 S°
False Easting: 2,510,000.00m, False Northing: 6,023,150.00m, Scale Reduction: 1.00000000

Grid Coordinates of Well: 6,214,665.80 m N, 2,625,724.00 m E
Geographical Coordinates of Well: 39° 16' 01.20" S, 174° 20' 25.38" E
Grid Convergence at Surface is: -0.89°

Based upon Minimum Curvature type calculations, at a Measured Depth of 3,625.00m
the Bottom Hole Displacement is 967.61m in the Direction of 136.09° (Grid).

Magnetic Convergence at surface is: -21.60° (11 August 2005, , BGGM2005)



Magnetic Model:	BGGM2005
Date:	11-Aug-05
Declination:	20.71°
Inclination/Dip:	-64.95°
Field Strength:	55440


Grid North is 0.89° West of True North (Grid Convergence)
Magnetic North is 20.71° East of True North (Magnetic Declination)
Magnetic North is 21.60° East of Grid North (Magnetic Convergence)

To convert a True Direction to a Grid Direction, Add 0.89°
To convert a Magnetic Direction to a True Direction, Add 20.71° East
To convert a Magnetic Direction to a Grid Direction, Add 21.60°

HALLIBURTON
SPERRY DRILLING SERVICES


Swift Energy NZ Ltd.

Ahuroa South B-1 rev7



REFERENCE INFORMATION

Co-ordinate (N/E) Reference:	Well Ahuroa South B-1, Grid North
Vertical (TVD) Reference:	RKB @ 201.84m (Rig 252)
Section (VS) Reference:	Slot - (0.00N, 0.00E)
Measured Depth Reference:	RKB @ 201.84m (Rig 252)
Calculation Method:	Minimum Curvature




Azimuths to Grid North
True North: 0.89°
Magnetic North: 21.60°

Magnetic Field
Strength: 55440.0nT
Dip Angle: -64.95°
Date: 11/08/2005
Model: BGGM2005

HALLIBURTON
SPERRY DRILLING SERVICES


Swift Energy NZ Ltd.

Ahuroa South B-1 rev7



REFERENCE INFORMATION

Co-ordinate (N/E) Reference:	Well Ahuroa South B-1, Grid North
Vertical (TVD) Reference:	RKB @ 201.84m (Rig 252)
Section (VS) Reference:	Slot - (0.00N, 0.00E)
Measured Depth Reference:	RKB @ 201.84m (Rig 252)
Calculation Method:	Minimum Curvature




Azimuths to Grid North
True North: 0.89°
Magnetic North: 21.60°

Magnetic Field
Strength: 55440.0nT
Dip Angle: -64.95°
Date: 11/08/2005
Model: BGGM2005

HALLIBURTON
SPERRY DRILLING SERVICES

Swift Energy NZ Ltd.

Ahuroa South B-1 rev7



REFERENCE INFORMATION

Co-ordinate (N/E) Reference: Well Ahuroa South B-1, Grid North
Vertical (TVD) Reference: RKB @ 201.84m (Rig 252)
Section (VS) Reference: Slot - (0.00N, 0.00E)
Measured Depth Reference: RKB @ 201.84m (Rig 252)
Calculation Method: Minimum Curvature

SECTION 3

DRILLING RECORD AND DAILY REPORTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 1 7/10/2005

Total Depth	**(m)**	:	571	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Suire
Drilled last 24 hrs	**(m)**	:	571	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (1)
Hole Size	**(in)**	:	12.250	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
562.69	1.70	122.65	562.57	4.39	S78.26W

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 2: 274.91 m; Bit #1rr1 (23.75 hrs), PDM #1 (23.75 hrs), Stab, Sub, DC, Sub, 2x DC, Sub, 6x DC, 12x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
	0.0		0	0.0	0.0 / 0.0					

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	00:15	0.25	200.00	2	Trip In
00:15	00:00	23.75	571.00	2	Drilling 12 1/4" Hole 240 - 571m.

COMMENTS

NB!!! Spudded well 14:00hrs 05 Oct '05. Rotary drilled to 200m by 12:300hrs 06 Oct'05 with W/L Surveys every 50m. POOH and picked up an 8" Mtr set at 1.15deg bend to control the angle and Az while we drilled top hole to KOP at +/- 650m where we will set 9 5/8" Csg.

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 2 8/10/2005

Total Depth	**(m)**	:	659	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: Suire
Drilled last 24 hrs	**(m)**	:	88	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: Lye (2)
Hole Size	**(in)**	:	12.250	**Casing ID**	**(in)**	:		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
640.10	2.03	114.20	639.94	2.73	S44.10W

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 2: 274.91 m; Bit #1rr1 (31.25 hrs), PDM #1 (32.25 hrs), Stab, Sub, DC, Sub, 2x DC, Sub, 6x DC, 12x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
					/					

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	07:30	7.50	659.00	2	Dir. Drill 12 1/4" hole 571 - 659m.
07:30	08:00	0.50	659.00	2	Circulate, sweep, slug.
08:00	12:30	4.50	659.00	2	Wiper Trip , t/30m.
12:30	14:30	2.00	659.00	2	Wiper trip , RIH t/659m.
14:30	15:00	0.50	659.00	2	Circulate, slug.
15:00	17:15	2.25	659.00	2	Trip Out
17:15	18:30	1.25	659.00	2	L/O Dir. Assy.
18:30	00:00	5.50	659.00		Rig up & Run Casing / Cement

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 3 9/10/2005

Total Depth	**(m)**	:	659	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: Suire
Drilled last 24 hrs	**(m)**	:	0	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: Lye (3)
Hole Size	**(in)**	:		**Casing ID**	**(in)**	:		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
640.10	2.03	114.20	639.94	2.73	S44.10W

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
					/					

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	04:00	4.00	659.00		Cont. Run Casing / Cement
04:00	09:30	5.50	659.00		Wait on Cement
09:30	00:00	14.50	659.00		Nipple Dn Cmt string, Nipple Up BOP

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 4 10/10/2005

Total Depth	**(m)**	:	659	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: Suire
Drilled last 24 hrs	**(m)**	:	0	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: Lye (4)
Hole Size	**(in)**	:		**Casing ID**	**(in)**	:		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
640.10	2.03	114.20	639.94	2.73	S44.10W

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
					/					

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	20:00	20.00	659.00		Nipple Up BOP, test same.
20:00	22:00	2.00	659.00		L/O DC's from Drk.
22:00	00:00	2.00	659.00		PU * 1/2" Dir. BHA. Align same w/MWD.

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 5 11/10/2005

Total Depth	**(m)**	:	927	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Suire
Drilled last 24 hrs	**(m)**	:	268	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (5), Harn (1)
Hole Size	**(in)**	:	8.500	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
908.74	19.55	131.17	901.38	55.14	S41.82E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 3: 200.31 m; Bit #2 (20.75 hrs), PDM #2 (20.75 hrs), Stab, Sub, DC, Sub, 12x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
					/					

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	02:00	2.00	659.00	3	Trip In w/8 1/2" dir. Assy t/630m.
02:00	04:00	2.00	659.00	3	Reaming , tag Cmt @ 634m, drill same t/639,drill float.
04:00	04:30	0.50	659.00	3	Leak-off Test on Csg t/1500psi OK
04:30	05:30	1.00	659.00	3	Reaming , Drill shoe track, to 652m, Clean R/Hole +3m to 662m.
05:30	06:15	0.75	659.00	3	FIT
06:15	00:00	17.75	927.00	3	Dir. Drill 8 1/2" hole 659 - 927m.

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 6 12/10/2005

Total Depth	**(m)**	:	1220	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: Suire
Drilled last 24 hrs	**(m)**	:	293	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: Lye (6), Harn (2)
Hole Size	**(in)**	:	8.500	**Casing ID**	**(in)**	:		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
1204.71	19.52	136.50	1180.66	152.94	S44.46E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 3: 200.31 m; Bit #2 (44.25 hrs), PDM #2 (44.25 hrs), Stab, Sub, DC, Sub, 12x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
					/					

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	14:15	14.25	1107.00	3	Dir. Drill 8 1/2" hole 927-1107m.
14:15	14:45	0.50	1107.00	3	Service Rig
14:45	00:00	9.25	1220.00	3	Dir. Drill 8 1/2" hole 1107 - 1220m.

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 7 13/10/2005

Total Depth	**(m)**	:	1418	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: Suire
Drilled last 24 hrs	**(m)**	:	198	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: Lye (7), Harn (3)
Hole Size	**(in)**	:	8.500	**Casing ID**	**(in)**	:		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
1392.60	17.53	138.57	1358.32	213.91	S44.01E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 3: 200.31 m; Bit #2 (63.75 hrs), PDM #2 (63.75 hrs), Stab, Sub, DC, Sub, 12x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
					/					

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	07:00	7.00	1278.00	3	Dir. Drill 8 1/2" hole 1220 - 1278m.
07:00	11:30	4.50	1278.00	3	Circulate B/U. Wiper trip to the shoe
11:30	00:00	12.50	1418.00	3	Dir. Drill 8 1/2" hole 1278 - 1418m.

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 8 14/10/2005

Total Depth	**(m)**	:	1654	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: Suire
Drilled last 24 hrs	**(m)**	:	236	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: Lye (8), Harn (4)
Hole Size	**(in)**	:	8.500	**Casing ID**	**(in)**	:		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
1635.53	19.73	135.14	1586.53	297.06	S44.24E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 3: 200.31 m; Bit #2 (87.75 hrs), PDM #2 (87.75 hrs), Stab, Sub, DC, Sub, 12x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
					/					

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	00:00	24.00	1654.00	3	Dir. Drill 8 1/2" hole 1418 - 1654m.

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 9 15/10/2005

Total Depth	**(m)**	:	1845	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: Suire
Drilled last 24 hrs	**(m)**	:	191	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: Lye (9), Harn (5)
Hole Size	**(in)**	:	8.500	**Casing ID**	**(in)**	:		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
1826.31	19.74	134.84	1765.48	363.19	S44.46E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 3: 200.31 m; Bit #2 (106.75 hrs), PDM #2 (108.25 hrs), Stab, Sub, DC, Sub, 12x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
					/					

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	17:30	17.50	1817.00	3	Dir. Drill 8 1/2" hole 1654 - 1817m.
17:30	19:00	1.50	1817.00	3	Circulate, slug.
19:00	22:30	3.50	1817.00	3	Short Trip to 2440m
22:30	00:00	1.50	1845.00	3	Dir. Drill 8 1/2" hole 1817m - 1845m

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 10 16/10/2005

Total Depth	**(m)**	:	2071	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: Suire
Drilled last 24 hrs	**(m)**	:	226	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: Lye (10), Mclennan (1)
Hole Size	**(in)**	:	8.500	**Casing ID**	**(in)**	:		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2052.56	19.21	136.77	1979.29	437.16	S44.52E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 3: 200.31 m; Bit #2 (130.75 hrs), PDM #2 (132.25 hrs), Stab, Sub, DC, Sub, 12x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
					/					

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	00:00	24.00	2071.00	3	Dir. Drill 8 1/2" hole 1845m - 2071m

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 11 17/10/2005

Total Depth	**(m)**	:	2348	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Suire
Drilled last 24 hrs	**(m)**	:	277	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (11), Wayne Mclennan (1)
Hole Size	**(in)**	:	8.500	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2319.87	20.22	139.30	2229.97	529.72	S43.82E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 3: 200.31 m; Bit #2 (154.25 hrs), PDM #2 (155.75 hrs), Stab, Sub, DC, Sub, 12x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
KCl/Polymer	9.3	44	15	23.0	7.0 / 15.0	6	9.5	3.40	0.30	

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	19:30	19.50	2291.00	3	Dir. Drill 8 1/2" hole 2071 - 2291m.
19:30	20:00	0.50	2291.00	3	Service Rig
20:00	00:00	4.00	2348.00	3	Drilling from 2291 - 2348m

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 12 18/10/2005

Total Depth	**(m)**	:	2400	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: Suire
Drilled last 24 hrs	**(m)**	:	52	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: Lye (12), Wayne Mclennan (2)
Hole Size	**(in)**	:	8.500	**Casing ID**	**(in)**	:		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2378.00	19.93	141.01	2284.59	549.57	S43.67E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 3: 200.31 m; Bit #2 (158. hrs), PDM #2 (162.25 hrs), Stab, Sub, DC, Sub, 12x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
KCl/Polymer	9.3	44	15	23.0	7.0 / 15.0	6	9.5	3.40	0.30	

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	03:15	3.25	2400.00	3	Dir. Drill 8 1/2" hole 2348 - 2400m.
03:15	04:30	1.25	2400.00	3	Circulate & cond mud.
04:30	09:00	4.50	2400.00	3	Short Trip t/shoe @ 652m.
09:00	10:30	1.50	2400.00	3	Slip & Cut Drill Line, service rig.
10:30	14:00	3.50	2400.00	3	Short Trip in.
14:00	14:30	0.50	2400.00	3	Reaming / Washing 2385-2400m.
14:30	16:00	1.50	2400.00	3	Circulate, sweep, spot, slug.
16:00	21:15	5.25	2400.00	3	Trip Out
21:15	22:30	1.25	2400.00	3	L/O Dir. Assy.
22:30	23:00	0.50	2400.00	3	Clean up rig floor.
23:00	00:00	1.00	2400.00	3	Rig up & run Wireline Logs

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 13 19/10/2005

Total Depth	**(m)**	:	2403	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Suire
Drilled last 24 hrs	**(m)**	:	3	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (13), Wayne Mclennan (3)
Hole Size	**(in)**	:	8.500	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2378.00	19.93	141.01	2284.59	549.57	S43.67E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 3: 200.31 m; Bit #2 (159. hrs), PDM #2 (164.75 hrs), Stab, Sub, DC, Sub, 12x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
KCl/Polymer	9.3	44	15	23.0	7.0 / 15.0	6	9.5	3.40	0.30	

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	08:30	8.50	2400.00	3	Wireline Logs
08:30	10:30	2.00	2400.00	3	PU/LD BHA
10:30	11:00	0.50	2400.00	3	Rig Up / Tear Down lay down machine
11:00	15:30	4.50	2400.00	3	Trip In with cleanout BHA
15:30	16:00	0.50	2400.00	3	Reaming / Washing
16:00	16:30	0.50	2403.00	3	Drilling
16:30	18:00	1.50	2403.00	3	Circulate
18:00	00:00	6.00	2403.00	3	Trip Out

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 14 20/10/2005

Total Depth	**(m)**	:	2403	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: Suire
Drilled last 24 hrs	**(m)**	:	0	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: Lye (14), Wayne Mclennan (4)
Hole Size	**(in)**	:	8.500	**Casing ID**	**(in)**	:		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2378.00	19.93	141.01	2284.59	549.57	S43.67E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 3: 200.31 m; Bit #2 (159. hrs), PDM #2 (164.75 hrs), Stab, Sub, DC, Sub, 12x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
KCl/Polymer	9.3	44	15	23.0	7.0 / 15.0	6	9.5	3.40	0.30	

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	02:30	2.50	2403.00	3	Trip Out (at Surface)
02:30	03:30	1.00	2403.00	3	LD BHA
03:30	05:30	2.00	2403.00	3	Pull wear bushing, m/u test plug
05:30	06:00	0.50	2403.00	3	Prep to run 7" csg
06:00	07:00	1.00	2403.00	3	Rig Up weatherford csg tools
07:00	23:30	16.50	2403.00		Run Casing
23:30	00:00	0.50	2403.00		Cement 7" csg

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 15 21/10/2005

Total Depth	**(m)**	:	2403	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Suire
Drilled last 24 hrs	**(m)**	:	0	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (15), Wayne Mclennan (5)
Hole Size	**(in)**	:		**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2378.00	19.93	141.01	2284.59	549.57	S43.67E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
KCl/Polymer	9.3	44	15	23.0	7.0 / 15.0	6	9.5	3.40	0.30	

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	16:00	16.00	2403.00		Wait on Cement
16:00	16:30	0.50	2403.00		M/U csg slips and set. PU BOP slings
16:30	22:00	5.50	2403.00		Cut csg, Lower stack, nipple down
22:00	00:00	2.00	2403.00		Nipple Up BOP

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 16 22/10/2005

Total Depth	**(m)**	:	2403	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Suire
Drilled last 24 hrs	**(m)**	:	0	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (16), Wayne Mclennan (6)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2378.00	19.93	141.01	2284.59	549.57	S43.67E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 4: 218.09 m; Bit #3 (2. hrs), PDM #3 (2. hrs), Sub, Stab, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
KCl/Polymer	9.3	44	15	23.0	7.0 / 15.0	6	9.5	3.40	0.30	

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	02:00	2.00	2403.00		Nipple Up BOP
02:00	03:30	1.50	2403.00		Pump plastic grease into B-section and test
03:30	05:00	1.50	2403.00		Change out pipe rams to 3 1/2"
05:00	06:30	1.50	2403.00		Rig up bell nipple and connect flow line
06:30	09:30	3.00	2403.00		Lay out kelly & bushing. PU 3 1/2" kelly & bushing
09:30	10:00	0.50	2403.00		M/U test plug and test.
10:00	16:00	6.00	2403.00		Test BOP
16:00	18:00	2.00	2403.00		M/U directional BHA
18:00	18:30	0.50	2403.00	4	Trip In
18:30	00:00	5.50	2403.00	4	Trip In

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 17 23/10/2005

Total Depth	**(m)**	:	2514	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Suire
Drilled last 24 hrs	**(m)**	:	111	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (17), Wayne Mclennan (7)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2493.65	18.81	135.44	2393.66	587.88	S43.41E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 4: 218.09 m; Bit #3 (16. hrs), PDM #3 (16. hrs), Sub, Stab, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
KCl/Polymer	9.3	44	15	23.0	7.0 / 15.0	6	9.5	3.40	0.30	

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	02:30	2.50	2403.00	4	Trip In from 1360m to 1932m MD
02:30	03:30	1.00	2403.00	4	Cut Drill Line
03:30	04:00	0.50	2403.00	4	Service Rig
04:00	06:00	2.00	2403.00	4	Trip In from 1932m to 2379m MD. Tag cement.
06:00	07:00	1.00	2403.00	4	Rig up Howco and conduct csg test
07:00	09:00	2.00	2403.00	4	Drill shoe track and Cement
09:00	09:30	0.50	2403.00	4	Leak-off Test
09:30	10:00	0.50	2403.00	4	Jack derrick
10:00	00:00	14.00	2514.00	4	Drilling 6" hole 2403 - 2514m

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 18 24/10/2005

Total Depth	**(m)**	:	2703	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Suire
Drilled last 24 hrs	**(m)**	:	189	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (18), Wayne Mclennan (8)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2690.57	18.77	134.20	2580.04	651.42	S43.54E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 4: 218.09 m; Bit #3 (40. hrs), PDM #3 (40. hrs), Sub, Stab, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.5	60	24	10.0	5.0 / 6.0	5		4.00	0.25	82.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	00:00	24.00	2703.00	4	Dir. Drill from 2514 - 2703m

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 19 25/10/2005

Total Depth	**(m)**	:	2770	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Suire
Drilled last 24 hrs	**(m)**	:	67	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (19), Wayne Mclennan (9)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2746.40	18.27	136.72	2632.87	669.47	S43.58E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 4: 218.09 m; Bit #3 (64. hrs), PDM #3 (64. hrs), Sub, Stab, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.5	60	24	10.0	5.0 / 6.0	5		4.00	0.25	82.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	00:00	24.00	2770.00	4	Dir. Drill 6" hole 2703 - 2786m.

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 20 26/10/2005

Total Depth	**(m)**	:	2826	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Suire
Drilled last 24 hrs	**(m)**	:	56	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (20), Wayne Mclennan (10)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2822.15	18.12	136.73	2704.58	693.87	S43.62E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 4: 218.09 m; Bit #3 (80.5 hrs), PDM #3 (84. hrs), Sub, Stab, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.5	59	29	17.0	7.0 / 10.0	5		3.50	0.25	85.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	00:30	0.50	2787.00	4	Dir. Drill 6" hole 2786 - 2787m.
00:30	02:00	1.50	2787.00	4	Circulate
02:00	03:00	1.00	2787.00	4	Wiper trip from 2787 - 2380m
03:00	03:30	0.50	2787.00	4	Service Rig
03:30	04:30	1.00	2787.00	4	Trip In
04:30	20:30	16.00	2826.00	4	Dir. Drill 6" hole 2787 - 2826m.
20:30	22:00	1.50	2826.00	4	Work pipe while check on press. loss.
22:00	00:00	2.00	2826.00	4	Circulate

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 21 27/10/2005

Total Depth	**(m)**	:	2871	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Suire
Drilled last 24 hrs	**(m)**	:	45	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (21), Wayne Mclennan (11)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2850.50	18.31	135.26	2731.51	702.73	S43.62E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 4: 218.09 m; Bit #3 (104.5 hrs), PDM #3 (108. hrs), Sub, Stab, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.6	65	28	20.0	7.0 / 12.0	5		3.80	0.25	87.20

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	00:00	24.00	2871.00	4	Dir drill 6" hole 2826 - 2871m.

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 22 28/10/2005

Total Depth	**(m)**	:	2903	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Reid
Drilled last 24 hrs	**(m)**	:	32	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (22), Wayne Mclennan (12)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2879.09	19.21	130.07	2758.58	711.90	S43.67E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 4: 218.09 m; Bit #3 (119.25 hrs), PDM #3 (124.5 hrs), Sub, Stab, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.6	62	22	19.0	6.0 / 10.0	4		4.80	0.25	81.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	14:45	14.75	2903.00	4	Dir. Drill 6" Hole 2871 - 2903m.
14:45	16:30	1.75	2903.00	4	Circulate , sweep, slug.
16:30	00:00	7.50	2903.00	4	Trip Out

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 23 29/10/2005

Total Depth	**(m)**	:	2903	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Reid
Drilled last 24 hrs	**(m)**	:	0	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (23), Wayne Mclennan (13)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2879.09	19.21	130.07	2758.58	711.90	S43.67E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 4: 218.09 m; Bit #3 (119.25 hrs), PDM #3 (124.5 hrs), Sub, Stab, MWD, HWDP, Jar, 4x HWDP
BHA 5: 215.87 m; Bit #4 (138.25 hrs), PDM #4 (1. hrs), Sub, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.6	62	22	19.0	6.0 / 10.0	4		4.80	0.25	81.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	00:30	0.50	2903.00	4	L/O Stb, Mtr.
00:30	01:30	1.00	2903.00	4	PU Dir. BHA, align same.
01:30	07:00	5.50	2903.00	5	P/U HWt, RIH
07:00	07:30	0.50	2903.00	5	Service Rig
07:30	08:30	1.00	2903.00	5	Cont. RIH.
08:30	09:30	1.00	2903.00	5	Circulate, wash 2877 - 2903m, sweep w/10 BBl
09:30	11:00	1.50	2903.00	5	Investigate MWD, no pulse.
11:00	19:00	8.00	2903.00	5	Trip Out
19:00	20:30	1.50	2903.00	5	C/O MWD, align same.
20:30	21:15	0.75	2903.00	5	PU HWt DP
21:15	21:30	0.25	2903.00	5	Misc Directional Work, surf. test MWD - OK.
21:30	00:00	2.50	2903.00	5	Trip In

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 24 30/10/2005

Total Depth	**(m)**	:	2974	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: Reid
Drilled last 24 hrs	**(m)**	:	71	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: Lye (24), Wayne Mclennan (14)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)**	:		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2972.15	21.26	130.94	2845.47	745.02	S43.94E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 5: 215.87 m; Bit #4 (138.25 hrs), PDM #4 (20. hrs), Sub, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.6	62	22	19.0	6.0 / 10.0	4		4.80	0.25	81.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	03:00	3.00	2903.00	5	Cont. Trip In.
03:00	03:30	0.50	2903.00	5	Service Rig
03:30	05:00	1.50	2903.00	5	Cont. Trip In
05:00	00:00	19.00	2974.00	5	Dir. Drill 6" Hole 2903 - 2974m

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 25 31/10/2005

Total Depth	**(m)**	:	3025	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: Suire
Drilled last 24 hrs	**(m)**	:	51	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: Lye (25), Wayne Mclennan (15)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)**	:		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
3000.49	20.97	132.92	2871.91	755.20	S44.00E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 5: 215.87 m; Bit #4 (162.25 hrs), PDM #4 (44. hrs), Sub, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	62	21	15.0	6.0 / 9.0	4		6.00	0.25	82.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	00:00	24.00	3025.00	5	Dir. Drill 6" Hole 2974 - 3025m

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 26 1/11/2005

Total Depth	**(m)**	:	3109	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Reid
Drilled last 24 hrs	**(m)**	:	84	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (26), Wayne Mclennan (16)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
3086.24	22.18	135.33	2951.48	787.13	S44.09E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 5: 215.87 m; Bit #4 (186.25 hrs), PDM #4 (68. hrs), Sub, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	65	22	18.0	6.0 / 13.0	4		4.80	0.25	89.30

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	00:00	24.00	3109.00	5	Dir. Drill 6" Hole 3025 - 3109m

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 27 2/11/2005

Total Depth	**(m)**	:	3162	**Casing Depth**	**(m)**	:	2395.00
Drilled last 24 hrs	**(m)**	:	53	**Casing Diameter**	**(in)**	:	7.000
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)**	:	

Operator Reps : Reid
SSDS Reps : Lye (27), Wayne Mclennan (17)

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
3143.80	21.05	141.58	3004.94	808.43	S44.02E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 5: 215.87 m; Bit #4 (210.25 hrs), PDM #4 (92. hrs), Sub, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	66	23	17.0	6.0 / 13.0	4		5.00	0.25	88.70

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	00:00	24.00	3162.00	5	Dir. Drill 6" Hole 3109 - 3162m

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS **Report #** 28 3/11/2005

Total Depth	**(m)**	:	3189	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Reid
Drilled last 24 hrs	**(m)**	:	27	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (28), Wayne Mclennan (18)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
3172.54	20.63	144.17	3031.80	818.58	S43.94E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 5: 215.87 m; Bit #4 (230.75 hrs), PDM #4 (113.5 hrs), Sub, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	70	23	20.0	7.0 / 14.0	5		4.90	0.25	87.60

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	10:30	10.50	3182.00	5	Dir. Drill 6" Hole 3162 - 3182m
10:30	11:30	1.00	3182.00	5	Circulate hole clean
11:30	12:00	0.50	3182.00	5	Deviation Survey, flow check
12:00	13:00	1.00	3182.00	5	15 stand wiper trip to 2849m
13:00	13:30	0.50	3182.00	5	Service Rig
13:30	14:00	0.50	3182.00	5	Trip In to 3161m
14:00	14:30	0.50	3182.00	5	Wash to bottom
14:30	00:00	9.50	3189.00	5	Dir. Drill 6" Hole 3182 - 3189m

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 29 4/11/2005

Total Depth	**(m)**	:	3223	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Reid
Drilled last 24 hrs	**(m)**	:	34	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (29), Wayne Mclennan (19)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
3201.13	19.54	147.86	3058.66	828.25	S43.82E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 5: 215.87 m; Bit #4 (254.75 hrs), PDM #4 (137.5 hrs), Sub, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	70	23	20.0	7.0 / 14.0	5		4.90	0.25	87.60

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	00:00	24.00	3223.00	5	Drill 6" Hole 3189 - 3223m

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 30 5/11/2005

Total Depth	**(m)**	:	3297	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Reid
Drilled last 24 hrs	**(m)**	:	74	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (30), Wayne Mclennan (20)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
3229.81	18.80	151.07	3085.75	837.41	S43.67E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 5: 215.87 m; Bit #4 (275.5 hrs), PDM #4 (159.5 hrs), Sub, MWD, HWDP, Jar, 4x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	77	28	18.0	7.0 / 15.0	3		4.90	0.25	87.10

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	20:00	20.00	3297.00	5	Rot. Drill 6" hole 3223 - 3297m.
20:00	20:45	0.75	3297.00	5	Reaming / Washing , work tite hole on Conn.
20:45	22:00	1.25	3297.00	5	Circulate, sweep, slug.
22:00	00:00	2.00	3297.00	5	Trip Out

COMMENTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048

CURRENT STATUS Report # 31 6/11/2005

Total Depth	**(m)**	:	3297	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : Reid
Drilled last 24 hrs	**(m)**	:	0	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : Lye (31), Wayne Mclennan (21)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
3229.81	18.80	151.07	3085.75	837.41	S43.67E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 5: 215.87 m; Bit #4 (275.5 hrs), PDM #4 (159.5 hrs), Sub, MWD, HWDP, Jar, 4x HWDP
BHA 6: 224.53 m; Bit # (0. hrs), Sub, 2x DC, 6x HWDP, Jar, 15x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	77	28	18.0	7.0 / 15.0	3		4.90	0.25	87.10

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	04:30	4.50	3297.00	5	Cont. POOH.
04:30	05:30	1.00	3297.00	5	Dir. BHA @ surface, L/O same.
05:30	06:30	1.00	3297.00	5	PU Rot. BHA
06:30	12:00	5.50	3297.00	6	Trip In

COMMENTS

SECTION 4

BHA REPORTS

sperry-sun
DRILLING SERVICES

BHA Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048 **BHA# 2**

BHA# 2 : **Date In** :7/10/2005 **MD In (m) :** 0 **TVD In (m) :** 0 **Date Out** 8/10/2005 **MD Out (m):** 659 **TVD Out (m):** 659

BIT DATA

Bit #	OD (in)	MFR	Style	Serial#	Nozzles (/32's)	TFA (in²)	Dull Condition
1rr1	12.250	Sec	XLC1	10584381	3x20	0.920	1-1-NO-A -G-I-NO-TD

MOTOR DATA

Run #	OD (in)	MFR	Model	Serial#	Bend	Nzl (/32's)	Avg Dif (psi)	Cum Circ Hrs
1	8.000	SSDS	SperryDrill	800237	1.15°		63	32.25

COMPONENT DATA

Item #	Description	Serial #	OD (in)	ID (in)	Gauge (in)	Weight (lbs/ft)	Top Con	Length (m)	Bit - Center Blade (m)
1	Roller Cone Steel	10584381	12.250		12.250	150.00	P 6-5/8" Reg	0.36	
2	8" SperryDrill Lobe 6/7 - 4.0 stg	800237	8.000	5.250	12.000	97.54	B 6-5/8" Reg	8.25	0.98
3	Integral Blade Stabilizer				12.250	180.00	B 6-5/8" Reg	2.21	9.72
4	Float Sub		8.000	3.250		143.03	B 6-5/8" Reg	0.97	
5	NMDrill collar		8.000	3.250		143.00	B 6-5/8" Reg	8.35	
6	Non-Mag NMHang-off Sub	413543	8.000	2.810		150.17	B 6-5/8" Reg	1.95	
7	2x Drill collar		8.000	2.810		150.17	B 6-5/8" Reg	17.85	
8	Cross Over Sub		8.000	2.810		150.17	B 4" IF	0.80	
9	6x Drill collar		6.500	2.813		92.00	B 4" IF	55.73	
10	12x HWDP		4.500	2.750		41.00	B 4" IF	112.11	
11	Dailey Drilling Jar					46.00	B 4" IF	9.87	
12	6x HWDP		4.500	2.750		41.00		56.46	
								274.91	

Parameter	Min	Max	Ave
WOB (lbs) :	3	15	9
RPM (rpm) :	80	90	90
Flow (gpm) :	570	630	576
SPP (psi) :	1070	1280	1154

Activity	Hrs
Drilling :	31.25
Reaming :	0.00
Circ-Other :	1.00
Total :	32.25

BHA Weight	(lb)
in Air (Total) :	59630
in Mud (Total) :	51419
in Air (Bel Jars) :	50546
in Mud (Bel Jars) :	43525

Drill String	OD(in)	Len (m)

PERFORMANCE

	In	Out
Inclination (deg)	0.00	1.99
Azimuth (deg)	0.00	112.05

	Distance (m)	ROP (m/hr)	Build (°/30m)	Turn (°/30m)	DLS (°/30m)
Oriented :	260.00	27			
Rotated :	399.00	17			
Total :	659.00	21	0.09	0.00	0.09

COMMENTS

OBJECTIVES:

To keep hole as near enough to vertical to avoid approaching the nearby producing well Piakau 2.

sperry-sun
DRILLING SERVICES

BHA Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048 **BHA# 3**

BHA# 3 : **Date In** :11/10/200 **MD In (m) :** 659 **TVD In (m) :** 659 **Date Out** 20/10/200 **MD Out (m):** 2403 **TVD Out (m):** 2308

BIT DATA

Bit #	OD (in)	MFR	Style	Serial#	Nozzles (/32's)	TFA (in²)	Dull Condition
2	8.500	Hycalog	DSX104HG	111856	5x13	0.648	2-6-BT-G -X-I-WT-TD

MOTOR DATA

Run #	OD (in)	MFR	Model	Serial#	Bend	Nzl (/32's)	Avg Dif (psi)	Cum Circ Hrs
2	6.750	SSDS	SperryDrill	675059	1.50°		111	164.75

COMPONENT DATA

Item #	Description	Serial #	OD (in)	ID (in)	Gauge (in)	Weight (lbs/ft)	Top Con	Length (m)	Bit - Center Blade (m)
1	8 1/2" Hyc PDC (5x 14)	111856	8.500	8.000	8.500	22.08	P 4-1/2" Reg	0.22	
2	6-3/4" SperryDrill Lobe 6/7 - 5.0 stg	675059	6.750	4.498	8.125	67.81	B 4-1/2" IF	7.70	0.87
3	Integral Blade Stabilizer	252804	6.500	2.810	7.750	91.95	B 4-1/2" IF	1.83	8.87
4	Non-Mag Float Sub	10752993	6.750	2.810		100.82	B 4-1/2" IF	1.02	
5	Non-Mag HOC	10459571	6.500	3.250		85.00	B 4-1/2" IF	9.94	
6	Cross Over Sub	GP1330339-6	6.250	2.810		83.42	B 4" IF	1.16	
7	12x HWDP		4.500	2.750		41.00	B 4" IF	112.11	
8	Dailey Drilling Jar	J63	6.250	2.750		84.31	B 4" IF	9.87	
9	6x HWDP		4.500	2.750		41.00	B 4" IF	56.46	
								200.31	

Parameter	Min	Max	Ave
WOB (lbs) :	2	14	5
RPM (rpm) :	50	80	72
Flow (gpm) :	456	510	485
SPP (psi) :	950	1850	1437

Activity	Hrs
Drilling :	155.00
Reaming :	4.00
Circ-Other :	5.75
Total :	164.75

BHA Weight	(lb)
in Air (Total) :	31113
in Mud (Total) :	26703
in Air (Bel Jars) :	20788
in Mud (Bel Jars) :	17842

Drill String	OD(in)	Len (m)

PERFORMANCE

	In	Out
Inclination (deg)	1.99	19.97
Azimuth (deg)	112.05	141.91

	Distance (m)	ROP (m/hr)	Build (°/30m)	Turn (°/30m)	DLS (°/30m)
Oriented :	171.00	13			
Rotated :	1573.00	11			
Total :	1744.00	11	0.31	0.51	0.31

COMMENTS

OBJECTIVES:

Drill out Float, shoe track, rotate MWD clear of magnetic interference from casing, then build at 3°/30m to 20 degrees on 136 degrees azimith by 850m MD then hold to 7" casing point @ 2400m.

RESULTS:

Excellent BHA, only required short slides to affect a correction. Became less responsive with depth probably due to some gauge wear with the 1.5 degree bend, which was to be expected. Hole became progressively stickier with depth, as expected with this type of mud, this caused more erratic tool faces during slides but as can be seen a good result is possible with perseverence.

RECOMMENDATIONS:

Good assembly to use at this sail angle.

sperry-sun
DRILLING SERVICES

BHA Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048 **BHA# 4**

BHA# 4 : **Date In** :22/10/200 **MD In (m) :** 2403 **TVD In (m) :** 2308 **Date Out** 29/10/200 **MD Out (m):** 2903 **TVD Out (m):** 2781

BIT DATA

Bit #	OD (in)	MFR	Style	Serial#	Nozzles (/32's)	TFA (in²)	Dull Condition
3	6.000	Reed Hycalog	DSX516	113097	5x13	0.648	3-6-WT-A -X-I-CT-PR

MOTOR DATA

Run #	OD (in)	MFR	Model	Serial#	Bend	Nzl (/32's)	Avg Dif (psi)	Cum Circ Hrs
3	4.750	SSDS	SperryDrill	475NZ1	1.15°		132	124.50

COMPONENT DATA

Item #	Description	Serial #	OD (in)	ID (in)	Gauge (in)	Weight (lbs/ft)	Top Con	Length (m)	Bit - Center Blade (m)
1	PDC Reed Hycalog	113097	6.000	2.800	6.000	75.37	P 3-1/2" Reg	0.20	
2	4-3/4" SperryDrill Lobe 7/8 - 2.2 stg	475NZ1	4.750	2.901	5.813	37.87	B 3-1/2" IF	6.17	0.84
3	Float Sub	SSDS2949	4.687	2.250		45.25	B 3-1/2" IF	0.48	
4	Integral Blade Stabilizer	240256	4.750	2.250	5.750	46.84	B 3-1/2" IF	1.57	7.45
5	DWD SlimHole	91927	4.750	2.625		41.95	B 3-1/2" IF	5.13	
6	17 x HWDP		3.500	2.063		25.30	B 3-1/2" IF	158.22	
7	Jar		4.750	2.500		43.66	B 3-1/2" IF	8.99	
8	4x HWDP		3.500	2.063		25.30	B 3-1/2" IF	37.33	
								218.09	

Parameter	Min	Max	Ave
WOB (lbs) :	3	13	7
RPM (rpm) :	60	80	75
Flow (gpm) :	200	245	222
SPP (psi) :	2380	2820	2524

Activity	Hrs
Drilling :	117.25
Reaming :	0.00
Circ-Other :	7.25
Total :	124.50

BHA Weight	(lb)
in Air (Total) :	19354
in Mud (Total) :	16817
in Air (Bel Jars) :	14968
in Mud (Bel Jars) :	13006

Drill String	OD(in)	Len (m)

PERFORMANCE

	In	Out
Inclination (deg)	19.97	20.49
Azimuth (deg)	141.91	130.14

	Distance (m)	ROP (m/hr)	Build (°/30m)	Turn (°/30m)	DLS (°/30m)
Oriented :	123.00	2			0.80
Rotated :	377.00	5	-0.30	0.80	
Total :	500.00	4	0.03	-0.71	0.25

COMMENTS

Drill out float, shoe, shoe track then hold tangent to TD with corrections where needed.

OBJECTIVES:

Drill out float, shoe and hold Tangent to TD with corrections where needed.

RESULTS:

Excellent, BHA performed as expected.

sperry-sun
DRILLING SERVICES

BHA Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1
Field : Ahuroa
Slot : B-1
Rig : Parker 252
Job # : NZ-DD-0003978048 **BHA# 5**

BHA# 5 : **Date In** :29/10/200 **MD In (m) :** 2903 **TVD In (m) :** 2781 **Date Out** 6/11/2005 **MD Out (m):** 3297 **TVD Out (m):** 3150

BIT DATA

Bit #	OD (in)	MFR	Style	Serial#	Nozzles (/32's)	TFA (in²)	Dull Condition
4	6.000	Reed Hycalog	DSX516M-B1	113097	3x13, 2x15	0.734	

MOTOR DATA

Run #	OD (in)	MFR	Model	Serial#	Bend	Nzl (/32's)	Avg Dif (psi)	Cum Circ Hrs
4	4.750	SSDS	SperryDrill	475364	1.15°		178	159.50

COMPONENT DATA

Item #	Description	Serial #	OD (in)	ID (in)	Gauge (in)	Weight (lbs/ft)	Top Con	Length (m)	Bit - Center Blade (m)
1	PDC Reed Hycalog	113097	6.000	2.800	6.000	75.37	P 3-1/2" Reg	0.20	
2	4-3/4" SperryDrill Lobe 7/8 - 2.2 stg	475364	4.750	2.901	5.813	37.87	B 3-1/2" IF	5.52	0.64
3	Float Sub	SSDS2949	4.687	2.250		45.25	B 3-1/2" IF	0.48	
4	DWD SlimHole	91927	4.750	2.625		41.95	B 3-1/2" IF	5.13	
5	17 x HWDP		3.500	2.063		25.30	B 3-1/2" IF	158.22	
6	Jar		4.750	2.500		43.66	B 3-1/2" IF	8.99	
7	4x HWDP		3.500	2.063		25.30	B 3-1/2" IF	37.33	
								215.87	

Parameter	Min	Max	Ave
WOB (lbs) :	2	12	9
RPM (rpm) :	80	80	80
Flow (gpm) :	200	200	200
SPP (psi) :	2130	2500	2332

Activity	Hrs
Drilling :	155.00
Reaming :	1.25
Circ-Other :	3.25
Total :	159.50

BHA Weight	(lb)
in Air (Total) :	19032
in Mud (Total) :	16508
in Air (Bel Jars) :	14646
in Mud (Bel Jars) :	12704

Drill String	OD(in)	Len (m)

PERFORMANCE

	In	Out
Inclination (deg)	20.49	17.31
Azimuth (deg)	130.14	159.55

	Distance (m)	ROP (m/hr)	Build (°/30m)	Turn (°/30m)	DLS (°/30m)
Oriented :	13.00	1			
Rotated :	381.00	3			
Total :	394.00	3	-0.24	2.24	0.76

COMMENTS

OBJECTIVES:

Hold tangent to TD with corrections where required.

RESULTS:

Achieved results required. Due to slow ROP on correction slides the operator requested that we rotated from 3100m as the well was well within tolerances.
Observed that the Lower bearing retainer sub had backed out of the bearing housing when motor reached surface. No loss of performance was noticed during the run. Only 1/8" movement in the bearing.

SECTION 5

FINAL SURVEY DATA AND PLOT

HALLIBURTON

Sperry Drilling Services

Swift Energy NZ Ltd.

Ahuroa
Ahuroa South
Ahuroa South B-1
Ahuroa South B-1

Design: Ahuroa South B-1

Standard Survey Report

14 February, 2006



Company:	Swift Energy NZ Ltd.	**Local Co-ordinate Reference:**	Well Ahuroa South B-1
Project:	Ahuroa	**TVD Reference:**	New RKB @ 201.74m (Rig 252)
Site:	Ahuroa South	**MD Reference:**	New RKB @ 201.74m (Rig 252)
Well:	Ahuroa South B-1	**North Reference:**	Grid
Wellbore:	Ahuroa South B-1	**Survey Calculation Method:**	Minimum Curvature
Design:	Ahuroa South B-1	**Database:**	New Zealand Database

Project Ahuroa

Map System:	New Zealand Map Grid	**System Datum:**	Mean Sea Level
Geo Datum:	Geodetic Datum 1949		
Map Zone:	New Zealand Map Grid		

Site Ahuroa South

Site Position:		**Northing:**	6,214,674.11 m	**Latitude:**	39° 16' 00.946" S
From:	Map	**Easting:**	2,625,685.92 m	**Longitude:**	174° 20' 23.782" E
Position Uncertainty:	0.00 m	**Slot Radius:**	20.000 in	**Grid Convergence:**	-0.89 °

Well Ahuroa South B-1

Well Position	**+N/-S**	0.00 m	**Northing:**	6,214,665.80 m	**Latitude:**	39° 16' 01.197" S
	+E/-W	0.00 m	**Easting:**	2,625,724.00 m	**Longitude:**	174° 20' 25.375" E
Position Uncertainty		0.00 m	**Wellhead Elevation:**	5.54 m	**Ground Level:**	196.20 m

Wellbore Ahuroa South B-1

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	BGGM2005	11/08/2005	20.71	-64.95	55,440

Design Ahuroa South B-1

Audit Notes:

Version:	1.0	**Phase:**	ACTUAL	**Tie On Depth:**	0.00

Vertical Section:	Depth From (TVD) (m)	+N/-S (m)	+E/-W (m)	Direction (°)
	0.00	0.00	0.00	136.086

Survey Program **Date** 13/02/2006

From (m)	To (m)	Survey (Wellbore)	Tool Name	Description
171.54	3,229.81	Ahurua South B-1 (Ahuroa South B-1)	MWD Magnetic	MWD Magnetic Survey (Thorogood)

Survey

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)
0.00	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.00	0.00
171.64	1.590	306.300	171.62	1.41	-1.92	-2.35	0.278	0.28	0.00
210.33	1.560	306.000	210.29	2.04	-2.78	-3.39	0.024	-0.02	-0.23
238.56	1.860	311.190	238.51	2.56	-3.43	-4.23	0.358	0.32	5.52
266.79	1.240	299.500	266.73	3.02	-4.04	-4.98	0.736	-0.66	-12.42
294.18	0.870	291.280	294.12	3.24	-4.50	-5.45	0.437	-0.41	-9.00
321.10	0.740	248.000	321.03	3.25	-4.85	-5.70	0.675	-0.14	-48.23
347.95	0.810	213.080	347.88	3.02	-5.11	-5.72	0.525	0.08	-39.02
374.63	0.810	204.330	374.56	2.69	-5.29	-5.61	0.139	0.00	-9.84
401.53	0.800	194.320	401.46	2.34	-5.42	-5.44	0.157	-0.01	-11.16
428.37	0.760	191.070	428.29	1.98	-5.50	-5.24	0.067	-0.04	-3.63
455.21	1.460	166.360	455.13	1.48	-5.45	-4.84	0.931	0.78	-27.62
482.01	1.610	157.580	481.92	0.80	-5.23	-4.20	0.312	0.17	-9.83

Company:	Swift Energy NZ Ltd.	**Local Co-ordinate Reference:**	Well Ahuroa South B-1
Project:	Ahuroa	**TVD Reference:**	New RKB @ 201.74m (Rig 252)
Site:	Ahuroa South	**MD Reference:**	New RKB @ 201.74m (Rig 252)
Well:	Ahuroa South B-1	**North Reference:**	Grid
Wellbore:	Ahuroa South B-1	**Survey Calculation Method:**	Minimum Curvature
Design:	Ahuroa South B-1	**Database:**	New Zealand Database

Survey

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)
508.82	1.350	159.080	508.72	0.15	-4.97	-3.56	0.294	-0.29	1.68
535.74	1.230	157.390	535.63	-0.41	-4.75	-3.00	0.140	-0.13	-1.88
562.69	1.700	122.650	562.57	-0.89	-4.30	-2.34	1.094	0.52	-38.67
598.41	2.020	110.640	598.28	-1.40	-3.26	-1.25	0.422	0.27	-10.09
640.10	2.030	114.200	639.94	-1.96	-1.90	0.09	0.091	0.01	2.56
666.76	1.980	111.150	666.58	-2.32	-1.04	0.95	0.133	-0.06	-3.43
702.54	6.800	153.150	702.25	-4.44	0.49	3.54	4.603	4.04	35.22
720.47	8.980	151.120	720.01	-6.61	1.65	5.90	3.677	3.65	-3.40
747.29	11.400	142.560	746.41	-10.55	4.27	10.56	3.186	2.71	-9.57
765.10	12.040	140.940	763.85	-13.39	6.51	14.16	1.212	1.08	-2.73
782.98	13.350	139.300	781.29	-16.40	9.03	18.08	2.279	2.20	-2.75
800.90	15.180	135.820	798.66	-19.65	12.02	22.49	3.382	3.06	-5.83
827.62	16.960	130.440	824.33	-24.69	17.42	29.87	2.604	2.00	-6.04
854.53	17.410	129.520	850.04	-29.80	23.51	37.77	0.586	0.50	-1.03
881.45	18.980	130.450	875.62	-35.20	29.95	46.13	1.779	1.75	1.04
908.74	19.550	131.170	901.38	-41.09	36.77	55.10	0.679	0.63	0.79
935.58	19.860	130.440	926.65	-47.00	43.62	64.11	0.442	0.35	-0.82
962.41	19.330	131.710	951.92	-52.91	50.40	73.07	0.760	-0.59	1.42
989.18	18.580	134.390	977.24	-58.84	56.76	81.75	1.287	-0.84	3.00
1,015.89	18.940	134.930	1,002.53	-64.88	62.87	90.34	0.449	0.40	0.61
1,042.82	19.460	134.620	1,027.96	-71.12	69.15	99.19	0.590	0.58	-0.35
1,070.64	19.790	133.810	1,054.17	-77.63	75.85	108.53	0.461	0.36	-0.87
1,097.43	19.810	132.430	1,079.37	-83.84	82.47	117.60	0.524	0.02	-1.55
1,124.27	19.470	133.900	1,104.65	-90.01	89.05	126.60	0.670	-0.38	1.64
1,151.11	18.960	137.120	1,130.00	-96.30	95.24	135.43	1.314	-0.57	3.60
1,178.00	18.890	137.820	1,155.43	-102.73	101.14	144.15	0.265	-0.08	0.78
1,204.71	19.520	136.500	1,180.66	-109.17	107.11	152.94	0.859	0.71	-1.48
1,231.46	20.140	136.470	1,205.82	-115.75	113.36	162.01	0.695	0.70	-0.03
1,258.28	20.760	135.860	1,230.95	-122.51	119.85	171.38	0.733	0.69	-0.68
1,285.30	20.580	135.560	1,256.23	-129.34	126.51	180.92	0.232	-0.20	-0.33
1,312.05	17.630	137.590	1,281.51	-135.69	132.54	189.67	3.391	-3.31	2.28
1,338.88	17.410	138.690	1,307.09	-141.70	137.93	197.74	0.445	-0.25	1.23
1,365.74	17.600	138.600	1,332.71	-147.77	143.27	205.81	0.214	0.21	-0.10
1,392.60	17.530	138.570	1,358.32	-153.84	148.63	213.91	0.079	-0.08	-0.03
1,420.46	18.940	136.540	1,384.78	-160.27	154.52	222.63	1.665	1.52	-2.19
1,447.30	19.290	135.900	1,410.14	-166.62	160.60	231.41	0.456	0.39	-0.72
1,474.18	19.860	135.220	1,435.46	-173.05	166.90	240.42	0.685	0.64	-0.76
1,500.90	20.160	134.480	1,460.57	-179.50	173.38	249.56	0.441	0.34	-0.83
1,528.27	20.680	134.120	1,486.22	-186.16	180.22	259.11	0.586	0.57	-0.39
1,555.00	21.300	133.720	1,511.18	-192.81	187.12	268.67	0.714	0.70	-0.45
1,581.80	20.840	134.880	1,536.18	-199.53	194.01	278.30	0.695	-0.51	1.30
1,608.56	20.570	135.080	1,561.22	-206.22	200.70	287.76	0.313	-0.30	0.22
1,635.53	19.730	135.140	1,586.53	-212.80	207.26	297.05	0.935	-0.93	0.07
1,662.21	20.060	135.120	1,611.62	-219.24	213.67	306.13	0.371	0.37	-0.02
1,689.11	20.170	135.160	1,636.88	-225.79	220.19	315.38	0.124	0.12	0.04
1,715.94	20.330	134.590	1,662.05	-232.35	226.77	324.66	0.284	0.18	-0.64
1,742.90	20.690	133.960	1,687.30	-238.94	233.54	334.10	0.470	0.40	-0.70
1,769.75	20.870	133.790	1,712.41	-245.54	240.40	343.62	0.212	0.20	-0.19
1,798.31	20.160	134.560	1,739.16	-252.52	247.58	353.63	0.798	-0.75	0.81
1,826.31	19.740	134.840	1,765.48	-259.24	254.37	363.18	0.461	-0.45	0.30
1,854.52	19.430	134.560	1,792.05	-265.89	261.09	372.63	0.344	-0.33	-0.30
1,882.71	19.250	135.040	1,818.65	-272.47	267.72	381.96	0.256	-0.19	0.51
1,910.83	18.930	134.200	1,845.23	-278.93	274.26	391.16	0.450	-0.34	-0.90
1,938.53	19.020	135.210	1,871.42	-285.26	280.67	400.16	0.369	0.10	1.09

Company:	Swift Energy NZ Ltd.	**Local Co-ordinate Reference:**	Well Ahuroa South B-1
Project:	Ahuroa	**TVD Reference:**	New RKB @ 201.74m (Rig 252)
Site:	Ahuroa South	**MD Reference:**	New RKB @ 201.74m (Rig 252)
Well:	Ahuroa South B-1	**North Reference:**	Grid
Wellbore:	Ahuroa South B-1	**Survey Calculation Method:**	Minimum Curvature
Design:	Ahuroa South B-1	**Database:**	New Zealand Database

Survey

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)
1,967.08	19.080	135.490	1,898.41	-291.89	287.21	409.48	0.115	0.06	0.29
1,995.35	18.900	135.710	1,925.14	-298.46	293.65	418.68	0.206	-0.19	0.23
2,023.52	18.590	135.520	1,951.82	-304.93	299.98	427.73	0.336	-0.33	-0.20
2,052.56	19.210	136.770	1,979.29	-311.72	306.50	437.14	0.765	0.64	1.29
2,081.20	19.190	137.350	2,006.34	-318.61	312.91	446.55	0.201	-0.02	0.61
2,110.05	19.430	138.720	2,033.56	-325.71	319.29	456.09	0.533	0.25	1.42
2,138.42	20.660	139.960	2,060.21	-333.08	325.63	465.79	1.376	1.30	1.31
2,167.28	20.950	140.910	2,087.19	-340.99	332.15	476.02	0.462	0.30	0.99
2,195.91	20.970	140.940	2,113.93	-348.94	338.61	486.22	0.024	0.02	0.03
2,224.19	20.970	141.280	2,140.34	-356.81	344.96	496.30	0.129	0.00	0.36
2,253.04	20.500	139.140	2,167.32	-364.66	351.50	506.49	0.927	-0.49	-2.23
2,291.52	20.350	138.830	2,203.38	-374.80	360.31	519.90	0.144	-0.12	-0.24
2,319.87	20.220	139.300	2,229.97	-382.22	366.75	529.71	0.221	-0.14	0.50
2,348.33	19.970	140.390	2,256.70	-389.69	373.06	539.47	0.475	-0.26	1.15
2,378.00	19.930	141.010	2,284.59	-397.53	379.47	549.56	0.218	-0.04	0.63
2,394.90	19.956	141.616	2,300.47	-402.03	383.07	555.30	0.370	0.05	1.08
7"									
2,409.54	19.980	142.140	2,314.23	-405.96	386.16	560.28	0.370	0.05	1.07
2,438.25	19.300	141.450	2,341.27	-413.54	392.13	569.88	0.751	-0.71	-0.72
2,466.42	18.890	138.580	2,367.89	-420.60	398.04	579.07	1.091	-0.44	-3.06
2,493.65	18.810	135.440	2,393.66	-427.04	404.04	587.86	1.121	-0.09	-3.46
2,521.81	18.400	135.690	2,420.35	-433.45	410.33	596.85	0.445	-0.44	0.27
2,549.28	18.540	134.410	2,446.41	-439.61	416.48	605.55	0.469	0.15	-1.40
2,577.88	18.980	134.620	2,473.49	-446.06	423.04	614.74	0.467	0.46	0.22
2,606.78	19.530	134.730	2,500.77	-452.76	429.81	624.27	0.572	0.57	0.11
2,634.32	19.030	136.130	2,526.77	-459.24	436.20	633.36	0.742	-0.54	1.53
2,662.32	18.530	137.150	2,553.28	-465.79	442.39	642.37	0.641	-0.54	1.09
2,690.57	18.770	134.200	2,580.04	-472.25	448.70	651.41	1.034	0.25	-3.13
2,718.54	19.230	133.960	2,606.49	-478.58	455.24	660.51	0.500	0.49	-0.26
2,746.40	18.270	136.720	2,632.87	-484.95	461.54	669.46	1.407	-1.03	2.97
2,773.77	19.190	134.730	2,658.79	-491.24	467.67	678.24	1.228	1.01	-2.18
2,803.47	18.900	135.140	2,686.87	-498.08	474.53	687.93	0.323	-0.29	0.41
2,822.15	18.120	136.730	2,704.58	-502.34	478.66	693.86	1.492	-1.25	2.55
2,850.50	18.310	135.260	2,731.51	-508.71	484.81	702.73	0.526	0.20	-1.56
2,879.09	19.210	130.070	2,758.58	-514.93	491.58	711.89	1.989	0.94	-5.45
2,915.60	21.160	130.180	2,792.85	-523.05	501.21	724.42	1.603	1.60	0.09
2,944.18	21.730	130.240	2,819.45	-529.80	509.19	734.82	0.599	0.60	0.06
2,972.15	21.260	130.940	2,845.47	-536.46	516.97	745.02	0.574	-0.50	0.75
3,000.49	20.970	132.920	2,871.91	-543.29	524.57	755.20	0.815	-0.31	2.10
3,029.69	21.950	133.210	2,899.09	-550.58	532.37	765.87	1.013	1.01	0.30
3,057.92	22.130	133.880	2,925.25	-557.88	540.05	776.45	0.329	0.19	0.71
3,086.24	22.180	135.330	2,951.48	-565.38	547.65	787.13	0.582	0.05	1.54
3,115.04	21.890	138.310	2,978.18	-573.25	555.04	797.93	1.203	-0.30	3.10
3,143.80	21.050	141.580	3,004.94	-581.30	561.82	808.43	1.525	-0.88	3.41
3,167.13	20.706	143.675	3,026.74	-587.91	566.87	816.68	1.057	-0.44	2.69
Target - Ahuroa South B-1 rev7									
3,172.54	20.630	144.170	3,031.81	-589.45	567.99	818.58	1.057	-0.42	2.75
3,201.13	19.540	147.860	3,058.66	-597.58	573.48	828.24	1.753	-1.14	3.87
3,229.81	18.800	151.070	3,085.75	-605.69	578.27	837.40	1.347	-0.77	3.36

Company:	Swift Energy NZ Ltd.	**Local Co-ordinate Reference:**	Well Ahuroa South B-1
Project:	Ahuroa	**TVD Reference:**	New RKB @ 201.74m (Rig 252)
Site:	Ahuroa South	**MD Reference:**	New RKB @ 201.74m (Rig 252)
Well:	Ahuroa South B-1	**North Reference:**	Grid
Wellbore:	Ahuroa South B-1	**Survey Calculation Method:**	Minimum Curvature
Design:	Ahuroa South B-1	**Database:**	New Zealand Database

Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (m)	+N/-S m	+E/-W m	Northing (m)	Easting (m)	Latitude	Longitude
Target - Ahuroa South	0.00	0.00	3,026.74	-585.80	564.00	6,214,080.00	2,626,288.00	39° 16' 19.908" S	174° 20' 49.282" E
- actual wellpath misses by 3.56m at 3167.13m MD (3026.74 TVD, -587.91 N, 566.87 E)									
- Circle (radius 50.00)									


Casing Points

Measured Depth (m)	Vertical Depth (m)	Name	Casing Diameter (in)	Hole Diameter (in)
2,394.90	2,300.47	7"	7.000	7.500

Checked By: _____ Approved By: _____ Date: _____

Sperry Drilling Services

Project: Ahuroa
Well: Ahuroa South B-1
Design: Ahuroa South B-1



POST WELL ANALYSIS

AHUROA SOUTH B-1 ST1

CUSTOMER : SWIFT ENERGY NZ LTD.

WELL : AHUROA SOUTH B-1 ST1

RIG : PARKER RIG 252

LOCATION : AHUROA

DIRECTIONAL DRILLING PERSONNEL

B. WOOD
G. HUNGER
P. GALLAGHER

Sperry Drilling Services

HALLIBURTON

Table of Contents

1. Job Objectives/Summary
2. Proposal Data & Plot
3. Directional Drilling Record / Daily Reports
4. BHA Reports
5. Definitive Survey and Plot

SECTION 1

JOB OBJECTIVES / SUMMARY

Customer : Swift Energy NZ Ltd

Well : Ahuroa South B-1 ST1

Job Objectives:

Side track the well directly outside the 7" shoe (low side).
Drop the inclination back past zero to 2.65 degrees in the opposite direction to intersect the new target.

Summary of Results:

BHA #1 2400 - 2433m MD

The well was sidetracked successfully during this interval. Time drilling began at 2400m MD and concluded at 2423m MD. Sliding continued from 2423 - 2429m MD and rotary mode was used through to 2433m MD.
The survey from 2422.8m MD indicated a build in the well where all sliding and time drilling was to side track the well low side. Further investigation found the MWD tool offset data had not been updated form the previous probe run and subsequently was 147 degrees out. ROP with the Smith 117 was poor and the agreed bit hours were nearly up so the decison was made to POOH and rectify all short commings.

BHA #2 2433 -2874m MD

Sliding was easy and controlable during the drop and early part of the build, then as formations became harder sliding became very slow. In the Tariki ROP slowed to 1 - 3m/hr. During the low angle tangent section the assembly built angle at 1.05°/30m on average. There were two large azimuth swings toward the west at 2734m and 2849m MD. Despite 12 metres of sliding between 2830m and 2858m, the assembly still built only 1.05 degrees. The assembly was pulled due to motor hours. The hole was good during the trip out.

BHA # 3 2874m - 3085m

As expected with the new bit ROP doubled and slides although not easy with the interbeded formations were drilled at a faster ROP and only one 6m slide was needed to ensure a west side target penetration. Initial rotary drilling ROP varied between 2 - 10m/hr with 3-7k WOB through the Tariki, and Lower Otaroa claystone.
The McKee sands did not develop and instead coals were hit at 2983m and stuck pipe stopped the drilling for 6 to 8hrs before working free and controlled drilling of 1-2m/hr continued for much of the remainder of the hole.The formations came in about 130m high and by the time the proposed target was hit at 3046.9m MD the Ahuroa thrust/fault had already been intersected at 3034m in the Manganui and rat hole to 3085m was drilled before the assembly was tripped out and layed out.

Discussion:

BHA Summary:

BHA # 1 2400m - 2433m MD
6" Rollercone mill tooth bit
4 3/4" Sperrydrill Motor 7/8 Lobe 2.2 Stg.
Motor complete with 5 7/8" sleeve stabilizer
5 13/16 " String Stabilizer
Float sub , with flapper type float
4 3/4" HOC with 350 DWD system
15 x 3½" HWDP
HE drilling jar
6 x 3½" HWDP

BHA # 2 2433m - 2874m MD
6" Reed PDC bit, 5 Blades
4 3/4" Sperrydrill Motor 7/8 Lobe 2.2 Stg.
Motor complete with 5 7/8" sleeve stabilizer
5 13/16 " String Stabilizer
Float sub , with flapper type float
4 3/4" HOC with 350 DWD system
15 x 3½" HWDP

HE drilling jar
6 x 3½" HWDP

BHA # 3 2874m - 3085m MD
6" Smith Geodiamond PDC bit, 5 Blades
4 3/4" Sperrydrill Motor 7/8 Lobe 2.2 Stg.
No sleeve stabilizer installed
Float sub , with dart type float,non ported
5 13/16 " String Stabilizer
4 3/4" HOC with 350 DWD system
15 x 3½" HWDP
HE drilling jar
6 x 3½" HWDP

BHA #	Bit #	Motor Run #	Hole Size (in)	MD In (m)	MD Out (m)	TVD In (m)	TVD Out (m)	Inc In (deg)	Inc Out (deg)	Azi In (deg)	Azi Out (deg)	Drlg hrs	Circ hrs
1	1	1	6.000	2400	2432	2305	2335	20.0	22.8	142	134	38	2
2	2	2	6.000	2432	2874	2335	2770	22.8	8.0	134	300	126	1
3	3	3	6.000	2874	3085	2770	2979	8.0	8.4	300	288	96	18

Table 1 - BHA Summary

Motor Run Summary:

Motor Run # 1 2400m - 2433m MD
Size: 4 3/4"
Type: Standard Sperrydrill
Serial No.: 475NZ1
Lobe Config.: 7/8 Lobe 2.2 Stg.
Bend: 1.50°
Sleeve Stab: 5 7/8"
Motor hours this run: 39.5 hrs
Total Motor Hours: 39.5 hrs

Motor Run # 2 2433 - 2874m MD
Size: 4 3/4"
Type: Standard Sperrydrill
Serial No.: 475NZ1
Lobe Config.: 7/8 Lobe 2.2 Stg.
Bend: 1.15°
Sleeve Stab: 5 7/8"
Motor hours this run: 127.25 hrs
Total Motor Hours: 166.75 hrs

Motor Run # 3 2874 - 3085m MD
Size: 4 3/4"
Type: Standard Sperrydrill
Serial No.: 475346
Lobe Config.: 7/8 Lobe 2.2 Stg.
Bend: 1.15°
Sleeve Stab: Not installed
Motor hours this run: 113.75 hrs
Total Motor Hours: 113.75 hrs

Motor Run #	Manufacturer	Type	Lobe	OD (in)	Gauge (in)	Bend (deg)	Adj	DLS (Ori) (°/30m)	ROP (Ori) (m/hr)	ROP (Rot) (m/hr)
1	SSDS	SperryDrill	7/8	4.750	5.875	1.50	Y	4.00	0	2
2	SSDS	SperryDrill	7/8	4.750	5.875	1.15	Y	7.00	2	4
3	SSDS	SperryDrill	7/8	4.750	5.875	1.15	Y		2	2

Table 2 - Motor Run Summary

Bit Run Summary:

Bit # 1, 2400m - 2433m MD
Size : 6"
Make : Smith
Type : XR+ (Tri-cone mill tooth)
IADC: 117
Serial No : PC7092
Jets : 3 x 18

TFA: 0.746
Grading : In : NEW
Out: 1-1-NO-AL-E-I-N0-PR

Bit # 2, 2433m - 2874m MD
Size : 6"
Make : Reed / Hycalog PDC
Type : DSX519S-A3
IADC:
Serial No : 211111
Jets : 5 x 14
TFA: 0.752
Grading : In : NEW
Out 3-4-WT-S-X-I-CT-BHA


Bit # 3, 2874m - 3085m MD

Size : 6"
Make : Smith GeoDiamond PDC
Type : M516LYPX
IADC:S123
Serial No : JW3280
Jets : 3 x 13 2x16
TFA: 0.782
Grading : In : NEW
Out:


Bit #	Manufacturer	Style	OD (in)	Gge Len (in)	Nozzles (/32's)	TFA (in²)	Dull Grades I O D L B G O R	Ftge (m)	Drlg hrs	ROP (m/hr)
1	Smith	XR+	6.000		3x18	0.746		32	37.50	1
2	REED / Hycalog	DSX519S-A3	6.000	4.000	5x14	0.752		442	126.25	4
3	Smith Geo Diamond	M516LYPX	6.000	1.500	3x13, 2x16	0.782		211	96.00	2

Table 3 - Bit Run Summary


Hours by Operation Summary




Hours per BHA Breakdown




Days vs. Depth



Average Rate of Penetration per BHA




Footage per BHA



Sperry-Sun Drilling Services

Swift Energy NZ Ltd
Ahuroa South B-1 ST1
Parker 252

Taranaki
Ahuroa
NZ-DD-0004047895



SECTION 2

PROPOSAL DATA AND PLOT

Swift Energy NZ Ltd.

Ahuroa
Ahuroa South
Ahuroa South B-1
Ahuroa South B-1

Plan: Ahuroa South B-1 ST-1 rev2

Standard Planning Report

08 November, 2005

Database:	EDM 2003.11 Single User Db	**Local Co-ordinate Reference:**	Well Ahuroa South B-1
Company:	Swift Energy NZ Ltd.	**TVD Reference:**	RKB @ 201.84m (Rig 252)
Project:	Ahuroa	**MD Reference:**	RKB @ 201.84m (Rig 252)
Site:	Ahuroa South	**North Reference:**	Grid
Well:	Ahuroa South B-1	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Ahuroa South B-1		
Design:	Ahuroa South B-1 ST-1 rev2		

Project	Ahuroa		
Map System:	New Zealand Map Grid	**System Datum:**	Mean Sea Level
Geo Datum:	Geodetic Datum 1949		
Map Zone:	New Zealand Map Grid		

Site	Ahuroa South				
Site Position:		**Northing:**	6,214,674.11 m	**Latitude:**	39° 16' 0.946 S
From:	Map	**Easting:**	2,625,685.92 m	**Longitude:**	174° 20' 23.782 E
Position Uncertainty:	0.00 m	**Slot Radius:**	20.000 in	**Grid Convergence:**	-0.89 °

Well	Ahuroa South B-1					
Well Position	**+N/-S**	0.00 m	**Northing:**	6,214,665.80 m	**Latitude:**	39° 16' 1.197 S
	+E/-W	0.00 m	**Easting:**	2,625,724.00 m	**Longitude:**	174° 20' 25.375 E
Position Uncertainty		0.00 m	**Wellhead Elevation:**	5.54 m	**Ground Level:**	196.30 m

Wellbore	Ahuroa South B-1				
Magnetics	**Model Name**	**Sample Date**	**Declination (°)**	**Dip Angle (°)**	**Field Strength (nT)**
	BGGM2005	11/08/2005	20.71	-64.95	55,440

Design	Ahuroa South B-1 ST-1 rev2				
Audit Notes:					
Version:		**Phase:**	PLAN	**Tie On Depth:**	2,405.00
Vertical Section:	**Depth From (TVD) (m)**	**+N/-S (m)**	**+E/-W (m)**	**Direction (°)**	
	2,941.84	0.00	0.00	136.61	

Plan Sections

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)	TFO (°)	Target
2,405.00	19.97	141.98	2,309.97	-404.75	385.20	0.000	0.000	0.000	0.00	
2,631.18	2.65	320.81	2,532.12	-431.48	405.97	3.000	-2.298	23.720	179.86	
3,041.34	2.65	320.81	2,941.84	-416.80	394.00	0.000	0.000	0.000	0.00	Target - Ahuroa South
3,270.00	2.65	320.81	3,170.26	-408.62	387.33	0.000	0.000	0.000	0.00	

Database:	EDM 2003.11 Single User Db	**Local Co-ordinate Reference:**	Well Ahuroa South B-1
Company:	Swift Energy NZ Ltd.	**TVD Reference:**	RKB @ 201.84m (Rig 252)
Project:	Ahuroa	**MD Reference:**	RKB @ 201.84m (Rig 252)
Site:	Ahuroa South	**North Reference:**	Grid
Well:	Ahuroa South B-1	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Ahuroa South B-1		
Design:	Ahuroa South B-1 ST-1 rev2		

Planned Survey

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.00	0.00
171.64	1.59	306.30	171.62	1.41	-1.92	-2.34	0.278	0.28	0.00
210.33	1.56	306.00	210.29	2.04	-2.78	-3.39	0.024	-0.02	-0.23
238.56	1.86	311.19	238.51	2.56	-3.43	-4.22	0.358	0.32	5.52
266.79	1.24	299.50	266.73	3.02	-4.04	-4.97	0.736	-0.66	-12.42
294.18	0.87	291.28	294.12	3.24	-4.50	-5.44	0.437	-0.41	-9.00
321.10	0.74	248.00	321.03	3.25	-4.85	-5.69	0.675	-0.14	-48.23
347.95	0.81	213.08	347.88	3.02	-5.11	-5.71	0.525	0.08	-39.02
374.63	0.81	204.33	374.56	2.69	-5.29	-5.59	0.139	0.00	-9.84
401.53	0.80	194.32	401.46	2.34	-5.42	-5.42	0.157	-0.01	-11.16
428.37	0.76	191.07	428.29	1.98	-5.50	-5.22	0.067	-0.04	-3.63
455.21	1.46	166.36	455.13	1.48	-5.45	-4.82	0.931	0.78	-27.62
482.01	1.61	157.58	481.92	0.80	-5.23	-4.17	0.312	0.17	-9.83
508.82	1.35	159.08	508.72	0.15	-4.97	-3.53	0.294	-0.29	1.68
535.74	1.23	157.39	535.63	-0.41	-4.75	-2.96	0.140	-0.13	-1.88
562.69	1.70	122.65	562.57	-0.89	-4.30	-2.30	1.094	0.52	-38.67
598.41	2.02	110.64	598.28	-1.40	-3.26	-1.22	0.422	0.27	-10.09
640.10	2.03	114.20	639.94	-1.96	-1.90	0.12	0.091	0.01	2.56
659.00	2.00	114.00	658.83	-2.23	-1.30	0.73	0.049	-0.05	-0.32
666.76	1.98	111.15	666.58	-2.34	-1.05	0.98	0.390	-0.08	-11.02
702.54	6.80	153.15	702.25	-4.45	0.49	3.57	4.603	4.04	35.22
720.47	8.98	151.12	720.01	-6.62	1.64	5.94	3.677	3.65	-3.40
747.29	11.40	142.56	746.41	-10.56	4.27	10.61	3.186	2.71	-9.57
765.10	12.04	140.94	763.85	-13.40	6.51	14.21	1.212	1.08	-2.73
782.98	13.35	139.30	781.29	-16.42	9.03	18.13	2.279	2.20	-2.75
800.90	15.18	135.82	798.66	-19.67	12.01	22.54	3.382	3.06	-5.83
827.62	16.96	130.44	824.33	-24.71	17.42	29.92	2.604	2.00	-6.04
854.53	17.41	129.52	850.04	-29.81	23.51	37.82	0.586	0.50	-1.03
881.45	18.98	130.45	875.62	-35.22	29.95	46.16	1.779	1.75	1.04
908.74	19.55	131.17	901.38	-41.10	36.76	55.12	0.679	0.63	0.79
935.58	19.86	130.44	926.65	-47.01	43.61	64.13	0.442	0.35	-0.82
962.41	19.33	131.71	951.92	-52.93	50.40	73.08	0.760	-0.59	1.42
989.18	18.58	134.39	977.24	-58.86	56.75	81.76	1.287	-0.84	3.00
1,015.89	18.94	134.93	1,002.53	-64.90	62.86	90.34	0.449	0.40	0.61
1,042.82	19.46	134.62	1,027.96	-71.13	69.15	99.19	0.590	0.58	-0.35
1,070.64	19.79	133.81	1,054.17	-77.65	75.85	108.53	0.461	0.36	-0.87
1,097.43	19.81	132.43	1,079.37	-83.85	82.47	117.59	0.524	0.02	-1.55
1,124.27	19.47	133.90	1,104.65	-90.02	89.05	126.59	0.670	-0.38	1.64
1,151.11	18.96	137.12	1,130.00	-96.32	95.24	135.42	1.314	-0.57	3.60
1,178.00	18.89	137.82	1,155.43	-102.74	101.13	144.14	0.265	-0.08	0.78
1,204.71	19.52	136.50	1,180.66	-109.19	107.11	152.92	0.859	0.71	-1.48
1,231.46	20.14	136.47	1,205.82	-115.77	113.36	162.00	0.695	0.70	-0.03
1,258.28	20.76	135.86	1,230.95	-122.52	119.85	171.37	0.733	0.69	-0.68
1,285.30	20.58	135.56	1,256.23	-129.35	126.51	180.91	0.232	-0.20	-0.33
1,312.05	17.63	137.59	1,281.51	-135.70	132.53	189.66	3.391	-3.31	2.28
1,338.88	17.41	138.69	1,307.09	-141.72	137.92	197.73	0.445	-0.25	1.23
1,365.74	17.60	138.60	1,332.71	-147.78	143.26	205.81	0.214	0.21	-0.10
1,392.60	17.53	138.57	1,358.32	-153.86	148.62	213.91	0.079	-0.08	-0.03
1,420.46	18.94	136.54	1,384.78	-160.29	154.51	222.62	1.665	1.52	-2.19
1,447.30	19.29	135.90	1,410.14	-166.63	160.59	231.41	0.456	0.39	-0.72
1,474.18	19.86	135.22	1,435.46	-173.06	166.90	240.42	0.685	0.64	-0.76
1,500.90	20.16	134.48	1,460.57	-179.51	173.38	249.55	0.441	0.34	-0.83
1,528.27	20.68	134.12	1,486.22	-186.18	180.21	259.10	0.586	0.57	-0.39
1,555.00	21.30	133.70	1,511.18	-192.82	187.11	268.66	0.716	0.70	-0.47

Database:	EDM 2003.11 Single User Db	**Local Co-ordinate Reference:**	Well Ahuroa South B-1
Company:	Swift Energy NZ Ltd.	**TVD Reference:**	RKB @ 201.84m (Rig 252)
Project:	Ahuroa	**MD Reference:**	RKB @ 201.84m (Rig 252)
Site:	Ahuroa South	**North Reference:**	Grid
Well:	Ahuroa South B-1	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Ahuroa South B-1		
Design:	Ahuroa South B-1 ST-1 rev2		

Planned Survey

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)
1,581.80	20.84	134.88	1,536.18	-199.55	194.01	278.29	0.700	-0.51	1.32
1,608.56	20.57	135.08	1,561.22	-206.23	200.70	287.74	0.313	-0.30	0.22
1,635.53	19.73	135.14	1,586.53	-212.82	207.26	297.03	0.935	-0.93	0.07
1,662.21	20.06	135.12	1,611.62	-219.25	213.66	306.11	0.371	0.37	-0.02
1,689.11	20.17	135.16	1,636.88	-225.81	220.19	315.35	0.124	0.12	0.04
1,715.94	20.33	134.59	1,662.05	-232.36	226.77	324.64	0.284	0.18	-0.64
1,742.90	20.69	133.96	1,687.30	-238.95	233.53	334.07	0.470	0.40	-0.70
1,769.75	20.87	133.79	1,712.41	-245.56	240.40	343.59	0.212	0.20	-0.19
1,798.31	20.16	134.56	1,739.16	-252.53	247.58	353.59	0.798	-0.75	0.81
1,826.31	19.74	134.84	1,765.48	-259.25	254.37	363.14	0.461	-0.45	0.30
1,854.52	19.43	134.56	1,792.05	-265.90	261.09	372.59	0.344	-0.33	-0.30
1,882.71	19.25	135.04	1,818.65	-272.48	267.72	381.92	0.256	-0.19	0.51
1,910.83	18.93	134.20	1,845.23	-278.94	274.26	391.11	0.450	-0.34	-0.90
1,938.53	19.02	135.21	1,871.42	-285.27	280.66	400.11	0.369	0.10	1.09
1,967.08	19.08	135.49	1,898.41	-291.90	287.21	409.43	0.115	0.06	0.29
1,995.35	18.90	135.71	1,925.14	-298.48	293.65	418.63	0.206	-0.19	0.23
2,023.52	18.59	135.52	1,951.82	-304.95	299.98	427.68	0.336	-0.33	-0.20
2,052.66	19.21	136.77	1,979.38	-311.75	306.52	437.12	0.762	0.64	1.29
2,081.20	19.19	137.35	2,006.34	-318.62	312.91	446.50	0.202	-0.02	0.61
2,110.05	19.43	138.72	2,033.56	-325.72	319.29	456.04	0.533	0.25	1.42
2,138.42	20.66	139.96	2,060.21	-333.10	325.62	465.75	1.376	1.30	1.31
2,167.28	20.95	140.91	2,087.19	-341.00	332.15	475.98	0.462	0.30	0.99
2,195.91	20.97	140.94	2,113.93	-348.95	338.61	486.19	0.024	0.02	0.03
2,224.19	20.97	141.28	2,140.34	-356.83	344.96	496.28	0.129	0.00	0.36
2,253.04	20.50	139.14	2,167.32	-364.67	351.50	506.47	0.927	-0.49	-2.23
2,291.52	20.35	138.83	2,203.38	-374.81	360.31	519.89	0.144	-0.12	-0.24
2,319.87	20.22	139.30	2,229.97	-382.23	366.75	529.71	0.221	-0.14	0.50
2,348.33	19.97	140.39	2,256.70	-389.71	373.05	539.47	0.475	-0.26	1.15
2,378.00	19.93	141.01	2,284.59	-397.54	379.47	549.57	0.218	-0.04	0.63
2,405.00	19.97	141.98	2,309.97	-404.75	385.20	558.75	0.370	0.05	1.08
Start DLS 3.000 TFO 179.86									
2,430.00	17.47	142.00	2,333.64	-411.07	390.14	566.74	3.000	-3.00	0.02
2,460.00	14.47	142.03	2,362.48	-417.58	395.22	574.95	3.000	-3.00	0.03
2,490.00	11.47	142.08	2,391.71	-422.89	399.36	581.66	3.000	-3.00	0.05
2,520.00	8.47	142.17	2,421.25	-426.99	402.55	586.83	3.000	-3.00	0.09
2,550.00	5.47	142.35	2,451.03	-429.86	404.78	590.45	3.000	-3.00	0.18
2,580.00	2.47	142.95	2,480.95	-431.51	406.05	592.52	3.000	-3.00	0.61
2,610.00	0.53	316.67	2,510.95	-431.93	406.34	593.02	3.000	-1.94	173.72
2,631.18	2.65	320.81	2,532.12	-431.48	405.97	592.44	3.000	3.00	5.86
Start 410.16 hold at 2631.18 MD									
2,640.00	2.65	320.81	2,540.93	-431.16	405.71	592.03	0.000	0.00	0.00
2,670.00	2.65	320.81	2,570.90	-430.09	404.83	590.65	0.000	0.00	0.00
2,700.00	2.65	320.81	2,600.86	-429.02	403.96	589.27	0.000	0.00	0.00
2,730.00	2.65	320.81	2,630.83	-427.94	403.08	587.89	0.000	0.00	0.00
2,760.00	2.65	320.81	2,660.80	-426.87	402.21	586.50	0.000	0.00	0.00
2,790.00	2.65	320.81	2,690.77	-425.80	401.33	585.12	0.000	0.00	0.00
2,820.00	2.65	320.81	2,720.74	-424.72	400.46	583.74	0.000	0.00	0.00
2,850.00	2.65	320.81	2,750.70	-423.65	399.58	582.36	0.000	0.00	0.00
2,880.00	2.65	320.81	2,780.67	-422.57	398.71	580.98	0.000	0.00	0.00
2,910.00	2.65	320.81	2,810.64	-421.50	397.83	579.60	0.000	0.00	0.00
2,940.00	2.65	320.81	2,840.61	-420.43	396.96	578.22	0.000	0.00	0.00
2,970.00	2.65	320.81	2,870.58	-419.35	396.08	576.83	0.000	0.00	0.00
3,000.00	2.65	320.81	2,900.54	-418.28	395.21	575.45	0.000	0.00	0.00

Database:	EDM 2003.11 Single User Db	**Local Co-ordinate Reference:**	Well Ahuroa South B-1
Company:	Swift Energy NZ Ltd.	**TVD Reference:**	RKB @ 201.84m (Rig 252)
Project:	Ahuroa	**MD Reference:**	RKB @ 201.84m (Rig 252)
Site:	Ahuroa South	**North Reference:**	Grid
Well:	Ahuroa South B-1	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Ahuroa South B-1		
Design:	Ahuroa South B-1 ST-1 rev2		

Planned Survey

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)
3,030.00	2.65	320.81	2,930.51	-417.21	394.33	574.07	0.000	0.00	0.00
3,041.34	2.65	320.81	2,941.84	-416.80	394.00	573.55	0.000	0.00	0.00
Start 228.66 hold at 3041.34 MD									
3,060.00	2.65	320.81	2,960.48	-416.13	393.46	572.69	0.000	0.00	0.00
3,090.00	2.65	320.81	2,990.45	-415.06	392.58	571.31	0.000	0.00	0.00
3,120.00	2.65	320.81	3,020.42	-413.98	391.71	569.93	0.000	0.00	0.00
3,150.00	2.65	320.81	3,050.38	-412.91	390.83	568.54	0.000	0.00	0.00
3,180.00	2.65	320.81	3,080.35	-411.84	389.95	567.16	0.000	0.00	0.00
3,210.00	2.65	320.81	3,110.32	-410.76	389.08	565.78	0.000	0.00	0.00
3,240.00	2.65	320.81	3,140.29	-409.69	388.20	564.40	0.000	0.00	0.00
3,270.00	2.65	320.81	3,170.26	-408.62	387.33	563.02	0.000	0.00	0.00
TD at 3270.00									

Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (m)	+N/-S (m)	+E/-W (m)	Northing (m)	Easting (m)	Latitude	Longitude
Target - Ahuroa South B - plan misses by 133.98m at 3201.51m MD (3101.84 TVD, -411.07 N, 389.33 E) - Circle (radius 50.00)	0.00	0.00	3,101.84	-435.80	521.00	6,214,230.00	2,626,245.00	39° 16' 15.066 S	174° 20' 47.391 E
Target - Ahuroa South B - plan hits target - Circle (radius 25.00)	0.00	0.00	2,941.84	-416.80	394.00	6,214,249.00	2,626,118.00	39° 16' 14.514 S	174° 20' 42.081 E
Target - Ahuroa South B - plan misses by 80.50m at 3001.30m MD (2901.84 TVD, -418.23 N, 395.17 E) - Circle (radius 50.00)	0.00	0.00	2,901.84	-432.80	316.00	6,214,233.00	2,626,040.00	39° 16' 15.072 S	174° 20' 38.837 E
Target - Ahuroa South B - plan misses by 158.06m at 2926.22m MD (2826.84 TVD, -420.92 N, 397.36 E) - Circle (radius 50.00)	0.00	0.00	2,826.84	-435.80	240.00	6,214,230.00	2,625,964.00	39° 16' 15.207 S	174° 20' 35.669 E
Target - Ahuroa South B - plan misses by 243.62m at 3126.43m MD (3026.84 TVD, -413.75 N, 391.52 E) - Circle (radius 50.00)	0.00	0.00	3,026.84	-585.80	564.00	6,214,080.00	2,626,288.00	39° 16' 19.908 S	174° 20' 49.282 E


Plan Annotations

Measured Depth (m)	Vertical Depth (m)	Local Coordinates +N/-S (m)	Local Coordinates +E/-W (m)	Comment
2,405.00	2,309.97	-404.75	385.20	Start DLS 3.000 TFO 179.86
2,631.18	2,532.12	-431.48	405.97	Start 410.16 hold at 2631.18 MD
3,041.34	2,941.84	-416.80	394.00	Start 228.66 hold at 3041.34 MD
3,270.00	3,170.26	-408.62	387.33	TD at 3270.00

HALLIBURTON
SPERRY DRILLING SERVICES

Swift Energy NZ Ltd.

Ahuroa South B-1 ST-1 rev2



REFERENCE INFORMATION

Co-ordinate (N/E) Reference:	Well Ahuroa South B-1, Grid North
Vertical (TVD) Reference:	RKB @ 201.84m (Rig 252)
Section (VS) Reference:	Slot - (0.00N, 0.00E)
Measured Depth Reference:	RKB @ 201.84m (Rig 252)
Calculation Method:	Minimum Curvature




Azimuths to Grid North
True North: 0.89°
Magnetic North: 21.60°

Magnetic Field
Strength: 55440.0nT
Dip Angle: -64.95°
Date: 11/08/2005
Model: BGGM2005

HALLIBURTON
SPERRY DRILLING SERVICES

Swift Energy NZ Ltd.

Ahuroa South B-1 ST-1 rev2



REFERENCE INFORMATION

Co-ordinate (N/E) Reference: Well Ahuroa South B-1, Grid North
Vertical (TVD) Reference: RKB @ 201.84m (Rig 252)
Section (VS) Reference: Slot - (0.00N, 0.00E)
Measured Depth Reference: RKB @ 201.84m (Rig 252)
Calculation Method: Minimum Curvature

SECTION 3

DRILLING RECORD AND DAILY REPORTS

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS Report # 1 11/11/2005

Total Depth	**(m)**	: 2405	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: G.Klenner, T.Reid
Drilled last 24 hrs	**(m)**	: 5	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: B.Wood (1), G.Hunger (1)
Hole Size	**(in)**	: 6.000	**Casing ID**	**(in)**	: 6.810		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2400.00	19.96	141.80	2305.27	557.04	S43.60E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 1: 217.88 m; Bit #1 (6.5 hrs), PDM #1 (7. hrs), Stab, Sub, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.5	89	26	18.0	8.0 / 17.0	1		4.60	0.25	79.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	07:30	7.50	2400.00		Pooh with cmt dressing assembly
07:30	09:00	1.50	2400.00		PU dir assy, orient, install probe
09:00	10:00	1.00	2400.00	1	Trip In to 237m
10:00	10:30	0.50	2400.00	1	Circulate, shallow test MWD, no go
10:30	11:30	1.00	2400.00	1	Trip Out to 13.5m
11:30	12:00	0.50	2400.00	1	Change out pulser & probe, shallow test good
12:00	12:30	0.50	2400.00	1	Trip In to 237m , shallow test MWD good
12:30	14:00	1.50	2400.00	1	Trip In to 779m
14:00	14:30	0.50	2400.00	1	Service Rig
14:30	17:30	3.00	2400.00	1	Trip In to 2400m
17:30	00:00	6.50	2405.00	1	Orient TF low side, time drill 1m /hr

COMMENTS

Sperry directional team arrive on site at 04:30 hrs
Begin time drilling to sidetrack well

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS Report # 2 12/11/2005

Total Depth	**(m)**	: 2425	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: T.Reid
Drilled last 24 hrs	**(m)**	: 20	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: B.Wood (2), G.Hunger (2)
Hole Size	**(in)**	: 6.000	**Casing ID**	**(in)**	: 6.810		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2422.80	21.91	134.54	2326.57	565.17	S43.58E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 1: 217.88 m; Bit #1 (30.5 hrs), PDM #1 (31. hrs), Stab, Sub, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.5	89	26	18.0	8.0 / 17.0	1		4.60	0.25	79.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	12:00	12.00	2415.00	1	Time Drilling 2405 - 2415
12:00	22:15	10.25	2423.00	1	Time Drilling 2415 -2423m
22:15	00:00	1.75	2425.50	1	Slide Drilling 2423 - 2425.50m

COMMENTS

Continue time drilling to side track well
Slide drilling with weight commence at 2423m MD

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS Report # 3 13/11/2005

Total Depth	**(m)**	: 2457	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: T.Reid
Drilled last 24 hrs	**(m)**	: 32	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: B.Wood (3), G.Hunger (3)
Hole Size	**(in)**	: 6.000	**Casing ID**	**(in)**	: 6.810		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2450.30	20.66	134.57	2352.07	575.44	S43.62E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 1: 217.88 m; Bit #1 (37.5 hrs), PDM #1 (39.5 hrs), Stab, Sub, MWD, 15x HWDP, Jar, 6x HWDP
BHA 2: 217.90 m; Bit #2 (5. hrs), PDM #2 (44.5 hrs), Stab, Sub, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.5	89	26	18.0	8.0 / 17.0	1		4.60	0.25	79.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	06:00	6.00	2429.00	1	Drilling, oriented 2425.5 - 2429m
06:00	07:00	1.00	2432.00	1	Drilling, rotary 2429 - 2432m
07:00	08:30	1.50	2432.00	1	Circulate bottoms up
08:30	12:00	3.50	2432.00	1	Trip Out to 520m
12:00	13:00	1.00	2432.00	1	Trip Out (at Surface)
13:00	14:00	1.00	2432.00	2	PU/LD BHA
14:00	14:30	0.50	2432.00	2	Trip In with BHA, Shallow test MWD
14:30	17:30	3.00	2432.00	2	Trip In to 2395m
17:30	18:30	1.00	2432.00	2	Cut Drill Line
18:30	19:00	0.50	2432.00	2	Service Rig
19:00	19:30	0.50	2432.00	2	Reaming / Washing to bottom
19:30	00:00	4.50	2457.00	2	Drilling 2432 - 2457m

COMMENTS

Pooh for bit change
Check MWD offsets
RIH
Drill ahead

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS Report # 4 14/11/2005

Total Depth	**(m)**	: 2581	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: T.Reid
Drilled last 24 hrs	**(m)**	: 124	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: B.Wood (4), G.Hunger (4)
Hole Size	**(in)**	: 6.000	**Casing ID**	**(in)**	: 6.810		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2563.69	6.61	140.33	2461.93	602.24	S43.61E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)

BHA SUMMARY

BHA 2: 217.90 m; Bit #2 (28.5 hrs), PDM #2 (68. hrs), Stab, Sub, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.5	71	22	19.0	7.0 / 18.0	1		4.10	0.25	85.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	12:00	12.00	2525.00	2	Drilling 2457 - 2525m
12:00	18:30	6.50	2556.00	2	Drilling 2525 - 2556m
18:30	19:00	0.50	2556.00	2	Service Rig
19:00	00:00	5.00	2581.00	2	Drilling 2556 - 2581m

COMMENTS

Rotate and orient drilling as required

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS Report # 5 15/11/2005

Total Depth	**(m)**	: 2706	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: T.Reid
Drilled last 24 hrs	**(m)**	: 125	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: B.Wood (5), G.Hunger (5)
Hole Size	**(in)**	: 6.000	**Casing ID**	**(in)**	: 6.810		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2677.58	6.06	304.39	2575.57	602.90	S43.51E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)
Tariki	2665.00	2563.05

BHA SUMMARY

BHA 2: 217.90 m; Bit #2 (52. hrs), PDM #2 (91.5 hrs), Stab, Sub, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.5	71	22	19.0	7.0 / 18.0	1		4.10	0.25	85.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	12:00	12.00	2658.00	2	Drilling 2581 - 2658m
12:00	18:00	6.00	2680.00	2	Drilling 2658 - 2680m
18:00	18:30	0.50	2680.00	2	Service Rig
18:30	00:00	5.50	2706.00	2	Drilling 2680 - 2706m

COMMENTS

Rotate and orient drilling as required

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS Report # 6 16/11/2005

Total Depth	**(m)**	:	2755	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : T.Reid
Drilled last 24 hrs	**(m)**	:	49	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : B.Wood (6), G.Hunger (6)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :	6.810	

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2734.87	6.73	299.84	2632.46	596.29	S43.35E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)
Tariki	2665.00	2563.05

BHA SUMMARY

BHA 2: 217.90 m; Bit #2 (73.25 hrs), PDM #2 (112.75 hrs), Stab, Sub, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.6	72	22	16.0	8.0 / 17.0	1		4.40	0.25	85.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	12:00	12.00	2732.00	2	Drilling 2706 - 2732m
12:00	14:45	2.75	2742.00	2	Drilling 2732 - 2742m
14:45	16:00	1.25	2742.00	2	Short Trip back to shoe
16:00	16:30	0.50	2742.00	2	Service Rig
16:30	17:30	1.00	2742.00	2	Short Trip RIH back to bottom
17:30	00:00	6.50	2755.00	2	Drilling 2742 - 2755m

COMMENTS

Rotate and orient drilling as required

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS **Report #** 7 17/11/2005

Total Depth	**(m)**	: 2824	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: W.Stonnell
Drilled last 24 hrs	**(m)**	: 69	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: G.Hunger (7)
Hole Size	**(in)**	: 6.000	**Casing ID**	**(in)**	: 6.810		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2820.60	7.90	303.50	2717.52	585.93	S43.11E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)
Tariki	2665.00	2563.05

BHA SUMMARY

BHA 2: 217.90 m; Bit #2 (96.75 hrs), PDM #2 (136.25 hrs), Stab, Sub, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.6	72	22	16.0	8.0 / 17.0	1		4.40	0.25	85.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	12:00	12.00	2793.00	2	Drilling 2755 - 2793m
12:00	14:30	2.50	2803.00	2	Drilling 2793 - 2803m
14:30	15:00	0.50	2803.00	2	Service Rig
15:00	00:00	9.00	2824.00	2	Drilling 2803 - 2824m

COMMENTS

Assembly building in rotary 0.41 degs / 30m

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS **Report #** 8 18/11/2005

Total Depth	**(m)**	:	2865	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : W.Stonnell
Drilled last 24 hrs	**(m)**	:	41	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : G.Hunger (8), P Gallagher (1)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :	6.810	

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2849.07	8.26	297.31	2745.71	582.10	S42.99E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)
Tariki	2665.00	2563.05

BHA SUMMARY

BHA 2: 217.90 m; Bit #2 (120.25 hrs), PDM #2 (159.75 hrs), Stab, Sub, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.6	72	22	16.0	8.0 / 17.0	1		4.40	0.25	85.00

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	20:30	20.50	2861.00	2	Drilling 2824 - 2861m
20:30	21:00	0.50	2861.00	2	Service Rig
21:00	00:00	3.00	2865.00	2	Drilling 2861 - 2865m

COMMENTS

Inclination building , hard to control.

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS Report # 9 19/11/2005

Total Depth	**(m)**	: 2874	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: W.Stonnell
Drilled last 24 hrs	**(m)**	: 9	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: G.Hunger (9), P Gallagher (2)
Hole Size	**(in)**	: 6.000	**Casing ID**	**(in)**	: 6.810		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2849.07	8.26	297.31	2745.71	582.10	S42.99E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)
Tariki	2665.00	2563.05

BHA SUMMARY

BHA 2: 217.90 m; Bit #2 (126.75 hrs), PDM #2 (166.75 hrs), Stab, Sub, MWD, 15x HWDP, Jar, 6x HWDP
BHA 3: 216.83 m; Bit #3 (1. hrs), PDM #3 (1.25 hrs), Sub, Stab, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	75	25	17.0	7.0 / 19.0	2		5.60	0.25	85.90

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	06:30	6.50	2874.00	2	Drilling 2865 - 2874m
06:30	07:00	0.50	2874.00	2	Circulate
07:00	11:30	4.50	2874.00	2	Trip Out to 217m
11:30	13:00	1.50	2874.00	2	Trip Out laying down HWDP & jar for inspection
13:00	13:30	0.50	2874.00	2	LD probe, bit drain & l/o motor
13:30	14:00	0.50	2874.00	2	PU motor,c/o float valve & m/u float sub, stab,& HOC.
14:00	14:30	0.50	2874.00	2	M/U bit, set bend on motor,Install probe, Scribe offset.
14:30	16:45	2.25	2874.00	3	RIH picking up HWDP & Jars to 226m
16:45	17:00	0.25	2874.00	3	Shallow test MWD.
17:00	21:00	4.00	2874.00	3	Trip In fm 226m to 2373m
21:00	22:00	1.00	2874.00	3	Slip & Cut 53' Drill Line
22:00	22:30	0.50	2874.00	3	Service Rig
22:30	23:00	0.50	2874.00	3	Trip In fm 2373m to 2414m Take weight at side track KOP.
23:00	00:00	1.00	2874.00	3	Pump up toolface and align and work through KOP fm 2414m to 2430m

COMMENTS

Trip for Bit and motor change
166.75 motor hours accumulated

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS **Report #** 10 20/11/2005

Total Depth	**(m)**	: 2936	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	:	W.Stonnell
Drilled last 24 hrs	**(m)**	: 62	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	:	G.Hunger (10), P Gallagher (3)
Hole Size	**(in)**	: 6.000	**Casing ID**	**(in)**	: 6.810			

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2933.32	7.21	296.81	2829.24	571.75	S42.64E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)
Lower Ahuroa	2920.00	2816.02

BHA SUMMARY

BHA 3: 216.83 m; Bit #3 (23.5 hrs), PDM #3 (23.75 hrs), Sub, Stab, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	75	25	17.0	7.0 / 19.0	2		5.60	0.25	85.90

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	01:00	1.00	2874.00	3	Trip In to 2858m
01:00	01:30	0.50	2874.00	3	Reaming / Washing fm 2858m to 2874m
01:30	02:00	0.50	2876.00	3	Work in bit profile fm 2874m to 2876m
02:00	12:00	10.00	2898.00	3	Drilling 2876 - 2898m
12:00	18:30	6.50	2917.00	3	Drilling 2898 - 2917m
18:30	19:00	0.50	2917.00	3	Service Rig
19:00	00:00	5.00	2936.00	3	Drilling 2917 - 2936m

COMMENTS

Continue trip in

Rotata and slide as required

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS **Report #** 11 21/11/2005

Total Depth	**(m)**	:	2993	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : W.Stonnell
Drilled last 24 hrs	**(m)**	:	57	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : G.Hunger (11), P Gallagher (4)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :	6.810	

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2988.33	7.39	288.92	2883.80	565.42	S42.33E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)
Mangahewa	2983.00	2878.51

BHA SUMMARY

BHA 3: 216.83 m; Bit #3 (47. hrs), PDM #3 (47.75 hrs), Sub, Stab, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	74	26	15.0	8.0 / 19.0	2		5.30	0.25	84.80

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	12:00	12.00	2962.00	3	Drilling 2936 - 2962m
12:00	23:30	11.50	2993.00	3	Drilling 2962 - 2993m
23:30	00:00	0.50	2993.00	3	Circulate, work tight hole at 2992m

COMMENTS

After kelly down at 2993m pipe became stuck at 2992m MD.
Criculation was maintained but rotation lost for 1/2 an hour.
Gained circulation and rotation but cannot pick up.
Wash and ream to clean up hole. (100% Coal cuttings)

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS Report # 12 22/11/2005

Total Depth	**(m)**	: 3011	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: W.Stonnell
Drilled last 24 hrs	**(m)**	: 18	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: G.Hunger (12), P Gallagher (5)
Hole Size	**(in)**	: 6.000	**Casing ID**	**(in)**	: 6.810		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
2988.33	7.39	288.92	2883.80	565.42	S42.33E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)
Mangahewa	2983.00	2878.51

BHA SUMMARY

BHA 3: 216.83 m; Bit #3 (70.5 hrs), PDM #3 (71.75 hrs), Sub, Stab, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	74	26	15.0	8.0 / 19.0	2		5.30	0.25	84.80

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	00:30	0.50	2993.00	3	Circulate working tight hole at 2992m
00:30	06:30	6.00	2993.00	3	Reaming / Washing tight hole 2992 - 2993m
06:30	07:00	0.50	2993.00	3	Pull back to 2986m, ream & wash to 2993m
07:00	09:00	2.00	2993.00	3	Reaming / Washing circulate sweep around
09:00	12:00	3.00	2996.00	3	Control drill 2993 - 2996m at 1m/hr thru coals
12:00	22:00	10.00	3006.00	3	Control drill 2996 - 3006m at 1m/hr thru coals
22:00	00:00	2.00	3011.00	3	Drill ahead 3006 - 3011m

COMMENTS

Wash and ream coals , circulate well clean
Control drill through coals at 1 metre per hour
Drill ahead

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS Report # 13 23/11/2005

Total Depth	**(m)**	:	3035	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps** : T Reid
Drilled last 24 hrs	**(m)**	:	24	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps** : G.Hunger (13), P Gallagher (6)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)**	: 6.810	

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
3019.26	8.03	288.39	2914.45	561.79	S42.13E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)
Manganui(thrust)	3034.00	2929.04

BHA SUMMARY

BHA 3: 216.83 m; Bit #3 (90.5 hrs), PDM #3 (93.75 hrs), Sub, Stab, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	75	26	16.0	12.0 / 20.0	2		5.30	0.25	84.80

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	02:00	2.00	3015.00	3	Drilling with constant WOB fm 3011m to 3015m
02:00	03:00	1.00	3016.00	3	Time Drilling @ 1m/hr (5% coal)
03:00	05:00	2.00	3018.00	3	Drilling with constant WOB fm 3016m to 3018m
05:00	06:30	1.50	3022.00	3	Time Drilling 1m/hr fm 3018m to 3022m (15% coal)
06:30	08:00	1.50	3025.00	3	Drilling with constant WOB fm 3022m 3025m
08:00	12:00	4.00	3028.00	3	Time Drilling 1m/hr fm 3025m to 3028m (80% coal) pump 5bbl sweep.
12:00	16:00	4.00	3031.00	3	Time Drilling 1m/hr fm 3028 to 3031m
16:00	18:00	2.00	3031.00	3	Circulate for wiper trip
18:00	19:00	1.00	3031.00	3	Short Trip back to 2868m
19:00	19:30	0.50	3031.00	3	Service Rig
19:30	20:00	0.50	3031.00	3	Short Trip in to bottom at 3031m
20:00	00:00	4.00	3035.00	3	Time Drilling 1m/hr fm 3031 to 3035m

COMMENTS

Control drill through coals at 1 metre per hour
Preform wiper trip back to old hole at 2868m MD
Continue to control drill through coals at 1 metre per hour

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS Report # 14 24/11/2005

Total Depth	**(m)**	:	3085	**Casing Depth**	**(m)** :	2395.00	**Operator Reps** : T Reid
Drilled last 24 hrs	**(m)**	:	50	**Casing Diameter**	**(in)** :	7.000	**SSDS Reps** : G.Hunger (14), P Gallagher (7)
Hole Size	**(in)**	:	6.000	**Casing ID**	**(in)** :	6.810	

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
3069.23	8.38	287.69	2963.90	555.59	S41.76E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)
Manganui(thrust)	3034.00	2929.04

BHA SUMMARY

BHA 3: 216.83 m; Bit #3 (106. hrs), PDM #3 (113.75 hrs), Sub, Stab, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	75	26	18.0	8.0 / 17.0	1		5.30	0.25	78.30

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	15:30	15.50	3085.00	3	Drill to TD at 3085m
15:30	17:30	2.00	3085.00	3	Pump 10bbl sweep / Circulate
17:30	21:30	4.00	3085.00	3	Short Trip to shoe and back to bottom
21:30	00:00	2.50	3085.00	3	Sweep hole and Circulate for logging

COMMENTS

Drill to TD for the well at 3085m MD
Perform wiper trip, hole in good shape
Circulate prior to trip out
Begin trip out at 24:00 hrs

sperry-sun
DRILLING SERVICES

Daily Drilling Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895

CURRENT STATUS Report # 15 25/11/2005

Total Depth	**(m)**	: 3085	**Casing Depth**	**(m)**	: 2395.00	**Operator Reps**	: T Reid
Drilled last 24 hrs	**(m)**	: 0	**Casing Diameter**	**(in)**	: 7.000	**SSDS Reps**	: G.Hunger (15), P Gallagher (8)
Hole Size	**(in)**	: 6.000	**Casing ID**	**(in)**	: 6.810		

LAST SURVEY

Depth (m)	Inclination	Azimuth	TVD (m)	Displ (m)	Direction
3069.23	8.38	287.69	2963.90	555.59	S41.76E

LAST FORMATION TOP

Formation Name	MD Top (m)	TVD Top (m)
Manganui(thrust)	3034.00	2929.04

BHA SUMMARY

BHA 3: 216.83 m; Bit #3 (106. hrs), PDM #3 (113.75 hrs), Sub, Stab, MWD, 15x HWDP, Jar, 6x HWDP

MUD DATA

Type	Weight (ppg)	FV (sec)	PV (cp)	YP (lbf/100ft²)	Gels	Fluid Loss	pH	Solids (%)	Sand (%)	Oil (%)
Oil Base	8.7	75	26	18.0	8.0 / 17.0	1		5.30	0.25	78.30

TIME BREAKDOWN

From	To	Hours	TMD (m)	BHA #	Activity
00:00	02:30	2.50	3085.00	3	Trip Out to shoe at 2395m
02:30	07:30	5.00	3085.00	3	Trip Out (at Surface)
07:30	08:15	0.75	3085.00	3	Lay down Directional tools

COMMENTS

POOH to surface
Lay down directional tools
Sperry-sun rep`s leave location

SECTION 4

BHA REPORTS

sperry-sun
DRILLING SERVICES

BHA Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895 **BHA# 1**

BHA# 1 : **Date In** :11/11/200 **MD In (m) :** 2400 **TVD In (m) :** 2305 **Date Out** 13/11/2005 **MD Out (m):** 2432 **TVD Out (m):** 2335

BIT DATA

Bit #	OD (in)	MFR	Style	Serial#	Nozzles (/32's)	TFA (in²)	Dull Condition
1	6.000	Smith	XR+	PC7092	3x18	0.746	

MOTOR DATA

Run #	OD (in)	MFR	Model	Serial#	Bend	Nzl (/32's)	Avg Dif (psi)	Cum Circ Hrs
1	4.750	SSDS	SperryDrill	475NZ1	1.50°		9	39.50

COMPONENT DATA

Item #	Description	Serial #	OD (in)	ID (in)	Gauge (in)	Weight (lbs/ft)	Top Con	Length (m)	Bit - Center Blade (m)
1	Roller Cone Steel, XR+	PC7092	6.000	2.813	6.000	75.18	P 3-1/2" Reg	0.19	
2	4-3/4" SperryDrill Lobe 7/8 - 2.2 stg	475NZ1	4.750	2.901	5.875	37.87	B 3-1/2" IF	6.17	0.89
3	Integral Blade Stabilizer	240242	4.687	2.250	5.812	45.25	B 3-1/2" IF	1.55	7.00
4	Float Sub	SSDS2949	4.625	1.812		48.47	B 3-1/2" IF	0.48	
5	DWD SlimHole	111325	4.750	2.625		41.95	B 3-1/2" IF	5.11	
6	15x HWDP		3.500	2.063		25.30	B 3-1/2" IF	139.76	
7	Jar	MAHOO195	4.750	2.250		46.84	B 3-1/2" IF	9.00	
8	6x HWDP		3.500	2.063		25.30	B 3-1/2" IF	55.62	
								217.88	

Parameter	Min	Max	Ave
WOB (klbs) :	0	12	2
RPM (rpm) :	70	70	70
Flow (gpm) :	243	243	243
SPP (psi) :	2750	2850	2759

Activity	Hrs
Drilling :	37.50
Reaming :	0.00
Circ-Other :	2.00
Total :	39.50

BHA Weight	(lb)
in Air (Total) :	19424
in Mud (Total) :	16907
in Air (Bel Jars) :	13424
in Mud (Bel Jars) :	11685

Drill String	OD(in)	Len (m)

PERFORMANCE

	In	Out
Inclination (deg)	19.96	22.78
Azimuth (deg)	141.80	133.88

	Distance (m)	ROP (m/hr)	Build (°/30m)	Turn (°/30m)	DLS (°/30m)
Oriented :	24.00	0			4.00
Rotated :	8.00	2			
Total :	32.00	1	2.65	-7.43	3.78

COMMENTS

Pump #1 has 5" liners
Pump #2 has 4 1/2" liners
Float is non ported flapper type

OBJECTIVES:

To sidetrack well lowside and continue droping angle until bit hours are up.

RESULTS:

Sidetrack achieved but in wrong direction due to incorrect offset entered into MWD computer. Could have corrected but only 3 bit hours left and ROP not very good, so POOH.

sperry-sun
DRILLING SERVICES

BHA Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895 **BHA# 2**

BHA# 2 : **Date In** :13/11/200 **MD In (m) :** 2432 **TVD In (m) :** 2335 **Date Out** 19/11/200 **MD Out (m):** 2874 **TVD Out (m):** 2770

BIT DATA

Bit #	OD (in)	MFR	Style	Serial#	Nozzles (/32's)	TFA (in²)	Dull Condition
2	6.000	REED / Hycalog	DSX519S-A3	211111	5x14	0.752	

MOTOR DATA

Run #	OD (in)	MFR	Model	Serial#	Bend	Nzl (/32's)	Avg Dif (psi)	Cum Circ Hrs
2	4.750	SSDS	SperryDrill	475NZ1	1.15°		178	166.75

COMPONENT DATA

Item #	Description	Serial #	OD (in)	ID (in)	Gauge (in)	Weight (lbs/ft)	Top Con	Length (m)	Bit - Center Blade (m)
1	PDC, DSX519	211111	6.000	4.500	6.000	42.16	P 3-1/2" IF	0.21	
2	4-3/4" SperryDrill Lobe 7/8 - 2.2 stg	475NZ1	4.750	2.901	5.875	37.87	B 3-1/2" IF	6.17	0.91
3	Integral Blade Stabilizer	240242	4.687	2.250	5.812	45.25	B 3-1/2" IF	1.55	7.02
4	Float Sub	SSDS2949	4.625	1.812		48.47	B 3-1/2" IF	0.48	
5	DWD SlimHole	111325	4.750	2.625		41.95	B 3-1/2" IF	5.11	
6	15x HWDP		3.500	2.063		25.30	B 3-1/2" IF	139.76	
7	Jar	MAHOO195	4.750	2.250		46.84	B 3-1/2" IF	9.00	
8	6x HWDP		3.500	2.063		25.30	B 3-1/2" IF	55.62	
								217.90	

Parameter	Min	Max	Ave
WOB (klbs) :	5	12	8
RPM (rpm) :	70	100	82
Flow (gpm) :	200	243	201
SPP (psi) :	2050	2800	2168

Activity	Hrs
Drilling :	126.25
Reaming :	0.50
Circ-Other :	0.50
Total :	127.25

BHA Weight	(lb)
in Air (Total) :	19406
in Mud (Total) :	16833
in Air (Bel Jars) :	13406
in Mud (Bel Jars) :	11628

Drill String	OD(in)	Len (m)

PERFORMANCE

	In	Out
Inclination (deg)	22.78	7.98
Azimuth (deg)	133.88	299.86

	Distance (m)	ROP (m/hr)	Build (°/30m)	Turn (°/30m)	DLS (°/30m)
Oriented :	157.50	2			7.00
Rotated :	284.50	4			
Total :	442.00	4	-1.00	11.27	2.08

COMMENTS

Pump #1 has 5" liners
Pump #2 has 4 1/2" liners
Float is non ported flapper type

OBJECTIVES:

To drop well back to vertical and build to 5 degrees in opposite direcion, then hold tangent to Target.

RESULTS:

No problems were encounted in dropping angle and turning well, the initial build was completed easily, but the assembly continued building in rotary.

sperry-sun
DRILLING SERVICES

BHA Report

Customer : Swift Energy NZ Ltd
Well : Ahuroa South B-1 ST1
Field : Taranaki
Lease : Ahuroa
Rig : Parker 252
Job # : NZ-DD-0004047895 **BHA# 3**

BHA# 3 : **Date In** :19/11/200 **MD In (m) :** 2874 **TVD In (m) :** 2770 **Date Cur**: 25/11/2005 **MD Cur (m):** 3085 **TVD Cur (m):** 2979

BIT DATA

Bit #	OD (in)	MFR	Style	Serial#	Nozzles (/32's)	TFA (in²)	Dull Condition
3	6.000	Smith Geo Diamond	M516LYPX	JW3280	3x13, 2x16	0.782	

MOTOR DATA

Run #	OD (in)	MFR	Model	Serial#	Bend	Nzl (/32's)	Avg Dif (psi)	Cum Circ Hrs
3	4.750	SSDS	SperryDrill	475346	1.15°		111	113.75

COMPONENT DATA

Item #	Description	Serial #	OD (in)	ID (in)	Gauge (in)	Weight (lbs/ft)	Top Con	Length (m)	Bit - Center Blade (m)
1	Smith Geo Diamond PDC	JW3280	6.000	4.500	6.000	42.16	P 3-1/2" IF	0.21	
2	4-3/4" SperryDrill Lobe 7/8 - 2.2 stg	475346	4.750	2.901	5.875	37.87	B 3-1/2" IF	5.52	
3	Float Sub	SSDS2949	4.625	1.812		48.47	B 3-1/2" IF	0.48	
4	Integral Blade Stabilizer	240242	4.687	2.250	5.812	45.25	B 3-1/2" IF	1.55	6.85
5	DWD SlimHole	111325	4.750	2.625		41.95	B 3-1/2" IF	5.11	
6	15x HWDP		3.500	2.063		25.30	B 3-1/2" IF	139.38	
7	Jar	MAHOO195	4.750	2.250		46.84	B 3-1/2" IF	9.00	
8	6x HWDP		3.500	2.063		25.30	B 3-1/2" IF	55.58	
								216.83	

Parameter	Min	Max	Ave
WOB (klbs) :	1	10	7
RPM (rpm) :	80	90	86
Flow (gpm) :	200	210	205
SPP (psi) :	2250	2750	2509

Activity	Hrs
Drilling :	96.00
Reaming :	10.00
Circ-Other :	7.75
Total :	113.75

BHA Weight	(lb)
in Air (Total) :	19290
in Mud (Total) :	16732
in Air (Bel Jars) :	13294
in Mud (Bel Jars) :	11531

Drill String	OD(in)	Len (m)

PERFORMANCE

	In	Out
Inclination (deg)	7.98	8.41
Azimuth (deg)	299.86	287.62

	Distance (m)	ROP (m/hr)	Build (°/30m)	Turn (°/30m)	DLS (°/30m)
Oriented :	11.00	2			
Rotated :	200.00	2			
Total :	211.00	2	0.06	-1.74	0.26

COMMENTS

Moved Float to below stab for smaller ID.
Changed out HWDP.(inspection due).
Changed out float to dart type (non ported)

OBJECTIVES:

To drop angle and hit target in the North west quarter.

RESULTS:

As expected with the new bit ROP doubled and slides although not easy with the interbeded formations were drilled at a faster ROP and only one 6m slide was needed to ensure a west side target penetration.
Initial rotary drilling ROP varied between 2-10m/hr with 3-7k WOB through the Tariki and Lower Ahuroa claystone. The McKee sands didn't develop and instead coals were hit at 2983m and stuck pipe stopped the drilling for 6 to 8hrs before working free and controlled drilling continued for much of the remainder of the hole. The formations came in about 130m high and by the time the proposed target was hit at 3046m the Ahuroa thrust/fault had already been intersected at 3034m in the Manganui, and rat hole to 3085m was drilled before the assembly was tripped out and layed out.

RECOMMENDATIONS:

No recommendations, the assembly worked well and achieved the desired result

SECTION 5

FINAL SURVEY DATA AND PLOT

HALLIBURTON

Sperry Drilling Services

Swift Energy NZ Ltd.

Ahuroa
Ahuroa South
Ahuroa South B-1
Ahuroa South B-1 ST-1

Design: Ahuroa South B-1 ST-1

Standard Survey Report

15 February, 2006



Sperry Drilling Services
Survey Report

Company:	Swift Energy NZ Ltd.	**Local Co-ordinate Reference:**	Well Ahuroa South B-1
Project:	Ahuroa	**TVD Reference:**	New RKB @ 201.74m (Rig 252)
Site:	Ahuroa South	**MD Reference:**	New RKB @ 201.74m (Rig 252)
Well:	Ahuroa South B-1	**North Reference:**	Grid
Wellbore:	Ahuroa South B-1 ST-1	**Survey Calculation Method:**	Minimum Curvature
Design:	Ahuroa South B-1 ST-1	**Database:**	New Zealand Database

Project Ahuroa

Map System:	New Zealand Map Grid	**System Datum:**	Mean Sea Level
Geo Datum:	Geodetic Datum 1949		
Map Zone:	New Zealand Map Grid		

Site Ahuroa South

Site Position:		**Northing:**	6,214,674.11 m	**Latitude:**	39° 16' 00.946" S
From:	Map	**Easting:**	2,625,685.92 m	**Longitude:**	174° 20' 23.782" E
Position Uncertainty:	0.00 m	**Slot Radius:**	20.000 in	**Grid Convergence:**	-0.89 °

Well Ahuroa South B-1

Well Position	**+N/-S**	0.00 m	**Northing:**	6,214,665.80 m	**Latitude:**	39° 16' 01.197" S
	+E/-W	0.00 m	**Easting:**	2,625,724.00 m	**Longitude:**	174° 20' 25.375" E
Position Uncertainty		0.00 m	**Wellhead Elevation:**	5.54 m	**Ground Level:**	196.20 m

Wellbore Ahuroa South B-1 ST-1

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	BGGM2005	14/11/2005	20.72	-64.95	55,428

Design Ahuroa South B-1 ST-1

Audit Notes: Casing and formation information is provisional, and should only be used as a guide.

Version: 1.0 **Phase:** ACTUAL **Tie On Depth:** 2,399.90

Vertical Section:	Depth From (TVD) (m)	+N/-S (m)	+E/-W (m)	Direction (°)
	0.00	0.00	0.00	136.610

Survey Program **Date** 15/02/2006

From (m)	To (m)	Survey (Wellbore)	Tool Name	Description
171.54	2,399.90	Ahurua South B-1 (Ahuroa South B-1)	MWD Magnetic	MWD Magnetic Survey (Thorogood)
2,422.80	3,069.23	MWD - 6" Hole (Ahuroa South B-1 ST-1)	MWD Magnetic	MWD Magnetic Survey (Thorogood)

Survey

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)
0.00	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.00	0.00
171.64	1.590	306.300	171.62	1.41	-1.92	-2.34	0.278	0.28	0.00
210.33	1.560	306.000	210.29	2.04	-2.78	-3.39	0.024	-0.02	-0.23
238.56	1.860	311.190	238.51	2.56	-3.43	-4.22	0.358	0.32	5.52
266.79	1.240	299.500	266.73	3.02	-4.04	-4.97	0.736	-0.66	-12.42
294.18	0.870	291.280	294.12	3.24	-4.50	-5.44	0.437	-0.41	-9.00
321.10	0.740	248.000	321.03	3.25	-4.85	-5.69	0.675	-0.14	-48.23
347.95	0.810	213.080	347.88	3.02	-5.11	-5.71	0.525	0.08	-39.02
374.63	0.810	204.330	374.56	2.69	-5.29	-5.59	0.139	0.00	-9.84
401.53	0.800	194.320	401.46	2.34	-5.42	-5.42	0.157	-0.01	-11.16
428.37	0.760	191.070	428.29	1.98	-5.50	-5.22	0.067	-0.04	-3.63
455.21	1.460	166.360	455.13	1.48	-5.45	-4.82	0.931	0.78	-27.62

Company:	Swift Energy NZ Ltd.	**Local Co-ordinate Reference:**	Well Ahuroa South B-1
Project:	Ahuroa	**TVD Reference:**	New RKB @ 201.74m (Rig 252)
Site:	Ahuroa South	**MD Reference:**	New RKB @ 201.74m (Rig 252)
Well:	Ahuroa South B-1	**North Reference:**	Grid
Wellbore:	Ahuroa South B-1 ST-1	**Survey Calculation Method:**	Minimum Curvature
Design:	Ahuroa South B-1 ST-1	**Database:**	New Zealand Database

Survey

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)
482.01	1.610	157.580	481.92	0.80	-5.23	-4.17	0.312	0.17	-9.83
508.82	1.350	159.080	508.72	0.15	-4.97	-3.53	0.294	-0.29	1.68
535.74	1.230	157.390	535.63	-0.41	-4.75	-2.96	0.140	-0.13	-1.88
562.69	1.700	122.650	562.57	-0.89	-4.30	-2.30	1.094	0.52	-38.67
598.41	2.020	110.640	598.28	-1.40	-3.26	-1.22	0.422	0.27	-10.09
640.10	2.030	114.200	639.94	-1.96	-1.90	0.12	0.091	0.01	2.56
666.76	1.980	111.150	666.58	-2.32	-1.04	0.97	0.133	-0.06	-3.43
702.54	6.800	153.150	702.25	-4.44	0.49	3.56	4.603	4.04	35.22
720.47	8.980	151.120	720.01	-6.61	1.65	5.94	3.677	3.65	-3.40
747.29	11.400	142.560	746.41	-10.55	4.27	10.60	3.186	2.71	-9.57
765.10	12.040	140.940	763.85	-13.39	6.51	14.20	1.212	1.08	-2.73
782.98	13.350	139.300	781.29	-16.40	9.03	18.12	2.279	2.20	-2.75
800.90	15.180	135.820	798.66	-19.65	12.02	22.54	3.382	3.06	-5.83
827.62	16.960	130.440	824.33	-24.69	17.42	29.91	2.604	2.00	-6.04
854.53	17.410	129.520	850.04	-29.80	23.51	37.81	0.586	0.50	-1.03
881.45	18.980	130.450	875.62	-35.20	29.95	46.16	1.779	1.75	1.04
908.74	19.550	131.170	901.38	-41.09	36.77	55.11	0.679	0.63	0.79
935.58	19.860	130.440	926.65	-47.00	43.62	64.12	0.442	0.35	-0.82
962.41	19.330	131.710	951.92	-52.91	50.40	73.07	0.760	-0.59	1.42
989.18	18.580	134.390	977.24	-58.84	56.76	81.75	1.287	-0.84	3.00
1,015.89	18.940	134.930	1,002.53	-64.88	62.87	90.33	0.449	0.40	0.61
1,042.82	19.460	134.620	1,027.96	-71.12	69.15	99.19	0.590	0.58	-0.35
1,070.64	19.790	133.810	1,054.17	-77.63	75.85	108.52	0.461	0.36	-0.87
1,097.43	19.810	132.430	1,079.37	-83.84	82.47	117.58	0.524	0.02	-1.55
1,124.27	19.470	133.900	1,104.65	-90.01	89.05	126.58	0.670	-0.38	1.64
1,151.11	18.960	137.120	1,130.00	-96.30	95.24	135.41	1.314	-0.57	3.60
1,178.00	18.890	137.820	1,155.43	-102.73	101.14	144.13	0.265	-0.08	0.78
1,204.71	19.520	136.500	1,180.66	-109.17	107.11	152.92	0.859	0.71	-1.48
1,231.46	20.140	136.470	1,205.82	-115.75	113.36	161.99	0.695	0.70	-0.03
1,258.28	20.760	135.860	1,230.95	-122.51	119.85	171.36	0.733	0.69	-0.68
1,285.30	20.580	135.560	1,256.23	-129.34	126.51	180.90	0.232	-0.20	-0.33
1,312.05	17.630	137.590	1,281.51	-135.69	132.54	189.65	3.391	-3.31	2.28
1,338.88	17.410	138.690	1,307.09	-141.70	137.93	197.72	0.445	-0.25	1.23
1,365.74	17.600	138.600	1,332.71	-147.77	143.27	205.80	0.214	0.21	-0.10
1,392.60	17.530	138.570	1,358.32	-153.84	148.63	213.90	0.079	-0.08	-0.03
1,420.46	18.940	136.540	1,384.78	-160.27	154.52	222.62	1.665	1.52	-2.19
1,447.30	19.290	135.900	1,410.14	-166.62	160.60	231.40	0.456	0.39	-0.72
1,474.18	19.860	135.220	1,435.46	-173.05	166.90	240.41	0.685	0.64	-0.76
1,500.90	20.160	134.480	1,460.57	-179.50	173.38	249.55	0.441	0.34	-0.83
1,528.27	20.680	134.120	1,486.22	-186.16	180.22	259.09	0.586	0.57	-0.39
1,555.00	21.300	133.720	1,511.18	-192.81	187.12	268.65	0.714	0.70	-0.45
1,581.80	20.840	134.880	1,536.18	-199.53	194.01	278.28	0.695	-0.51	1.30
1,608.56	20.570	135.080	1,561.22	-206.22	200.70	287.74	0.313	-0.30	0.22
1,635.53	19.730	135.140	1,586.53	-212.80	207.26	297.02	0.935	-0.93	0.07
1,662.21	20.060	135.120	1,611.62	-219.24	213.67	306.10	0.371	0.37	-0.02
1,689.11	20.170	135.160	1,636.88	-225.79	220.19	315.35	0.124	0.12	0.04
1,715.94	20.330	134.590	1,662.05	-232.35	226.77	324.63	0.284	0.18	-0.64
1,742.90	20.690	133.960	1,687.30	-238.94	233.54	334.07	0.470	0.40	-0.70
1,769.75	20.870	133.790	1,712.41	-245.54	240.40	343.58	0.212	0.20	-0.19
1,798.31	20.160	134.560	1,739.16	-252.52	247.58	353.58	0.798	-0.75	0.81
1,826.31	19.740	134.840	1,765.48	-259.24	254.37	363.13	0.461	-0.45	0.30
1,854.52	19.430	134.560	1,792.05	-265.89	261.09	372.58	0.344	-0.33	-0.30
1,882.71	19.250	135.040	1,818.65	-272.47	267.72	381.91	0.256	-0.19	0.51
1,910.83	18.930	134.200	1,845.23	-278.93	274.26	391.10	0.450	-0.34	-0.90

Company:	Swift Energy NZ Ltd.	**Local Co-ordinate Reference:**	Well Ahuroa South B-1
Project:	Ahuroa	**TVD Reference:**	New RKB @ 201.74m (Rig 252)
Site:	Ahuroa South	**MD Reference:**	New RKB @ 201.74m (Rig 252)
Well:	Ahuroa South B-1	**North Reference:**	Grid
Wellbore:	Ahuroa South B-1 ST-1	**Survey Calculation Method:**	Minimum Curvature
Design:	Ahuroa South B-1 ST-1	**Database:**	New Zealand Database

Survey

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)
1,938.53	19.020	135.210	1,871.42	-285.26	280.67	400.10	0.369	0.10	1.09
1,967.08	19.080	135.490	1,898.41	-291.89	287.21	409.42	0.115	0.06	0.29
1,995.35	18.900	135.710	1,925.14	-298.46	293.65	418.62	0.206	-0.19	0.23
2,023.52	18.590	135.520	1,951.82	-304.93	299.98	427.67	0.336	-0.33	-0.20
2,052.56	19.210	136.770	1,979.29	-311.72	306.50	437.08	0.765	0.64	1.29
2,081.20	19.190	137.350	2,006.34	-318.61	312.91	446.49	0.201	-0.02	0.61
2,110.05	19.430	138.720	2,033.56	-325.71	319.29	456.03	0.533	0.25	1.42
2,138.42	20.660	139.960	2,060.21	-333.08	325.63	465.74	1.376	1.30	1.31
2,167.28	20.950	140.910	2,087.19	-340.99	332.15	475.97	0.462	0.30	0.99
2,195.91	20.970	140.940	2,113.93	-348.94	338.61	486.18	0.024	0.02	0.03
2,224.19	20.970	141.280	2,140.34	-356.81	344.96	496.27	0.129	0.00	0.36
2,253.04	20.500	139.140	2,167.32	-364.66	351.50	506.46	0.927	-0.49	-2.23
2,291.52	20.350	138.830	2,203.38	-374.80	360.31	519.88	0.144	-0.12	-0.24
2,319.87	20.220	139.300	2,229.97	-382.22	366.75	529.70	0.221	-0.14	0.50
2,348.33	19.970	140.390	2,256.70	-389.69	373.06	539.46	0.475	-0.26	1.15
2,378.00	19.930	141.010	2,284.59	-397.53	379.47	549.56	0.218	-0.04	0.63
2,394.90	19.956	141.616	2,300.47	-402.03	383.07	555.31	0.370	0.05	1.08
7"									
2,400.00	19.964	141.799	2,305.27	-403.39	384.15	557.04	0.370	0.05	1.07
2,422.80	21.910	134.540	2,326.56	-409.44	389.59	565.17	4.262	2.56	-9.55
2,431.15	22.880	133.850	2,334.28	-411.65	391.87	568.35	3.611	3.49	-2.48
2,450.30	20.660	134.570	2,352.07	-416.60	396.96	575.44	3.503	-3.48	1.13
2,469.33	18.660	135.400	2,369.99	-421.13	401.49	581.84	3.183	-3.15	1.31
2,487.27	16.440	137.170	2,387.09	-425.03	405.24	587.25	3.818	-3.71	2.96
2,506.30	13.880	136.690	2,405.46	-428.67	408.63	592.23	4.041	-4.04	-0.76
2,525.37	11.290	136.360	2,424.07	-431.69	411.49	596.38	4.076	-4.07	-0.52
2,544.56	8.660	138.640	2,442.97	-434.13	413.74	599.70	4.157	-4.11	3.56
2,563.69	6.610	140.330	2,461.93	-436.06	415.40	602.24	3.234	-3.21	2.65
2,582.64	4.820	144.360	2,480.78	-437.55	416.56	604.12	2.902	-2.83	6.38
2,601.65	2.510	140.100	2,499.75	-438.51	417.29	605.33	3.668	-3.65	-6.72
2,620.61	0.180	144.650	2,518.70	-438.86	417.57	605.77	3.688	-3.69	7.20
2,639.60	2.090	303.510	2,537.69	-438.69	417.30	605.46	3.568	3.02	250.96
2,658.51	3.840	303.520	2,556.57	-438.15	416.49	604.51	2.776	2.78	0.02
2,665.00	4.595	303.910	2,563.05	-437.89	416.09	604.05	3.494	3.49	1.80
Tariki									
2,677.58	6.060	304.390	2,575.57	-437.23	415.12	602.90	3.494	3.49	1.14
2,706.24	7.300	302.280	2,604.04	-435.40	412.33	599.66	1.323	1.30	-2.21
2,734.87	6.730	299.840	2,632.45	-433.60	409.34	596.29	0.674	-0.60	-2.56
2,763.61	6.990	303.150	2,660.99	-431.80	406.42	592.98	0.494	0.27	3.46
2,792.08	7.140	304.100	2,689.24	-429.86	403.50	589.57	0.200	0.16	1.00
2,820.60	7.900	303.500	2,717.51	-427.79	400.40	585.93	0.804	0.80	-0.63
2,849.07	8.260	297.310	2,745.70	-425.77	396.95	582.09	0.992	0.38	-6.52
2,876.40	7.950	300.120	2,772.76	-423.92	393.57	578.43	0.552	-0.34	3.08
2,904.99	6.760	297.110	2,801.11	-422.16	390.36	574.95	1.312	-1.25	-3.16
2,920.00	6.998	296.946	2,816.02	-421.34	388.76	573.25	0.478	0.48	-0.33
Lower Ahuroa									
2,933.32	7.210	296.810	2,829.23	-420.60	387.29	571.70	0.478	0.48	-0.31
2,961.96	7.370	291.000	2,857.64	-419.13	383.97	568.35	0.790	0.17	-6.09
2,983.00	7.385	289.339	2,878.51	-418.20	381.44	565.94	0.305	0.02	-2.37
Mangahewa									
2,988.33	7.390	288.920	2,883.79	-417.97	380.79	565.33	0.305	0.03	-2.36
3,019.26	8.030	288.390	2,914.44	-416.65	376.86	561.66	0.625	0.62	-0.51
3,034.00	8.190	288.070	2,929.04	-416.00	374.88	559.83	0.338	0.32	-0.65
Manganui									

Sperry Drilling Services
Survey Report

Company:	Swift Energy NZ Ltd.	**Local Co-ordinate Reference:**	Well Ahuroa South B-1
Project:	Ahuroa	**TVD Reference:**	New RKB @ 201.74m (Rig 252)
Site:	Ahuroa South	**MD Reference:**	New RKB @ 201.74m (Rig 252)
Well:	Ahuroa South B-1	**North Reference:**	Grid
Wellbore:	Ahuroa South B-1 ST-1	**Survey Calculation Method:**	Minimum Curvature
Design:	Ahuroa South B-1 ST-1	**Database:**	New Zealand Database

Survey

Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)
3,046.84	8.329	287.801	2,941.74	-415.43	373.13	558.22	0.338	0.33	-0.63
Target - Ahuroa South B-1 ST-1 rev2									
3,047.86	8.340	287.780	2,942.75	-415.38	372.99	558.09	0.338	0.33	-0.62
3,069.23	8.380	287.690	2,963.90	-414.44	370.03	555.36	0.059	0.06	-0.13

Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (m)	+N/-S m	+E/-W m	Northing (m)	Easting (m)	Latitude	Longitude
Target - Ahuroa South	0.00	0.00	2,941.74	-416.80	394.00	6,214,249.00	2,626,118.00	39° 16' 14.514" S	174° 20' 42.081" E
- actual wellpath misses by 20.92m at 3046.84m MD (2941.74 TVD, -415.43 N, 373.13 E)									
- Circle (radius 25.00)									

Casing Points

Measured Depth (m)	Vertical Depth (m)	Name	Casing Diameter (in)	Hole Diameter (in)
2,394.90	2,300.47	7"	7.000	7.500


Formations

Measured Depth (m)	Vertical Depth (m)	Name	Lithology	Dip (°)	Dip Direction (°)
2,665.00	2,563.05	Tariki		0.00	
2,920.00	2,816.02	Lower Ahuroa		0.00	
2,983.00	2,878.51	Mangahewa		0.00	
3,034.00	2,929.04	Manganui		0.00	

Checked By: _____ Approved By: _____ Date: _____

Sperry Drilling Services

Swift Energy NZ Ltd.
Project: Ahuroa Well: Ahuroa South B-1 Design: Ahuroa South B-1 ST-1




Days Vs Depth Graph

NZ050091A

Swift Energy New Zealand Ltd

Well Name: Ahuroa South B-1 ST# 1




Printed: 14:58 21-Mar-06

Cost Vs Depth Graph

Swift Energy New Zealand Ltd

Well ID: NZ050091A

Well Name: Ahuroa South B-1 ST# 1



Printed: 14:57 21-Mar-06


Well Elevation View

Well ID: NZ050091

Well Name: Ahuroa South B-1

Well Bore: All Well Bores

Plane of Vertical Section: N 0.0 E




Printed: 12:17 25-May-07

Well Elevation View

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Well Bore: All Well Bores **Plane of Vertical Section: N 0.0 E**




Printed: 12:17 25-May-07

Well Plan View

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Well Bore: All Well Bores




Printed: 12:18 25-May-07

Well Plan View

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Well Bore: All Well Bores



Printed: 12:18 25-May-07

Well Summary Report

Swift Energy New Zealand Ltd

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Operator:	Swift Energy New Zealand Ltd	**Field:**	WAIHAPA
AFE Nos:	051203; 051203-C; 051203-ST1		
API No:		**Working Interest:**	100.00%
Spud Date:	05-Oct-05		
Section:	inter. **Township:** Tariki	**Range:**	
Location:	Ahuroa A Site, Croydon Rd		

Reports for 06:00 on date shown

10-Nov-05 **Current Depth:** 3370.0 **Hole Drilled:** 0.0 **Ave ROP:**

Current Ops: Trouble shoot well head problem

Operations Summary:

WOO. (6 hrs)

TRPI to 2526m and circulate while mixing mix water,spacer and prepare for cement job (kick off plug) (1 hrs)

Continue to mix mix water and spacers..Hold pre job safety meeting .Rig up surface lines. (0.5 hrs)

Pump 10 bbbls spacer .test surface lines to 3000 psi ok.Continue pump remaining 20bbls spacer. (0.5 hrs)

Pump 21.6 bbls 17.2 ppg Class G cement @ 3.6 bpm.Pump 6.3 bbls tail spacer.Displace balanced plug with 41.6 bbls 8.7ppg OBM. Check for flow back .OK. (1 hrs)

TRPO f/- 2526m to 2242m .Install wiper sponge and circulate 2 x bottoms up. Slight cement contaminated at bttms/up. (1.5 hrs)

TRPO laying out 104 jnts 3 1/2 DP. (4 hrs)

Continue TRPO with 3 1/2 DP to 146m (2 hrs)

Lay out 2 7/8 tubing (2 hrs)

Retrieve wear bushing (0.5 hrs)

Hold pre tour safety meeting prior to rigging up test lines Drain stack set test plug..Fill stack .Test surface lines to 5000 psi.ok.

Attempt test # 1 annular .leaking past test plug seal. Drill crew member closed annulus valve. (1 hrs)

Bled of pressure on annulus test.Unseated Test plug lifted string and bent kelly.Trouble shoot open annulus valve .reset test plug .Bypassing test plug.Unable to get test.Drain stack check test plug profile. Junk observed flush well head . Prepare RTTS packer to isolate well bore to enable lifting stack. (4 hrs)

Comments: Drill crew member closed B section valve prior to pressure testing . Test leaked past test plug hydraulicing test plug and bending kelly.
* Start of the Ahuroa Sth B1 Sidetrack.
** Total Cost of Original Hole = 2,687,184.00

Mud Data: MW: 8.9 Viscosity: 108 Filtrate: HTHP Filtrate: 0.5

Surveys: None

Daily Costs $: 2,721,320 **Well Costs $:** 2,721,320

Drilling Days: 36 **Completion Days:**

11-Nov-05 **Current Depth:** 2400.0 **Hole Drilled:** -970.0 **Ave ROP:**

Current Ops: TRPO and m/up Directional assy

Operations Summary:

Trouble shoot BOP problem. ok. (0.5 hrs)

Test BOP as per Parker drilling procedure. 250psi low 5 mins/ 5000psi high 10mins. Annular 250 low 5mins/3000psi high 10mins. ok. (6.5 hrs)

Install wear bushing and lock down. (1 hrs)

M/up rotary BHA anfd TIHBHA to 224m (1.5 hrs)

TRPI with 3 1/2 dp to 800m, (1 hrs)

Layout bent 3 1/2 kelly and install new 3 1/2 kelly. (2.5 hrs)

Continue to TRPI with 3 1/2 dp to 2356m Tag cement. (3.5 hrs)
Drill out cement f/- 2356m to 2400m . Cement firm. GPM 175,RPM 40,WOB 4/5k. (2 hrs)
Circulate and condition well bore to 8.5 ppg. (2.5 hrs)
Flowcheck (static) TRPO. 750m @ 06:00 hrs (3 hrs)

Comments: Change out bent kelly.
Drill out cement to 2400m . Cement firm .
Prepare directional equipment .

Mud Data: MW: 8.6 Viscosity: 112 Filtrate: HTHP Filtrate: 0.5

Surveys: None

Daily Costs $: 28,750 **Well Costs $:** 2,750,071

Drilling Days: 37 **Completion Days:**

12-Nov-05 **Current Depth:** 2411.0 **Hole Drilled:** 11.0 **Ave ROP:** 0.92

Current Ops: Continue to drill 6" hole sliding to kick off cement plug. 30% Formation at 06:00 hrs.

Operations Summary:

POOH BHA, Lay out 2 HWDP. (2 hrs)
P/U Motor w/- 1.5 deg bend. 117 bit. Install MWD probe. (1 hrs)
P/U 2 HWDP and run BHA f/- mast. (1 hrs)
Test MWD. (0.5 hrs)
No pulse observed during testing of MWD. POOH and Change Probe. (orifice upside down) RIH test okay. (2.5 hrs)
RIH. (4.5 hrs)
P/U kelly, check MWD, tag cement plug. Orientate. (0.5 hrs)
Directional Drill Time drilling f/- 2400m to 2411m. GPM 203, WOB 4-6k, SPM 125=1980 psi. (12 hrs)

Comments: Time drill to Kick off f/- 2400.
Pump sweeps as required.

Mud Data: MW: 8.5 Viscosity: 108 Filtrate: HTHP Filtrate: 0.5

Surveys: None

Daily Costs $: 59,941 **Well Costs $:** 2,810,011

Drilling Days: 38 **Completion Days:**

13-Nov-05 **Current Depth:** 2428.0 **Hole Drilled:** 17.0 **Ave ROP:** 0.71

Current Ops: Continue to drill 6" hole sliding to 2428m,GPM 202,WOB 4-8k, ROP .7-1m/hr, Pump sweeps as required.No conclusive surveys to report.

Operations Summary:

Continue to time drill to 2425m. 95% formation.ROP 1mhr ,WOB 2-3k. (18 hrs)
Continue to drill 6" hole to 2428m 95% formation . Slow ROP .5m/hr . Work sting and pump 5 bbls sweeps as required. GPM 202, WOB 6-8k. (6 hrs)

Comments: Continue to Kick off. slow ROP due to fomation .7-1m/hr.
No conclusive surveys to report.

Mud Data: MW: 8.5 Viscosity: 75 Filtrate: HTHP Filtrate: 1

Surveys: None

Daily Costs $: 44,391 **Well Costs $:** 2,854,402

Drilling Days: 39 **Completion Days:**

14-Nov-05 **Current Depth:** 2491.0 **Hole Drilled:** 63.0 **Ave ROP:** 5.48

Current Ops: Continue to drill 6" hole to 2491m .GPM 200,RPM 80,WOB 4-6k, Torque 6/7000 ft/bls, ROP 4-16 m/hr. Pump sweeps as required.

Operations Summary:

Continue to drill 6" hole to 2433m. Check shot survey .inclination and azimuth not on track. Building

angle instead of dropping. (1 hrs)

Pump sweep and circulate and condition mud prior to TRPO to change bit and check BHA. (1.5 hrs)

Flow check (static) Pump slug and TRPO to BHA. (4 hrs)

Flow check at BHA .continue to TOHBHA. lay out MWD probe and L/out 6" Mill tooth bit. (0.5 hrs)

M/up New MWD Probe ,6" DSX519 PDC BIT AND TIHBHA to 225m (1.5 hrs)

Test MWD OK. Continue TRPI to 2395m.Filling pipe @798,2395m (3 hrs)

Slip and cut 72ft drilling line (1 hrs)

Rig Service (0.5 hrs)

Continue TRPI to 2400m wash down f/-2400m to 2428m No fill (0.5 hrs)

Continue drill 6" hole sliding to 2442m (1.5 hrs)

Continue drill 6" hole Rotating to 2451m (1.5 hrs)

Continue drill 6" hole Sliding to 2457m. ROP 5m/hr. (1.5 hrs)

Continue drill 6" hole Sliding first 5m of single then rotate the rest. ROP Sliding 5/6m/hr Rotating 14/16m/hr. (6 hrs)

Comments: Continue to drill 6" hole sliding and rotating .
Prepare sound walls to erect.

Mud Data: MW: 8.5 Viscosity: 84 Filtrate: HTHP Filtrate: 1.2

Surveys: 2431ft - 22.88 deg Inc, 133.85 deg Az; 2450ft - 20.66 deg Inc, 134.57 deg Az; 2469ft - 18.66 deg Inc, 135.4 deg Az

Daily Costs $: 58,274 **Well Costs $:** 2,912,676

Drilling Days: 40 **Completion Days:**

15-Nov-05

Current Depth: 2616.0 **Hole Drilled:** 125.0 **Ave ROP:** 5.21

Current Ops: Continue to drill 6" hole sliding and rotaing. Pump sweeps as required. Work connections twice. 36 units back ground gas .

Operations Summary:

Continue to drill 6" hole sliding and rotating to 2581m ROP 5-7m/hr, (18 hrs)

Continue to drill 6" hole sliding and rotating to 2616m. ROP 5-6m/hr,GPM 201,4/6000 ft/bls, WOB 8/10k.Pump sweeps as required. (6 hrs)

Comments: Continue drill 6" hole sliding and rotating.GPM 202,RPM 80, Torque 5/7000ft/lbs, Pump sweeps as required.No drag on connections.
36 units max back ground gas.

Mud Data: MW: 8.5 Viscosity: 70 Filtrate: HTHP Filtrate: 1.4

Surveys: 2487ft - 16.44 deg Inc, 137.17 deg Az; 2506ft - 13.88 deg Inc, 136.69 deg Az; 2525ft - 11.29 deg Inc, 136.36 deg Az; 2545ft - 8.66 deg Inc, 138.64 deg Az; 2564ft - 6.61 deg Inc, 140.33 deg Az; 2583ft - 4.82 deg Inc, 144.36 deg Az

Daily Costs $: 33,771 **Well Costs $:** 2,946,447

Drilling Days: 41 **Completion Days:**

16-Nov-05

Current Depth: 2721.0 **Hole Drilled:** 105.0 **Ave ROP:** 4.38

Current Ops: Continue to drill 6" hole sliding and rotating . GPM 200, RPM 80, Toque 6/7000 ft/bls, WOB 8/10k,Pump 5 bbls sweeps as required.Back ground gas 25/40 units.

Operations Summary:

Continue to drill 6" hole rotating and sliding to 2703m . ROP 4.8m/hr. Pump 5 bbls sweeps as required (18 hrs)

Continue to drill 6" hle sliding and rotating to 2721m.
3m/hr.GPM 202,Torque 5/7000 ft/bs, SPM 125=2200psi, WOB 8/10k. (6 hrs)

Comments: Drill into tariki formation at 2667m MD ,2570m TVD.

Mud Data: MW: 8.6 Viscosity: 68 Filtrate: HTHP Filtrate: 1.4

Surveys: 33ft - 1.0 deg Inc, 0 deg Az; 100ft - 1.0 deg; 145ft - 1.0 deg; 195ft - 1.0 deg; 239ft - 1.86 deg Inc, 311.19 deg Az; 267ft - 1.24 deg Inc, 299.5 deg Az; 2601ft - 2.51 deg Inc, 140.1 deg Az; 2620ft - 0.18 deg Inc, 144.65 deg Az; 2640ft - 2.09 deg Inc, 303.51

deg Az; 2659ft - 3.84 deg Inc, 303.52 deg Az; 2678ft - 6.06 deg Inc, 304.39 deg Az; 2706ft - 7.3 deg Inc, 302.28 deg Az

Daily Costs $: 34,665 **Well Costs $:** 2,981,112

Drilling Days: 42 **Completion Days:**

17-Nov-05 **Current Depth:** 2768.0 **Hole Drilled:** 47.0 **Ave ROP:** 2.19

Current Ops: Drilling 6" hole sliding & rotating. GPM-200, RPM-80, WOB-8/10k, Torque-6/7000 ft/lbs, Av ROP-5 m/hr.

Operations Summary:

Slide 6" hole f/- 2721m to 2727m. WOB 6/8, GPM 198, m/hr 1.6 (4 hrs)

Rotate 6" hole f/- 2719m to 2742m. WOB 8/10, GPM 198, RPM 80, m/hr 2.6 (5 hrs)

Flow check, POOH f/- 2742m to shoe. (1 hrs)

Full rig service & adjust brake. (0.5 hrs)

RIH f/- shoe to 2726m, wash down last single to 2742m. (1 hrs)

Con't rotate 6" hole f/- 2742m to 2751. WOB 8/10, GPM 200, RPM 80, m/hr 2 (4.5 hrs)

Slide 6" hole f/- 2751m to 2755m. WOB 5/10, GPM 200, m/hr 2. (2 hrs)

Rotate 6" hole f/- 2755m to 2756m. WOB 8/10, GPM 200, RPM 80, m/hr 1 (1 hrs)

Slide 6" hole f/- 2756m to 2760m. WOB 5/10, GPM 200, m/hr 2. (2 hrs)

Rotate 6" hole f/- 2760m to 2768m. WOB 8/10, GPM 200, RPM 80, m/hr 2.5. (3 hrs)

Mud Data: MW: 8.65 Viscosity: 71 Filtrate: HTHP Filtrate: 1.6

Surveys: None

Daily Costs $: 122,236 **Well Costs $:** 3,103,347

Drilling Days: 43 **Completion Days:**

18-Nov-05 **Current Depth:** 2836.0 **Hole Drilled:** 68.0 **Ave ROP:** 2.89

Current Ops: Drilling 6" hole in slide mode @ 2836m

Operations Summary:

Drill 6" hole f/-2768m to 2803m. WOB 8/10, GPM 200, 2200 psi, RPM 100, m/hr 3.1 (8.5 hrs)

Full rig service. (0.5 hrs)

Drill 6" hole f/- 2803m to 2830m. WOB 8/10, GPM 200, 2200 psi, RPM 80/100, Torque 6/8k lbs. (12 hrs)

Drill 6" hole Slide f/- 2830m to 2836m. WOB 6/8, GPM 200, 2200psi on bottom / 2100 psi off bottom. (3 hrs)

Comments: ROP has been down to .7 m/hr, as we incounter higher ROP we are attempting to slide to reduce angle.

Mud Data: MW: 8.7 Viscosity: 72 Filtrate: HTHP Filtrate: 2

Surveys: 294ft - 0.87 deg Inc, 291 deg Az; 321ft - 0.74 deg Inc, 248 deg Az; 348ft - 0.81 deg Inc, 213.08 deg Az; 375ft - 0.81 deg Inc, 204.33 deg Az; 401ft - 0.8 deg Inc, 194.32 deg Az; 428ft - 0.76 deg Inc, 191.07 deg Az; 455ft - 1.46 deg Inc, 166.37 deg Az; 482ft - 1.61 deg Inc, 157.58 deg Az; 509ft - 1.35 deg Inc, 159.08 deg Az; 563ft - 1.7 deg Inc, 122.65 deg Az; 640ft - 2.03 deg Inc, 114.2 deg Az; 2735ft - 6.73 deg Inc, 299.84 deg Az; 2764ft - 6.99 deg Inc, 303.15 deg Az; 2792ft - 7.14 deg Inc, 304.1 deg Az; 2821ft - 7.9 deg Inc, 303.5 deg Az

Daily Costs $: 30,022 **Well Costs $:** 3,133,369

Drilling Days: 44 **Completion Days:**

19-Nov-05 **Current Depth:** 2873.0 **Hole Drilled:** 37.0 **Ave ROP:** 1.57

Current Ops: Drilling 6" hole in Slide mode.

Operations Summary:

Drill 6" hole Slide f/- 2836m to 2837m. WOB 5/6k, GPM 200, psi 2200. (0.5 hrs)

Drill 6" hole Rotate f/- 2837m to 2845m. WOB 8/10k, GPM 200, psi 2200, Torque 6/8k, RPM 80/90. (4 hrs)

Drill 6" hole Slide f/- 2845m to 2849m. WOB 5/8k, GPM 200, psi 2200. (5 hrs)

Drill 6" hole Rotate f/- 2849m to 2861m. WOB 8/10, GPM 200, psi 2200, Torque 6/8k, RPM 80/90. (5 hrs)
Full rig service, clean pump strainers. (0.5 hrs)
Drill 6" hole Slide f/- 2861m to 2865m. WOB 8/10, GPM 200, psi 2200, (3 hrs)
Drill 6" hole Rotate f/- 2865m to 2867m. WOB 8/10, GPM 200, psi 2200, Torque 6/8k, RPM 80/100 (1 hrs)
Drill 6" hole Slide f/- 2867m to 2868m. WOB 8/10, GPM 200, psi 2400. (0.5 hrs)
Drill 6" hole Rotate f/- 2868m to 2870m. WOB 8/10, GPM 200, psi 2400, Torque 6/8k, RPM 80. (1.5 hrs)
Drill 6" hole Slide f/- 2868m to 2873m. WOB 8/10, GPM 200, psi 2400. (3 hrs)

Mud Data: MW: 8.7 Viscosity: 72 Filtrate: HTHP Filtrate: 1.8

Surveys: 2849ft - 8.26 deg Inc, 297.31 deg Az

Daily Costs $: 38,397 **Well Costs $:** 3,171,765

Drilling Days: 45 **Completion Days:**

20-Nov-05

Current Depth: 2885.0 **Hole Drilled:** 12.0 **Ave ROP:** 2.40

Current Ops: Drill 6" hole to 2885m.

Operations Summary:

Drill 6" hole Slide f/- 2873m to 2874m. WOB 8/10, GPM 200, psi 2400. (0.5 hrs)
Circ & condition shakers clean. (0.5 hrs)
Pump slug, flow check, POOH f/- 2874m to BHA. (4.5 hrs)
Lay out HWDP, brk bit, layout motor. (2.5 hrs)
P/up new motor, m/up bit #10, set bend to 1.15 deg. Scribe MWD. P/up new HWDP f/- rack. (3 hrs)
Surface test MWD. RIH drill pipe f/- mast to 2373m. Fill pipe every 30 std's. (4 hrs)
Slip & cut drilling line. monitor trip tank. (1 hrs)
Full rig service. monitor trip tank. (0.5 hrs)
Con't RIH f/- 2373m to 2414m. Took wt (10,000 lbs) (0.5 hrs)
Work pipe through tight spot @ 2414m. P/up kelly & oreintate toolface & slide through tite area to 2430m. (1 hrs)
RIH f/- 2430m to 2858m. fill pipe. (1 hrs)
Wash down f/- 2858m to 2874m. tag 2m fill. (0.5 hrs)
Drill 6" hole Rotate f/- 2874m to 2876m, cut new bit profile. WOB 2/4k, GPM 200, psi 2200, RPM 80, Torque 5/7k. (0.5 hrs)
Drill 6" hole Slide f/- 2876m to 2879m. WOB 5/6k, GPM 200, psi 2200, (2 hrs)
Drill 6" hole Rotate f/- 2879m to 2885m. WOB 5/6k, GPM 200, psi 2200, RPM 80, Torque 5/7k. (2 hrs)

Comments: Azimuth swing on last survey. Similar occured @ 2734.87m.
Did a check survey 1 sng after last survey & build was @ 8.95 deg. f/- 8.26. Azimuth was 295.47 f/- 297.31 in slide mode! decide to POOH.
At this point we can afford to get out to 9.47 deg. & still hit the target. Azimuth is not a problem.

Mud Data: MW: 8.7 Viscosity: 74 Filtrate: HTHP Filtrate: 1.8

Surveys: None

Daily Costs $: 74,585 **Well Costs $:** 3,246,351

Drilling Days: 46 **Completion Days:**

21-Nov-05

Current Depth: 2953.0 **Hole Drilled:** 68.0 **Ave ROP:** 2.89

Current Ops: Drilling 6" hole in Rotate mode. @ 2955m WOB 5/6k, GPM 200, psi 2450, RPM 80/100, Torque 5/7k ft/lbs. ROP 3.7 m/hr

Operations Summary:

Drill 6" hole Rotate f/- 2885m to 2888m. WOB 5k, GPM 200, psi 2350, RPM 80, Torque 6k ft/lbs. (0.5 hrs)

Drill 6" hole Slide f/- 2888m to 2889m. WOB 5k, GPM 200, psi 2350. (0.5 hrs)

Drill 6" hole Rotate f/- 2889m to 2892m. WOB 5k, GPM 200 psi 2350, RPM 80, Torque 6/7k ft/lbs. (1.5 hrs)

Drill 6" hole Slide f/- 2892m to 2898m. WOB 5/6k, GPM 200, psi 2350, (3.5 hrs)

Drill 6" hole Rotate f/- 2898m to 2917m. WOB 5/6k, GPM 200, psi 2350, RPM 80, Torque 6/7k ft/lbs. (6.5 hrs)

Full rig service. (0.5 hrs)

Drill 6" hole Rotate f/- 2917m to 2953m. WOB 5/6k, GPM 200, psi 2450, RPM 80/100, Torque 5/7k ft/lbs. (11 hrs)

Comments: Good responce f/- slide section, able to rotate through target, & on to section TD.

Mud Data: MW: 8.7 Viscosity: 72 Filtrate: HTHP Filtrate: 1.8

Surveys: 616ft - 2.02 deg Inc, 111 deg Az; 667ft - 1.98 deg Inc, 111.15 deg Az; 703ft - 6.8 deg Inc, 153.15 deg Az; 720ft - 8.98 deg Inc, 151.12 deg Az; 747ft - 11.4 deg Inc, 142.56 deg Az; 765ft - 12.04 deg Inc, 140.94 deg Az; 2876ft - 7.95 deg Inc, 300.12 deg Az; 2905ft - 6.76 deg Inc, 297.11 deg Az; 2933ft - 7.21 deg Inc, 296.81 deg Az

Daily Costs $: 49,317 **Well Costs $:** 3,295,668

Drilling Days: 47 **Completion Days:**

22-Nov-05

Current Depth: 2993.0 **Hole Drilled:** 40.0 **Ave ROP:** 2.42

Current Ops: Attempt to work way out of coal seam. RPM 70, Torque 3/15k ft/lbs, GPM 160, psi 1500. WOB 1k.

Operations Summary:

Drill 6" hole Rotate f/- 2953m to 2993m. WOB 5/10k, GPM 200, psi 2450, RPM 80/100, Torque 5/7k ft/lbs. (16.5 hrs)

Attempt to p/up & make connection. No go, attempt to rotate. No go. Work pipe free. Slow pump rate to 160 GPM. (0.5 hrs)

Establish rotary & circ b/up @ GPM 160, psi 1500, RPM 70, still unable to p/up. 100% coal @ shakers. (1 hrs)

Con't circ & work pipe down/up to gain larger free spot. Work way out of coal seam. (6 hrs)

Comments: Stuck in coal seam for 1/2 hour last night, managed to regain rotation. Attempting to work out of coal seam.

Mud Data: MW: 8.7 Viscosity: 77 Filtrate: HTHP Filtrate: 1.8

Surveys: 783ft - 13.35 deg Inc, 139.3 deg Az; 801ft - 15.18 deg Inc, 135.82 deg Az; 962ft - 19.33 deg Inc, 131.71 deg Az; 989ft - 18.58 deg Inc, 134.39 deg Az; 1016ft - 18.94 deg Inc, 134.93 deg Az; 1043ft - 19.46 deg Inc, 134.62 deg Az; 1071ft - 19.79 deg Inc, 133.81 deg Az; 1098ft - 19.81 deg Inc, 132.43 deg Az; 1124ft - 19.47 deg Inc, 133.9 deg Az; 1151ft - 18.96 deg Inc, 137.12 deg Az; 1178ft - 18.89 deg Inc, 137.82 deg Az; 2962ft - 7.37 deg Inc, 291 deg Az

Daily Costs $: 44,205 **Well Costs $:** 3,339,873

Drilling Days: 48 **Completion Days:**

23-Nov-05

Current Depth: 3022.0 **Hole Drilled:** 29.0 **Ave ROP:** 1.38

Current Ops: Time drill 6" hole while wait on sample f/- drill brk @ 3021m. 06:00 depth 3022m

Operations Summary:

Ream f/- 2992.5m to 2993m. WOB 0-1k, GPM 160, psi 1500, RPM 70, Torque 5/15k ft/lbs. 100% coal @ shakers. (0.5 hrs)

Pull back to 2986m w/- 5k over pull, ream back to 2993m. (0.5 hrs)

Pump 10 bbls low vis low wt (base oil), pump 10 bbls 10.7 ppg 74 vis, & circ out of hole. 100% coal @ shakers. (2 hrs)

Time drill 6" hole Rotate f/- 2993m to 3005m. WOB 2/4k, GPM 160/200, psi 1500/2200. Torque 5/7k ft/lbs. 100/20% coal @ shakers. (13 hrs)

Drill 6" hole Rotate f/- 3005m to 3015m. Constant WOB 6K, GPM 200, psi 2200, RPM 80, Torque 5/7k ft/lbs. 10% coal @ shakers. (4 hrs)

Time drill 6" hole Rotate f/-3015m to 3016m. WOB 2/5k, GPM 200, psi 2200, RPM 80, Torque 6k

ft/lbs, 15/20% coal @ shakers. (1 hrs)

Drill 6" hole Rotate f/- 3016m to 3021m. Constant WOB 6k, GPM 200, psi 2300, RPM 80, Torque 5/7k ft/lbs. 20% coal @ shakers, drill brk. (2 hrs)

Time drill 6" hole Rotate f/- 3021m to 3022m. WOB 4/6k, GPM 200, psi 2300, RPM 80, Torque 5/7k ft/lbs. (1 hrs)

Comments: Ditch magnet recovery: 400 grms

Mud Data: MW: 8.7 Viscosity: 76 Filtrate: HTHP Filtrate: 1.4

Surveys: 1205ft - 19.52 deg Inc, 136.5 deg Az; 1232ft - 20.14 deg Inc, 136.47 deg Az; 1258ft - 20.76 deg Inc, 135.86 deg Az; 1285ft - 20.58 deg Inc, 135.56 deg Az; 1312ft - 17.63 deg Inc, 137.59 deg Az; 2988ft - 7.39 deg Inc, 288.92 deg Az

Daily Costs $: 41,709 **Well Costs $:** 3,381,582

Drilling Days: 49 **Completion Days:**

24-Nov-05

Current Depth: 3050.0 **Hole Drilled:** 28.0 **Ave ROP:** 1.40

Current Ops: Continue to drill 6" hole .Base of ahuroa trust 3034m. TD prognosed 3084m. GPM 200 ,SPM 160, SPP 2350psi. WOB 3/6K, RPM 80,ROP 2-3.5m/hr. Back ground gas 6/15 units.Pump sweeps as required.

Operations Summary:

Continue to time drill 1m/hr through coal seam to to 3022m.15% coal. (0.5 hrs)

Continue to time drill 1 m/hr to 3025m 100% coal .Pump 5 bbls sweeps to keep well bore clean . maintain 4 bpb barablok in mud system to control coal.GPM 200, SPM 160 SPP=2300psi (1.5 hrs)

Time drill at 1m/hr to 3028m .100% coal.Pump 5 bbls sweeps as required (4 hrs)

Continue to time drill 6" hole to 3031m .Sample 3030m 100% coal ,sample 3031m 70% coal /30% claystone.GPM 200, WOB 2/4k.SPM 160 ,SPP 2300psi. (4 hrs)

Pump 10 bbls sweep and circulate clean prior to wiper trip. (1.5 hrs)

Flow check (static) Pump slug . (0.5 hrs)

Wiper trip back to 2868m . No hang ups. (1 hrs)

Rig service . Circulate and condition mud while performing Rig service. (0.5 hrs)

TRPI to 3020m wash down last single to 3031m. 1m fill. (0.5 hrs)

Continue to time drill 6" hole to 3036.5m. 3034m geologist called base of ahuroa trust .GPM 200 ,SPM 160,SPP 2300psi, (5.5 hrs)

Continue to drill 6" hole conventionally f/-3036.5m to 3050m Coal percentages dropped of to only traces.
GPM 200,WOB 4/6k, Torque 4/5000 ft/lbs,RPM 80 ,SPM 160=SPP 2350psi.,ROP 3.1m/hr. Pump sweeps as required. (4.5 hrs)

Comments: Control drill through coal 100% f/- 3023m to 3032m.
Drill to 3032m hole getting sticky and overpull increasing to 10/12k.Pump sweep and wiper trip back to old hole 2874m.
Check all pressure sensor diaphrams.
Clean out discharge strainers on mud pumps during wiper trip.
Base of ahuroa trust 3034m(Geologist prognosis)

Mud Data: MW: 8.7 Viscosity: 74 Filtrate: HTHP Filtrate: 1.4

Surveys: 1339ft - 17.41 deg Inc, 138.69 deg Az; 1366ft - 17.6 deg Inc, 138.6 deg Az; 1393ft - 17.53 deg Inc, 138.57 deg Az; 1421ft - 18.94 deg Inc, 136.54 deg Az; 1447ft - 19.29 deg Inc, 135.9 deg Az; 1474ft - 19.86 deg Inc, 135.22 deg Az; 1501ft - 20.16 deg Inc, 134.48 deg Az; 1528ft - 20.68 deg Inc, 134.12 deg Az; 1555ft - 21.3 deg Inc, 133.7 deg Az; 3019ft - 8.03 deg Inc, 288.39 deg Az

Daily Costs $: 48,008 **Well Costs $:** 3,429,590

Drilling Days: 50 **Completion Days:**

25-Nov-05

Current Depth: 3085.0 **Hole Drilled:** 35.0 **Ave ROP:** 3.68

Current Ops: TRPO layout directional equipment.Rig up schlumberger wireline equipment.

Operations Summary:

Continue drill 6" hole to 3071m .GPM 200, SPM 160 ,SPP 2400psi,Torque 6/7000 ft/bls. (6 hrs)

Drill 6" hole to target depth 3085m ,50m below the ahuroa thrust basement.GPM 200, ROP 3/4m/hr,Torque 6/7000 ft/bls. 100% claystone formation,SPM 160 ,SPP 2350psi. (3.5 hrs)

Pump 10bbls sweep and circulate well clean. (1.5 hrs)

Flow check ,(static)Pump slug . (0.5 hrs)

Wiper trip back to shoe 2395m .no hang ups. (2 hrs)

TRPI to 3055m , wash down toTD 3085m .1.2m fill. (2 hrs)

Sweep 10bbls high vis and circulate clean.Flow check (static) Spot 15 bbls high vis on bottom. (2.5 hrs)

TRPO to 7" casing shoe 2395m no hang ups. (2 hrs)

Flow check at 7" casing shoe 5 mins (static) Continue TRPO to BHA.216m. (4 hrs)

Comments: Drill 6 " to 3085m TD 50m below the ahuroa trust..
Wiper trip back to old hole good .no hang ups.
Schlumberger on site and inducted.

Mud Data: MW: 8.7 Viscosity: 74 Filtrate: HTHP Filtrate: 1.4

Surveys: 1582ft - 20.84 deg Inc, 134.88 deg Az; 1609ft - 20.57 deg Inc, 135.08 deg Az; 1636ft - 19.73 deg Inc, 135.14 deg Az; 1662ft - 20.06 deg Inc, 135.12 deg Az; 3048ft - 8.34 deg Inc, 287.78 deg Az; 3069ft - 8.38 deg Inc, 287.69 deg Az

Daily Costs $: 43,583 **Well Costs $:** 3,473,173

Drilling Days: 51 **Completion Days:**

26-Nov-05 **Current Depth:** 3085.0 **Hole Drilled:** 0.0 **Ave ROP:**

Current Ops: Mix and pump cement plug across 7" casing shoe.

Operations Summary:

Flow check at BHA and TOHBHA and layout mwd , remove probe ,mud motor ,stab ,bit. (1 hrs)

HPJSM Proir to rigging up schlumbereger equipment.
Rig up schhlumberger equipment. (1 hrs)

P/up run# 1 PEX -AIT.load source.
Run in hole tag bottom W/L MD 3087m.
Log up to shoe and Pull out with W/l to surface . (5 hrs)

Unload source at surface . Lay out run#1 PEX-AIT. (0.5 hrs)

M/up run # 2 . UBI. (0.5 hrs)

Run in hole w/- UBI.Log up f/- 3085m. (6.5 hrs)

Wire line at surface . Comfirm logs.ok Lay out UBI tools. Rig down schlumbereger surface equipment (2 hrs)

Rig up floor for 2 7/8 tubing .P/up mule shoe and run cement stinger to 146m (1 hrs)

Change out handling equipment for 3 1/2 dp.TRPI to 2430m. (4 hrs)

Circulate and condition mud while mix spacers and prepare cement plug. (2 hrs)

Held pre job meeting prior to Cement operations.
Rig up cement surface lines. (0.5 hrs)

Comments: Prepare displacement mud .
Site inspection on Kauri F location.
Contact John Molloy from OSH re T&A plan .
Sperry sun DD/MWD prepared equipment for rig move and vacated rig site.

Mud Data: MW: 8.7 Viscosity: 77 Filtrate: HTHP Filtrate: 1.4

Surveys: 1689ft - 20.17 deg Inc, 135.16 deg Az; 1716ft - 20.33 deg Inc, 134.59 deg Az; 1743ft - 20.69 deg Inc, 133.96 deg Az; 1770ft - 20.87 deg Inc, 133.79 deg Az; 1798ft - 20.16 deg Inc, 134.56 deg Az; 1826ft - 19.74 deg Inc, 134.84 deg Az; 1855ft - 19.43 deg Inc, 134.56 deg Az; 1911ft - 18.93 deg Inc, 134.2 deg Az; 1939ft - 19.02 deg Inc, 135.21 deg Az; 1967ft - 19.08 deg Inc, 135.49 deg Az; 1995ft - 18.9 deg Inc, 135.71 deg Az; 2024ft - 18.59 deg Inc, 135.52 deg Az

Daily Costs $: 26,854 **Well Costs $:** 3,500,027

Drilling Days: 52 **Completion Days:**

27-Nov-05 **Current Depth:** 3085.0 **Hole Drilled:** 0.0 **Ave ROP:**

Current Ops: TRPO to pick up cement stinger

Operations Summary:

Pump 10 bbls spacer . Test surface lines to 3000psi ok,Continue pump 20 bbls spacer Total 30 bbls.Mix and pump 11 bbls 17.2ppg slurry . pump 7 bbls spacer to balance plug. Displace with 44 bls SBM. Check back flow .(static). (1 hrs)

Rig down cement surface lines and TRPO to 2283m slowly.No overpull . (0.5 hrs)

Drop wiper ball and Circulate bottoms up .no cement contamination back at surface. Some spacer returns at surface. (1 hrs)

Lay out excess 3 1/2 drill pipe to 1581m (2 hrs)

Continue to TRPO to 146m 2 7/8 cement stinger (2.5 hrs)

Layout 2 7/8 cement stinger and handling quipment (1.5 hrs)

HPJSM prior to rigging up vause W/L. R/up vause W/L surface equipment (0.5 hrs)

Run # 1 CBL .log down to 1500m them log up to 500m to evaluate cement bond.Soilid cement up to 905m . (2.5 hrs)

M/up clean out assy and TIHBHA to 205m (1 hrs)

Continue TRPI to 2320m filling as required (5 hrs)

Wash down f/- 2320m to 2450m No cement tagged. (1 hrs)

Circulate bottoms up . No cement contamination at bottoms up (1 hrs)

Pump slug and TRPO to BHA. (4.5 hrs)

Comments: Transfer 422 bbls 70/30 SBM f/- ahuroa st-1 to goss well site.
Back load 68 jnts 3 1/2 dp f/- ahuroa to TOT
TRPI to 2320m, wash down to top of plug no cement tagged continue wash down to 2450m no cement tagged.

Mud Data: MW: 8.5 Viscosity: Filtrate:

Surveys: 2053ft - 19.21 deg Inc, 136.77 deg Az; 2081ft - 19.19 deg Inc, 137.35 deg Az; 2110ft - 19.43 deg Inc, 138.72 deg Az; 2138ft - 20.66 deg Inc, 139.96 deg Az; 2167ft - 20.95 deg Inc, 140.91 deg Az; 2196ft - 20.97 deg Inc, 140.94 deg Az; 2224ft - 20.97 deg Inc, 141.28 deg Az; 2253ft - 20.5 deg Inc, 139.14 deg Az; 2292ft - 20.35 deg Inc, 138.83 deg Az; 2320ft - 20.22 deg Inc, 139.3 deg Az; 2348ft - 19.97 deg Inc, 140.39 deg Az; 2378ft - 19.93 deg Inc, 141.01 deg Az

Daily Costs $: 100,694 **Well Costs $:** 3,600,721

Drilling Days: 53 **Completion Days:**

28-Nov-05

Current Depth: 3085.0 **Hole Drilled:** 0.0 **Ave ROP:**

Current Ops: Layout remaining 3 1/2 DP/HWDP.

Operations Summary:

Continue TRPO to BHA 205m (1.5 hrs)

TOHBHA layout bit ,bit sub, (1 hrs)

M/up EZSV packer assy. (0.5 hrs)

TRPI with EZSV as per haliburton engineers parameters to 2365m (6 hrs)

Circulate and condition mud prior to setting EZSV packer. work string through setting zone (0.5 hrs)

Get up/ down weights.122k up 95k down,Set ezsv packer with 35 turns right .Pick up 15k over string weight and let packer element expand.Continue to pull to 170k and shear packer. Set down 20k to confirm packer set ok. (0.5 hrs)

Establish injectivity rate under EZSV . Break over at 1550psi. pump 1.5bpb = 1340psi. (0.5 hrs)

Sting out of EZSV. Pump 5 bbls spacer ,test surface lines to 3000psi ok. continue pump spacer total 10bbls.

Mix and pump 12 bbls 15.2ppg cement slurry , pump 1.3 bbls tail spacer for balance.
Displace with SBM 32 bbls, sting into EZSV and inject 5 bbls slurry under EZSV1.7bpm= 800psi.
Pump 5bbls then unsting out of EZSV. Continue to displace total 48 bbls.displace at 6bpm=450 psi.Stop pumping check back flow .(static) (0.5 hrs)

TRPO slowly to 2235m and reverse circulate tubing volume . no cement returns. (1 hrs)

Pressure test EZSV against casing to 3000psi 10mins ok. (0.5 hrs)

Rig down cementing surface equipment. (0.5 hrs)
Displace SBM to caCL brine .Flush all drilling quipment. (2 hrs)
Lay down 3 1/2 DP ,3 1/2 HWDP.Soft break kellly. (9 hrs)

Comments: Held pre job meeting prior to setting EZSV, Cementing operations,Laying down 3 1/2 DP.
Injection test on a annulus 1 bpm= 120psi 5bpm=650 psi.

Mud Data: MW: 8.5 Viscosity: Filtrate:

Surveys: None

Daily Costs $: (29,298) **Well Costs $:** 3,571,423

Drilling Days: 54 **Completion Days:**

29-Nov-05

Current Depth: 3085.0 **Hole Drilled:** 0.0 **Ave ROP:**

Current Ops: Rig move .Rig release at 24:00 hrs on the 28th november

Operations Summary:

Layout 3 1/2 hwdp. (2 hrs)
Retrieve wearbushing and set test plug. (0.5 hrs)
Layout kelly, L/out RKB , (1.5 hrs)
Layout 3 1/2 handling equipment (0.5 hrs)
Rig down flow line ,blow back koomey lines, l/out annular, rams, spacer spool. (6.5 hrs)
Nipple up well head valve and pressure test to 3000psi ok. (1 hrs)
Continue cleaning tanks and preparing for rig move (6 hrs)
Release rig at midnight 28th november. (6 hrs)

Comments: Production handed over KAURI F2 to drilling 10:00 am 28th November.
Pre job safety meeting prior to rigging down BOPS.
Clean out mud pits with steam cleaner and vacume truck.
Transfer 330 bbls sump waste to spence rd.
Break down mud tanks /remove flow line.
Back load third party rental equipment.
Final fuel dip 38" 8863 ltrs.

Mud Data: MW: Viscosity: Filtrate:

Surveys: None

Daily Costs $: 26,098 **Well Costs $:** 3,597,521

Drilling Days: 55 **Completion Days:**

30-Nov-05

Current Depth: 0.0 **Hole Drilled:** -3085.0 **Ave ROP:**

Current Ops: Rig move from ahuroa south B-1 ST-1 to Kauri F2.

Operations Summary:

Rig move camp 100% rig down rig 25%.
Stripped down mud tanks , Undressed rig floor , Scoped mast in and layed over.Steam clean and pressure wash mud tanks. Remove shaker tanks. Backload third party equipment.Backload excess mud chemicals.
All lifts over live wells ,production operator to be on site to observe.
Mi swaco rigged down there equipment aslo TOT rigged down ther rental equipment. (13 hrs)

Comments: Transfered 330 bbls sump waste and taken to spence road for land farming. total removed 660 bbls.
Fuel dip at 39"=8863 ltrs on rig release.

Mud Data: None

Surveys: None

Daily Costs $: 23,760 **Well Costs $:** 3,621,281

Drilling Days: 56 **Completion Days:**

Well Information Report

Well ID: NZ050091 **Well Name:Ahuroa South B-1**

Operator:	Swift Energy New Zealand Ltd	**Division:**	New Zealand
Classification:	drilling exp/ ☐ **Tight Hole**	**Working Interest:**	100.0%
On/OffShore:	Onshore	**API No:**	
Section:	**Township:** Tariki	**Range:**	
Latitude:	2625724mE	**Longitude:**	6214665.8mN
Location:	Ahuroa A Site, Croydon Rd		
Field:	WAIHAPA	**County:**	Taranaki
State:	TKI	**Country:**	New Zealand
Orig. RKB Elev:	5.230 m	**Ground Elev:**	196.200 m
Casing Head Elev:	-0.650 m	**Tubing Head Elev:**	0.100 m
Other Datum Point:		**Other Datum Elev:**	m
Date On Locn:	29-Sep-05	**Spud Date:**	05-Oct-05
Engineer(s):	Don Green / Allen Faircloth	**Rig Tel No:**	06 762 8743

Well Bore: Original Well Bore **Proposed TD: 3430.0** **ID No: 0**

No hydrocarbon sands. Sidetrack on 10th Novemeber

Target Zones for this Well Bore:		Top MD	Top TVD	Bottom MD	Bottom TVD
Mt Messenger	**from Prognosis:**	1230.0	1196.0		
	Actual:	1200	1176		
Last Sand Bed					
Tikorangi Top	**from Prognosis:**	1940.0	1856.0		
	Actual:	1911	1845		
ROP/Samples					
Otaraoa	**from Prognosis:**	2100.0	2006.0		
	Actual:	2010	1940		
Samples					
Tariki	**from Prognosis:**	2765.0	2636.0		
	Actual:	2710	2598		
Samples					
Mckee	**from Prognosis:**	3180.0	3021.0		
	Actual:				
Mangahewa	**from Prognosis:**	3215.0	3056.0		
	Actual:				
Ahuroa Thrust	**from Prognosis:**	3360.0	3196.0		
	Actual:				
Total Depth	**from Prognosis:**	3430.0	3256.0		
	Actual:	3370	3281		

Section: Conductor

Time/Cost Estimates:	Bottom Depth MD	Bottom Depth TVD	Hole Size	Drill Days	Drill Cost	Case/Eval/Complete Days	Case/Eval/Complete Cost
	36.0	36.0	17.500	2	50,000	1	0

Casing Plan:

Type	Top MD	Top TVD	Btm MD	Btm TVD	O.D.	Weight	Grade	Thread
FULL	0.0	0.0	36.0	36.0	13.375	68.0	L-80	WELD

Plan Comments: Installed by Interdrill

Well Information Report

Section: Surface

Time/Cost Estimates:	Bottom Depth MD	Bottom Depth TVD	Hole Size	Drill Days	Drill Cost	Case/Eval/Complete Days	Case/Eval/Complete Cost
	650.0	650.0	12.250	2			

Casing Plan:

Type	Top MD	Top TVD	Btm MD	Btm TVD	O.D.	Weight	Grade	Thread
FULL	0.0	0.0	650.0	650.0	9.625	53.5	P-110	BUTT

Plan Comments:

Section: Intermediate String 1

Time/Cost Estimates:	Bottom Depth MD	Bottom Depth TVD	Hole Size	Drill Days	Drill Cost	Case/Eval/Complete Days	Case/Eval/Complete Cost
	2670.0	2500.0	8.500	15			

Casing Plan:

Type	Top MD	Top TVD	Btm MD	Btm TVD	O.D.	Weight	Grade	Thread
FULL	0.0	0.0	2400.0	2284.0	7.000	29.0	P-110	BUTT

Plan Comments:

Section: Liner

Time/Cost Estimates:	Bottom Depth MD	Bottom Depth TVD	Hole Size	Drill Days	Drill Cost	Case/Eval/Complete Days	Case/Eval/Complete Cost
	3430.0	3256.0	6.000				

Casing Plan:

Type	Top MD	Top TVD	Btm MD	Btm TVD	O.D.	Weight	Grade	Thread
LINER	2300.0	2200.0	3430.0	3256.0	4.500	11.6	L-80	LTC

Plan Comments:

Actual Data:

TD Date: 07-Nov-05 **Depth - Measured:** 3370.0 **TVD:** 3281.0 m **Status:** P&A

Ending Comments: Sidetracked

Well Bore: Side Track **Proposed TD: 3270.0** **ID No: 1**

Target Zones for this Well Bore:		Top MD	Top TVD	Bottom MD	Bottom TVD
Tariki	from Prognosis:	2670.0	2574.0		
	Actual:				
Mckee	from Prognosis:	3040.0	2934.0		
	Actual:				
Mangahewa	from Prognosis:	3060.0	2964.0		
	Actual:				
Ahuroa Thrust	from Prognosis:	3160.0	3064.0		
	Actual:				
Total Depth	from Prognosis:	3270.0	3174.0		
	Actual:				

Section: Liner

Time/Cost Estimates:	Bottom Depth MD	Bottom Depth TVD	Hole Size	Drill Days	Drill Cost	Case/Eval/Complete Days	Case/Eval/Complete Cost
	3270.0	3174.0	6.000	14	700,000	3	200,000

Casing Plan:

Well Information Report

Type	Top MD	Top TVD	Btm MD	Btm TVD	O.D.	Weight	Grade	Thread
FULL	2300.0	2200.0	3270.0	3123.0	4.500	13.5	P-110	FOX

Plan Comments:

AFE Information

AFE No.	Description	Amount $
051203	Dry Hole Cost	2,731,110
051203-C	Completion Cost	1,017,775
051203-ST1	Sidetrack Cost	910,019

Well Information Report

Well ID: NZ050091A **Well Name:Ahuroa South B-1 ST# 1**

Operator:	Swift Energy New Zealand Ltd	**Division:**	New Zealand
Classification:	drilling exp/ ☐ Tight Hole	**Working Interest:**	100.0%
On/OffShore:	Onshore	**API No:**	
Section: inter.	**Township:** Tariki	**Range:**	
Latitude:	2625724mE	**Longitude:**	6214665.8mN
Location:	Ahuroa A Site, Croydon Rd		
Field:	WAIHAPA	**County:**	Taranaki
State:	TKI	**Country:**	New Zealand
Orig. RKB Elev:	5.230 m	**Ground Elev:**	196.200 m
Casing Head Elev:	-0.650 m	**Tubing Head Elev:**	0.100 m
Other Datum Point:	Sidetrack KOP	**Other Datum Elev:**	2400.000 m
Date On Locn:	29-Sep-05	**Spud Date:**	05-Oct-05
Engineer(s):	Don Green / Allen Faircloth	**Rig Tel No:**	06 762 8743

Well Bore: Original Well Bore **Proposed TD: 3270.0** **ID No: 0**

No hydrocarbon sands.Sidetracked well on 10th Nov 05 from 2405mMD.

Target Zones for this Well Bore:		**Top**		**Bottom**	
		MD	**TVD**	**MD**	**TVD**
Tariki	**from Prognosis:**	2765.0	2636.0		
	Actual:	2710	2598		
Samples					
Mckee	**from Prognosis:**	3180.0	3021.0		
	Actual:				
Not seen					
Mangahewa	**from Prognosis:**	3215.0	3056.0		
	Actual:	2983	2878		
Samples coal in spot sample					
Ahuroa Thrust	**from Prognosis:**	3360.0	3196.0		
	Actual:				
Total Depth	**from Prognosis:**	3430.0	3256.0		
	Actual:				

Section: Conductor

Time/Cost Estimates:	**Bottom Depth**		**Hole**	**Drill**		**Case/Eval/Complete**	
	MD	**TVD**	**Size**	**Days**	**Cost**	**Days**	**Cost**
	36.0	36.0	17.500	2	50,000	1	0

Casing Plan:

Type	**Top MD**	**Top TVD**	**Btm MD**	**Btm TVD**	**O.D.**	**Weight**	**Grade**	**Thread**
FULL	0.0	0.0	36.0	36.0	13.375	68.0	L-80	WELD

Plan Comments: Installed by Interdrill

Section: Surface

Time/Cost Estimates:	**Bottom Depth**		**Hole**	**Drill**		**Case/Eval/Complete**	
	MD	**TVD**	**Size**	**Days**	**Cost**	**Days**	**Cost**
	650.0	650.0	12.250	2			

Casing Plan:

Type	**Top MD**	**Top TVD**	**Btm MD**	**Btm TVD**	**O.D.**	**Weight**	**Grade**	**Thread**
FULL	0.0	0.0	650.0	650.0	9.625	53.5	P-110	BUTT

Plan Comments:

Well Information Report

Section: Intermediate String 1

Time/Cost Estimates:	Bottom Depth MD	Bottom Depth TVD	Hole Size	Drill Days	Drill Cost	Case/Eval/Complete Days	Case/Eval/Complete Cost
	2670.0	2500.0	8.500				

Casing Plan:

Type	Top MD	Top TVD	Btm MD	Btm TVD	O.D.	Weight	Grade	Thread
FULL	0.0	0.0	2400.0	2284.0	7.000	29.0	P-110	BUTT

Plan Comments:

Section: Liner

Time/Cost Estimates:	Bottom Depth MD	Bottom Depth TVD	Hole Size	Drill Days	Drill Cost	Case/Eval/Complete Days	Case/Eval/Complete Cost
	3270.0	3174.0	6.000				

Casing Plan:

Type	Top MD	Top TVD	Btm MD	Btm TVD	O.D.	Weight	Grade	Thread
LINER	2300.0	2200.0	3430.0	3256.0	4.500	11.6	L-80	LTC

Plan Comments:

Well Bore: Side Track **Proposed TD: 3270.0** **ID No: 1**

Target Zones for this Well Bore:		Top MD	Top TVD	Bottom MD	Bottom TVD
Tariki	from Prognosis:	2670.0	2574.0		
	Actual:	2665	2565	2920	
Picked f/- samples					
Mckee	from Prognosis:	3040.0	2944.0		
	Actual:				
Not seen					
Mangahewa	from Prognosis:	3060.0	2964.0		
	Actual:	2983	2878		
Samples coal in spot sample					
Ahuroa Thrust	from Prognosis:	3160.0	3064.0		
	Actual:	3034	2929		
Samples					
Total Depth	from Prognosis:	3270.0	3174.0		
	Actual:	3085	2979		
24th Nov 15:30hrs.					

Section: Liner

Time/Cost Estimates:	Bottom Depth MD	Bottom Depth TVD	Hole Size	Drill Days	Drill Cost	Case/Eval/Complete Days	Case/Eval/Complete Cost
	3270.0	3174.0	6.000	14	900,000	4	400,000

Casing Plan:

Type	Top MD	Top TVD	Btm MD	Btm TVD	O.D.	Weight	Grade	Thread
LINER	2300.0	2200.0	3270.0	3174.0	4.500	13.5	P-110	FOX

Plan Comments: P&A'd

Actual Data:

TD Date: 24-Nov-05 **Depth - Measured:** 3085.0 **TVD:** 2979.0 m **Status:** SUSP

Ending Comments: Set a EZSV @ 2,365m with cement above and below. Possibly used as a water injector.

AFE Information

AFE No.	Description	Amount $
051203	Dry Hole Cost Original Wellbore cost = 2,687,184 to TD @ 3,370mMD	2,731,110
051203-C	Completion Cost	1,017,775
051203-ST1	Sidetrack Cost	910,019

RigName: Parker 252
SpudDate: B-1 5 Nov 05 & B-1 ST1 10 Nov 05
ReleaseDate: 28 November 05

Ahuroa South B-1 / ST1

Suspension / Casing & Cementing Diagram

SWIFT ENERGY
NEW ZEALAND LTD

GL=196.2m AMSL , KB= 201.74m AMSL , SL - 2625724mE 2146656mN

Wellhead and 'drytree' on well

CEMENT DESCRIPTION

13 3/8" Conductor cemented to surface
(topped up with stinger)

12-1/4" x 9-5/8" No returns. Cement to surface.
Lead 420sx Class A @ 11.8ppg 191bbls
Tail 158sx class A @ 15.6ppg 33bbls

Run 1" stinger to 60ft (9 Oct 05)
cement with 20sks 15.6ppg Class G
Slurry vol 4bbls = ± 67ft cap


8 1/2" x 7" Cement job
Lead 200sx Class G @ 11.8ppg 88bbls
Tail 850sx class G @ 15.6ppg 170bbls
displace with 280bbl Sbm and 20bbls water
Pump plug with 2200psi
(Cal top of lead to 499m and top of tail to 1220m)
Good returns while cementing.
Final differential was higher than expected.

27 Nov 05
± 6bbls (± 50m) 15.8 Class G above EZSV
7"EZSV set with pipe @ 2365m
± 6bbls 15.8 Class G below (± 50m) EZSV

6" Openhole Section w/ 8.7ppg SBM

Suspension Plug 11bbl (± 100m) 17.2ppg Class G, 26 Nov 05

Note: Ahuroa South B-1 TD 3370m (6 Nov 05)
Place kick off plug ± 2380-2562m
9 Nov 05 - well becomes Ahuroa South B-1 ST1



CASING DESCRIPTION

Depth m	Size "	Jnts	Grde	Wght ppf	Rnge	Thrd
33	13 3/8	6	L-80	68	-	Welded
			(by Interdrill)			
652.22	9 5/8	55	P110	53.5	3	BTC
2395	7	206	L-80	29	3	BTC

B-1 to B-1 ST1 Kick Off plug 9 Nov 05
123sks Class G, 17.2ppg
2380-2526m
KO @ ± 2425m

± 2985m

TD= B-1 3,370mMD & B-1 ST1 3,085mMD (24 Nov 05)

Author: G.Fagg - Drawn by: T.Hunter - Updated: 27 July 07

Drawing #: 809509

Well Costs Summary Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Code	Account Description	Account Total $
AFE Number: 051203		
Tangible Costs		
1220 02	Conductor	12,200
1220 03	Surface	119,360
1220 04	Protection	26,500
1220 61	Packers/Other Subsurface Equip	6,475
1220 62	Wellhead/Tree	19,600
Intangible Costs		
1210 02	Daywork w/ DP	340,600
1210 03	Daywork w/out DP	217,500
1210 11	Permitting, Surveying, Staking	10,100
1210 22	Directional Drilling	332,375
1210 24	Mud Logging	54,200
1210 26	Open Hole Wireline Service	73,996
1210 45	Insurance	28,220
1210 60	Rig Mobilization/Demobilization	148,000
1210 61	Location, Roads, Pit, etc.	57,300
1210 62	Water/Fuel	77,058
1210 63	Overhead	37,700
1210 64	Drilling Fluids	311,721
1210 65	Environmental (pit disposal etc)	19,850
1210 66	Cement & Cement Services	74,190
1210 68	Transportation/Trucking	36,695
1210 69	Bits, Stabilizers, Reamers, etc	152,350
1210 70	Surf Rentals	36,545
1210 71	Downhole Rentals	49,076
1210 72	Supervision-Engineering/Geology	78,400
1210 73	Contract Services/Labor	53,195
1210 74	Communications	4,200
1210 85	Misc Costs 10%	309,779
	Total for AFE No. 051203 $:	**2,687,184**
AFE Number: 051203-ST1		
Intangible Costs		
1210 03	Daywork w/out DP	14,500
1210 24	Mud Logging	1,760
1210 62	Water/Fuel	5,893
1210 63	Overhead	1,000
1210 64	Drilling Fluids	1,776
1210 65	Environmental (pit disposal etc)	500
1210 66	Cement & Cement Services	150
1210 70	Surf Rentals	845
1210 71	Downhole Rentals	2,009
1210 72	Supervision-Engineering/Geology	2,500
1210 74	Communications	100

Well Costs Summary Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Code	Account Description	Account Total $
1210 85	Misc Costs 10%	3,103
	Total for AFE No. 051203-ST1 $:	**34,136**
	Total Tangible Cost $:	**184,135**
	Total Intangible Cost $:	**2,537,185**
	Total Well Cost $:	**2,721,320**

Well Costs Summary Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Code	Account Description	Account Total $
AFE Number: 051203		
Intangible Costs		
1210 02	Daywork w/ DP	2,375,463
1210 64	Drilling Fluids	311,721
	Total for AFE No. 051203 $:	**2,687,184**
AFE Number: 051203-ST1		
Intangible Costs		
1210 03	Daywork w/out DP	304,500
1210 22	Directional Drilling	96,945
1210 24	Mud Logging	33,440
1210 26	Open Hole Wireline Service	51,045
1210 62	Water/Fuel	27,986
1210 63	Overhead	21,000
1210 64	Drilling Fluids	91,177
1210 65	Environmental (pit disposal etc)	10,500
1210 66	Cement & Cement Services	27,700
1210 67	Cased Hole Wireline Service	13,080
1210 68	Transportation/Trucking	8,990
1210 69	Bits, Stabilizers, Reamers, etc	58,500
1210 70	Surf Rentals	17,745
1210 71	Downhole Rentals	43,233
1210 72	Supervision-Engineering/Geology	60,150
1210 74	Communications	2,100
1210 85	Misc Costs 10%	66,006
	Total for AFE No. 051203-ST1 $:	**934,097**
	Total Tangible Cost $:	**0**
	Total Intangible Cost $:	**3,621,281**
	Total Well Cost $:	**3,621,281**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 1 **Report for 06:00 AM 01-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	0.0	**Drilling Days:**		**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	0.0	**Days On Location:**	1	**Last Casing:**	13.375 at 30.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	9.625 at 650.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**		**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 25 **Service:** 6 **Other:** 4 **Total:** 36

Current Operations: Continue rigging up.

Planned Operations:

Toolpusher: Mick Preston

Wellsite Supervisors: Nathan Peri **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:00	24.00	0	RIGU	Continue rigging up

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110			90,290	90,290	3.3%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904			90,290	90,290	

BHA Information

BHA - None

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 0

Accident Description:

Meetings/Drills	Time	Description
Safety:	60	Safety meeting on new site.

☐ **BOP Test** ☐ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 2 **Report for 06:00 AM 02-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:		**Drilling Days:**	0	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:		**Days On Location:**	2	**Last Casing:**	13.375 at 30.0	**Field:**	WAIHAPA
Hole Made:		**Spud Date:**	05-Oct-05	**Next Casing:**	9.625 at 650.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**		**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 22 **Service:** 8 **Other:** 2 **Total:** 33

Current Operations: Continue rig moving

Planned Operations:

Toolpusher: Mick Preston

Wellsite Supervisors: Nathan Peri **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	18:00	12.00		RIGU	Rig move

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110			2,320	92,610	3.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904			2,320	92,610	

BHA Information

BHA - None

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 1

Accident Description: None reported

Meetings/Drills	Time	Description
Safety:	30	Toolbox meetings

☐ **BOP Test** ☐ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 3 **Report for 06:00 AM 03-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	0.0	**Drilling Days:**	0	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:		**Days On Location:**	3	**Last Casing:**	13.375 at 30.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	9.625 at 650.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**		**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 22 **Service:** 8 **Other:** 4 **Total:** 35

Current Operations: Rig move

Planned Operations:

Toolpusher: Mick Preston

Wellsite Supervisors: Nathan Peri **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	18:00	12.00	0	RIGU	Rig move

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110			5,320	97,930	3.6%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904			5,320	97,930	

BHA Information

BHA - None

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 2

Accident Description: None reported

Meetings/Drills	Time	Description
Safety:	30	Toolbox meetings

☐ **BOP Test** ☐ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 4 **Report for 06:00 AM 04-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	0.0	**Drilling Days:**	0	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:		**Days On Location:**	4	**Last Casing:**	13.375 at 30.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	9.625 at 650.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**		**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 22 **Service:** 6 **Other:** 3 **Total:** 32

Current Operations: Rigging up.

Planned Operations: Rigging up. Mix spud mud.

Toolpusher: Mick Preston

Wellsite Supervisors: Nathan Peri **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:00	24.00	0	RIGU	Continue rigging up. Break tour. Filled mud tanks with processed water from production facilities (Baroid sampled water OK for spud mud).

Comments

90% rigged up.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110			13,320	111,250	4.1%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904			13,320	111,250	

BHA Information

BHA - None

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 3

Accident Description: No accidents reported.

Meetings/Drills	Time	Description
Safety:	60	Toolbox meetings

☐ **BOP Test** ☐ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 5 **Report for 06:00 AM 05-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	0.0	**Drilling Days:**	0	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	0.0	**Days On Location:**	5	**Last Casing:**	13.375 at 30.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	9.625 at 650.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**		**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 22 **Service:** 8 **Other:** 5 **Total:** 36

Current Operations: Continue rigging up.

Planned Operations: Spud well.

Toolpusher: Mick Preston / Ian Hough

Wellsite Supervisors: Nathan Peri **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:00	24.00	0	RIGU	Continue rigging up.

Comments

Last minute change to BHA, pick up MWD and Mud motor.
Nightpusher on tour.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	1,400	1,400	25,617	136,867	5.0%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	1,400	1,400	25,617	136,867	

BHA Information

BHA - None

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Location Condition: Very tight lease, takes longer to manoeuver equipment into place.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	110	110	110	**Desander:**	
Shaker No 2:	110	110	110	**Desilter:**	
Shaker No 3:	110	110	110	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 4

Accident Description: No accidents reported

Meetings/Drills	Time	Description
Safety:	60	2 x Pre tour meeting

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Rain **Visibility:**

Air Temperature: degC **Bar. Pressure:**

Wind Speed/Dir: / **Wind Gusts:**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 6 **Report for 06:00 AM 06-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	155.0	**Drilling Days:**	1	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	155.0	**Days On Location:**	6	**Last Casing:**	13.375 at 30.0	**Field:**	WAIHAPA
Hole Made:	155.0	**Spud Date:**	05-Oct-05	**Next Casing:**	9.625 at 650.0	**Working Interest:**	100.00%
Drilling Hrs:	15.0	**Average ROP:**	10.33	**Last BOP Test:**		**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 22 **Service:** 8 **Other:** 5 **Total:** 36

Current Operations: spud well at 1400 hour's on 10/5/05 drilling to 155 m and running wire line survey 1.0 degree

Planned Operations: drill to 155 m , circ out ,pooh for directional assembly, p/u same tih , drill ahead

Toolpusher: Mick Preston / Ian Hough

Wellsite Supervisors: wallace suire steve john's **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description	Non-Prod
6:00	9:30	3.50	0	RIGU	install rat hole ,r/u d-tank , mix spud mud	
9:30	12:00	2.50	22	BHA	p/u 8" bha to 22meter's	
12:00	12:30	0.50	22	RIGU	welding in 2'' nipple and valve at grd level on riser	X
12:30	13:00	0.50	33	BHA	finished p/u 8" bha tag at 33 meter's	
13:00	14:00	1.00	33	REPR	working on rotary tong's	X
14:00	17:00	3.00	43	DRIL	drill from 33 m to 43m	
17:00	17:30	0.50	43	SURV	run wire line survey at 33 m 1 degree	
17:30	23:30	6.00	100	DRIL	drill from 43m to 100 m	
23:30	0:00	0.50	100	SURV	run wire line survey at 90m 1 degree	
0:00	6:00	6.00	155	DRIL	drill from 100 m to 155 m at 0600 am. prepare to run wire line survey at 145m 1.0 degree	

Comments

note =spud well at 1400 hour's on 10/5/05

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	12,836	14,236	62,739	199,606	7.3%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	12,836	14,236	62,739	199,606	

Mud Information

							%					Gels			Temp	
Density	Vis	Filt.	Cake	PV	YP	pH	Solids	Water	Oil	Sand	Chloride	10s	10m	30m	In	Out
06-Oct 02:00 at Depth 90.0																
9.00	44	22	3	11	8	9.5	2.9	96.8		0.15	720	16	20	24		

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	16	11,200	Bentonite - 25KG sxs	137	1,073
BARAZAN D PLUS - 25KG sxs	2	473	Caustic soda -	3	90
Drill plug - 25KG sxs	4	0			

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
32.0	155.0	8.00	8.00	0	5	90	100	2	5	513	513	500

Annular Velocity: **Drill Collars:** 44.50 **Drill Pipe:** 29.50

Comments: rt. drill

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 44 **Pick Up:** 46 **Slack Off:** 43 **Drag Avg/Max:** 1 / 2

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	68 spm	220 psi	68 spm	220 psi	spm	psi	

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 6 **Report for 06:00 AM 06-Oct-05**

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
1	1	SEC	xlc-1	12.250	33.0	123.0	15	8.20	10.00	5	100	5	9.00	513	500	55	257	77	130

Jets: 20 20 20 Out: 659.0 Grade: Cutter: 1 / 1 Dull: NO / BU Wear: S Brgs: 2 Gge: 1 Pull: TD

BHA - No. 1 - BIT, NBS, DCM, STAB, DC, STAB, DC, XO, 6 DC = 89.72

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	110	110	110
Shaker No 2:	110	110	110
Shaker No 3:	110	110	110
Shaker No 4:			

Equipment Usage:	Hrs.
Desander:	16
Desilter:	16
Degasser:	
Centrifuge No 1:	Solids Removal
Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			1343			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 5

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: clear **Visibility:** 5

Air Temperature: 56.0 degC **Bar. Pressure:** 0

Wind Speed/Dir: 0 / 0 **Wind Gusts:** 0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 7 **Report for 06:00 AM 07-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	302.0	**Drilling Days:**	2	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	302.0	**Days On Location:**	7	**Last Casing:**	13.375 at 30.0	**Field:**	WAIHAPA
Hole Made:	147.0	**Spud Date:**	05-Oct-05	**Next Casing:**	9.625 at 650.0	**Working Interest:**	100.00%
Drilling Hrs:	15.0	**Average ROP:**	9.80	**Last BOP Test:**		**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 22 **Service:** 5 **Other:** 8 **Total:** 36

Current Operations: drill from 155 m to 302m at 0600 am.
note= 1-hour slide and 7 1/2 hour's rotate

Planned Operations: drill to csg point of 650 meter's

Toolpusher: Mick Preston / Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description	Non-Prod
6:00	12:30	6.50	200	DRIL	drill from 155m to 200 m	
12:30	13:00	0.50	195	SURV	run wire line survey at 195m 1.0 degree	
13:00	13:30	0.50	200	CIRC	circ btm's up at 200 m while build slug	
13:30	15:30	2.00	200	TRPO	slug d.p. and pooh for directional assembly	
15:30	18:00	2.50	200	BHA	p/u directional assembly ,and orient same	
18:00	19:00	1.00	200	REPS	mwd had problem.s spacing out mwd tool with proper compression down time on halco	X
19:00	20:30	1.50	200	TRPI	continue tih with bha from derrick	
20:30	21:30	1.00	200	PUDP	p/u 10 joint's of hwdp. from pipe rack and wash to btm. at 200 m took survey at 171m = 1.59 degree's 306 azmt.	
21:30	6:00	8.50	302	DRIL	drill from 200 m to 302m at 0600 am.	

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	2,699	16,935	61,238	260,844	9.6%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	2,699	16,935	61,238	260,844	

Mud Information

								%					Gels			Temp	
Density	Vis	Filt.	Cake	PV	YP	pH	Solids	Water	Oil	Sand	Chloride	10s	10m	30m	In	Out
07-Oct 02:00 at Depth 248.0																
9.10	43	22	3	8	16	9.5	3.9	95.8		0.25	700	12	22	28	20.0	20.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Barite - 1500 MT	1	316	BARAZAN D PLUS - 25KG sxs	1	237
Bentonite - 25KG sxs	20	157	Caustic soda -	1	30
Drill plug - 25KG sxs	2	0			

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
155.0	302.0	17.00	25.00	10	20	30	90	5000	5000	840	860	1200

Annular Velocity: **Drill Collars:** 67.60 **Drill Pipe:** 50.20

Comments: rt. drill

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 64 **Pick Up:** 64 **Slack Off:** 64 **Drag Avg/Max:** 0 / 0

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	100 spm	1100 psi	100 spm	1200 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	23.0	**Casing:** 31.5	3.0
Total:	23.0		
Jars:	8.5		

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 7 **Report for 06:00 AM 07-Oct-05**

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
** TieIn	0.0	0.00	N 0 E	0.0		0.0			
TOTCO	33.0	1.00	N 0 E	33.0	0	0.3	N 0.29		0.909
TOTCO	100.0	1.00							
TOTCO	145.0	1.00							
TOTCO	195.0	1.00							
** TieIn	210.0	1.56	N 54 W	210.0	4	2.0	N 2.04	E 2.78	
MWD	238.6	1.86	N 48.81 W	238.5	3	2.6	N 2.57	E 2.12	0.354
MWD	266.8	1.24	N 60.5 W	266.7	3	3.0	N 3.03	E 1.51	0.736

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
1	1	SEC	xlc-1	12.250	33.0	270.0	23.5	11.49	25.00	15	120	5000	9.10	840	1200	89	698	342	353

Jets: 20 20 20 Out: 659.0 Grade: Cutter: 1 / 1 Dull: NO / BU Wear: S Brgs: 2 Gge: 1 Pull: TD

BHA - No. 2 - BIT, MMTR, STAB, FS, DCM, MWD, 2 DC, XO, 6 DC, 12 HWDP, JAR = 218.33

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
155.0	302.0													

Lithology:

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	110	110	110	Desander:	13
Shaker No 2:	110	110	110	Desilter:	13
Shaker No 3:	110	110	110	Degasser:	
Shaker No 4:				Centrifuge No 1:	Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL		15851	17194			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 6

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: clear **Visibility:** 2

Air Temperature: 48.0 degC **Bar. Pressure:** 0

Wind Speed/Dir: 5 / SE **Wind Gusts:**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 8 **Report for 06:00 AM 08-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	643.0	**Drilling Days:**	3	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	643.0	**Days On Location:**	8	**Last Casing:**	13.375 at 30.0	**Field:**	WAIHAPA
Hole Made:	341.0	**Spud Date:**	05-Oct-05	**Next Casing:**	9.625 at 650.0	**Working Interest:**	100.00%
Drilling Hrs:	24.0	**Average ROP:**	14.21	**Last BOP Test:**		**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 22 **Service:** 5 **Other:** 8 **Total:** 36

Current Operations: drill from 302m to 643m at 0600 am.

Planned Operations: drill to csg point of 659 m , circ , short trip, condition hole for 9 5/8" csg

Toolpusher: Mick Preston / Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:00	24.00		DRIL	drill from 302 m to 643m at 0600 am.

Comments

note= td csg point at 659 meter's
csg length = 645.99 meter's
elevation = 6.23 meter;s
csg shoe = 652.22 meter's
rat hole =6.78 meter's = 22 feet with no fill

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	2,544	19,479	48,559	309,403	11.3%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	2,544	19,479	48,559	309,403	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
08-Oct 02:00 at Depth 589.0																
9.10	42	10	3	6	18	9.5	4	95.7		0.2	750	12	23	28	25.0	25.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
pac-r -	8	741	Bentonite - 25KG sxs	40	313
Caustic soda -	1	30	Drill plug - 25KG sxs	3	0

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
302.0	643.0	14.00	20.00	15	20	50	90	5000	5000	756	760	1200

Annular Velocity: Drill Collars: 60.80 **Drill Pipe:** 45.20

Comments: rotate drill

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 84 **Pick Up:** 84 **Slack Off:** 84 **Drag Avg/Max:** 0 / 0

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1: 90 spm 1100 psi 90 spm 1200 psi spm psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	47.0	**Casing:** 55.0	0.0
Total:	47.0		
Jars:	32.5		

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Pump Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
1	1	SEC	xlc-1	12.250	33.0	611.0	47.5	12.86	20.00	20	140	5000	9.10	760	1200	81	571	253	289
Jets:	20	20	20		Out: 659.0			Grade:	Cutter:	1 / 1	Dull: NO / BU		Wear: S		Brgs: 2	Gge: 1		Pull: TD	

BHA - No. 2 - BIT, MMTR, STAB, FS, DCM, MWD, 2 DC, XO, 6 DC, 12 HWDP, JAR = 218.33

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 8 **Report for 06:00 AM 08-Oct-05**

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
302.0	643.0													

Lithology:

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	110	110	110
Shaker No 2:	110	110	110
Shaker No 3:	175	110	110
Shaker No 4:			

Equipment Usage:	Hrs.
Desander:	24
Desilter:	24
Degasser:	
Centrifuge No 1:	Solids Removal
Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			17194			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 7

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition:	rain/cold	**Visibility:**	5
Air Temperature:	43.0 degC	**Bar. Pressure:**	0
Wind Speed/Dir:	15 / SE	**Wind Gusts:**	20

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 9 **Report for 06:00 AM 09-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	659.0	**Drilling Days:**	4	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	659.0	**Days On Location:**	9	**Last Casing:**	13.375 at 30.0	**Field:**	WAIHAPA
Hole Made:	16.0	**Spud Date:**	05-Oct-05	**Next Casing:**	9.625 at 650.0	**Working Interest:**	100.00%
Drilling Hrs:	1.5	**Average ROP:**	10.67	**Last BOP Test:**		**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 22 **Service:** 5 **Other:** 8 **Total:** 36

Current Operations: wait on cmt. prepare bop's for n/u and n/d flow line

Planned Operations: condition hole and run 9 5/8" csg , cmt and n/u , test bop's

Toolpusher: Mick Preston / Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:30	1.50	659	DRIL	drill from 643m to 659m csg point
7:30	8:30	1.00	659	CIRC	circ sweep surface to surface , slug dp
8:30	12:30	4.00	659	WIPE	short trip up to csg shoe had excess drag for 12 stand's
12:30	14:30	2.00	659	WIPE	tih to 659m
14:30	15:30	1.00	659	CIRC	circ hole clean slug d.p.
15:30	19:00	3.50	659	TRPO	pooh l/d directional tool's
19:00	20:00	1.00	659	SERV	service rig ,while r/u csg tool's , held jsa before running csg with all hand's
20:00	20:30	0.50	659	CASE	run two joint;s of 9 5/8" csg and level derrick
20:30	1:30	5.00	659	CASE	run 55 joint's of 9 5/8" 53.5 p-110 csg to 652meter's
1:30	2:00	0.50	659	CIRC	r/u plug container and circ. csg cap/
2:00	3:30	1.50	659	CMTP	test line's to 3000 psi , pump 60 bbl's wtr spacer. followed with 420 sk's class -a cmt at 11.8 ppg yield= 2.56 wtr= 15.29 slurry volume =191 bbl's plus 158 sk's of class -g cmt at 15.6 ppg yield =1.17 wtr=5.05 slurry volume 33 bbl's
3:30	4:00	0.50	659	CIRC	displace cmt plug at 6.5 bpm had full return's seen only 12 bbl's water back no ctm. job bump plug with 1500 psi cmt in place at 0400 am.
4:00	4:30	0.50	659	CMTS	p/u 1" stinger to 60 feet and cmt with 20 sk's class -g at 15.6 ppg slurry volume of 4 bbl;s 67 feet cap.
4:30	6:00	1.50	659	WOC	woc while prepare bop's to be nippled up

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	2,042	21,521	360,582	669,985	24.5%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	2,042	21,521	360,582	669,985	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
09-Oct 06:00 at Depth 659.0																
9.20	42	8	2	8	17		4.3	95.4	0	0.2	650	12	22	27		

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Barite - 1500 MT	1	316	Bentonite - 25KG sxs	34	266

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
643.0	659.0	15.00	20.00	15	20	50	90	5000	5000	756	756	1200

Annular Velocity: **Drill Collars:** 60.80 **Drill Pipe:** 45.20

Comments: rt. drill

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 9 **Report for 06:00 AM 09-Oct-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 84 **Pick Up:** 84 **Slack Off:** 84 **Drag Avg/Max:** 0 / 0

☐ **Wear Bushing Installed**

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	48.5	**Casing:**	56.5	6.0
Total:	48.5			
Jars:	34.0			

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	294.2	0.87	N 69 W	294.1	3	3.2	N 3.25	E 1.05	0.439
MWD	321.0	0.74	S 68 W	320.9	3	3.3	N 3.25	E 0.70	0.674
MWD	348.0	0.81	S 33.08 W	347.9	3	3.0	N 3.03	E 0.44	0.522
MWD	374.6	0.81	S 24.33 W	374.6	3	2.7	N 2.70	E 0.26	0.139
MWD	401.0	0.80	S 14.3200	400.9	2	2.4	N 2.35	E 0.13	0.160
MWD	428.4	0.76	S 11.0700	428.3	2	2.0	N 1.99	E 0.05	0.065
MWD	455.2	1.46	S 13.63 E	455.1	1	1.5	N 1.48	E 0.10	0.930
MWD	482.0	1.61	S 22.42 E	481.9	1	0.8	N 0.80	E 0.32	0.312
MWD	508.8	1.35	S 20.92 E	508.7	1	0.2	N 0.16	E 0.58	0.294
MWD	562.7	1.70	S 57.35 E	562.6	2	-0.9	S 0.89	E 1.25	1.094
MWD	640.1	2.03	S 65.8 E	639.9	4	-1.9	S 1.94	E 3.65	0.141

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
1	1	SEC	xlc-1	12.250	33.0	627.0	49	12.80	20.00	15	150	5000	9.10	756	1200	80	565	249	286

Jets: 20 20 20 Out: 659.0 Grade: Cutter: 1 / 1 Dull: NO / BU Wear: S Brgs: 2 Gge: 1 Pull: TD

BHA - No. 2 - BIT, MMTR, STAB, FS, DCM, MWD, 2 DC, XO, 6 DC, 12 HWDP, JAR = 218.33

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	110	110	110	**Desander:**	3.5
Shaker No 2:	110	110	110	**Desilter:**	3.5
Shaker No 3:	110	110	110	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			17194			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 8

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: clear **Visibility:** 2

Air Temperature: 44.0 degC **Bar. Pressure:** 0

Wind Speed/Dir: 5 / SE **Wind Gusts:** 10

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 10 **Report for 06:00 AM 10-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	659.0	**Drilling Days:**	5	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	659.0	**Days On Location:**	10	**Last Casing:**	9.625 at 652.2	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	7.000 at 2400.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	10-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 22 **Service:** 8 **Other:** 8 **Total:** 39

Current Operations: nippling up bop's

Planned Operations: n/u test bop's , mix new mud , p/u directional assembly & orient same, tih

Toolpusher: Mick Preston / Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	9:30	3.50	659	WOC	attempt to back out landing collar backed out 2" and started backing out down hole
9:30	12:00	2.50	659	BOPNU	made up csg to 10000 and test same to 1500 psi failed 250 psi and leaking at landing collar
12:00	16:30	4.50	659	WELD	cut landing jt. below collar l/d same and cut and remove 13 3/8" riser and removed same , dress off csg top install sow head
16:30	21:30	5.00	659	WELD	cooling off sow head
21:30	6:00	8.50	659	BOPNU	n/u bop's

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	7,234	28,755	51,944	721,929	26.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	7,234	28,755	51,944	721,929	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
10-Oct 02:00 at Depth 659.0																
8.70	38	10.2	1	11	14	7.2	0.6	95.6			45200	3	5			

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
KCl -	6	2,836	BARAZAN D PLUS - 25KG sxs	6	1,420
pac-r -	6	556	Aldacide G -	4	499
EZ MUD DP -	6	463			

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
1	1	SEC	xlc-1	12.250	33.0	627.0	49												
Jets:	20	20	20		Out: 659.0			Grade:	Cutter:	1 / 1	Dull: NO / BU		Wear: S		Brgs: 2		Gge: 1		Pull: TD

BHA - No. 2 - BIT, MMTR, STAB, FS, DCM, MWD, 2 DC, XO, 6 DC, 12 HWDP, JAR = 218.33

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	110	110	110	**Desander:**	
Shaker No 2:	110	110	110	**Desilter:**	
Shaker No 3:	110	110	110	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			17194			

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 10 **Report for 06:00 AM 10-Oct-05**

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 9

Accident Description: none reported

Meetings/Drills **Time** **Description**

☑ **BOP Test** ☐ **Crownamatic Check**

Weather

Sky Condition: rain **Visibility:** 44

Air Temperature: 0.0 degC **Bar. Pressure:** 0

Wind Speed/Dir: 0 / 0 **Wind Gusts:** 0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 11 **Report for 06:00 AM 11-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	662.0	**Drilling Days:**	6	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	662.0	**Days On Location:**	11	**Last Casing:**	9.625 at 652.2	**Field:**	WAIHAPA
Hole Made:	3.0	**Spud Date:**	05-Oct-05	**Next Casing:**	7.000 at 2400.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	11-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 14 **Total:** 46

Current Operations: r/u halco line's prepare to test forn to 310 psi with 8/8 ppg mud equiv. to 11.5 ppg

Planned Operations: drill shoe track , 10 feet of new form. , test shoe to 11.5 equiv. drill ahead to csg point of 2670 m

Toolpusher: lindsey baker

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:00	1.00	659	BOPNU	finished n/u bop's ,function test bop's
7:00	12:00	5.00	659	BOPT	attempt to test csg to 1500 psi bop camlock below cross flange leaking tighten same twice no change leaking started testing choke manifold while changing out ring gasket and bop clamp
12:00	19:00	7.00	659	BOPT	test csg to 1500 psi ,test all ram's , line's , valve's to 250/5000 test hydrill to 250 / 2500 psi test alll surface equip to 250 /5000 psi r/d test equip.note =camlock clamp's causing leak's
19:00	21:30	2.50	659	BHA	n/u bell nipple , lay down 3- 8" drill collar's & 6-6 1/2 " d.c.'s from derrick
21:30	2:00	4.50	659	BHA	p/u 8 1/2" directional assembly , orient same , and tih tag cmt at 639
2:00	3:30	1.50	643	CMTD	drill cmt float collar , found bop's turned,choke line against sub base
3:30	4:30	1.00	643	RIGU	realine flow line ; install double line;s on bop's , test bop's and csg to 1500 psi held ok
4:30	5:30	1.00	662	CMTD	drill shoe track to 652m , drill cmt wash out rat hole and 3 meter's of new hole to 662 meter's
5:30	6:00	0.50	662	CIRC	circ. btm's up, and r/u test line's test form with 8.8 ppg to 310 psi equiv. to 11.5 ppg

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	2,272	31,027	115,755	837,684	30.7%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	2,272	31,027	115,755	837,684	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
11-Oct 02:00 at Depth 659.0																
8.70	39	10.2	1	10	16	7.2	0.7	95.8			42000	4	5			

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	4	120
BARAZAN D PLUS - 25KG sxs	2	473	EZ MUD DP -	2	154
Aldacide G -	1	125	Drill plug - 25KG sxs	2	0

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
659.0	662.0	5.00	5.00	2	5	40	90	4	5	800	840	1200

Annular Velocity: Drill Collars: 82.70 **Drill Pipe:** 180.10

Comments: rt. drilg

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 67 **Pick Up:** 70 **Slack Off:** 67 **Drag Avg/Max:** 3 / 3

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	800 psi	68 spm	800 psi	spm	psi	

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	50.0	**Casing:** 50.0	9.0
Total:	50.0		
Jars:	36.0		

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 11 **Report for 06:00 AM 11-Oct-05**

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
2	1	HYC	DSX104H	8.500	659.0	3.0	0.5	6.00	5.00	2	130	5	8.80	840	1200	109	1012	496	418

Jets: 14 14 14 Out: 2400.0 Grade: Cutter: 1 / 3 Dull: CT / CT Wear: T Brgs: X Gge: 1 Pull: CSG

BHA - No. 3 - BIT, MMTR, STAB, FS, MWD, XO, 12 HWDP, JAR = 143.85

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
659.0	662.0			3	0	0					9		3.0	3.0

Lithology: cmt / gumbo

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	110	110	110	**Desander:**	
Shaker No 2:	110	110	110	**Desilter:**	
Shaker No 3:	110	110	110	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL		12205	29399			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 10

Accident Description: none reported

Meetings/Drills **Time** **Description**

☑ **BOP Test** ☐ **Crownamatic Check**

Weather

Sky Condition: rain /cold **Visibility:** 5

Air Temperature: 56.0 degC **Bar. Pressure:** 0

Wind Speed/Dir: 5 / SE **Wind Gusts:** 10

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 12 **Report for 06:00 AM 12-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	986.0	**Drilling Days:**	7	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	973.0	**Days On Location:**	12	**Last Casing:**	9.625 at 652.2	**Field:**	WAIHAPA
Hole Made:	324.0	**Spud Date:**	05-Oct-05	**Next Casing:**	7.000 at 2400.0	**Working Interest:**	100.00%
Drilling Hrs:	24.0	**Average ROP:**	13.50	**Last BOP Test:**	11-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 20 **Service:** 10 **Other:** 13 **Total:** 44

Current Operations: drill from 659 mto 986 m at 0600 am
slide = 5 hour's
rotate = 19 hour's

Planned Operations: drill to csg point 2670 m

Toolpusher: Lindsey Baker, Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:00	24.00	986	DRIL	drill from 659 m to 986 meter's at 0600 am.

Comments

note = transmission for one main engine is due here today when all part's arrive on location we will short trip and change out same

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	6,095	37,122	50,421	888,105	32.5%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	6,095	37,122	50,421	888,105	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
12-Oct 02:00 at Depth 946.0																
9.05	48	6.2	1	8	16	11.9	1.3	95.4		0.5	40000	5	6	8	40.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	4	120
KCl -	6	2,836	BARAZAN D PLUS - 25KG sxs	2	473
Pac-L -	5	463	EZ MUD DP -	3	231
pac-r -	2	185	sodium bicarbonate -	10	163
Aldacide G -	1	125	Con Det -	2	94

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
659.0	986.0	14.00	65.00	5	10	40	200	5	6	730	730	1050

Annular Velocity: **Drill Collars:** 75.50 **Drill Pipe:** 164.30

Comments: rt. / slide

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 79 **Pick Up:** 85 **Slack Off:** 76 **Drag Avg/Max:** 5 / 10

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	68 spm	240 psi	75 spm	290 psi	spm	psi	
Pump 2:	68 spm	240 psi	75 spm	290 psi	spm	psi	

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	74.0	**Casing:** 74.0	
Total:	74.0		
Jars:	60.0		

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 12 **Report for 06:00 AM 12-Oct-05**

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	616.0	2.02	S 69 E	615.9	3	-1.6	S 1.62	E 2.87	0.022
MWD	667.0	1.98	S 68.85 E	666.8	5	-2.3	S 2.31	E 4.52	0.131
MWD	703.0	6.80	S 26.8500	702.7	8	-4.4	S 4.43	E 6.06	4.575
MWD	720.0	8.98	S 28.88 E	719.5	10	-6.5	S 6.49	E 7.16	3.878
MWD	747.0	11.40	S 37.44 E	746.1	14	-10.5	S 10.46	E 9.80	3.165
MWD	765.0	12.04	S 39.06 E	763.7	18	-13.3	S 13.33	E 12.06	1.199

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
2	1	HYC	DSX104H	8.500	659.0	330.0	24.5	13.47	65.00	15	240	5	9.00	730	1000	95	782	333	323

Jets: 14 14 14 Out: 2400.0 Grade: Cutter: 1 / 3 Dull: CT / CT Wear: T Brgs: X Gge: 1 Pull: CSG

BHA - No. 3 - BIT, MMTR, STAB, FS, MWD, XO, 12 HWDP, JAR = 143.85

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
662.0	936.0	662.0	927.0	2	2	936	0	0	0	0.00	9	0	17.0	30.0

Lithology:

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.	
Shaker No 1:	175	175	175	Desander:	16	
Shaker No 2:	175	110	110	Desilter:	16	
Shaker No 3:	175	175	175	Degasser:		
Shaker No 4:				Centrifuge No 1:	116	Solids Removal
				Centrifuge No 2:		Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			29399			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 11

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: clear **Visibility:** 5

Air Temperature: 56.0 degC **Bar. Pressure:** 0

Wind Speed/Dir: 0 / 0 **Wind Gusts:** 0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 13 **Report for 06:00 AM 13-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	1270.0	**Drilling Days:**	8	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	1242.0	**Days On Location:**	13	**Last Casing:**	9.625 at 652.2	**Field:**	WAIHAPA
Hole Made:	284.0	**Spud Date:**	05-Oct-05	**Next Casing:**	7.000 at 2400.0	**Working Interest:**	100.00%
Drilling Hrs:	23.5	**Average ROP:**	12.09	**Last BOP Test:**	11-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 20 **Service:** 8 **Other:** 11 **Total:** 40

Current Operations: drill from 986 meter's to 1270 meter's at 0600 am.

Planned Operations: drill untill main engine transmission arrive's at loc. due at 0800 am. we will short trip while changing out same

Toolpusher: Lindsey Baker, Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	14:00	8.00	1087	DRIL	drill from 986 meter's to 1087 m
14:00	14:30	0.50	1087	SERV	service rig
14:30	6:00	15.50	1270	DRIL	drill from 1087 m to 1270 meter's at 0600 am.

Comments

slide hour's = 5 1/2
rotate hour's = 18 1/2
off btm. pressure = 1050 psi
on btm. pressure = 1200 psi
pumping 10 bbl sweep's each 2 connection's drilled

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	4,785	41,907	48,870	936,975	34.3%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	4,785	41,907	48,870	936,975	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
13-Oct 02:00 at Depth 1223.0																
9.15	40	6	1	9	17		2.1	93.8		0.25	50000	4	5	8	41.0	41.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	4	120
KCl -	3	1,418	BARAZAN D PLUS - 25KG sxs	4	946
pac-r -	5	463	EZ MUD DP -	4	309
Aldacide G -	1	125			

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
986.0	1270.0	12.00	17.00	3	10	40	140	5	6	485	485	1200

Annular Velocity: **Drill Collars:** 120.80 **Drill Pipe:** 109.20

Comments: rt./slide

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 94 **Pick Up:** 100 **Slack Off:** 88 **Drag Avg/Max:** 6 / 6

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	68 spm	300 psi	75 spm	340 psi	spm	psi
Pump 2:	68 spm	300 psi	75 spm	340 psi	spm	psi

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	98.0	**Casing:**	98.0	9.0
Total:	98.0			
Jars:	84.0			

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 13 **Report for 06:00 AM 13-Oct-05**

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	783.0	13.35	S 40.7 E	781.3	22	-16.4	S 16.36	E 14.60	2.264
MWD	801.0	15.18	S 44.1799	798.8	26	-19.6	S 19.63	E 17.60	3.367
MWD	962.0	19.33	S 48.2899	951.5	77	-52.8	S 52.78	E 55.86	0.772
MWD	989.0	18.58	S 45.61 E	977.1	86	-58.8	S 58.76	E 62.27	1.277
MWD	1016.0	18.94	S 45.0700	1002.6	94	-64.9	S 64.86	E 68.45	0.444
MWD	1043.0	19.46	S 45.38 E	1028.1	103	-71.1	S 71.12	E 74.75	0.589
MWD	1071.0	19.79	S 46.19 E	1054.5	113	-77.7	S 77.67	E 81.49	0.458
MWD	1098.0	19.81	S 47.5700	1079.9	122	-83.9	S 83.92	E 88.17	0.520
MWD	1124.0	19.47	S 46.1000	1104.4	130	-89.9	S 89.90	E 94.54	0.692
MWD	1151.0	18.96	S 42.88 E	1129.9	139	-96.2	S 96.24	E 100.77	1.307
MWD	1178.0	18.89	S 42.1799	1155.4	148	-102.7	S 102.69	E 106.69	0.264

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
2	1	HYC	DSX104H	8.500	659.0	614.0	48	12.79	17.00	5	180	5	9.20	485	1200	63	353	100	146

Jets: 14 14 14 Out: 2400.0 Grade: Cutter: 1 / 3 Dull: CT / CT Wear: T Brgs: X Gge: 1 Pull: CSG

BHA - No. 3 - BIT, MMTR, STAB, FS, MWD, XO, 12 HWDP, JAR = 143.85

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
986.0	1270.0	973.0	1243.0	2	3	1205	0	0	0	0.00	9	0	12.0	18.0

Lithology:

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	175	175	175
Shaker No 2:	175	110	110
Shaker No 3:	175	175	175
Shaker No 4:			

Equipment Usage:	Hrs.	
Desander:		
Desilter:	5	
Degasser:		
Centrifuge No 1:	24	Solids Removal
Centrifuge No 2:		Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			29399			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 12

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition:	clear	**Visibility:**	5
Air Temperature:	59.0 degC	**Bar. Pressure:**	0
Wind Speed/Dir:	0 / 0	**Wind Gusts:**	0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 14 **Report for 06:00 AM 14-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	1485.0	**Drilling Days:**	9	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	1446.0	**Days On Location:**	14	**Last Casing:**	9.625 at 652.2	**Field:**	WAIHAPA
Hole Made:	215.0	**Spud Date:**	05-Oct-05	**Next Casing:**	7.000 at 2400.0	**Working Interest:**	100.00%
Drilling Hrs:	19.5	**Average ROP:**	11.03	**Last BOP Test:**	11-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 20 **Service:** 10 **Other:** 13 **Total:** 44

Current Operations: drill from 1270 meter's to 1485 m at 0600 am.

Planned Operations: drill to csg point of 2670 meter's short trip as needed

Toolpusher: Lindsey Baker, Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:00	1.00	1279	DRIL	drill from 1270 m to 1279 m
7:00	8:00	1.00	1279	CIRC	circ hi vis sweep surface to surface ,flow check and ,slug d.p.
8:00	9:30	1.50	1279	TRPO	pooh to csg shoe from 1279 m up to 650 m no excess drag
9:30	10:00	0.50	1279	SERV	service rig
10:00	11:30	1.50	1279	TRPI	tih to 1279 meter's no excess drag ,& no fill
11:30	6:00	18.50	1485	DRIL	drill from 1279 m to 1340 m mud losses 30 bbl's /hr. pumped 25 bbl sweep losses down to 2 bbl's / hr.continue drilling from 1340 m to 1485 m at 0600 am.

Comments

slide drill = 3 1/2 hour's
rotate drill= 20 1/2 hour's
note = had show's from 1410 to 1470 meter's
total mud lost to formation = 64 bbl's

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	6,857	48,764	50,657	987,632	36.2%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	6,857	48,764	50,657	987,632	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
14-Oct 02:00 at Depth 1430.0																
9.20	44	5.8	1	12	23	9.5	2.5	93.5		0.25	49000	6	12	17	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	4	120
KCl -	3	1,418	BARAZAN D PLUS - 25KG sxs	5	1,183
pac-r -	8	741	BARACARB 25 -	40	501
EZ MUD DP -	5	386	Barofibre -	10	319
Pac-L -	3	278	Aldacide G -	2	250
Con Det -	3	142	Caustic soda -	4	120

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
1270.0	1485.0	12.00	18.00	2	5	60	135	5	6	470	470	1200

Annular Velocity: **Drill Collars:** 67.50 **Drill Pipe:** 105.80

Comments: rt. /slide

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 14 **Report for 06:00 AM 14-Oct-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 98 **Pick Up:** 110 **Slack Off:** 93 **Drag Avg/Max:** 10 / 15

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	68 spm	340 psi	75 spm	400 psi	spm	psi
Pump 2:	68 spm	340 psi	75 spm	400 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	117.5	**Casing:** 117.5	12.0
Total:	117.5		
Jars:	103.5		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	1205.0	19.52	S 43.5 E	1180.9	157	-109.2	S 109.20	E 112.73	0.850
MWD	1232.0	20.14	S 43.53 E	1206.3	166	-115.8	S 115.84	E 119.03	0.689
MWD	1258.0	20.76	S 44.14 E	1230.7	175	-122.4	S 122.39	E 125.33	0.756
MWD	1285.0	20.58	S 44.44 E	1256.0	185	-129.2	S 129.22	E 131.98	0.232
MWD	1312.0	17.63	S 42.41 E	1281.5	194	-135.6	S 135.62	E 138.06	3.359

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
2	1	HYC	DSX104H	8.500	659.0	829.0	67.5	12.28	18.00	5	185	5	9.20	470	1200	61	331	91	137

Jets: 14 14 14 Out: 2400.0 Grade: Cutter: 1 / 3 Dull: CT / CT Wear: T Brgs: X Gge: 1 Pull: CSG

BHA - No. 3 - BIT, MMTR, STAB, FS, MWD, XO, 12 HWDP, JAR = 143.85

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
1270.0	1485.0	1242.0	1446.0	3	4	1485	0	0	0	0.00	9	0	12.0	18.0

Lithology: claystone , sandstone

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	175	175	175	**Desander:**	
Shaker No 2:	175	110	110	**Desilter:**	5
Shaker No 3:	175	175	175	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	24 Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			29399			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 13

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 14 **Report for 06:00 AM 14-Oct-05**

Weather

Sky Condition:	clear	**Visibility:**	5
Air Temperature:	46.0 degC	**Bar. Pressure:**	0
Wind Speed/Dir:	0 / 0	**Wind Gusts:**	0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 15 **Report for 06:00 AM 15-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	1700.0	**Drilling Days:**	10	**RKB Elevation:**	201.84	**County:**	Taranaki
Vertical Depth:	1645.0	**Days On Location:**	15	**Last Casing:**	9.625 at 652.2	**Field:**	WAIHAPA
Hole Made:	215.0	**Spud Date:**	05-Oct-05	**Next Casing:**	7.000 at 2400.0	**Working Interest:**	100.00%
Drilling Hrs:	23.5	**Average ROP:**	9.15	**Last BOP Test:**	11-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 20 **Service:** 10 **Other:** 15 **Total:** 46

Current Operations: drill from 1485 m to 1700 meter's at 0600 am.

Planned Operations: drill to csg point of 2670m short trip's as hole dictate's

Toolpusher: Lindsey Baker, Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	17:00	11.00	1594	DRIL	drill from 1485 m to 1594 m
17:00	17:30	0.50	1594	SERV	service rig
17:30	6:00	12.50	1700	DRIL	drill from 1594 m to 1700 meter's at 0600 am.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	8,473	57,237	63,428	1,051,060	38.5%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	8,473	57,237	63,428	1,051,060	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
15-Oct 02:00 at Depth 1668.0																
9.20	42	5.8	1	14	23	9.5	2.5	93.5		0.25	49000	9	15	18	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	4	120
KCl -	4	1,891	BARAZAN D PLUS - 25KG sxs	6	1,420
Barofibre -	40	1,275	BARACARB 25 -	40	501
Pac-L -	5	463	Aldacide G -	3	375
mica fine - 25kg	40	680	pac-r -	2	185
Caustic soda -	6	180	mica medium - 25kg	10	170
EZ MUD DP -	2	154	Drill plug - 25KG sxs	15	0

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
1485.0	1700.0	9.00	15.00	2	5	60	130	6	7	515	515	1600

Annular Velocity: **Drill Collars:** 128.20 **Drill Pipe:** 115.90

Comments: rt./slide

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 112 **Pick Up:** 124 **Slack Off:** 105 **Drag Avg/Max:** 10 / 15

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	340 psi	75 spm	420 psi	spm	psi
Pump 2:	68 spm	340 psi	75 spm	420 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	141.5	**Casing:** 141.5	0.0
Total:	141.5		
Jars:	127.5		

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 15 **Report for 06:00 AM 15-Oct-05**

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	1339.0	17.41	S 41.31 E	1307.2	202	-141.7	S 141.68	E 143.49	0.442
MWD	1366.0	17.60	S 41.3999	1333.0	210	-147.8	S 147.77	E 148.85	0.213
MWD	1393.0	17.53	S 41.4299	1358.7	218	-153.9	S 153.88	E 154.24	0.078
MWD	1421.0	18.94	S 43.4600	1385.3	227	-160.3	S 160.34	E 160.16	1.657
MWD	1447.0	19.29	S 44.1000	1409.9	235	-166.5	S 166.49	E 166.05	0.471
MWD	1474.0	19.86	S 44.78 E	1435.3	244	-172.9	S 172.95	E 172.38	0.682
MWD	1501.0	20.16	S 45.52 E	1460.7	253	-179.5	S 179.47	E 178.93	0.436
MWD	1528.0	20.68	S 45.88 E	1486.0	263	-186.0	S 186.04	E 185.68	0.594
MWD	1555.0	21.30	S 46.3 E	1511.2	273	-192.8	S 192.75	E 192.64	0.709

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Pump Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
2	1	HYC	DSX104H	8.500	659.0	1044.0	91.5	11.41	15.00	5	200	7000	9.20	515	1600	67	398	120	164

Jets: 14 14 14 Out: 2400.0 Grade: Cutter: 1 / 3 Dull: CT / CT Wear: T Brgs: X Gge: 1 Pull: CSG

BHA - No. 3 - BIT, MMTR, STAB, FS, MWD, XO, 12 HWDP, JAR = 143.85

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
1485.0	1700.0	1446.0	1644.0	4	4	1686	0	0	0	0.00	9	0	9.0	15.0

Lithology: claystone / sandstone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 201.84 m

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.	
Shaker No 1:	175	175	175	**Desander:**		
Shaker No 2:	175	110	110	**Desilter:**	5	
Shaker No 3:	175	175	175	**Degasser:**		
Shaker No 4:				**Centrifuge No 1:**	24	Solids Removal
				Centrifuge No 2:		Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL		15000	22350			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 14

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: clear **Visibility:** 5

Air Temperature: 49.0 degC **Bar. Pressure:** 0

Wind Speed/Dir: 0 / 0 **Wind Gusts:** 0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 16 **Report for 06:00 AM 16-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	1915.0	**Drilling Days:**	11	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	1846.0	**Days On Location:**	16	**Last Casing:**	9.625 at 652.2	**Field:**	WAIHAPA
Hole Made:	215.0	**Spud Date:**	05-Oct-05	**Next Casing:**	7.000 at 2400.0	**Working Interest:**	100.00%
Drilling Hrs:	19.5	**Average ROP:**	11.03	**Last BOP Test:**	11-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 14 **Total:** 46

Current Operations: drill from 1700 m to 1915 m at 0600 am.

Planned Operations: drill to csg point short trip as hole dictate's

Toolpusher: Lindsey Baker, Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	14:30	8.50	1787	DRIL	drill from 1700 m to 1787 m
14:30	15:00	0.50	1787	SERV	service rig
15:00	18:30	3.50	1824	DRIL	drill from 1787 m to 1824 m drag increased pipe torqued up, drop down and rotate free at 1824m pump sweep
18:30	19:00	0.50	1824	CIRC	circ hole clean ,flow check ,slug d.p.
19:00	22:30	3.50	1824	STRIP	short trip up to 1240 m tih max drag 15 k 1- meter fill on btm max trip gas 11 unit's no mud cut
22:30	6:00	7.50		DRIL	drill from 1824 m to 1915 m at 0600 am.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	7,802	65,039	52,120	1,103,180	40.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	7,802	65,039	52,120	1,103,180	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
16-Oct 02:00 at Depth 1854.0																
9.30	44	6	1	13	24		2.8	93		0.25	51000	8	16	19	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	4	120
KCl -	4	1,891	BARAZAN D PLUS - 25KG sxs	5	1,183
Barofibre -	30	956	BARACARB 25 -	40	501
EZ MUD DP -	5	386	pac-r -	4	370
Pac-L -	4	370	mica medium - 25kg	15	255
Aldacide G -	2	250	Caustic soda -	4	120

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
1700.0	1915.0	10.00	20.00	5	10	80	130	6000	9000	515	515	1890

Annular Velocity: Drill Collars: 128.20 **Drill Pipe:** 115.90

Comments: rt. drill

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 120 **Pick Up:** 135 **Slack Off:** 112 **Drag Avg/Max:** 10 / 20

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	68 spm	400 psi	75 spm	980 psi	spm	psi
Pump 2:	68 spm	400 psi	75 spm	480 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	161.5	**Casing:** 161.5	12.5
Total:	161.5		
Jars:	147.5		

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 16 **Report for 06:00 AM 16-Oct-05**

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	1582.0	20.84	S 45.12 E	1536.4	282	-199.5	S 199.53	E 199.59	0.695
MWD	1609.0	20.57	S 44.92 E	1561.6	292	-206.3	S 206.28	E 206.34	0.310
MWD	1636.0	19.73	S 44.86 E	1587.0	301	-212.9	S 212.86	E 212.91	0.934
MWD	1662.0	20.06	S 44.88 E	1611.4	310	-219.1	S 219.14	E 219.15	0.381

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
2	1	HYC	DSX104H	8.500	659.0	1259.0	112	11.29	20.00	8	132	8000	9.30	515	1890	67	402	121	166

Jets: 14 14 14 Out: 2400.0 Grade: Cutter: 1 / 3 Dull: CT / CT Wear: T Brgs: X Gge: 1 Pull: CSG

BHA - No. 3 - BIT, MMTR, STAB, FS, MWD, XO, 12 HWDP, JAR = 143.85

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
1700.0	1905.0	1645.0	1837.0	4	6	1902	19	11	0	0.00	9	0	12.0	20.0

Lithology: claystone, trace sandstone , siltstone , limestone
note = we are seeing connection gas last one at 1908 m = 19 unit's

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	175	175	175
Shaker No 2:	175	110	110
Shaker No 3:	175	175	175
Shaker No 4:			

Equipment Usage:	Hrs.	
Desander:		
Desilter:	3	
Degasser:		
Centrifuge No 1:	24	Solids Removal
Centrifuge No 2:		Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			22350			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 15

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: fog **Visibility:** 1

Air Temperature: 46.0 degC **Bar. Pressure:** 0

Wind Speed/Dir: 0 / 0 **Wind Gusts:** 0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 17 **Report for 06:00 AM 17-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2130.0	**Drilling Days:**	12	**RKB Elevation:**	5.5	**County:**	Taranaki
Vertical Depth:	2052.0	**Days On Location:**	17	**Last Casing:**	9.625 at 652.2	**Field:**	WAIHAPA
Hole Made:	215.0	**Spud Date:**	05-Oct-05	**Next Casing:**	7.000 at 2400.0	**Working Interest:**	100.00%
Drilling Hrs:	23.5	**Average ROP:**	9.15	**Last BOP Test:**	11-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 14 **Total:** 46

Current Operations: drill from 1915 meter's to 2130 m at 0600 am.

Planned Operations: drill to csg point of 2670 m , short trip as hole dictate's

Toolpusher: Lindsey Baker, Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	17:00	11.00	2005	DRIL	drill from 1915 m to 2005 m
17:00	17:30	0.50	2005	SERV	service rig
17:30	6:00	12.50	2130	DRIL	drill from 2005 m to 2130 m at 0600 am.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	4,302	69,341	46,537	1,149,717	42.1%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	4,302	69,341	46,537	1,149,717	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
17-Oct 02:00 at Depth 2088.0																
9.35	44	5.2	1	14	24	9.5	3.3	92.8		0.4	48000	8	14	18	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	4	120
KCl -	4	1,891	condet - 55 Gal Drum	1	493
Pac-L -	3	278	Caustic soda -	4	120

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
1915.0	2130.0	10.00	15.00	5	6	80	130	5	7	515	515	1805

Annular Velocity: **Drill Collars:** 128.20 **Drill Pipe:** 115.90

Comments: slide drill at 0600 am.

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 130 **Pick Up:** 150 **Slack Off:** 125 **Drag Avg/Max:** 15 / 20

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	450 psi	75 spm	500 psi
Pump 2:	68 spm	450 psi	75 spm	500 psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	185.0	**Casing:** 185.0	15.5
Total:	185.0		
Jars:	171.0		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	1689.0	20.17	S 44.84 E	1636.8	319	-225.7	S 225.72	E 225.70	0.123
MWD	1716.0	20.33	S 45.41 E	1662.1	329	-232.3	S 232.31	E 232.32	0.282
MWD	1743.0	20.69	S 46.0399	1687.4	338	-238.9	S 238.91	E 239.10	0.469
MWD	1770.0	20.87	S 46.2100	1712.6	348	-245.6	S 245.55	E 246.00	0.211

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 17 **Report for 06:00 AM 17-Oct-05**

MWD	1798.0	20.16	S 45.44 E	1738.9	357	-252.4	S 252.39	E 253.04	0.814
MWD	1826.0	19.74	S 45.16 E	1765.2	367	-259.1	S 259.11	E 259.83	0.461
MWD	1855.0	19.43	S 45.44 E	1792.5	377	-265.9	S 265.95	E 266.74	0.335
MWD	1910.8	18.93	S 45.8 E	1845.2	395	-278.8	S 278.78	E 279.85	0.276
MWD	1938.5	19.02	S 44.7899	1871.4	404	-285.1	S 285.11	E 286.25	0.369
MWD	1967.1	19.08	S 44.5099	1898.4	413	-291.7	S 291.74	E 292.80	0.115
MWD	1995.3	18.90	S 44.2899	1925.2	423	-298.3	S 298.31	E 299.24	0.206
MWD	2023.5	18.59	S 44.48 E	1951.8	432	-304.8	S 304.78	E 305.57	0.336

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Pump Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
2	1	HYC	DSX104H	8.500	659.0	1474.0	135	10.92	15.00	5	210	6000	9.30	515	1805	67	402	121	166

Jets: 14 14 14 Out: 2400.0 Grade: Cutter: 1 / 3 Dull: CT / CT Wear: T Brgs: X Gge: 1 Pull: CSG

BHA - No. 3 - BIT, MMTR, STAB, FS, MWD, XO, 12 HWDP, JAR = 143.85

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
1915.0	2130.0	1846.0	2052.0	2	5	1904	0	11	0	0.00	9	0	10.0	15.0

Lithology: limestone minor siltstone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.5 m

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.	
Shaker No 1:	175	175	175	**Desander:**		
Shaker No 2:	175	110	110	**Desilter:**	3	
Shaker No 3:	175	175	175	**Degasser:**		
Shaker No 4:				**Centrifuge No 1:**	24	Solids Removal
				Centrifuge No 2:		Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			22350			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 16

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: rain/ fog **Visibility:** 5

Air Temperature: 47.0 degC **Bar. Pressure:** 0

Wind Speed/Dir: 0 / 0 **Wind Gusts:** 0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 18 **Report for 06:00 AM 18-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2400.0	**Drilling Days:**	13	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	2304.0	**Days On Location:**	18	**Last Casing:**	9.625 at 652.2	**Field:**	WAIHAPA
Hole Made:	270.0	**Spud Date:**	05-Oct-05	**Next Casing:**	7.000 at 2400.0	**Working Interest:**	100.00%
Drilling Hrs:	21.0	**Average ROP:**	12.86	**Last BOP Test:**	11-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 15 **Total:** 47

Current Operations: wiper trip to csg shoe at 652 m

Planned Operations: wiper trip, and pooh to log

Toolpusher: Lindsey Baker, Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	3:00	21.00	2400	DRIL	drill from 2130 m to 2400 m csg point
3:00	4:30	1.50	2400	CIRC	pump hi- vis sweep surface to surface , flow check , slug d.p.
4:30	6:00	1.50	2400	STRIP	short trip to csg shoe at 652 m

Comments

received order's to stop csg point at 2400 meter's

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	8,834	78,175	66,029	1,215,746	44.5%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	8,834	78,175	66,029	1,215,746	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
18-Oct 02:00 at Depth 2370.0																
9.30	45	6	1	14	26	9.5	3.1	93		0.5	47000	8	15	19	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	4	120
KCl -	6	2,836	BARAZAN D PLUS - 25KG sxs	10	2,366
pac-r -	8	741	EZ MUD DP -	9	694
Barofibre -	10	319	Caustic soda -	6	180
Pac-L -	1	93	mica medium - 25kg	5	85
Drill plug - 25KG sxs	15	0			

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
2130.0	2400.0	15.00	20.00	5	8	80	130	6	7	485	490	1850

Annular Velocity: **Drill Collars:** 120.80 **Drill Pipe:** 109.20

Comments: rt. drill

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 145 **Pick Up:** 170 **Slack Off:** 136 **Drag Avg/Max:** 15 / 20

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	68 spm	420 psi	75 spm	520 psi	spm	psi	
Pump 2:	68 spm	420 psi	75 spm	520 psi	spm	psi	

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	206.0	**Casing:** 206.0	17.0
Total:	206.0		
Jars:	192.0		

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 18 **Report for 06:00 AM 18-Oct-05**

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	2052.7	19.21	S 43.23 E	1979.4	441	-311.6	S 311.59	E 312.11	0.762
MWD	2081.2	19.19	S 42.6499	2006.4	450	-318.5	S 318.46	E 318.50	0.202
MWD	2110.1	19.43	S 41.28 E	2033.6	460	-325.6	S 325.56	E 324.88	0.533
MWD	2138.4	20.66	S 40.0399	2060.2	470	-332.9	S 332.93	E 331.21	1.376
MWD	2167.3	20.95	S 39.09 E	2087.2	480	-340.8	S 340.84	E 337.74	0.462
MWD	2195.9	20.97	S 39.06 E	2113.9	490	-348.8	S 348.79	E 344.20	0.024
MWD	2224.2	20.97	S 38.72 E	2140.4	500	-356.7	S 356.66	E 350.55	0.129
MWD	2253.0	20.50	S 40.86 E	2167.3	510	-364.5	S 364.51	E 357.08	0.927
MWD	2291.5	20.35	S 41.17 E	2203.4	524	-374.6	S 374.65	E 365.90	0.144
MWD	2319.6	20.22	S 40.7 E	2229.7	533	-382.0	S 381.99	E 372.27	0.223
MWD	2348.3	19.97	S 39.61 E	2256.7	543	-389.5	S 389.54	E 378.64	0.470
MWD	2378.0	19.93	S 38.9900	2284.6	553	-397.4	S 397.38	E 385.05	0.218

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
2	1	HYC	DSX104H	8.500	659.0	1744.0	156	11.18	15.00	5	210	6	9.30	485	1850	63	357	101	147

Jets: 14 14 14 Out: 2400.0 Grade: Cutter: 1 / 3 Dull: CT / CT Wear: T Brgs: X Gge: 1 Pull: CSG

BHA - No. 3 - BIT, MMTR, STAB, FS, MWD, XO, 12 HWDP, JAR = 143.85

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2130.0	2400.0	2052.0	2304.0	4	7	2290	0	0	0	0.00	9	0	11.0	15.0

Lithology:

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	175	175	175
Shaker No 2:	175	175	110
Shaker No 3:	175	175	175
Shaker No 4:			

Equipment Usage:	Hrs.	
Desander:		
Desilter:	3	
Degasser:		
Centrifuge No 1:	24	Solids Removal
Centrifuge No 2:		Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			22350			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 17

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition:	clear	**Visibility:**	5
Air Temperature:	56.0 degC	**Bar. Pressure:**	0
Wind Speed/Dir:	0 / 0	**Wind Gusts:**	0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 19 **Report for 06:00 AM 19-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2400.0	**Drilling Days:**	14	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	2304.0	**Days On Location:**	19	**Last Casing:**	9.625 at 652.2	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	7.000 at 2400.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	11-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 14 **Total:** 46

Current Operations: logging up from 2400 meter's with pex-hria- sonic

Planned Operations: run open hole log's tih , condition mud, pooh l/d d.p.

Toolpusher: Lindsey Baker, Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	9:00	3.00	2400	TRPO	pooh to 650 m no excess drag hole took proper fill
9:00	10:00	1.00	2400	CUTDL	slip and cut 127 feet of drill line and rig service
10:00	14:00	4.00	2400	TRPI	tih filling dp. every 30 stand's to 23841/2 meter's tag fill
14:00	14:30	0.50	2400	CIRC	wash and ream from 2384 m to 2400 m
14:30	16:00	1.50	2400	CIRC	pump 15 bbl's of hi-vis sweep surface to surface , flow check , spot 25 bbl,s 10.0 ppg pill on btm , slug d.p.
16:00	21:30	5.50	2400	TRPO	pooh to directional assembly
21:30	22:30	1.00	2400	BHA	lay down directional assembly, and mwd tool's
22:30	23:00	0.50	2400	RIGU	spot offshore schl. unit through side of derrick, rigging up with one schl hand , logging crew arrived at 2330 hr's
23:00	2:30	3.50	2400	RIGU	r/u schl tool's pex- hria- sonic
2:30	6:00	3.50	2400	LOG	tih with pex- hr[a -sonic tag btm. at 2400 m run repeat tih tag btm logging up from 2399 m

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	3,925	82,100	61,699	1,277,445	46.8%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	3,925	82,100	61,699	1,277,445	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
19-Oct 02:00 at Depth 2399.0																
9.30	45	6	1	16	22	9.5	3.2	93		0.25	46000	8	16	24	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	4	120
Barite - 1500 MT	3	948	KCl -	2	945
pac-r -	2	185	mica medium - 25kg	10	170
EZ MUD DP -	2	154			

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 147 **Pick Up:** 170 **Slack Off:** 136 **Drag Avg/Max:** 15 / 25

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	68 spm	420 psi	75 spm	520 psi	spm	psi
Pump 2:	68 spm	420 psi	75 spm	520 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	206.0	**Casing:** 206.0	24.0
Total:	206.0		
Jars:	192.0		

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 19 **Report for 06:00 AM 19-Oct-05**

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
2	1	HYC	DSX104H	8.500	659.0	1744.0	156												

Jets: 14 14 14 Out: 2400.0 Grade: Cutter: 1 / 3 Dull: CT / CT Wear: T Brgs: X Gge: 1 Pull: CSG

BHA - No. 3 - BIT, MMTR, STAB, FS, MWD, XO, 12 HWDP, JAR = 143.85

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	175	175	175
Shaker No 2:	175	175	175
Shaker No 3:	175	175	175
Shaker No 4:			

Equipment Usage:	Hrs.	
Desander:		
Desilter:		
Degasser:		
Centrifuge No 1:	22	Solids Removal
Centrifuge No 2:		Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL		14995	37345			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 18

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition:	clear	**Visibility:**	5
Air Temperature:	56.0 degC	**Bar. Pressure:**	0
Wind Speed/Dir:	0 / 0	**Wind Gusts:**	0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 20 **Report for 06:00 AM 20-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2403.0	**Drilling Days:**	15	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	2305.0	**Days On Location:**	20	**Last Casing:**	9.625 at 652.2	**Field:**	WAIHAPA
Hole Made:	3.0	**Spud Date:**	05-Oct-05	**Next Casing:**	7.000 at 2400.0	**Working Interest:**	100.00%
Drilling Hrs:	0.5	**Average ROP:**	6.00	**Last BOP Test:**	11-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 13 **Total:** 45

Current Operations: r/u test plug and test bonnet seal's to 1500 psi

Planned Operations: r/u csg tool's , run and cmt csg., set csg slip's /seal

Toolpusher: Lindsey Baker, Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	8:30	2.50	2400	RIGD	finished pooh with logging tool's , layed down and load out same
8:30	9:30	1.00	2400	BHA	p/u new bha
9:30	10:30	1.00	2400	TRPI	tih to 652 m fill dp. every 30 stand's
10:30	11:00	0.50	2400	CIRC	circ. btm's up at 652'
11:00	15:30	4.50	2400	TRPI	tih circ 20 min's every 30 stand'sto 2384 m tag fill
15:30	16:00	0.50	2400	CIRC	wash and ream from 2384m to 2400
16:00	16:30	0.50	2403	DRIL	drill from 2400 to 2403 m to space out csg
16:30	17:30	1.00	2403	CIRC	circ hi - vis sweep surface to surface , spot 25 bbl;s of 11.0 ppg mud on btm , slug dp
17:30	2:30	9.00	2403	LDDP	pooh laying down d.p.to bha
2:30	3:30	1.00	2403	BHA	driller broke out bit , and rotated off bit pdc breaker lock released and bit fell in hole on top of blind ram's , open pipe ram door above blind ram's and recovered bit ,down time
3:30	5:00	1.50	2403	BOPT	finished l/d bha , pull wear bushing
5:00	6:00	1.00	2403	BOPT	p/u test plug and test bonnet seal's to 1500 psi ,down time

Comments

note= drill 3- meter's to space out csg collar clear of well head

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	3,825	85,925	88,627	1,366,072	50.0%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	3,825	85,925	88,627	1,366,072	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
20-Oct 02:00 at Depth 2403.0																
9.30	45	5.6	1	15	24	9	3.3	92.6		0.25	49500	9	16	23	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	4	120
Barite - 1500 MT	4	1,265	KCl -	1	473
BARAZAN D PLUS - 25KG sxs	1	237	Barofibre -	5	159
pac-r -	1	93	EZ MUD DP -	1	77

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
2400.0	2403.0	15.00	15.00	5	5	80	130	6	7	515	515	1800

Annular Velocity: **Drill Collars:** 128.20 **Drill Pipe:** 115.90

Comments: rotate drill 3 meter's

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 20 **Report for 06:00 AM 20-Oct-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 147 **Pick Up:** 170 **Slack Off:** 136 **Drag Avg/Max:** 15 / 25

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	68 spm	400 psi	75 spm	500 psi	spm	psi	
Pump 2:	68 spm	400 psi	75 spm	500 psi	spm	psi	

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	206.5	**Casing:**	206.5	32.0
Total:	206.5			
Jars:	192.5			

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
2	1	HYC	DSX104H	8.500	659.0	1747.0	157	11.16	15.00	5	130	6	9.30	515	1800	67	402	121	166

Jets: 14 14 14 Out: 2400.0 Grade: Cutter: 1 / 3 Dull: CT / CT Wear: T Brgs: X Gge: 1 Pull: CSG

BHA - No. 3 - BIT, MMTR, STAB, FS, MWD, XO, 12 HWDP, JAR = 143.85

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2400.0	2403.0	2304.0	2305.0	3	6	2400	0	9	0	0.00	9	0	15.0	15.0

Lithology:

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.	
Shaker No 1:	175	175	175	**Desander:**		
Shaker No 2:	175	175	175	**Desilter:**		
Shaker No 3:	175	175	175	**Degasser:**		
Shaker No 4:				**Centrifuge No 1:**	11	Solids Removal
				Centrifuge No 2:		Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			37345			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 19

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: rain **Visibility:** 2

Air Temperature: 47.0 degC **Bar. Pressure:** 0

Wind Speed/Dir: 0 / 00 **Wind Gusts:** 0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 21 **Report for 06:00 AM 21-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2403.0	**Drilling Days:**	16	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	2305.0	**Days On Location:**	21	**Last Casing:**	9.625 at 652.2	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	7.000 at 2400.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	21-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 12 **Total:** 44

Current Operations: n/d flow line , bell nipple , choke and kill line's note csg shoe at 2395 meter's

Planned Operations: wait on cmt , n/d bop's , set slip's , cut csg , dress off same , n/u b-section, n/u bop's

Toolpusher: Lindsey Baker, Ian Hough

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:30	1.50	2403	RIGU	held prejob safety meeting and r/u csg tool's
7:30	21:00	13.50	2403	CASE	run 204 joint's of 29 # L -80 butt. csg to 2384 m tag up wash from 2384 m to 2395 m would not wash past 2395 m
21:00	23:00	2.00	2395	RIGD	remove circ swege and install cmt retainer and line's test line's to 4000 psi release btm plug
23:00	1:00	2.00	2395	CMTP	pump 60 bbl's of water for spacer plus 200 sk's of cl-g at 11.8 ppg yield at 2.56 mix wtr = 15.29 slurry volume = 88 bbl's plus 850 sk's of cl-g at 15.6 ppg yield at 1.17 mix wtr = 5.05 slurry volume = 170
1:00	2:30	1.50	2395	CMTPL	diisplace plug with 280 bbl's of sbm and 20 bbl's of water bump plug with 2200 psi ,bled down pressure float's held ok
2:30	6:00	3.50	2395	BOPND	n/d flow line bell nipple choke & kill line'swhile waiting on cmt

Comments

csg shoe at 2395 meter's
float colar at 2383 meter's

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	1,625	87,550	207,485	1,573,557	57.6%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	1,625	87,550	207,485	1,573,557	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
21-Oct 02:00 at Depth 2403.0																
9.30	44	5.8	1	15	25	9.2	3	92.8		0.25	51000	8	17	23	25.0	25.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	4	120
Barite - 1500 MT	1	316			

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: **Pick Up:** 250 **Slack Off:** 155 **Drag Avg/Max:** 45 / 55

☐ **Wear Bushing Installed**

BHA Information

BHA - No. 3 - BIT, MMTR, STAB, FS, MWD, XO, 12 HWDP, JAR = 143.85

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	175	175	175
Shaker No 2:	175	175	175
Shaker No 3:	175	175	175
Shaker No 4:			

Equipment Usage:	Hrs.
Desander:	
Desilter:	
Degasser:	
Centrifuge No 1:	8 Solids Removal
Centrifuge No 2:	Solids Removal

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 21 **Report for 06:00 AM 21-Oct-05**

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			37345			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 20

Accident Description: none reported

Meetings/Drills **Time** **Description**

☑ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: rainning **Visibility:** 2

Air Temperature: 49.0 degC **Bar. Pressure:** 0

Wind Speed/Dir: 0 / 0 **Wind Gusts:** 0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 22 **Report for 06:00 AM 22-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2403.0	**Drilling Days:**	17	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	2305.0	**Days On Location:**	22	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	22-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 13 **Total:** 45

Current Operations: changing out ram's in bop's from 4 1/2" to 3 1/2" n/u bell nipple

Planned Operations: finish n/u bop's , r/u and test to 250/5000 / 250/3000 , p/u directional assembly & tih

Toolpusher: Lindsey Baker, Steve John

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	14:30	8.50	2403	WOC	while waiting on cmt , changed out liner's in both mud pump's, off loaded 3 1/2" rental's and d.p. washing out mud tank's , clearing way behind mud tank's to run pipe line
14:30	17:30	3.00	2403	BOPND	r/d plug container and line's ,r/u pick up line's and latch on to bop's n/d flange at a-section set csg slip's with 200 k made rough cut l/dexcess csg
17:30	6:00	12.50	2403	BOPND	make final cut on 7" dress off same, n/d two adaptor spool's and n/u b section and bop's packed and tested well head to 5000 psi , cleaning mud pit's , open bop's changing out ram's from 4 1/2" to 3 1/2" n/u bell nipple

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	39,821	127,371	93,419	1,666,976	61.0%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	39,821	127,371	93,419	1,666,976	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
22-Oct 02:00 at Depth 2403.0																
8.90	80		2	26	19		6.5	12	80	0.25		8	15	20	25.0	25.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	4	120
COREDRIL-N - bbl	293	38,090			

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
3	1	HYC	dsx516m-b	6.000	2403.0														

Jets: 13 13 13 13 13 Out: 2903.0 Grade: Cutter: 3 / 6 Dull: WT / CT Wear: S Brgs: N Gge: 1 Pull: PR

BHA - No. 4 - BIT, MMTR, FS, STAB, MWD, 17 HWDP, JAR, 4 HWDP = 218.32

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	175	175	175	**Desander:**	
Shaker No 2:	175	175	175	**Desilter:**	
Shaker No 3:	175	175	175	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			37345			

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 22 **Report for 06:00 AM 22-Oct-05**

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 21

Accident Description: none reported

Meetings/Drills **Time** **Description**

☑ **BOP Test** ☐ **Crownamatic Check**

Weather

Sky Condition: rain **Visibility:** 2

Air Temperature: 42.0 degC **Bar. Pressure:** 0

Wind Speed/Dir: 10 / S **Wind Gusts:** 15

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 23 **Report for 06:00 AM 23-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2403.0	**Drilling Days:**	18	**RKB Elevation:**	5.5	**County:**	Taranaki
Vertical Depth:	2305.0	**Days On Location:**	23	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 14 **Total:** 46

Current Operations: break circ and testing 7" 29 # L-80 butt csg to 2000 psi at 2379 meter's

Planned Operations: finished tih tag cmt ,break circ. ,test csg to 2000 psi ,drill shoe track and 3 meter's of new hole , circ. and test to equiv. to 11.5 ppg and drill ahead to csg point

Toolpusher: Lindsey Baker, Steve John

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:30	0.50	2403	BOPNU	finished n/u bell nipple & flow line
6:30	9:30	3.00	2403	RIGU	changed out 4 1/2" kelly for 3 1/2" kelly
9:30	10:00	0.50	2403	BOPT	p/u test equip.
10:00	16:00	6.00	2403	BOPT	test annular to 250/ 3000 , test ram's , valve's and line's to bop's and choke manifold to 250 /5000 psi ,test all surface equip. to 250/ 5000 psi
16:00	18:00	2.00	2403	BHA	p/u directional assembly orient and test same
18:00	2:30	8.50	2403	PUDP	p/u hwdp jar's and drill pipe from pipe rack to 1932 m tighten kelly and broke circ
2:30	3:30	1.00	2403	SERV	slip and cut 75 feet of drill line and service rig
3:30	6:00	2.50	2403	PUDP	continue tih from 1932 m to 2379 m tag cmt , break circ , test csg to 2000 psi

Comments

note = mr. john molloy with osh visit loc. on 10/20/05 he stated to keep up the good work all was good

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	131,942	259,313	200,032	1,867,008	68.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	131,942	259,313	200,032	1,867,008	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
23-Oct 02:00 at Depth 2403.0																
8.70	55		2	15	15		4	12	82	0.2		5	8	13	25.0	25.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
SOBM -	750	97,500	Saraline 185 -	214	28,239
EZ MUL NT -	5	3,334	Calcium chloride bulk bag -	2	742
Barite - 1500 MT	1	316	Lime -	22	192
Barofibre -	5	159			

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** **Pick Up:** **Slack Off:** **Drag Avg/Max:** /

☑ **Wear Bushing Installed**

	Rotate Hrs	Trip Hrs
Casing:		11.0

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
3	1	HYC	dsx516m-b	6.000	2403.0														

Jets: 13 13 13 13 13 Out: 2903.0 Grade: Cutter: 3 / 6 Dull: WT / CT Wear: S Brgs: N Gge: 1 Pull: PR

BHA - No. 4 - BIT, MMTR, FS, STAB, MWD, 17 HWDP, JAR, 4 HWDP = 218.32

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 23 **Report for 06:00 AM 23-Oct-05**

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.5 m

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	175	175	175	Desander:	
Shaker No 2:	175	175	175	Desilter:	
Shaker No 3:	175	175	175	Degasser:	
Shaker No 4:				Centrifuge No 1:	Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			37345			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 22

Accident Description: none reported

Meetings/Drills **Time** **Description**

BOP: test bop's on 10/22/05

☑ **BOP Test** ☐ **Crownamatic Check**

Weather

Sky Condition:	clear	**Visibility:**	5
Air Temperature:	49.0 degC	**Bar. Pressure:**	0
Wind Speed/Dir:	0 / 0	**Wind Gusts:**	0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 24 **Report for 06:00 AM 24-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2555.0	**Drilling Days:**	19	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	2445.0	**Days On Location:**	24	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	152.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	19.5	**Average ROP:**	7.79	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 13 **Total:** 45

Current Operations: drill from 2403 m to 2555 m at 0600 am.

Planned Operations: drill to csg point of 3430 m / 3256 m tvd

Toolpusher: Mike preston / Steve John

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:00	1.00	2403	BOPT	test 7'' 29 # L-80 butt csg. to 2000 psi for 30 min's
7:00	9:00	2.00	2406	SRT	drill shoe track to 2395 and wash out rat hole , drill 3 meter's of new hole to 2406 m circ. hole clean
9:00	9:30	0.50	2406	SRT	test formation with 8.9 ppg to 1030 equiv to 11.5 ppg 7562 tvd ft.
9:30	10:30	1.00	2409	DRIL	drill from 2406 meter's to 2409 m
10:30	11:30	1.00	2409	OTHER	relevel derrick to center pipe in rotary
11:30	6:00	18.50	2555	DRIL	drill from 2409 m to 2555 m at 0600 am.

Comments

note =found the shoe 3 meter's high at 2392

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		259,313	86,740	1,953,748	71.5%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904		259,313	86,740	1,953,748	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
24-Oct 02:00 at Depth 2486.0																
8.50	56		2	20	16		4	12	82	0.25		6	8	12	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
BDF-303 -	2	863	Lime -	20	175
Barofibre -	5	159	Con Det -	0	0

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
2403.0	2555.0	15.00	19.00	5	6	80	190	5000	6000	219	240	2480

Annular Velocity: **Drill Collars:** 121.80 **Drill Pipe:** 68.90

Comments: rt. drill

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 120 **Pick Up:** 133 **Slack Off:** 110 **Drag Avg/Max:** 10 / 17

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	68 spm	1060 psi	75 spm	1180 psi	spm	psi
Pump 2:	68 spm	660 psi	75 spm	820 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	19.5	**Casing:** 19.5	3.0
Total:	19.5		
Jars:	19.5		

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 24 **Report for 06:00 AM 24-Oct-05**

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	2409.5	19.98	S 37.86 E	2314.2	564	-405.8	S 405.81	E 391.74	0.370
MWD	2438.3	19.30	S 38.55 E	2341.3	574	-413.4	S 413.39	E 397.71	0.751
MWD	2466.4	18.89	S 41.42 E	2367.9	583	-420.5	S 420.45	E 403.63	1.091
MWD	2493.6	18.81	S 44.56 E	2393.7	592	-426.9	S 426.89	E 409.62	1.121

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
3	1	HYC	dsx516m-b	6.000	2403.0	152.0	19.5	7.79	20.00	5	190	6000	8.50	219	2480	33	89	11	32

Jets: 13 13 13 13 13 Out: 2903.0 Grade: Cutter: 3 / 6 Dull: WT / CT Wear: S Brgs: N Gge: 1 Pull: PR

BHA - No. 4 - BIT, MMTR, FS, STAB, MWD, 17 HWDP, JAR, 4 HWDP = 218.32

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	Desander:	
Shaker No 2:	210	210	210	Desilter:	
Shaker No 3:	210	210	210	Degasser:	
Shaker No 4:				Centrifuge No 1:	2 Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			37345			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
4.5	130	16.6	S-135	4.0IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 23

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition:	clear	**Visibility:**	5
Air Temperature:	38.0 degC	**Bar. Pressure:**	0
Wind Speed/Dir:	0 / 0	**Wind Gusts:**	0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 25 **Report for 06:00 AM 25-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2740.0	**Drilling Days:**	20	**RKB Elevation:**	5.5	**County:**	Taranaki
Vertical Depth:	2626.0	**Days On Location:**	25	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	185.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	24.0	**Average ROP:**	7.71	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 13 **Total:** 45

Current Operations: drill from 2555 m to 2740 m at 0600 a.m. ,top tariki sand at 2710 meter's 2605 tvd
slide hr's = 8
rotate hr's = 16

Planned Operations: drill to csg point at 3430 m 3256 m tvd

Toolpusher: Mike preston / Steve John

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:00	24.00	2740	DRIL	drill from 2555 meter's to 2740 meter's at 0600 am.

Comments

note = top tariki at 2710 md 2605 tvd seen first connection gas 28 over 10 unit's seen second connection gas 22 over 10 unit's mud wt. 8.5 ppg no losses
total slide hour's = 8 hour's
total rotate hour's = 16 hour's

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	2,066	261,379	54,902	2,008,650	73.5%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	2,066	261,379	54,902	2,008,650	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
25-Oct 02:00 at Depth 2690.0																
8.50	58		2	22	21		3.8	14	80	0.25		6	9	12	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
BDF-303 -	1	432	Lime -	20	175

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
2555.0	2740.0	8.00	12.00	5	7	80	113	5000	7000	218	220	2450

Annular Velocity: **Drill Collars:** 121.20 **Drill Pipe:** 68.60

Comments: rt./slide

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 128 **Pick Up:** 143 **Slack Off:** 116 **Drag Avg/Max:** 15 / 20

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	950 psi	75 spm	1120 psi	spm	psi
Pump 2:	68 spm	550 psi	75 spm	760 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	43.5	**Casing:** 43.5	0.0
Total:	43.5		
Jars:	43.5		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	2521.8	18.40	S 44.31 E	2420.4	601	-433.3	S 433.30	E 415.91	0.445
MWD	2549.3	18.54	S 45.59 E	2446.4	609	-439.5	S 439.46	E 422.06	0.469

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 25 **Report for 06:00 AM 25-Oct-05**

MWD	2577.9	18.98	S 45.38 E	2473.5	619	-445.9	S 445.91	E 428.62	0.467
MWD	2606.8	19.53	S 45.27 E	2500.8	628	-452.6	S 452.61	E 435.40	0.572
MWD	2634.3	19.03	S 43.87 E	2526.8	637	-459.1	S 459.09	E 441.78	0.742
MWD	2662.3	18.53	S 42.8500	2553.3	646	-465.6	S 465.64	E 447.97	0.641
MWD	2690.6	18.77	S 45.8 E	2580.1	655	-472.1	S 472.10	E 454.28	1.034

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
3	1	HYC	dsx516m-b	6.000	2403.0	337.0	43.5	7.75	25.00	7	193	7000	8.50	218	2450	33	89	11	32

Jets: 13 13 13 13 13 Out: 2903.0 Grade: Cutter: 3 / 6 Dull: WT / CT Wear: S Brgs: N Gge: 1 Pull: PR

BHA - No. 4 - BIT, MMTR, FS, STAB, MWD, 17 HWDP, JAR, 4 HWDP = 218.32

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2555.0	2740.0	2445.0	2626.0	10	28	2710	28	0	0	0.00	9	0	8.0	25.0

Lithology: claystone ,limestone and sandstone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.5 m

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	Desander:	
Shaker No 2:	210	210	210	Desilter:	
Shaker No 3:	210	210	210	Degasser:	
Shaker No 4:				Centrifuge No 1:	24 Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	3184	13945	20232			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 24

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition:	clear	**Visibility:**	5
Air Temperature:	56.0 degC	**Bar. Pressure:**	0
Wind Speed/Dir:	0 / 0	**Wind Gusts:**	0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 26 **Report for 06:00 AM 26-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2788.0	**Drilling Days:**	21	**RKB Elevation:**	5.5	**County:**	Taranaki
Vertical Depth:	2671.0	**Days On Location:**	26	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	48.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	21.5	**Average ROP:**	2.23	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 2 **Contractor:** 0 **Service:** 0 **Other:** 0 **Total:** 2

Current Operations: Continue drill 6" hole to 2788m Sliding and rotating .GPM 238, WOB 5/10, Torque 7/9000 ft/bls,Max gas 28 units, Back ground gas 10 units..

Planned Operations: Continue to drill 6" hole to sliding and rotating to target depth.

Toolpusher: Mike preston / Steve John

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	0:30	18.50	2787	DRIL	Continue to drill 6" hole sliding and rotating .GPM 238, WOB 5/10k, Torque 5/10000 ft/lbs, ROP 1-2m/hr .Hard sandstone stringers unable to slide through .Hole getting sticky.Pump sweeps as required
0:30	2:00	1.50	2787	DRIL	Pump 10 bbls high vis and cirulate clean prior to wiper trip.Take survey
2:00	3:00	1.00	2380	TRPO	Flow check (static) TRPO f/- 2877m to 2380m no over pull hole in good condition.
3:00	3:30	0.50	2380	SERV	Rig service at 7" casing shoe.
3:30	4:30	1.00	2787	TRPI	TRPI to 2776m pick up kelly and wash down to 2787m no fill.
4:30	6:00	1.50	2788	DRIL	Continue to drill ahead sliding and rotating to 2788m .GPM 238, WOB 5-10k, Torque 5-9000 ft/lbs MW 8.5ppg.

Comments

Pump KCL sweeps as required. Bit balling up KCL sweeps improve ROP .
Total losses 24hr period 18 bbls,.
Wash pipe hrs 278.Jar hrs 62

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	3,347	264,726	54,908	2,063,558	75.6%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	3,347	264,726	54,908	2,063,558	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
26-Oct 02:00 at Depth 2785.0																
8.50	60		2	21	21		3.6	12	82	0.25		6	9	13	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	8	1,154	Barofibre -	23	733

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
2740.0	2788.0	2.40	3.00	5	10	80	80	6500	8000	238	238	2850

Annular Velocity: **Drill Collars:** 49.40 **Drill Pipe:** 74.90

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 132000 **Pick Up:** 146000 **Slack Off:** 118000 **Drag Avg/Max:** /

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	950 psi	75 spm	1120 psi	spm	psi
Pump 2:	68 spm	550 psi	75 spm	760 psi	spm	psi

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	63.5	**Casing:**	63.5	2.0
Total:	63.5			
Jars:	63.5			

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 26 **Report for 06:00 AM 26-Oct-05**

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	2718.5	19.23	S 46.0399	2606.5	664	-478.4	S 478.43	E 460.82	0.500
MWD	2746.4	18.27	S 43.28 E	2632.9	673	-484.8	S 484.80	E 467.12	1.407
MWD	2773.8	19.19	S 45.27 E	2658.8	682	-491.1	S 491.09	E 473.26	1.228

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
3	1	HYC	dsx516m-b	6.000	2403.0	385.0	64	6.02	5.00	5	80	6500	8.50	238	2850	36	106	15	38

Jets: 13 13 13 13 13 Out: 2903.0 Grade: Cutter: 3 / 6 Dull: WT / CT Wear: S Brgs: N Gge: 1 Pull: PR

BHA - No. 4 - BIT, MMTR, FS, STAB, MWD, 17 HWDP, JAR, 4 HWDP = 218.32

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2740.0	2788.0		2672.0	11	15	2736					9			

Lithology: Claystone ,Siltstone, Sanstone,

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.5 m

Location Condition: Made containment area for chemical drum storage.
Continue general site housekeeping.
Chemical injection line found broken on rig site .informed Production .

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	10 Solids Removal
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	3765		16467			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 25

Accident Description: No accidents or incidents to report.

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meeting .Topic discussed.Correct hand position on rig tongs. step back 5x5.
Pit:	23	23 seconds to install FOSV

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: overcast **Visibility:**

Air Temperature: 20.0 degC **Bar. Pressure:**

Wind Speed/Dir: 2 / SE **Wind Gusts:** 5

Comments: Expected to clear and be fine.

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 26 **Report for 06:00 AM 26-Oct-05**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 27 **Report for 06:00 AM 27-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2833.0	**Drilling Days:**	22	**RKB Elevation:**	5.5	**County:**	Taranaki
Vertical Depth:	2714.0	**Days On Location:**	27	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	45.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	24.0	**Average ROP:**	1.88	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 2 **Total:** 34

Current Operations: Continue drill 6" hole sliding and rotating to maintain azimuth and inclination. GPM 238, WOB 8-10k, Torque 6.5--7000 ft/bls. Background gas 10 units.ROP .5-1m/hr due to hard cemented sandstones .Pump kcl sweeps to assist with bit balling and hole cleaning.

Planned Operations: Continue drill 6" hole to target .

Toolpusher: Mike preston / Steve John

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:30	0.50	2789	DRILS	Continue drill Siding to 2789m.
6:30	9:30	3.00	2796	DRLR	Continue drill 6" hole rotating to 2796m
9:30	11:30	2.00	2802	DRILS	Contnue drill 6" hole sliding to 2802m start getting connection gas .increase mw 1 point to 8.6ppg
11:30	0:00	12.50	2826	DRILR	Continue drill 6" hole rotating to 2826m. ROP 1-1.5m/hr,GPM 238,
0:00	6:00	6.00	2833	DRILR	Continue drill 6"hole rotating to 2833m . ROP reduced to .5-1m/hr very hard cemented sandstones.GPM 238,Torque 6.5/7000 ft/bls,WOB 8-10k.back ground gaas 10-15 units.Pump high vis sweeps as required.

Comments

Vause wireline services installed guages on Ahuroa 2 A site at 15:00 hrs 26th october.
Rental 3 1/2 elevators not latching ,change out and send back for inspection/repair.
Losses 24 hr period 14 bbls,

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	5,021	269,747	45,182	2,108,740	77.2%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	5,021	269,747	45,182	2,108,740	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
27-Oct 02:00 at Depth 2819.0																
8.60	62		2	23	19		4.7	12	81	0.25		7	10	15	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	6	866	Barofibre -	20	637
Barite - 1500 MT	2	632	BARACARB 25 -	40	501
condet - 55 Gal Drum	1	493	BDF-303 -	1	432

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
2788.0	2833.0	1.87	5.00	8	12	75	80	6500	7000	238	238	2850

Annular Velocity: **Drill Collars:** 49.40 **Drill Pipe:** 74.90

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 132000 **Pick Up:** 148000 **Slack Off:** 120000 **Drag Avg/Max:** /

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	950 psi	75 spm	1120 psi	spm	psi
Pump 2:	68 spm	550 psi	75 spm	760 psi	spm	psi

BHA Rotate Hrs	Rotate Hrs	Trip Hrs

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 27 **Report for 06:00 AM 27-Oct-05**

Since Inspection:	87.5	**Casing:**	87.5	2.0
Total:	87.0			
Jars:	87.5			

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	2803.5	18.90	S 44.86 E	2686.9	692	-497.9	S 497.93	E 480.12	0.323

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
3	1	HYC	dsx516m-b	6.000	2403.0	430.0	88	4.89	5.00	8	75	6500	8.60	238	2850	36	107	15	38

Jets: 13 13 13 13 13 Out: 2903.0 Grade: Cutter: 3 / 6 Dull: WT / CT Wear: S Brgs: N Gge: 1 Pull: PR

BHA - No. 4 - BIT, MMTR, FS, STAB, MWD, 17 HWDP, JAR, 4 HWDP = 218.32

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2788.0	2833.0		2714.0	13	30	2822					9			

Lithology: Claystone 20%,siltstone 40%,sandston 40%

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.5 m

Equipment Problems: Repaired mud pump #1

Location Condition: General housekeeping.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	11 Solids Removal
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	3609		12858			

Truck/Boat Status: 2 x loads of cutting removed from dee tank

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 26

Accident Description: No accidents or incidents to report

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meetings .Topic Discussed, Working with SPM. Wearing correct PPE on loction.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Clear **Visibility:**

Air Temperature: degC **Bar. Pressure:**

Wind Speed/Dir: 0 / NE **Wind Gusts:** 2

Comments: Fine clear day.

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 28 **Report for 06:00 AM 28-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2880.0	**Drilling Days:**	23	**RKB Elevation:**	5.5	**County:**	Taranaki
Vertical Depth:	2760.0	**Days On Location:**	28	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	47.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	23.0	**Average ROP:**	2.04	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 22 **Service:** 10 **Other:** 2 **Total:** 35

Current Operations: Continue drill 6" hole sliding and rotating as per Sperry sun dirctional drillers parameters .GPM 195, RPM 80, Torque 65-7000 ft/bls. pumps KCL sweeps as needed.

Planned Operations: Continue to dril 6" hole to target depth.

Toolpusher: Mike preston / Steve John

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	8:00	2.00	2836	DRLR	Contnue to drill 6" hole rotating to 2836m
8:00	9:30	1.50	2838	DRILS	Dill 6" hole sliding to 2838m unable to slide hard formation.
9:30	16:00	6.50	2847	DRILR	Continue to drill 6" hole rotating to 2841m
16:00	20:30	4.50	2862	DRILS	Continue to drill 6 " hole sliding to 2862m
20:30	21:30	1.00	2862	OTHER	Sudden pressure loss in standpipe pressure reduced 1000 psi.Check pumps ok. All pressure transducers plugged up clean and pump up . Work string during operation, Test run pump pressure ok.
21:30	23:00	1.50	2868	DRILS	Continue to dril 6" hole sliding to 2868m
23:00	0:00	1.00	2871	DRILR	Drill 6" hole to 2871m. ROP2-4m/hr ,GPM 200. Torque 6-7000 ft/bls.
0:00	2:30	2.50	2876	DRILR	Drill 6" hole rotating to 2876m
2:30	3:30	1.00	2877	DRLS	Drill 6" hole sliding to 2877m. unable to slide weight stacking up .
3:30	6:00	2.50	2880	DRILR	Continure to drill 6" hole to 2880m. GPM 195, WOB 5-12k, Torque 6-7000 ft/bls, rpm 80.Back ground gas 10-25 units.MW 8.6 ppg ,Vis 59. ROP 1-3m/hr. Pump kcl sweeps as required.

Comments

Installed and funcion tested ESD on rig floor .
Continue rotate and slide to maintain azimuth and inclination. Unable to slide in cemented sandstone. Rotate through until able to slide.
Background gas max 33 units.
Wireline retieved guages from Ahuroa 1 A.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	3,819	273,566	44,553	2,153,293	78.8%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	3,819	273,566	44,553	2,153,293	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
28-Oct 02:00 at Depth 2864.0																
8.60	55		2	19	19		4.8	12	81	0.25		7	9	14	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	6	866	RM 63 -	1	674
BARACARB 25 -	40	501	Barofibre -	10	319

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
2833.0	2880.0	2.00	5.00	8	12	80	80	6500	7000	195	230	2250

Annular Velocity: Drill Collars: 40.50 **Drill Pipe:** 61.30

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 28 **Report for 06:00 AM 28-Oct-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 135000 **Pick Up:** 148000 **Slack Off:** 124000 **Drag Avg/Max:** 13000 / 15000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	950 psi	75 spm	1120 psi	spm	psi	
Pump 2:	68 spm	550 psi	75 spm	760 psi	spm	psi	

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	110.5	**Casing:** 110.5	
Total:	110.5		
Jars:	110.5		

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
3	1	HYC	dsx516m-b	6.000	2403.0	477.0	111	4.30	5.00	8	80	6500	8.60	192	2250	29	70	8	25

Jets: 13 13 13 13 13 Out: 2903.0 Grade: Cutter: 3 / 6 Dull: WT / CT Wear: S Brgs: N Gge: 1 Pull: PR

BHA - No. 4 - BIT, MMTR, FS, STAB, MWD, 17 HWDP, JAR, 4 HWDP = 218.32

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2833.0	2880.0		2760.0	18	34	2845					9			

Lithology: Sandstone 90% minor traces of claystone and siltstone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.5 m

Equipment Problems: Repair suction cap retainer on mud pump #2
Clean out all pressure sensors on standpipe due to 1000 psi drop in pressure.

Location Condition: Continue housekeeping

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	8 Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	3387		9471			

Truck/Boat Status: 1 x 40 ft flatdeck delivered mud motor.
1 x 40 ft flatdeck delivered mud chemicals

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 27

Accident Description: No accidents or incidents.

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meeting.Topics discussed.Working with SBM.Housekeeping on site. Smoking only in smoking areas.

☐ **BOP Test** ☑ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 28 **Report for 06:00 AM 28-Oct-05**

Weather

Sky Condition:	Clear	**Visibility:**	
Air Temperature:	21.0 degC	**Bar. Pressure:**	
Wind Speed/Dir:	2 / SE	**Wind Gusts:**	2
Comments:	Fine clear condition		

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 29 **Report for 06:00 AM 29-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2903.0	**Drilling Days:**	24	**RKB Elevation:**	5.5	**County:**	Taranaki
Vertical Depth:	2781.0	**Days On Location:**	29	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	23.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	8.5	**Average ROP:**	2.71	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 2 **Total:** 34

Current Operations: Continue TRPI with bit# 5

Planned Operations: Continue to drill 6" hole to target depth maintaining inclination and azimuth

Toolpusher: Mike preston / Steve John

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:30	1.50	2884	DRLR	Continue to drill 6" hole rotating to 2884m Pump sweeps as required
7:30	9:00	1.50	2886	DRILS	Continue to drill 6" hole sliding to 2886m. Unable to slide .
9:00	10:00	1.00	2891	DRILR	Continue to drill 6" hole rotating to 2891m.
10:00	12:00	2.00	2895	DRILS	Continue to drill 6" hole sliding to 2895m GPM 195, ROP 1-2m/hr. Pump sweeps as required
12:00	14:30	2.50	2903	DRILS	Continue drill 6" hole sliding to 2903m .GPM 195,ROP 1-2m/hr .surveys reflect unable to build or maintain angle.
14:30	16:30	2.00	2903	CIRC	Pump 15 bbls high vis sweep and circulate clean.
16:30	17:00	0.50	2903	FLOW	Flow check (static) Pump slug
17:00	23:00	6.00	218	TRPO	TRPO out to 7" casing shoe 2390m(static) Continue to TRPO to BHA 218m.
23:00	0:00	1.00	22	TOHBHA	TROHBHA to directional tools.
0:00	0:30	0.50	0	TOHBHA	Layout Top stabilizer , miud motor and bit.
0:30	1:30	1.00	11	DIR	m/up new mud motor , m/up bit, Orientate tool face ok.
1:30	2:30	1.00	215	TIHBHA	TIHBHA to 215m .Conduct shallow pulse test with MWD ok.
2:30	6:00	3.50	1650	TRPI	Continue TRPI WITH 3 1/2 DP to 1650m

Comments

Install SBM vacume system.
Unable to slide due to BHA configuration.Bits # 4 outer shoulder very dull .

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	3,595	277,161	52,694	2,205,987	80.8%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	3,595	277,161	52,694	2,205,987	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
29-Oct 02:00 at Depth 2903.0																
8.65	58		2	18	25		4.6	12	81.2	0.25		8	11	15	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	6	866	Barofibre -	20	637
Barite - 1500 MT	2	632			

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
2880.0	2781.0	1.00	5.00	8	12	80	80	6500	7000	195	200	2500

Annular Velocity: **Drill Collars:** 40.50 **Drill Pipe:** 61.30

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 29 **Report for 06:00 AM 29-Oct-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 136000 **Pick Up:** 150000 **Slack Off:** 125000 **Drag Avg/Max:** /

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	950 psi	75 spm	1120 psi	spm	psi	
Pump 2:	68 spm	550 psi	75 spm	760 psi	spm	psi	

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	121.0	**Casing:**	121.0	11.5
Total:	121.0			
Jars:	121.0			

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
3	1	HYC	dsx516m-b	6.000	2403.0	500.0	122	4.12	5.00	8	80	6500	8.60	195	2500	29	72	8	26
Jets:	13	13	13	13	13		Out: 2903.0		Grade:	Cutter:	3 / 6	Dull: WT / CT		Wear: S		Brgs: N		Gge: 1		Pull: PR
4	1	HYC	DSX 516 M	6.000	2903.0														
Jets:	15	15	15	13	13		Out: 3296.0		Grade:	Cutter:	-2 / 6	Dull: VT / WT		Wear: S		Brgs: X		Gge: 1		Pull: FM

BHA - No. 5 - BIT, MMTR, FS, MWD, 17 HWDP, JAR, 4 HWDP = 215.89

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2880.0	2903.0		2781.0	36	46	2889					9			

Lithology: 90% Sandstone. Minor traces of siltstine and claystone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.5 m

Location Condition: Continue housekeeping./
Install and function test mud vacume system ok.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	8 Solids Removal
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	2714.6	14815.6	21572			

Truck/Boat Status: Delivered nud vacume system

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 28

Accident Description: No accidents or incidents to report

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meeting. Topic discussed. Tripping pipe. Working with SPM.
Trip:	23	23 seconds to install FOSV

☐ **BOP Test** ☑ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 29 **Report for 06:00 AM 29-Oct-05**

Weather

Sky Condition:	Overcast	**Visibility:**	
Air Temperature:	21.0 degC	**Bar. Pressure:**	
Wind Speed/Dir:	2 / NE	**Wind Gusts:**	5

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 30 **Report for 06:00 AM 30-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2906.0	**Drilling Days:**	25	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	2784.0	**Days On Location:**	30	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	3.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	1.0	**Average ROP:**	3.00	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 2 **Total:** 34

Current Operations: Continue to drill 6" hole maintaining azimuth and inclination.GPM 200, ROP 4-6m/hr.WOB 4-8k.

Planned Operations: Continue to drill 6" hole to target depth

Toolpusher: Mike preston / Steve John

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:00	1.00	2388	TRPI	Continue TRPI to 2388m .filling every 25 stds.
7:00	7:30	0.50	2388	SERV	Rig service
7:30	8:30	1.00	2877	TRPI	Continue TRPI to 2877m good hole no hang ups.
8:30	9:30	1.00	2903	WASH	Wash down f/-2877m to 2903m .1m fill
9:30	11:00	1.50	2903	OTHER	Take survey prior to drilling . No pulse signal indentified.Trouble shoot system , recycle pumps, change out transducers, change out link cable . no go. Unable to communicate to MWD tool.
11:00	18:00	7.00	281	TRPO	Flow check (static) pump slug TRPO. to 7" casing shoe.Flow check at 7" casing shoe (static). continue TRPO to BHA.
18:00	19:00	1.00	0	TOHBHA	Flow check at BHA. (static).TOHBHA. Lay out MWD pulsing assy.
19:00	20:00	1.00	0	OTHER	Install new MWDpulsing assy. Install new float.Orientate MWD.
20:00	21:30	1.50	235	TIHBHA	TIHBHA to 235m . Shallow test MWD. All systems operational
21:30	0:00	2.50	1358	TRPI	TRPI to 1358m filling pipe every 25 stds.
0:00	2:00	2.00	2378	TRPI	Continue TRPI to 7" casing shoe.
2:00	3:00	1.00	2378	CUTDL	Slip and cut 78ft drilling line . circulate well while slip and cutting drilling line.Install drill piipe screen when circulating
3:00	4:30	1.50	2378	TRPI	Continue TRPI to 2378m . no hang ups.
4:30	5:00	0.50	2903	WASH	Wash down f/- 2378m to 2903m. No fill .
5:00	6:00	1.00	2906	DRILS	Continue drill 6" hole sliding to 2906m. GPM 200, WOB 2-4k. ROP 6-8m/hr.

Comments

Tested MWD at surface ok. Down hole test prior to drilling no go. Trouble shoot.
MWD rotor plugged up when inspected at surface. Use drill pipe screens when ever pumping.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	2,570	279,732	70,283	2,276,271	83.3%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	2,570	279,732	70,283	2,276,271	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
30-Oct 02:00 at Depth 2903.0																
8.65	62		2	21	14		4	12	81.6	0.25		5	9	12	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Barite - 1500 MT	2	632	Barofibre -	15	478

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
2903.0	2906.0	4.00	6.00	4	8	80	80	6500	7000	200	200	2100

Annular Velocity: **Drill Collars:** 41.50 **Drill Pipe:** 62.90

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 30 **Report for 06:00 AM 30-Oct-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 136000 **Pick Up:** 147000 **Slack Off:** 121000 **Drag Avg/Max:** 6000 / 12000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	950 psi	75 spm	1120 psi	spm	psi	
Pump 2:	68 spm	550 psi	75 spm	760 psi	spm	psi	

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	122.0	**Casing:**	121.0	22.5
Total:	122.0			
Jars:	122.0			

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
4	1	HYC	DSX 516 M	6.000	2903.0	3.0	1	3.00	5.00	8	80	6500	8.60	200	2100	27	59	7	24

Jets: 15 15 15 13 13 Out: 3296.0 Grade: Cutter: -2 / 6 Dull: VT / WT Wear: S Brgs: X Gge: 1 Pull: FM

BHA - No. 5 - BIT, MMTR, FS, MWD, 17 HWDP, JAR, 4 HWDP = 215.89

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2903.0	2906.0		2784.0											

Lithology: No samples up before report time

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.	
Shaker No 1:	210	210	210	**Desander:**		
Shaker No 2:	210	210	210	**Desilter:**		
Shaker No 3:	210	210	210	**Degasser:**		
Shaker No 4:				**Centrifuge No 1:**	3	Solids Removal
				Centrifuge No 2:		Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	1831		19741			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 29

Accident Description: No accidents or incidents to report

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meetings. Topic discussed.Forklift operations . Slip and trip hazards

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: overcast **Visibility:**

Air Temperature: 18.0 degC **Bar. Pressure:**

Wind Speed/Dir: 5 / SE **Wind Gusts:** 5

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 31 **Report for 06:00 AM 31-Oct-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	2992.0	**Drilling Days:**	26	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2863.0	**Days On Location:**	31	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	86.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	24.0	**Average ROP:**	3.58	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 6 **Total:** 38

Current Operations: drill from 2906 meter's to 2992 meter's at 0600 am.

Planned Operations: drill to csg point , short trip as needed

Toolpusher: Mike preston / Steve John

Wellsite Supervisors: Wallace Suire **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:00	24.00	2992	DRIL	drill from 2906 meter's to 2992 meter's at 0600 am.

Comments

slide drill = 2 ,1/2 hour's
21 , 1/2 hour's = rotate drill

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	3,433	283,165	71,846	2,348,117	86.0%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	3,433	283,165	71,846	2,348,117	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
31-Oct 02:00 at Depth 2975.0																
8.65	62		2	22	21		4.8	11.8	81.2	0.25		8	13	17	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
RM 63 -	1	674	Barite - 1500 MT	2	632
Lime -	40	349	Barofibre -	10	319

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
2906.0	2992.0	6.00	18.00	6	10	80	105	6000	7000	202	202	2300

Annular Velocity: **Drill Collars:** 112.30 **Drill Pipe:** 63.50

Comments: rotate drill

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 139 **Pick Up:** 155 **Slack Off:** 128 **Drag Avg/Max:** 10 / 20

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	58 spm	740 psi	68 spm	1100 psi
Pump 2:	67 spm	640 psi	75 spm	760 psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	145.5	**Casing:** 144.5	0.0
Total:	145.5		
Jars:	145.5		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	2822.1	18.90	S 44.86 E	2704.6	698	-502.2	S 502.22	E 484.38	0.000
MWD	2850.5	18.31	S 44.7400	2731.4	707	-508.6	S 508.64	E 490.76	0.626
MWD	2879.1	19.21	S 49.9299	2758.5	716	-514.9	S 514.86	E 497.52	1.989

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 31 **Report for 06:00 AM 31-Oct-05**

MWD	2915.6	21.16	S 49.8200	2792.8	728	-523.0	S 522.98	E 507.15	1.603
MWD	2944.2	21.73	S 49.7599	2819.4	739	-529.7	S 529.72	E 515.13	0.599
MWD	2972.1	21.26	S 49.06 E	2845.4	749	-536.4	S 536.39	E 522.91	0.574

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
4	1	HYC	DSX 516 M	6.000	2903.0	89.0	25	3.56	18.00	7	185	7500	8.60	202	2300	27	60	7	24

Jets: 15 15 15 13 13 Out: 3296.0 Grade: Cutter: -2 / 6 Dull: VT / WT Wear: S Brgs: X Gge: 1 Pull: FM

BHA - No. 5 - BIT, MMTR, FS, MWD, 17 HWDP, JAR, 4 HWDP = 215.89

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2906.0	2992.0	2784.0	2863.0	15	25	2995	25	20	0	0.00	9	0	10.0	2.0

Lithology: sandstone/ claystone / siltstone / and limestone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	Desander:	
Shaker No 2:	210	210	210	Desilter:	
Shaker No 3:	210	210	210	Degasser:	
Shaker No 4:				Centrifuge No 1:	6 Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	2132		17609			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 30

Accident Description: none reported

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition:	clear/cold	**Visibility:**	5
Air Temperature:	59.0 degC	**Bar. Pressure:**	0
Wind Speed/Dir:	0 / 0	**Wind Gusts:**	0

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 32 **Report for 06:00 AM 01-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	3054.0	**Drilling Days:**	27	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2922.0	**Days On Location:**	32	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	62.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	24.0	**Average ROP:**	2.58	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 6 **Total:** 38

Current Operations: drill from 2992m to 3054m sliding and rotating .GPM 202, WOB 8-10k, ROP 2-3m/hr avg, Torque 6-9000 ft/bls, Max gas 1.03 units, Pump 5 bbls sweeps as required.

Planned Operations: drill to csg point , short trip as needed

Toolpusher: Mike preston / Steve John

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:30	1.50	2995	DRILR	Continue drill 6" hole Rotating to 2995m
7:30	8:00	0.50	2993	DRILS	Contnue to drill 6" hole to 2996m sliding Very hard formation unable to make progress
8:00	10:00	2.00	3002	DRILR	Continue to drill 6" hole to 3002m Rotating.ROP 2-3m/hr
10:00	12:00	2.00	3005	DRILS	Continue to drill 6" hole to 3005m sliding .
12:00	0:00	12.00	3047	DRILR	Continue drill 6" hole to 3047m rotating. GPM 202, WOB 5-12, SPM 125 = 2200psi. Torque 8-9000 ft/bls
0:00	6:00	6.00	3054	DRILR	Continue to drill 6" to 30544m Rotating . GPM 202, WOB 8-10k. Torque 8-9000 ft/bls.ROP 1-2m/hr , Very hard siltstone stringers . Pump 5 bbbls sweeps as required.

Comments

Continue drill 6" hole , Clean out cellar.
Continue to pump 5 bbls sweeps as required.
Ditch magnet 67 grams. wash pipe 386.5 hrs, Jars 169 hrs,

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	3,496	286,661	39,310	2,387,427	87.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	3,496	286,661	39,310	2,387,427	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
01-Nov 02:00 at Depth 3037.0																
8.70	63		2	22	19		4.8	10	83.2	0.25		7	13	15	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	6	866	RM 63 -	1	674
Barofibre -	10	319	Calcium chloride 25 kg bag -	5	52
BARACARB 150 -	10	125			

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
2992.0	3054.0	2.50	5.00	8	12	80	80	6500	9000	202	202	2250

Annular Velocity: Drill Collars: 41.90 **Drill Pipe:** 63.50

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 142000 **Pick Up:** 157000 **Slack Off:** 130000 **Drag Avg/Max:** 12000 / 15000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	58 spm	740 psi	68 spm	1100 psi	spm	psi	
Pump 2:	67 spm	640 psi	75 spm	760 psi	spm	psi	

BHA Rotate Hrs **Rotate Hrs** **Trip Hrs**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 32 **Report for 06:00 AM 01-Nov-05**

Since Inspection:	169.5	**Casing:**	16.5	11.0
Total:	169.5			
Jars:	169.5			

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	3000.5	20.97	S 47.08 E	2871.8	759	-543.2	S 543.21	E 530.51	0.815
MWD	3029.7	21.95	S 46.7899	2899.0	770	-550.5	S 550.50	E 538.31	1.013

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Pump Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
4	1	HYC	DSX 516 M	6.000	2903.0	151.0	49	3.08	6.00	8	80	6500	8.70	202	2250	27	61	7	24

Jets: 15 15 15 13 13 Out: 3296.0 Grade: Cutter: -2 / 6 Dull: VT / WT Wear: S Brgs: X Gge: 1 Pull: FM

BHA - No. 5 - BIT, MMTR, FS, MWD, 17 HWDP, JAR, 4 HWDP = 215.89

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2922.0	3054.0		3054.0	57	39	3014					9			

Lithology: 20% claystone , 70% siltstone , 10% sandstone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Location Condition: Continue general housekeeping.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	210	210	210
Shaker No 2:	210	210	210
Shaker No 3:	210	210	210
Shaker No 4:			

Equipment Usage:	Hrs.	
Desander:		
Desilter:		
Degasser:		
Centrifuge No 1:	7	Solids Removal
Centrifuge No 2:		Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	3837		13772			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 31

Accident Description: No accidents or incidents to report.

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meetings . Topic discussed . New crew first day back.Good handovers

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition:	clear	**Visibility:**	5
Air Temperature:	59.0 degC	**Bar. Pressure:**	0
Wind Speed/Dir:	5 / ESE	**Wind Gusts:**	7

Comments: Fine clear conditions.

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 33 **Report for 06:00 AM 02-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	3115.0	**Drilling Days:**	28	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2978.0	**Days On Location:**	33	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	61.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	24.0	**Average ROP:**	2.54	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 2 **Total:** 34

Current Operations: Continue to drill 6" hole rotating. GPM 200, WOB 5/12k, Torque 6/7000 ft/lbs, mas gas 58 units, ROP 2-3m/hr. Pump sweeps as required.

Planned Operations: Continue to drill 6" hole to target depth.

Toolpusher: Mike preston / Steve John

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	0:00	18.00	3105	DRLR	Continue drill 6" hole to 3105m. ROP 2.8m/hr,GPM 200, RPM 70/90, Torque 6/7000 ft/bls,
0:00	6:00	6.00	3115	DRLR	Continue drill 6" hole to 3115m . ROP 1.6m/hr,GPM 200, RPM 70/90, WOB 5-12k, Torque 6/7000 ft/bls.SPM 125 =2100psi.Max gas 58 units at 3074m

Comments

Continue to pump kcl sweeps to assist in prevention of bit balling.
Ditch magnet 162 grams 24 hr period.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	1,460	288,121	45,786	2,433,213	89.1%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	1,460	288,121	45,786	2,433,213	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
02-Nov 02:00 at Depth 3098.0																
8.70	66		2	23	18		5	10	83	0.25		7	12	15	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
3054.0	3115.0	2.54	5.00	8	12	80	90	6500	7000	200	200	2150

Annular Velocity: **Drill Collars:** 41.50 **Drill Pipe:** 62.90

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 144000 **Pick Up:** 161000 **Slack Off:** 131000 **Drag Avg/Max:** 17000 / 18000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	60 spm	880 psi	70 spm	1100 psi
Pump 2:	66 spm	600 psi	75 spm	850 psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	193.5	**Casing:** 40.5	11.0
Total:	193.5		
Jars:	193.5		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	3057.9	22.13	S 46.12 E	2925.2	781	-557.8	S 557.80	E 545.99	0.329
MWD	3086.2	22.18	S 44.67 E	2951.4	791	-565.3	S 565.30	E 553.59	0.582

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 33 **Report for 06:00 AM 02-Nov-05**

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
4	1	HYC	DSX 516 M	6.000	2903.0	212.0	73	2.90	5.00	8	80	6500	8.70	200	2100	27	59	7	24

Jets: 15 15 15 13 13 Out: 3296.0 Grade: Cutter: -2 / 6 Dull: VT / WT Wear: S Brgs: X Gge: 1 Pull: FM

BHA - No. 5 - BIT, MMTR, FS, MWD, 17 HWDP, JAR, 4 HWDP = 215.89

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3054.0	3115.0		2978.0	40	58	3074					9			

Lithology: 90% claystone /10% sandstone.

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Location Condition: Continue general maintainence.
Clear area for drilling conductor.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	210	210	210
Shaker No 2:	210	210	210
Shaker No 3:	210	210	210
Shaker No 4:			

Equipment Usage:	Hrs.
Desander:	
Desilter:	
Degasser:	
Centrifuge No 1:	8 Solids Removal
Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	3689		10083			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 32

Accident Description: No accidents or incidents to report

Meetings/Drills	Time	Description
Safety:	30	Held2 x pre tour safety meeting. Topic discussed ,Mixing chemicals, stowing chemicals,MSDS sheeys.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: overcast **Visibility:**

Air Temperature: 18.0 degC **Bar. Pressure:**

Wind Speed/Dir: 2 / E **Wind Gusts:** 5

Comments: Overcast with intermitant showers.

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 34 **Report for 06:00 AM 03-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	3172.0	**Drilling Days:**	29	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	3032.0	**Days On Location:**	34	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	57.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	24.0	**Average ROP:**	2.38	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 2 **Total:** 34

Current Operations: Continue to drill 6" hole to 3172m. GPM 200, WOB 7/12k , ROP 2.53 m/hr, Torque 7/9000 ft/bls, Pump 5 bbls sweep as required.

Planned Operations: Wiper trip continue to drill 6" hole.

Toolpusher: Mike preston / Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	0:00	18.00	3158	DRILR	Continue to drill 6' hole to 3158m.Pumping sweeps as required.
0:00	6:00	6.00	3172	DRILR	Continue to drill 6" hole to 3172m ,GPM 200, WOB 6/12k, Torque 7/9000 ft/bls, SPM 125 = 2250 psi. MW 8.65 ,VIS 69 ,

Comments

Continue to sweep hole as required.
Mckee sands not at propsoed depth TVD 3021m , Possible Mckee sands at TVD 2927m 94m high.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	4,144	292,264	44,437	2,477,649	90.7%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	4,144	292,264	44,437	2,477,649	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
03-Nov 02:00 at Depth 3138.0																
8.70	68		2	23	18		5	10.5	82.5	0.25		7	12	15	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	12	1,731	Barofibre -	15	478
Lime -	40	349	BARACARB 25 -	10	125

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
3115.0	2172.0	2.53	3.00	8	12	80	90	7000	9000	200	200	2250

Annular Velocity: **Drill Collars:** 41.50 **Drill Pipe:** 62.90

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 144000 **Pick Up:** 162000 **Slack Off:** 131000 **Drag Avg/Max:** 14000 / 18000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	60 spm	880 psi	70 spm	1100 psi
Pump 2:	66 spm	600 psi	75 spm	850 psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	217.5	**Casing:** 64.5	11.0
Total:	217.5		
Jars:	217.5		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	3115.0	21.89	S 41.69 E	2978.1	802	-573.2	S 573.18	E 560.99	1.203
MWD	3143.8	21.05	S 38.42 E	3004.9	813	-581.2	S 581.23	E 567.76	1.525

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 34 **Report for 06:00 AM 03-Nov-05**

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
4	1	HYC	DSX 516 M	6.000	2903.0	269.0	97	2.77	5.00	8	80	7000	8.65	200	2250	27	59	7	24

Jets: 15 15 15 13 13 Out: 3296.0 Grade: Cutter: -2 / 6 Dull: VT / WT Wear: S Brgs: X Gge: 1 Pull: FM

BHA - No. 5 - BIT, MMTR, FS, MWD, 17 HWDP, JAR, 4 HWDP = 215.89

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3115.0	3172.0		3032.0	24	30	3120					9			

Lithology: 95% claystone, 5% sandstone with minor traces siltstone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Location Condition: Continue general housekeeping.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	210	210	210
Shaker No 2:	210	210	210
Shaker No 3:	210	210	210
Shaker No 4:			

Equipment Usage:	Hrs.	
Desander:		
Desilter:		
Degasser:		
Centrifuge No 1:	10	Solids Removal
Centrifuge No 2:		Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	3878		6205			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 33

Accident Description: No accidents and incidents

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meeting.Topic discussed .Pinch points ,communication,

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: overcast **Visibility:**

Air Temperature: 20.0 degC **Bar. Pressure:**

Wind Speed/Dir: 2 / ENE **Wind Gusts:** 5

Comments: overcast no rain predicted

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 35 **Report for 06:00 AM 04-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	3195.0	**Drilling Days:**	30	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	3053.5	**Days On Location:**	35	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	23.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	20.0	**Average ROP:**	1.15	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 2 **Total:** 34

Current Operations: Continue to drill 6" hole to 3195m .GPM 200. RPM 80/90, Torque 6/8000 ft/bls, ROP 1-1.2 m/hr.

Planned Operations: Continue to drill 6" hole to target depth.

Toolpusher: Mike preston / Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	10:30	4.50	3182	DRILR	Continue drill to 3182m Rotating
10:30	11:30	1.00	3182	CIRC	Pump 10 bbls sweep and circulate clean
11:30	12:00	0.50	3182	OTHER	Take survey ,Flow check 10mins (static), Pump slug
12:00	13:00	1.00	2840	WIPE	TRPO to 2840 last old hole .hole good correct displacement.
13:00	13:30	0.50	2840	SERV	Rig service .circulate while performing rig service
13:30	14:00	0.50	3161	WIPE	TRPI to 3161m no hang ups.
14:00	14:30	0.50	3182	WASH	Wash down f/-3161m to 3182m No fill .
14:30	17:00	2.50	3182.5	DRILS	Continue drill 6" hole sliding to 3182.5m Unable to slide due to formation ROP .2m/hr
17:00	0:00	7.00	3189	DRILR	Continue to drill 6" hole to 3189m . ROP .9-1m/h
0:00	6:00	6.00	3195	DRILR	Continue to drill 6"hole to 3195m .GPM 200, RPM 60-90,SPM 125= 2300psi WOB 5-12k ,Torque 6/8000 ft/lbs.ROP 1m/hr.Pump 5 bbls kcl sweeps as required

Comments

Pump 5 bbls sweeps as required.
New cellar arrived on site . earth moving equipment arrive on site in preparation for installing new cellar.
Paleontologist arrived on site .observed we are in the marine zone which indicates we are still in the otaraoa above the Mckee.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	2,862	295,127	25,693	2,503,342	91.7%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	2,862	295,127	25,693	2,503,342	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
04-Nov 02:00 at Depth 3186.0																
8.75	76		2	27	21		5.6	10.5	82	0.25		8	14	19	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
RM 63 -	1	674	Barofibre -	15	478
BARACARB 150 -	10	125	BARACARB 25 -	10	125

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
3172.0	3195.0	1.00	1.50	8	12	80	90	6500	8000	200	200	2300

Annular Velocity: **Drill Collars:** 41.50 **Drill Pipe:** 62.90

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 35 **Report for 06:00 AM 04-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 144000 **Pick Up:** 164000 **Slack Off:** 131000 **Drag Avg/Max:** 20000 / 22000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	60 spm	880 psi	70 spm	1100 psi	spm	psi	
Pump 2:	66 spm	600 psi	75 spm	850 psi	spm	psi	

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	236.5	**Casing:** 83.0	16.0
Total:	236.5		
Jars:	236.5		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	3172.5	20.63	S 35.83 E	3031.7	823	-589.4	S 589.38	E 573.93	1.057

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
4	1	HYC	DSX 516 M	6.000	2903.0	292.0	116	2.52	3.00	8	80	6500	8.70	200	2300	27	59	7	24

Jets: 15 15 15 13 13 Out: 3296.0 Grade: Cutter: -2 / 6 Dull: VT / WT Wear: S Brgs: X Gge: 1 Pull: FM

BHA - No. 5 - BIT, MMTR, FS, MWD, 17 HWDP, JAR, 4 HWDP = 215.89

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3172.0	3195.0		3053.0	23	39	3182					9			

Lithology: 100% claystone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: Rig service

Location Condition: General housekeeping

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	9 Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			6205			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 34

Accident Description:

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour meetings.Topics discussed. Drilling into unknown formations.MSDS Sheets.

☐ **BOP Test** ☑ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 35 **Report for 06:00 AM 04-Nov-05**

Weather

Sky Condition:	overcast	**Visibility:**	
Air Temperature:	20.0 degC	**Bar. Pressure:**	
Wind Speed/Dir:	5 / SSW	**Wind Gusts:**	10

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 36 **Report for 06:00 AM 05-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	3245.0	**Drilling Days:**	31	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	3099.0	**Days On Location:**	36	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	50.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	24.0	**Average ROP:**	2.08	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 2 **Total:** 34

Current Operations: Continue to drill 6" hole rotary. GPM 200,WOB 5/8k. Back ground gas 15 units.ROP 2.4m/hr, Torque 6/7000 ft/bls

Planned Operations: Continue to drill 6" hole to target.

Toolpusher: Mike preston / Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	0:00	18.00	3223	DRILR	Continue drill 6" hole to 3223m Rotating ,ROP 1.4m/hr avg.
0:00	6:00	6.00	3245	DRILR	Continue to drill 6" hole to 3245m. ROP 3.6m/hr avg. rop increased at 3225m max 18m/hr.Formation change to siltstone.,GPM 200,WOB 4-9k, Torque 6/7000 ft/bls. SPM 125=2400psi.

Comments

Drilling ROP increase 3225m. Formation changed to Siltstone.
Continue to pump kcl sweeps.
Losses nil. ditch magnet 60g 24hr period.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	3,276	298,403	49,456	2,552,799	93.5%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	3,276	298,403	49,456	2,552,799	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
05-Nov 02:00 at Depth 3201.0																
8.70	75		2	27	19		4.8	12	81	0.25		8	14	18	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	8	1,154	Barite - 1500 MT	1	316
BARACARB 150 -	20	250	Barofibre -	3	96

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
3195.0	3245.0	2.00	15.00	7	9	80	85	6500	7000	200	200	2400

Annular Velocity: Drill Collars: 41.50 **Drill Pipe:** 62.90

Comments: ROP picked up at 3225m. Formation to siltstone.

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 146000 **Pick Up:** 165000 **Slack Off:** 133000 **Drag Avg/Max:** 18000 / 20000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	60 spm	880 psi	70 spm	1100 psi	spm	psi
Pump 2:	66 spm	600 psi	75 spm	850 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	260.5	**Casing:** 107.0	16.0
Total:	260.5		
Jars:	260.5		

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 36 **Report for 06:00 AM 05-Nov-05**

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	3201.1	19.54	S 32.14 E	3058.6	832	-597.5	S 597.51	E 579.43	1.753
MWD	3229.8	18.80	S 28.9299	3085.7	841	-605.6	S 605.62	E 584.21	1.347

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
4	1	HYC	DSX 516 M	6.000	2903.0	342.0	140	2.44	15.00	8	200	6500	8.70	200	2400	27	59	7	24

Jets: 15 15 15 13 13 Out: 3296.0 Grade: Cutter: -2 / 6 Dull: VT / WT Wear: S Brgs: X Gge: 1 Pull: FM

BHA - No. 5 - BIT, MMTR, FS, MWD, 17 HWDP, JAR, 4 HWDP = 215.89

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3195.0	3245.0		3099.0	13	25	3212					9			

Lithology: 15% claystone, 85% siltstone.

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Location Condition: Conitinue general housekeeping

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	Desander:	
Shaker No 2:	210	210	210	Desilter:	
Shaker No 3:	210	210	210	Degasser:	
Shaker No 4:				Centrifuge No 1:	10 Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	7355.9	22722.9	21572			

Truck/Boat Status: Recieved 1 x 40ft flatdeck mud chemicals.
Recieved diesel fuel.

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 35

Accident Description: No accidents or incidents to report.

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meetings,Topic discussed.Working aroound third party equipment.Buddy system. Confined space entry permits.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Overcast **Visibility:**

Air Temperature: 25.0 degC **Bar. Pressure:**

Wind Speed/Dir: 5 / S **Wind Gusts:** 10

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 37 **Report for 06:00 AM 06-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	3296.0	**Drilling Days:**	32	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	3149.0	**Days On Location:**	37	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	51.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	12.5	**Average ROP:**	4.08	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 11 **Other:** 2 **Total:** 35

Current Operations: M/up rotary BHA and TRPI.

Planned Operations: Continue drill 6" hole f/- 3296m

Toolpusher: Mike preston / Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	11:00	5.00	3268	DRILR	Continue drill 6" hole rotating to 3268m. Attempt connection very tight.
11:00	11:30	0.50	3268	CIRC	Pump sweep and circulate. work pipe through coal seam until free.
11:30	19:00	7.50	3296	DRILR	Continue drill 6" hole to 3296m .Working through all drilling breaks .Attempt connection at 3296m .tight hole coal seam.
19:00	20:00	1.00	3296	REAM	Backream 3296 to 3295m 15k overpull well packing off.Pump sweep and circulate while working pipe free. 100% coal at shaker on bottoms up.
20:00	22:00	2.00	3296	CIRC	Pump 10bbls sweep and circulate clean . Excessive cutting /caving over shakers
22:00	0:00	2.00	2311	TRPO	Flow check .pump slug .TRPO to 7" casing shoe. hole in good condition
0:00	3:30	3.50	215	TRPO	Flow check at 7" casing shoe (static). Continue TRPO to BHA 215m.Condition active with 4 bpb barablok to held with coal seams.
3:30	5:30	2.00	10	TOHBHA	Continue TOHBHA. layout jar. MWD, Mud motor ,Bit.
5:30	6:00	0.50	25	TIHBHA	P/UP Bit,bit sub. 2 x 4 3/4 DC.

Comments

Bearing retainer on mud motor broken of and still on motor.
100% coal at 3294.5m to 3296m 100% coal .very sticky ,well packing off.tight hole.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	4,169	302,572	44,646	2,597,444	95.1%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	4,169	302,572	44,646	2,597,444	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
06-Nov 02:00 at Depth 3296.0																
8.80	81		2	29	18		5.5	12	80.5	0.25		7	14	19	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	6	866	BARABLOK -	27	863
Barite - 1500 MT	2	632	BARACARB 150 -	15	188
Barofibre -	5	159			

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
3245.0	3296.0	3.90	5.00	6	8	80	80	6500	7000	200	200	2400

Annular Velocity: Drill Collars: 111.20 **Drill Pipe:** 62.90

Comments: Coal seam at 3294.5- 3296.8. 100% coal

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 37 **Report for 06:00 AM 06-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 146000 **Pick Up:** 167000 **Slack Off:** 133000 **Drag Avg/Max:** /

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	60 spm	880 psi	70 spm	1100 psi	spm	psi	
Pump 2:	66 spm	600 psi	75 spm	850 psi	spm	psi	

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	273.0	**Casing:**	120.0	22.0
Total:	273.0			
Jars:	273.0			

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	3258.7	18.55	S 27.7100	3113.1	850	-613.8	S 613.77	E 588.61	0.481

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
4	1	HYC	DSX 516 M	6.000	2903.0	393.0	152	2.59	3.00	8	80	6500	8.80	200	2400	25	54	6	23
Jets:	15	15	15	13	13	Out: 3296.0		Grade:	Cutter:	-2 / 6	Dull: WT / WT		Wear: S		Brgs: X	Gge: 1		Pull: FM	
5	1	HYC	DSX 413M-	6.000	3296.0														
Jets:	15	15	15	15		Out: 3370.0		Grade:	Cutter:	1 / 1	Dull: NO / NO		Wear:		Brgs: X	Gge:		Pull: TD	

BHA - No. 6 - BIT, BS, 2 DC, 6 HWDP, JAR, 15 HWDP = 224.33

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3245.0	3296.0		3149.0	25	50	3262					9			

Lithology: 85% coal. 15% siltstone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Location Condition: Continue housekeeping

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210		**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	8 Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	3684		17888			

Truck/Boat Status: 1 x 40ft flatdeck delivered 4 3/4 drilling jar (GJ Sole)

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 37 **Report for 06:00 AM 06-Nov-05**

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 36

Accident Description: No accidents or incidents to report

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meeting.Topic discussed. SBM mud. Mixing chemicals.MSDS. Lifting techiques.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Clear **Visibility:**

Air Temperature: 18.0 degC **Bar. Pressure:**

Wind Speed/Dir: 2 / ESE **Wind Gusts:** 5

Comments: Fine clear conditions

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 38 **Report for 06:00 AM 07-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	3370.0	**Drilling Days:**	33	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:		**Days On Location:**	38	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	74.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	11.5	**Average ROP:**	6.43	**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 2 **Contractor:** 22 **Service:** 8 **Other:** 2 **Total:** 34

Current Operations: Drilled f/- 3297m to section TD 3370m. Circ B/up after TD 3370m.

Planned Operations: POOH to old hole, RIH to TD. Spot 10bbl pill on bottom for logging. POOH to above pill & pump heavy slug. POOH to surface. R/up Schlumberger to log.

Toolpusher: Mike preston / Ian Haughey

Wellsite Supervisors: Nathan Peri Wayne Stonnell **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:00	1.00	224	TIHBHA	RIH w/- BHA & break circ @ 224m.
7:00	11:30	4.50	2377	TRPI	RIH w/- drill pipe to 2377m.
11:30	12:00	0.50	2377	SERV	Conduct full rig service.
12:00	13:00	1.00	2377	CIRC	Circ. B/up & condition mud w/- Bareblok
13:00	15:00	2.00	3266	TRPI	Con't RIH f/- 2377m to 3266m. (fill pipe every 25 stands)
15:00	16:00	1.00	3297	REAM	Wash & ream f/- 3266m to 3297m. (1m fill)
16:00	17:00	1.00	3297	CIRC	Circ B/up (gas peak 5.2%)
17:00	4:30	11.50	3370	DRIL	Drill 6" hole f/- 3297m to 3370m (TD)
4:30	6:00	1.50	370	CIRC	Circulate bttms up w/ low/hi vis sweeps.

Comments

TD hole 3,370mMD @ 04:20hrs 7th Nov 05.
Ahuroa Thrust 3320MD, 3171m TVD. (prognosed 3360m MD)

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	3,729	306,301	62,533	2,659,977	97.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	3,729	306,301	62,533	2,659,977	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
07-Nov 02:00 at Depth 3316.0																
8.80	98		2	30	20		5.8	12	80	0.25		9	17	23	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
BARABLOK -	35	1,119	Saraline 185 -	6	866
Barofibre -	5	159	BARACARB 150 -	10	125

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
3296.0	3370.0	10.00	10.00	9	9	200	200	7	9	202	202	1900

Annular Velocity: **Drill Collars:** 112.30 **Drill Pipe:** 63.50

Comments: TD well 3370m.

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 38 **Report for 06:00 AM 07-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 150 **Pick Up:** 173 **Slack Off:** 133 **Drag Avg/Max:** /

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	60 spm	880 psi	70 spm	1100 psi	spm	psi	
Pump 2:	66 spm	600 psi	75 spm	850 psi	spm	psi	

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	12.0	**Casing:** 132.0	38.0
Total:	285.0		
Jars:	12.0		

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
5	1	HYC	DSX 413M-	6.000	3296.0	74.0	11.5	6.43	9.00	8	200	7	8.80	202	1900	29	69	8	26

Jets: 15 15 15 15 Out: 3370.0 Grade: Cutter: 1 / 1 Dull: NO / NO Wear: Brgs: X Gge: Pull: TD

BHA - No. 6 - BIT, BS, 2 DC, 6 HWDP, JAR, 15 HWDP = 224.33

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3296.0	3370.0	3149.0	3218.0	15	41	3295	0	255	0		9		8.3	

Lithology:

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	210	210	210
Shaker No 2:	210	210	210
Shaker No 3:	210	210	210
Shaker No 4:			

Equipment Usage:	Hrs.	
Desander:	0	
Desilter:	0	
Degasser:	0	
Centrifuge No 1:	0	Solids Removal
Centrifuge No 2:	0	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	2303		15585			
BAR 1.5T		16	16			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 37

Accident Description: No accidents or incidents to report

Meetings/Drills	Time	Description
Safety:	1	2 x Pre tour meetings. Discuss drilling through coal seams.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Fine / Overcast **Visibility:**

Air Temperature: degC **Bar. Pressure:**

Wind Speed/Dir: / **Wind Gusts:**

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 39 **Report for 06:00 AM 08-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	3370.0	**Drilling Days:**	34	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	3281.0	**Days On Location:**	39	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 5 **Other:** 2 **Total:** 29

Current Operations: Circulate at 7" casing shoe

Planned Operations: Set cement kick of plug

Toolpusher: Lindsay Baker/ Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:00	1.00	3370	WIPE	Flow check TRPO to 3297m. good hole TRPI to 3370m no fill.
7:00	8:00	1.00	3370	CIRC	Pump 10 bbls sweep and circulate clean
8:00	8:30	0.50	3370	CIRC	Spot 10 bbls high vis on bottom.
8:30	10:00	1.50	3036	TRPO	Flow check TRPO to 3036m wet. no overpull. pump slug at 3036m
10:00	16:00	6.00	215	TRPO	Continue to TRPO to BHA .
16:00	16:30	0.50	0	TOHBHA	TOHBHA Layout bit ,bit sub.
16:30	17:00	0.50	0	LOG	Held job safety meeting prior to rigging up Schlumberger surface equipment.Rig up surface equipment
17:00	18:00	1.00	0	LOG	Prepare run#1 PEX,BHC,AIT. Load radioactive sources.
18:00	22:00	4.00	3370	LOG	RIH with run# 1log up f/- 3370 to 2402m 7" casing .Continue to log up to surface .Schlumberger W/L MD 3374m. Monitor well via trip tank while logging.
22:00	22:30	0.50	0	LOG	Unload radio active sources.Lay out schlumberger tools.
22:30	23:00	0.50	0	LOG	Lay out schlumberger surface equipment.
23:00	1:00	2.00	146	TRPI	Rig up 2 7/8 handling equipment. M/up mule shoe and p/up 2 7/8 cement stinger f/- catwalk.TRPI to 146m
1:00	5:00	4.00	2375	TRPI	Change out to 3 1/2 handling equipment and TRPI w/- 3 1/2 DP to 2395m
5:00	5:30	0.50	2375	SERV	Rig service
5:30	6:00	0.50	2375	CIRC	Circululate and condition well while analyze logs.

Comments

Pre job meeting prior to loading radio active sources w/- wireline .

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
	No AFE Assigned				0	0	
051203	Dry Hole Cost	2,731,110	3,960	310,261	31,376	2,691,353	98.5%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	3,960	310,261	31,376	2,691,353	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
08-Nov 02:00 at Depth 3370.0																
8.85	92		2	31	20		5.8	12	80		0.25	8	16	20	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Saraline 185 -	14	2,020
Barite - 1500 MT	1	316	BARACARB 150 -	8	100
BARABLOK -	2	64	Mud Storage Tanks -	2	60

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
3371.0	3370.0											

Comments: No drilling , wireline operation

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 39 **Report for 06:00 AM 08-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** **Pick Up:** **Slack Off:** **Drag Avg/Max:** /

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	60 spm	880 psi	70 spm	1100 psi	spm	psi
Pump 2:	66 spm	600 psi	75 spm	850 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	12.0	**Casing:** 132.0	146.0
Total:	285.0		
Jars:	12.0		

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
5	1	HYC	DSX 413M-	6.000	3296.0	74.0	11.5	6.43	8.00	8	80	6500	8.70	200	2450	28	67	8	26

Jets: 15 15 15 15 Out: 3370.0 Grade: Cutter: 1 / 1 Dull: NO / NO Wear: Brgs: X Gge: Pull: TD

BHA - No. 6 - BIT, BS, 2 DC, 6 HWDP, JAR, 15 HWDP = 224.33

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3370.0	3370.0													

Lithology: No drilling activity

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: Remove modules from M/Pump # 1 and send to town for repair

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	2114		13471			
BAR 1.5T			16			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 38

Accident Description: No accidents or incidents to report

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meeting .Topic discussed. Tripping pipe .wireline operations.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: overcast **Visibility:**

Air Temperature: degC **Bar. Pressure:**

Wind Speed/Dir: 2 / SE **Wind Gusts:** 5

Comments: Ovecast with showers

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 40 **Report for 06:00 AM 09-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	3370.0	**Drilling Days:**	35	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	3281.0	**Days On Location:**	40	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 4 **Other:** 2 **Total:** 28

Current Operations: WOO.Cirulate and condition mud

Planned Operations: Cement kick off plug

Toolpusher: Lindsay Baker/ Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description	Non-Prod
6:00	6:00	24.00	0	WOO	Circulate and condition well while wait on cement plug details.	X

Comments

Continue rig maintanance.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
	No AFE Assigned				0	0	
051203	Dry Hole Cost	2,731,110	1,460	311,721	-4,169	2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019					0.0%
	Totals $:	4,658,904	1,460	311,721	-4,169	2,687,184	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
09-Nov 02:00 at Depth 3370.0																
8.85	88		2	30	20		5.9	12	80	0.25		8	17	23	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
3370.0	3370.0											

Comments: No drilling activity

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: **Pick Up:** **Slack Off:** **Drag Avg/Max:** /

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	60 spm	880 psi	70 spm	1100 psi	spm	psi
Pump 2:	66 spm	600 psi	75 spm	850 psi	spm	psi

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	285.0	**Casing:**	132.0	146.0
Total:	285.0			
Jars:	12.0			

BHA Information

BHA - No. 6 - BIT, BS, 2 DC, 6 HWDP, JAR, 15 HWDP = 224.33

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3370.0	3370.0										9			

Lithology: No drilling activity

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: Rig mud pump # 1 Modules in town for repair

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 40 **Report for 06:00 AM 09-Nov-05**

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	Desander:	
Shaker No 2:	210	210	210	Desilter:	
Shaker No 3:	210	210	210	Degasser:	
Shaker No 4:				Centrifuge No 1:	Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	1536		11935			
BAR 1.5T			16			

Truck/Boat Status: 1 x 40ft flat deck picked up schlumberger tools. (G J Sole)

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 39

Accident Description: No aciidents or incidents to report.

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meetings. Topics discussed. Working at heights, Routine safety checks of PPE equipment.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Clear **Visibility:**

Air Temperature: 21.0 degC **Bar. Pressure:**

Wind Speed/Dir: 2 / SE **Wind Gusts:** 2

Comments: Fine clear day

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 41 **Report for 06:00 AM 10-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	3370.0	**Drilling Days:**	36	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	3281.0	**Days On Location:**	41	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 4 **Other:** 2 **Total:** 28

Current Operations: Trouble shoot well head problem

Planned Operations: Test BOP'S and drill clean out well to KOP

Toolpusher: Lindsay Baker/ Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description	Non-Prod
6:00	12:00	6.00	0	WOO	WOO.	X
12:00	13:00	1.00	2526	TRPI	TRPI to 2526m and circulate while mixing mix water,spacer and prepare for cement job (kick off plug)	
13:00	13:30	0.50	2526	CIRC	Continue to mix mix water and spacers..Hold pre job safety meeting .Rig up surface lines.	
13:30	14:00	0.50	2526	CMTPL	Pump 10 bbbls spacer .test surface lines to 3000 psi ok.Continue pump remaining 20bbls spacer.	
14:00	15:00	1.00	2526	CMTPL	Pump 21.6 bbls 17.2 ppg Class G cement @ 3.6 bpm.Pump 6.3 bbls tail spacer.Displace balanced plug with 41.6 bbls 8.7ppg OBM. Check for flow back .OK.	
15:00	16:30	1.50	2242	TRPI	TRPO f/- 2526m to 2242m .Install wiper sponge and circulate 2 x bottoms up. Slight cement contaminated at bttms/up.	
16:30	20:30	4.00	2000	LDDP	TRPO laying out 104 jnts 3 1/2 DP.	
20:30	22:30	2.00	1000	TRPO	Continue TRPO with 3 1/2 DP to 146m	
22:30	0:30	2.00	0	LDDP	Lay out 2 7/8 tubing	
0:30	1:00	0.50	0	OTHER	Retrieve wear bushing	
1:00	2:00	1.00	0	BOPT	Hold pre tour safety meeting prior to rigging up test lines Drain stack set test plug..Fill stack .Test surface lines to 5000 psi.ok. Attempt test # 1 annular .leaking past test plug seal. Drill crew member closed annulus valve.	
2:00	6:00	4.00	0	REPR	Bled of pressure on annulus test.Unseated Test plug lifted string and bent kelly.Trouble shoot open annulus valve .reset test plug .Bypassing test plug.Unable to get test.Drain stack check test plug profile. Junk observed flush well head . Prepare RTTS packer to isolate well bore to enable lifting stack.	X

Comments

Drill crew member closed B section valve prior to pressure testing . Test leaked past test plug hydraulicing test plug and bending kelly.
* Start of the Ahuroa Sth B1 Sidetrack.
** Total Cost of Original Hole = 2,687,184.00

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
	No AFE Assigned					0	
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	1,776	1,776	34,136	34,136	3.8%
	Totals $:	4,658,904	1,776	313,497	34,136	2,721,320	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
10-Nov 02:00 at Depth 2381.0																
8.90	108		2	31	26		5.6	16	76	0.25	3	10	17	25		

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Barite - 1500 MT	1	316			

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 41 **Report for 06:00 AM 10-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: **Pick Up:** **Slack Off:** **Drag Avg/Max:** /

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	60 spm	880 psi	70 spm	1100 psi	spm	psi
Pump 2:	66 spm	600 psi	75 spm	850 psi	spm	psi

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	285.0	**Casing:**	132.0	146.0
Total:	28.0			
Jars:	12.0			

BHA Information

BHA - No. 6 - BIT, BS, 2 DC, 6 HWDP, JAR, 15 HWDP = 224.33

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3370.0	3370.0													

Lithology: No drilling activity .monitor trip tank.

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: During testing BOP operation drill crew member closed B section valve . Test leaked past test plug pressuring up annulus. Bled of and kelly.hydraulicing test plug up and bending kelly.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	Barite Recovery
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	1551.9	10767.9	21151			
BAR 1.5T			16			

Truck/Boat Status: Recieved 10767.9 ltrs diesel fuel.

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 40

Accident Description: no accidents or incidents to reports

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meetings.Topic Discussed.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Fine **Visibility:**

Air Temperature: 21.0 degC **Bar. Pressure:**

Wind Speed/Dir: 2 / ESE **Wind Gusts:** 2

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 41 **Report for 06:00 AM 10-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3430.0	**State:**	TKI
Measured Depth:	3370.0	**Drilling Days:**	36	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	3281.0	**Days On Location:**	41	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3430.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	23-Oct-05	**Well Bore:**	Original Well Bore

Personnel: Operator: 1 **Contractor:** 21 **Service:** 4 **Other:** 2 **Total:** 28

Current Operations: Trouble shoot well head problem

Planned Operations: Test BOP'S and drill clean out well to KOP

Toolpusher: Lindsay Baker/ Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description	Non-Prod
6:00	12:00	6.00	0	WOO	WOO.	X
12:00	13:00	1.00	2526	TRPI	TRPI to 2526m and circulate while mixing mix water,spacer and prepare for cement job (kick off plug)	
13:00	13:30	0.50	2526	CIRC	Continue to mix mix water and spacers..Hold pre job safety meeting .Rig up surface lines.	
13:30	14:00	0.50	2526	CMTPL	Pump 10 bbbls spacer .test surface lines to 3000 psi ok.Continue pump remaining 20bbls spacer.	
14:00	15:00	1.00	2526	CMTPL	Pump 21.6 bbls 17.2 ppg Class G cement @ 3.6 bpm.Pump 6.3 bbls tail spacer.Displace balanced plug with 41.6 bbls 8.7ppg OBM. Check for flow back .OK.	
15:00	16:30	1.50	2242	TRPI	TRPO f/- 2526m to 2242m .Install wiper sponge and circulate 2 x bottoms up. Slight cement contaminated at bttms/up.	
16:30	20:30	4.00	2000	LDDP	TRPO laying out 104 jnts 3 1/2 DP.	
20:30	22:30	2.00	1000	TRPO	Continue TRPO with 3 1/2 DP to 146m	
22:30	0:30	2.00	0	LDDP	Lay out 2 7/8 tubing	
0:30	1:00	0.50	0	OTHER	Retrieve wear bushing	
1:00	2:00	1.00	0	BOPT	Hold pre tour safety meeting prior to rigging up test lines Drain stack set test plug..Fill stack .Test surface lines to 5000 psi.ok. Attempt test # 1 annular .leaking past test plug seal. Drill crew member closed annulus valve.	
2:00	6:00	4.00	0	REPR	Bled of pressure on annulus test.Unseated Test plug lifted string and bent kelly.Trouble shoot open annulus valve .reset test plug .Bypassing test plug.Unable to get test.Drain stack check test plug profile. Junk observed flush well head . Prepare RTTS packer to isolate well bore to enable lifting stack.	X

Comments

Drill crew member closed B section valve prior to pressure testing . Test leaked past test plug hydraulicing test plug and bending kelly.
* Start of the Ahuroa Sth B1 Sidetrack.
** Total Cost of Original Hole = 2,687,184.00

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
	No AFE Assigned					0	
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	1,776	1,776	34,136	34,136	3.8%
	Totals $:	4,658,904	1,776	313,497	34,136	2,721,320	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
10-Nov 02:00 at Depth 2381.0																
8.90	108		2	31	26		5.6	16	76	0.25	3	10	17	25		

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Barite - 1500 MT	1	316			

Daily Drilling Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Report No: 41 **Report for 06:00 AM 10-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** **Pick Up:** **Slack Off:** **Drag Avg/Max:** /

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	60 spm	880 psi	70 spm	1100 psi	spm	psi
Pump 2:	66 spm	600 psi	75 spm	850 psi	spm	psi

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	285.0	**Casing:**	132.0	146.0
Total:	28.0			
Jars:	12.0			

BHA Information

BHA - No. 6 - BIT, BS, 2 DC, 6 HWDP, JAR, 15 HWDP = 224.33

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3370.0	3370.0													

Lithology: No drilling activity .monitor trip tank.

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: During testing BOP operation drill crew member closed B section valve . Test leaked past test plug pressuring up annulus. Bled of and kelly.hydraulicing test plug up and bending kelly.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	Barite Recovery
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	1551.9	10767.9	21151			
BAR 1.5T			16			

Truck/Boat Status: Recieved 10767.9 ltrs diesel fuel.

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 40

Accident Description: no accidents or incidents to reports

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meetings.Topic Discussed.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Fine **Visibility:**

Air Temperature: 21.0 degC **Bar. Pressure:**

Wind Speed/Dir: 2 / ESE **Wind Gusts:** 2

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 1 **Report for 06:00 AM 10-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	3370.0	**Drilling Days:**	36	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	3281.0	**Days On Location:**	41	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**		**Well Bore:**	Side Track

Personnel: Operator: 1 **Contractor:** 21 **Service:** 4 **Other:** 2 **Total:** 28

Current Operations: Trouble shoot well head problem

Planned Operations: Test BOP'S and drill clean out well to KOP

Toolpusher: Lindsay Baker/ Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description	Non-Prod
6:00	12:00	6.00	0	WOO	WOO.	X
12:00	13:00	1.00	2526	TRPI	TRPI to 2526m and circulate while mixing mix water,spacer and prepare for cement job (kick off plug)	
13:00	13:30	0.50	2526	CIRC	Continue to mix mix water and spacers..Hold pre job safety meeting .Rig up surface lines.	
13:30	14:00	0.50	2526	CMTPL	Pump 10 bbbls spacer .test surface lines to 3000 psi ok.Continue pump remaining 20bbls spacer.	
14:00	15:00	1.00	2526	CMTPL	Pump 21.6 bbls 17.2 ppg Class G cement @ 3.6 bpm.Pump 6.3 bbls tail spacer.Displace balanced plug with 41.6 bbls 8.7ppg OBM. Check for flow back .OK.	
15:00	16:30	1.50	2242	TRPI	TRPO f/- 2526m to 2242m .Install wiper sponge and circulate 2 x bottoms up. Slight cement contaminated at bttms/up.	
16:30	20:30	4.00	2000	LDDP	TRPO laying out 104 jnts 3 1/2 DP.	
20:30	22:30	2.00	1000	TRPO	Continue TRPO with 3 1/2 DP to 146m	
22:30	0:30	2.00	0	LDDP	Lay out 2 7/8 tubing	
0:30	1:00	0.50	0	OTHER	Retrieve wear bushing	
1:00	2:00	1.00	0	BOPT	Hold pre tour safety meeting prior to rigging up test lines Drain stack set test plug..Fill stack .Test surface lines to 5000 psi.ok. Attempt test # 1 annular .leaking past test plug seal. Drill crew member closed annulus valve.	
2:00	6:00	4.00	0	REPR	Bled of pressure on annulus test.Unseated Test plug lifted string and bent kelly.Trouble shoot open annulus valve .reset test plug .Bypassing test plug.Unable to get test.Drain stack check test plug profile. Junk observed flush well head . Prepare RTTS packer to isolate well bore to enable lifting stack.	X

Comments

Drill crew member closed B section valve prior to pressure testing . Test leaked past test plug hydraulicing test plug and bending kelly.
* Start of the Ahuroa Sth B1 Sidetrack.
** Total Cost of Original Hole = 2,687,184.00

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110	311,721	311,721	2,687,184	2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	1,776	1,776	34,136	34,136	3.8%
	Totals $:	4,658,904	313,497	313,497	2,721,320	2,721,320	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
10-Nov 02:00 at Depth 2381.0																
8.90	108		2	31	26		5.6	16	76	0.25	3	10	17	25		

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Barite - 1500 MT	1	316			

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 1 **Report for 06:00 AM 10-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** **Pick Up:** **Slack Off:** **Drag Avg/Max:** /

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	60 spm	880 psi	70 spm	1100 psi	spm	psi
Pump 2:	66 spm	600 psi	75 spm	850 psi	spm	psi

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	285.0	**Casing:**	132.0	146.0
Total:	28.0			
Jars:	12.0			

BHA Information

BHA - None

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3370.0	3370.0													

Lithology: No drilling activity .monitor trip tank.

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: During testing BOP operation drill crew member closed B section valve . Test leaked past test plug pressuring up annulus. Bled of and kelly.hydraulicing test plug up and bending kelly.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	Barite Recovery
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	1551.9	10767.9	21151			
BAR 1.5T			16			

Truck/Boat Status: Recieved 10767.9 ltrs diesel fuel.

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 40

Accident Description: no accidents or incidents to reports

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meetings.Topic Discussed.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Fine **Visibility:**

Air Temperature: 21.0 degC **Bar. Pressure:**

Wind Speed/Dir: 2 / ESE **Wind Gusts:** 2

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 2 **Report for 06:00 AM 11-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	2400.0	**Drilling Days:**	37	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2314.0	**Days On Location:**	42	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	-970.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 1 **Contractor:** 21 **Service:** 4 **Other:** 2 **Total:** 28

Current Operations: TRPO and m/up Directional assy

Planned Operations: Kick off sidetrack at 2400m

Toolpusher: Lindsay Baker/ Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description	Non-Prod
6:00	6:30	0.50	0	REPR	Trouble shoot BOP problem. ok.	X
6:30	13:00	6.50	0	BOPT	Test BOP as per Parker drilling procedure. 250psi low 5 mins/ 5000psi high 10mins. Annular 250 low 5mins/3000psi high 10mins. ok.	
13:00	14:00	1.00	0	BOPO	Install wear bushing and lock down.	
14:00	15:30	1.50	224	TIHBHA	M/up rotary BHA anfd TIHBHA to 224m	
15:30	16:30	1.00	800	TRPI	TRPI with 3 1/2 dp to 800m,	
16:30	19:00	2.50	800	REPR	Layout bent 3 1/2 kelly and install new 3 1/2 kelly.	X
19:00	22:30	3.50	2356	TRPI	Continue to TRPI with 3 1/2 dp to 2356m Tag cement.	
22:30	0:30	2.00	2400	CMTD	Drill out cement f/- 2356m to 2400m . Cement firm. GPM 175,RPM 40,WOB 4/5k.	
0:30	3:00	2.50	2400	CIRC	Circulate and condition well bore to 8.5 ppg.	
3:00	6:00	3.00	1200	TRPO	Flowcheck (static) TRPO. 750m @ 06:00 hrs	

Comments

Change out bent kelly.
Drill out cement to 2400m . Cement firm .
Prepare directional equipment .

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	2,323	4,099	28,750	62,887	6.9%
	Totals $:	4,658,904	2,323	315,820	28,750	2,750,071	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
11-Nov 02:00 at Depth 2400.0																
8.60	112		2	29	22		4.7	15.5	77.4	0.25	3.2	9	17	24		

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
BDF-303 -	2	863			

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
2356.0	2400.0	15.00	22.00	5	5	40	40	3500	4000	175	175	1300

Annular Velocity: **Drill Collars:** 97.30 **Drill Pipe:** 55.00

Comments: Drill out cement to 2400m

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 2 **Report for 06:00 AM 11-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 115000 **Pick Up:** 125000 **Slack Off:** 103000 **Drag Avg/Max:** /

☑ **Wear Bushing Installed**

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	287.0	**Casing:**	134.0	152.0
Total:	287.0			
Jars:	14.0			

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
6	1	HTC	XR PS	6.000	2385.0	44.0	2	22.00	22.00	5	40		8.50	175	1300	7	4	0	6

Jets: 32 32 32 Out: 2400.0 Grade: Cutter: 2 / 2 Dull: VT / WT Wear: A Brgs: 0 Gge: 1 Pull: BHA

BHA - No. 7 - BIT, BS, 2 DC, 6 HWDP, JAR, 15 HWDP = 224.33

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2356.0	2400.0		2314.0								9			

Lithology: Drill out cement

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: Replaced bent kelly.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	210	210	210
Shaker No 2:	210	210	210
Shaker No 3:	210	210	210
Shaker No 4:			

Equipment Usage:	Hrs.	
Desander:		
Desilter:		
Degasser:		
Centrifuge No 1:	9	Solids Removal
Centrifuge No 2:		Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	1920		19231			
BAR 1.5T	2		14			

Truck/Boat Status: 1 x 40 ft flat deck delicered sperry directional equipment.
1 x ute delivered bit breaker.

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 41

Accident Description: No incidents or accidents to reoport.

Meetings/Drills **Time** **Description**

Safety: 30 Held 2 x pre tour safety meetings. Topics discussed. BOP testing. Mixing chemicals.

☑ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: clear **Visibility:**

Air Temperature: degC **Bar. Pressure:**

Wind Speed/Dir: 5 / NW **Wind Gusts:** 10

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 3 **Report for 06:00 AM 12-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	2411.0	**Drilling Days:**	38	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	2315.0	**Days On Location:**	43	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	11.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	12.0	**Average ROP:**	0.92	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 3 **Total:** 35

Current Operations: Continue to drill 6" hole sliding to kick off cement plug. 30% Formation at 06:00 hrs.

Planned Operations: Drill 6" hole to target.

Toolpusher: Lindsay Baker/ Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description	Non-Prod
6:00	8:00	2.00		TOHBHA	POOH BHA, Lay out 2 HWDP.	
8:00	9:00	1.00		TIHBHA	P/U Motor w/- 1.5 deg bend. 117 bit. Install MWD probe.	
9:00	10:00	1.00		TIHBHA	P/U 2 HWDP and run BHA f/- mast.	
10:00	10:30	0.50		OTHER	Test MWD.	
10:30	13:00	2.50		REPS	No pulse observed during testing of MWD. POOH and Change Probe. (orifice upside down) RIH test okay.	X
13:00	17:30	4.50		TRPI	RIH.	
17:30	18:00	0.50	2400	REAM	P/U kelly, check MWD, tag cement plug. Orientate.	
18:00	6:00	12.00	2411	DRLS	Directional Drill Time drilling f/- 2400m to 2411m. GPM 203, WOB 4-6k, SPM 125=1980 psi.	

Comments

Time drill to Kick off f/- 2400.
Pump sweeps as required.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	27,732	31,831	59,941	122,827	13.5%
	Totals $:	4,658,904	27,732	343,552	59,941	2,810,011	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
12-Nov 02:00 at Depth 2424.0																
8.50	108		2	22	16		4.3	15.5	78		2.6	9	20	26		

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
BDF-303 -	1	432	Barite - 1500 MT	1	316
SOBM credit - bbls	782.4	-78,240	SOBM RECEIVED - bbls	782	78,200
Saraline 185 -	122	17,602	MEG -	5	3,990
BDF-303 -	3	1,295	Geltone II -	25	1,171
BDF-352 -	1	683	condet - 55 Gal Drum	1	493
BARACARB 150 -	18	225	Lime -	12	105

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
2400.0	2411.0	0.90	1.00	3	4					200	203	1980

Annular Velocity: Drill Collars: 111.20 **Drill Pipe:** 62.90

Comments: Continue to time drill to kick of well

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 3 **Report for 06:00 AM 12-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 115000 **Pick Up:** 125000 **Slack Off:** 110000 **Drag Avg/Max:** /

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	1040 psi	75 spm	1100 psi	spm	psi	
Pump 2:	68 spm	650 psi	75 spm	700 psi	spm	psi	

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	299.5	**Casing:**	134.0	160.0
Total:	299.5			
Jars:	26.5			

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
6	1	HTC	XR PS	6.000	2385.0	45.0	2	22.50											
Jets:	32	32	32		Out: 2400.0			Grade:	Cutter:	2 / 2	Dull:VT / WT		Wear: A		Brgs: 0		Gge: 1		Pull: BHA
7	1	SMITH	XR+	6.000	2400.0	11.0	12.5	0.88	1.00	4			8.50	203	1980	27	58	7	24
Jets:	18	18	18		Out: 2433.0			Grade:	Cutter:	1 / 1	Dull:NO / NO		Wear:		Brgs: 1		Gge: 1		Pull: BHA

BHA - No. 8 - BIT, MWD, STAB, FS, MWD, 15 HWDP, JAR, 6 HWDP = 217.88

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2400.0	2411.0		2315.0								9			

Lithology: 30% FORMATION (Silstone) 70% Cement

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	Barite Recovery
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	2188		17043			
BAR 1.5T		7	21			

Truck/Boat Status: Recieved 1 x truck base oil/1 x 40 ft flatdeck with mud chemicals

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 42

Accident Description: No incidents or accidents to report

Meetings/Drills	Time	Description
Safety:	30	2 x pre tour safety meeting.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Clear **Visibility:**

Air Temperature: degC **Bar. Pressure:**

Wind Speed/Dir: 1 / SE **Wind Gusts:** 2

Comments: Fine clear day

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 3 **Report for 06:00 AM 12-Nov-05**

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 4 **Report for 06:00 AM 13-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	2428.0	**Drilling Days:**	39	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2331.0	**Days On Location:**	44	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	17.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	24.0	**Average ROP:**	0.71	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 1 **Contractor:** 20 **Service:** 10 **Other:** 2 **Total:** 33

Current Operations: Continue to drill 6" hole sliding to 2428m,GPM 202,WOB 4-8k, ROP .7-1m/hr, Pump sweeps as required.No conclusive surveys to report.

Planned Operations: Continue to drill with mill tooth 117 bit +/- 40hrs . TPRO for bit change.

Toolpusher: Lindsay Baker/ Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	0:00	18.00	2425	DRILS	Continue to time drill to 2425m. 95% formation.ROP 1mhr ,WOB 2-3k.
0:00	6:00	6.00	2428	DRILS	Continue to drill 6" hole to 2428m 95% formation . Slow ROP .5m/hr . Work sting and pump 5 bbls sweeps as required. GPM 202, WOB 6-8k.

Comments

Continue to Kick off. slow ROP due to fomation .7-1m/hr.
No conclusive surveys to report.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	6,021	37,852	44,391	167,218	18.4%
	Totals $:	4,658,904	6,021	349,573	44,391	2,854,402	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
13-Nov 02:00 at Depth 2424.0																
8.50	75		2	23	19		4.1	14.5	79	0.25	2.8	7	14	18	37.0	37.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	26	3,751	condet - 55 Gal Drum	1	493
Barite - 1500 MT	1	316			

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
2411.0	2428.0	0.70	1.00	4	8					200	205	2880

Annular Velocity: Drill Collars: 41.50 **Drill Pipe:** 62.90

Comments: Continue to slide drill to kick off cement plug

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 116000 **Pick Up:** 125000 **Slack Off:** 110000 **Drag Avg/Max:** 7000 / 9000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	1040 psi	75 spm	1100 psi	spm	psi
Pump 2:	68 spm	650 psi	75 spm	700 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	323.5	**Casing:** 134.0	160.0
Total:	323.5		
Jars:	50.5		

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
7	1	SMITH	XR+	6.000	2400.0	28.0	36.5	0.77	1.00	5	139		8.50	200	2880	26	56	7	23
Jets:	18	18	18		Out: 2433.0			Grade:	Cutter:	1 / 1	Dull: NO / NO		Wear:		Brgs: 1		Gge: 1		Pull: BHA

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 4 **Report for 06:00 AM 13-Nov-05**

BHA - No. 8 - BIT, MWD, STAB, FS, MWD, 15 HWDP, JAR, 6 HWDP = 217.88

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2411.0	2428.0		2331.0	20		2418					9			

Lithology: 100% claystone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Location Condition: Continue general housekeeping

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	Desander:	
Shaker No 2:	210	210	210	Desilter:	
Shaker No 3:	210	210	210	Degasser:	
Shaker No 4:				Centrifuge No 1:	4 Solids Removal
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	2962		14081			
BAR 1.5T			21			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 43

Accident Description: No accidents or incidents to report.

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meeting.Topic discussed.Mixing SBM,Forklift operations.

☐ **BOP Test** ☑ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 5 **Report for 06:00 AM 14-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	2491.0	**Drilling Days:**	40	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2389.0	**Days On Location:**	45	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	63.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	11.5	**Average ROP:**	5.48	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 2 **Total:** 34

Current Operations: Continue to drill 6" hole to 2491m .GPM 200,RPM 80,WOB 4-6k, Torque 6/7000 ft/bls, ROP 4-16 m/hr. Pump sweeps as required.

Planned Operations: Continue to drill 6" sliding and rotating ,.

Toolpusher: Lindsay Baker/ Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:00	1.00	2433	DRILR	Continue to drill 6" hole to 2433m. Check shot survey .inclination and azimuth not on track. Building angle instead of dropping.
7:00	8:30	1.50	2433	CIRC	Pump sweep and circulate and condition mud prior to TRPO to change bit and check BHA.
8:30	12:30	4.00	225	TRPO	Flow check (static) Pump slug and TRPO to BHA.
12:30	13:00	0.50	0	TOHBHA	Flow check at BHA .continue to TOHBHA. lay out MWD probe and L/out 6" Mill tooth bit.
13:00	14:30	1.50	225	TIHBHA	M/up New MWD Probe ,6" DSX519 PDC BIT AND TIHBHA to 225m
14:30	17:30	3.00	2395	TRPI	Test MWD OK. Continue TRPI to 2395m.Filling pipe @798,2395m
17:30	18:30	1.00	2395	CUTDL	Slip and cut 72ft drilling line
18:30	19:00	0.50	2395	SERV	Rig Service
19:00	19:30	0.50	2428	WASH	Continue TRPI to 2400m wash down f/-2400m to 2428m No fill
19:30	21:00	1.50	2442	DRILS	Continue drill 6" hole sliding to 2442m
21:00	22:30	1.50	2451	DRILR	Continue drill 6" hole Rotating to 2451m
22:30	0:00	1.50	2457	DRILS	Continue drill 6" hole Sliding to 2457m. ROP 5m/hr.
0:00	6:00	6.00	2492	DRILR	Continue drill 6" hole Sliding first 5m of single then rotate the rest. ROP Sliding 5/6m/hr Rotating 14/16m/hr.

Comments

Continue to drill 6" hole sliding and rotating .
Prepare sound walls to erect.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	2,142	39,994	58,274	225,492	24.8%
	Totals $:	4,658,904	2,142	351,715	58,274	2,912,676	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
14-Nov 02:00 at Depth 2455.0																
8.50	84		2	23	20		4.4	14	79.2	0.25	2.8	8	17	23	39.0	39.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
BDF-303 -	1	432	BARACARB 150 -	20	250

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
2428.0	2491.0	6.00	16.00	4	6	80	80	6000	7000	200	200	2200

Annular Velocity: **Drill Collars:** 41.50 **Drill Pipe:** 62.90

Comments: Drill sliding and rotating

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 5 **Report for 06:00 AM 14-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 118000 **Pick Up:** 130000 **Slack Off:** 107000 **Drag Avg/Max:** 10000 / 12000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	1040 psi	75 spm	1100 psi	spm	psi
Pump 2:	68 spm	650 psi	75 spm	700 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	333.5	**Casing:** 144.0	167.0
Total:	333.5		
Jars:	60.5		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Side Track									
** TieIn	2422.0	21.91	S 45.4600	2325.7	569	-409.0	S 408.97	E 395.62	
MWD	2431.1	22.88	S 46.1499	2334.2	572	-411.4	S 411.40	E 398.12	3.295
MWD	2450.3	20.66	S 45.4299	2352.0	580	-416.4	S 416.35	E 403.21	3.503
MWD	2469.3	18.66	S 44.6000	2369.9	586	-420.9	S 420.87	E 407.74	3.183

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
7	1	SMITH	XR+	6.000	2400.0	28.0	36.5												
Jets:	18	18	18		Out: 2433.0			Grade:	Cutter:	1 / 1	Dull: NO / NO		Wear:		Brgs: 1		Gge: 1		Pull: BHA
8	1	HYC	DSX 519S	6.000	2433.0	63.0	10.5	6.00	16.00	6	80	6500	8.50	202	2200	26	57	7	23
Jets:	14	14	14	14	14	Out: 2874.0		Grade:	Cutter:	3 / 4	Dull: NT / NO		Wear: S		Brgs: X		Gge: 6		Pull: OTH

BHA - No. 8 - BIT, MWD, STAB, FS, MWD, 15 HWDP, JAR, 6 HWDP = 217.88

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2428.0	2491.0		2389.0	0		2479					9			

Lithology: 100% Claystone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Location Condition: Continue general housekeeping

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	210	210	210
Shaker No 2:	210	210	210
Shaker No 3:	210	210	210
Shaker No 4:			

Equipment Usage:	Hrs.
Desander:	
Desilter:	
Degasser:	
Centrifuge No 1:	4 Solids Removal
Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	3076		11005			
BAR 1.5T			21			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 5 **Report for 06:00 AM 14-Nov-05**

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 44

Accident Description: No accidents or incidents to report.

Meetings/Drills	Time	Description
Safety:	30	held 2 x pre our safety meeting. Topic discussed. Tripping pipe, Unloading third party trucks.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: overcast **Visibility:**

Air Temperature: 20.0 degC **Bar. Pressure:**

Wind Speed/Dir: 5 / ENE **Wind Gusts:** 5

Comments: Overcast with showers

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 6 **Report for 06:00 AM 15-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	2616.0	**Drilling Days:**	41	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2513.0	**Days On Location:**	46	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	125.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	24.0	**Average ROP:**	5.21	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 2 **Total:** 34

Current Operations: Continue to drill 6" hole sliding and rotaing. Pump sweeps as required. Work connections twice. 36 units back ground gas .

Planned Operations: Continue to drill 6" hole to target depth.

Toolpusher: Lindsay Baker/ Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	0:00	18.00	2581	DRILR	Continue to drill 6" hole sliding and rotating to 2581m ROP 5-7m/hr,
0:00	6:00	6.00	2616	DRILR	Continue to drill 6" hole sliding and rotating to 2616m. ROP 5-6m/hr,GPM 201,4/6000 ft/bls, WOB 8/10k.Pump sweeps as required.

Comments

Continue drill 6" hole sliding and rotating.GPM 202,RPM 80, Torque 5/7000ft/lbs, Pump sweeps as required.No drag on connections.
36 units max back ground gas.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	1	39,995	33,771	259,263	28.5%
	Totals $:	4,658,904	1	351,716	33,771	2,946,447	

Mud Information

							%					Gels			Temp	
Density	Vis	Filt.	Cake	PV	YP	pH	Solids	Water	Oil	Sand	Chloride	10s	10m	30m	In	Out
15-Nov 02:00 at Depth 2566.0																
8.50	70		2	24	15		4.6	14	79	0.25	2.6	8	15	26	40.0	40.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	6	866			

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
2491.0	2616.0	5.20	15.00	6	10	80	80	6500	7000	200	200	2100

Annular Velocity: Drill Collars: 41.50 **Drill Pipe:** 62.90

Comments: Continue drill 6" hole sliding and rotating.

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 127000 **Pick Up:** 140000 **Slack Off:** 116000 **Drag Avg/Max:** 12000 / 13000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	1100 psi	75 spm	1180 psi	spm	psi
Pump 2:	66 spm	640 psi	75 spm	700 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	346.0	**Casing:** 156.5	167.0
Total:	236.0		
Jars:	84.5		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Side Track									
MWD	2487.3	16.44	S 42.83 E	2387.0	591	-424.8	S 424.78	E 411.48	3.818
MWD	2506.3	13.88	S 43.31 E	2405.3	596	-428.4	S 428.42	E 414.88	4.041

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 6 **Report for 06:00 AM 15-Nov-05**

MWD	2525.4	11.29	S 43.64 E	2424.0	601	-431.4	S 431.43	E 417.74	4.076
MWD	2544.6	8.66	S 41.36 E	2442.9	604	-433.9	S 433.88	E 419.99	4.157
MWD	2563.7	6.61	S 39.67 E	2461.8	606	-435.8	S 435.81	E 421.64	3.234
MWD	2582.6	4.82	S 35.64 E	2480.7	608	-437.3	S 437.29	E 422.80	2.902

Bit Information

					Depth	This Run		ROP					Mud	Pump				
No	Run	Make	Model	Diam	In	Dist.	Hrs	Avg	Max	WOB	RPM	Torq	Wt	Flow	Press	J. Vel	P.Drp	HHP	JIF
8	1	HYC	DSX 519S	6.000	2433.0	188.0	34.5	5.45	15.00	8	80	6500	8.50	200	2100	26	55	6	23

Jets: 14 14 14 14 14 Out: 2874.0 Grade: Cutter: 3 / 4 Dull: NT / NO Wear: S Brgs: X Gge: 6 Pull: OTH

BHA - None

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2491.0	2616.0		2513.0	18	36	2517					9			

Lithology: 100% claystone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Location Condition: Install sound walls around rig.
Continue general house keeping

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	Desander:	
Shaker No 2:	210	210	210	Desilter:	
Shaker No 3:	210	210	210	Degasser:	
Shaker No 4:				Centrifuge No 1:	5 Solids Removal
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			11005			
BAR 1.5T			21			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 45

Accident Description: No accidents or incidents to report.

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meetings. Topic discussed, New crews first day back keep focused. Crane and forklift operations.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Clear **Visibility:**

Air Temperature: degC **Bar. Pressure:**

Wind Speed/Dir: 2 / SE **Wind Gusts:** 5

Comments: Fine clear day

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 7 **Report for 06:00 AM 16-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	2721.0	**Drilling Days:**	42	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2618.0	**Days On Location:**	47	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	105.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	24.0	**Average ROP:**	4.38	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 2 **Total:** 34

Current Operations: Continue to drill 6" hole sliding and rotating . GPM 200, RPM 80, Toque 6/7000 ft/bls, WOB 8/10k,Pump 5 bbls sweeps as required.Back ground gas 25/40 units.

Planned Operations: Continue to drill 6" hole sliding and rotating to target.

Toolpusher: Lindsay Baker/ Ian Haughey

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	0:00	18.00	2703	DRIL	Continue to drill 6" hole rotating and sliding to 2703m . ROP 4.8m/hr. Pump 5 bbls sweeps as required
0:00	6:00	6.00	2721	DRIL	Continue to drill 6" hle sliding and rotating to 2721m. 3m/hr.GPM 202,Torque 5/7000 ft/bs, SPM 125=2200psi, WOB 8/10k.

Comments

Drill into tariki formation at 2667m MD ,2570m TVD.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	5,629	45,623	34,665	293,928	32.3%
	Totals $:	4,658,904	5,629	357,344	34,665	2,981,112	

Mud Information

							%					Gels			Temp	
Density	**Vis**	**Filt.**	**Cake**	**PV**	**YP**	**pH**	**Solids**	**Water**	**Oil**	**Sand**	**Chloride**	**10s**	**10m**	**30m**	**In**	**Out**
16-Nov 02:00 at Depth 2698.0																
8.60	68		2	23	13		4.8	14	78.8	0.25	2.2	8	16	22	44.0	44.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
BARACARB 150 -	20	250	BARACARB 25 -	60	751
Barite - 1500 MT	2	632	Calcium chloride 25 kg bag -	20	210

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	**To**	**Avg**	**Max**	**Avg**	**Max**	**Avg**	**Max**	**Avg**	**Max**	**Avg**	**Max**	**PSI**
2616.0	2721.0	4.30	6.00	8	10	80	90	6500	7000	200	200	2200

Annular Velocity: Drill Collars: 41.50 **Drill Pipe:** 62.90

Comments: Continue drill 6" hole sliding and rotating

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 133000 **Pick Up:** 144000 **Slack Off:** 116000 **Drag Avg/Max:** 9000 / 11000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	1100 psi	75 spm	1180 psi
Pump 2:	66 spm	640 psi	75 spm	700 psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	356.0	**Casing:** 166.5	167.0
Total:	356.0		
Jars:	108.5		

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 7 **Report for 06:00 AM 16-Nov-05**

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
** TieIn	0.0	0.00	N 0 E	0.0		0.0			
TOTCO	33.0	1.00	N 0 E	33.0	0	0.3	N 0.29		0.909
TOTCO	100.0	1.00							
TOTCO	145.0	1.00							
TOTCO	195.0	1.00							
** TieIn	210.0	1.56	N 54 W	210.0	4	2.0	N 2.04	E 2.78	
MWD	238.6	1.86	N 48.81 W	238.5	3	2.6	N 2.57	E 2.12	0.354
MWD	266.8	1.24	N 60.5 W	266.7	3	3.0	N 3.03	E 1.51	0.736
Side Track									
MWD	2601.0	2.51	S 39.8999	2499.0	609	-438.2	S 438.23	E 423.51	3.798
MWD	2620.0	0.18	S 35.3500	2518.0	610	-438.6	S 438.57	E 423.80	3.680
MWD	2639.6	2.09	N 56.4899	2537.6	610	-438.4	S 438.40	E 423.52	3.457
MWD	2658.5	3.84	N 56.4800	2556.5	609	-437.9	S 437.86	E 422.70	2.776
MWD	2677.6	6.06	N 55.6099	2575.5	607	-436.9	S 436.94	E 421.34	3.494
MWD	2706.2	7.30	N 57.72 W	2603.9	604	-435.1	S 435.11	E 418.55	1.323

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
8	1	HYC	DSX 519S	6.000	2433.0	293.0	58.5	5.01	8.00	8	80	6500	8.60	200	2200	26	56	7	23

Jets: 14 14 14 14 14 Out: 2874.0 Grade: Cutter: 3 / 4 Dull: /T / NO Wear: S Brgs: X Gge: 6 Pull: OTH

BHA - None

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2616.0	2721.0		2618.0	25	68	2669					9			

Lithology: 2600m-2710m 100% claystone
Last sample 90% sandstone ,10% claystone.

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Location Condition: Continue general housekeeping

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	210	210	210
Shaker No 2:	210	210	210
Shaker No 3:	210	210	210
Shaker No 4:			

Equipment Usage:	Hrs.
Desander:	
Desilter:	
Degasser:	
Centrifuge No 1:	4 Solids Removal
Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	4296	14221	20930			
BAR 1.5T	3		18			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 7 **Report for 06:00 AM 16-Nov-05**

Safety Information

First Aid:	0	**Medical:**	0	**Lost Time Accidents:**	0	**Days Since LTA:**	46

Accident Description: No accients or incidents to report

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meeting. Topic Discussed. Handling SBM. Hand tool operations.

☐ **BOP Test** ☑ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 8 **Report for 06:00 AM 17-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	2768.0	**Drilling Days:**	43	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2666.0	**Days On Location:**	48	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	47.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	21.5	**Average ROP:**	2.19	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 3 **Contractor:** 21 **Service:** 10 **Other:** 14 **Total:** 48

Current Operations: Drilling 6" hole sliding & rotating. GPM-200, RPM-80, WOB-8/10k, Torque-6/7000 ft/lbs, Av ROP-5 m/hr.

Planned Operations: Drill 6" side track to section TD in slide/rotate mode.

Toolpusher: Lindsay Baker / Ian Haughey

Wellsite Supervisors: Troy Reid Wayne Stonnell **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	10:00	4.00	2727	DRILS	Slide 6" hole f/- 2721m to 2727m. WOB 6/8, GPM 198, m/hr 1.6
10:00	15:00	5.00	2742	DRILR	Rotate 6" hole f/- 2719m to 2742m. WOB 8/10, GPM 198, RPM 80, m/hr 2.6
15:00	16:00	1.00	2742	STRIP	Flow check, POOH f/- 2742m to shoe.
16:00	16:30	0.50	2742	SERV	Full rig service & adjust brake.
16:30	17:30	1.00	2742	STRIP	RIH f/- shoe to 2726m, wash down last single to 2742m.
17:30	22:00	4.50	2751	DRILR	Con't rotate 6" hole f/- 2742m to 2751. WOB 8/10, GPM 200, RPM 80, m/hr 2
22:00	0:00	2.00	2755	DRILS	Slide 6" hole f/- 2751m to 2755m. WOB 5/10, GPM 200, m/hr 2.
0:00	1:00	1.00	2756	DRILR	Rotate 6" hole f/- 2755m to 2756m. WOB 8/10, GPM 200, RPM 80, m/hr 1
1:00	3:00	2.00	2760	DRILS	Slide 6" hole f/- 2756m to 2760m. WOB 5/10, GPM 200, m/hr 2.
3:00	6:00	3.00	2768	DRILR	Rotate 6" hole f/- 2760m to 2768m. WOB 8/10, GPM 200, RPM 80, m/hr 2.5.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	96,412	142,035	122,236	416,163	45.7%
	Totals $:	4,658,904	96,412	453,756	122,236	3,103,347	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
17-Nov 02:00 at Depth 2751.0																
8.65	71		2	23	14		5	14	78.6	0.25	2.3	8	18	22	44.0	44.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	112	16,159	MEG -	3	2,394
BDF-303 -	3	1,295	BDF-352 -	1	683
BARACARB 150 -	37	463	Barite - 1500 MT	1	316
Geltone II -	4	187	Lime -	7	61

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
2719.0	2768.0	5.00		6	10	80	80	6000	7000	198	200	2200

Annular Velocity: Drill Collars: 110.00 **Drill Pipe:** 63.00

Comments: Drill in slide & rotate mode. Ditch magnets = 40 grms

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 8 **Report for 06:00 AM 17-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 134000 **Pick Up:** 150000 **Slack Off:** 120000 **Drag Avg/Max:** 16000 / 18000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	68 spm	990 psi	75 spm	1190 psi	spm	psi	
Pump 2:	68 spm	660 psi	75 spm	740 psi	spm	psi	

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	380.0	**Casing:**	188.0	169.0
Total:	380.0			
Jars:	130.5			

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
8	1	HYC	DSX 519S	6.000	2433.0	342.0	76.5	4.47		10	80	6000	8.60	198	2150	26	55	6	23

Jets: 14 14 14 14 14 Out: 2874.0 Grade: Cutter: 3 / 4 Dull: NT / NO Wear: S Brgs: X Gge: 6 Pull: OTH

BHA - None

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2721.0	2768.0	2618.0	2666.0	30	41	2739					9			

Lithology: 5-10% Claystone, 10-60% Siltstone, 20-80% Sandstone.
2760m sample 85% Sandstone, 15% Siltstone.

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	4 Solids Removal
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	4755		16175			
BAR 1.5T			18			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 47

Accident Description:

Meetings/Drills **Time** **Description**

Safety: Held 2 x pre-tour safety mtg's

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition:	Mostly cloudy during the morning, patc	**Visibility:**	
Air Temperature:	17.0 degC	**Bar. Pressure:**	
Wind Speed/Dir:	/	**Wind Gusts:**	

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 9 **Report for 06:00 AM 18-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	2836.0	**Drilling Days:**	44	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	2733.0	**Days On Location:**	49	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	68.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	23.5	**Average ROP:**	2.89	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 2 **Contractor:** 21 **Service:** 9 **Other:** 15 **Total:** 47

Current Operations: Drilling 6" hole in slide mode @ 2836m

Planned Operations: Drill till midnight when motor hours will be up, POOH for BHA.

Toolpusher: Lindsay Baker / Ian Haughey

Wellsite Supervisors: Wayne Stonnell **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	14:30	8.50	2803	DRILR	Drill 6" hole f/-2768m to 2803m. WOB 8/10, GPM 200, 2200 psi, RPM 100, m/hr 3.1
14:30	15:00	0.50	2803	SERV	Full rig service.
15:00	3:00	12.00	2830	DRILR	Drill 6" hole f/- 2803m to 2830m. WOB 8/10, GPM 200, 2200 psi, RPM 80/100, Torque 6/8k lbs.
3:00	6:00	3.00	2836	DRILS	Drill 6" hole Slide f/- 2830m to 2836m. WOB 6/8, GPM 200, 2200psi on bottom / 2100 psi off bottom.

Comments

ROP has been down to .7 m/hr, as we incounter higher ROP we are attempting to slide to reduce angle.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	3,790	145,825	30,022	446,185	49.0%
	Totals $:	4,658,904	3,790	457,546	30,022	3,133,369	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
18-Nov 02:00 at Depth 2818.0																
8.70	72		2	25	17		5.1	14	78.5	0.2	2.6	8	17	25	42.0	42.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	6	866	condet - 55 Gal Drum	1	493
BDF-352 -	1	683	BARACARB 150 -	23	288

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
2768.0	2836.0	4.00	6.00	10	12	80	100	6000	8000	200	200	2200

Annular Velocity: **Drill Collars:** 110.00 **Drill Pipe:** 63.00

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 134000 **Pick Up:** 150000 **Slack Off:** 121000 **Drag Avg/Max:** 16000 / 18000

Slow Circulation Data: ☐ **Wear Bushing Installed**

Pump 1:	58 spm	730 psi	68 spm	890 psi	75 spm	960 psi	
Pump 2:	68 spm	740 psi	75 spm	810 psi	spm	psi	

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	404.0	**Casing:** 212.0	169.0
Total:	404.0		
Jars:	154.0		

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 9 **Report for 06:00 AM 18-Nov-05**

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	294.2	0.87	N 69 W	294.1	3	3.2	N 3.25	E 1.05	0.439
MWD	321.0	0.74	S 68 W	320.9	3	3.3	N 3.25	E 0.70	0.674
MWD	348.0	0.81	S 33.08 W	347.9	3	3.0	N 3.03	E 0.44	0.522
MWD	374.6	0.81	S 24.33 W	374.6	3	2.7	N 2.70	E 0.26	0.139
MWD	401.0	0.80	S 14.3200	400.9	2	2.4	N 2.35	E 0.13	0.160
MWD	428.4	0.76	S 11.0700	428.3	2	2.0	N 1.99	E 0.05	0.065
MWD	455.2	1.46	S 13.63 E	455.1	1	1.5	N 1.48	E 0.10	0.930
MWD	482.0	1.61	S 22.42 E	481.9	1	0.8	N 0.80	E 0.32	0.312
MWD	508.8	1.35	S 20.92 E	508.7	1	0.2	N 0.16	E 0.58	0.294
MWD	562.7	1.70	S 57.35 E	562.6	2	-0.9	S 0.89	E 1.25	1.094
MWD	640.1	2.03	S 65.8 E	639.9	4	-1.9	S 1.94	E 3.65	0.141
Side Track									
MWD	2734.9	6.73	N 60.16 W	2632.3	600	-433.3	S 433.30	E 415.56	0.674
MWD	2763.6	6.99	N 56.8500	2660.9	597	-431.5	S 431.51	E 412.63	0.494
MWD	2792.1	7.14	N 55.8999	2689.1	594	-429.6	S 429.57	E 409.72	0.200
MWD	2820.6	7.90	N 56.5 W	2717.4	590	-427.5	S 427.50	E 406.61	0.804

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
8	1	HYC	DSX 519S	6.000	2433.0	342.0	76.5												

Jets: 14 14 14 14 14 Out: 2874.0 Grade: Cutter: 3 / 4 Dull: NT / NO Wear: S Brgs: X Gge: 6 Pull: OTH

BHA - None

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2768.0	2836.0	2666.0	2732.0	50	94	2791	60				9		2.0	6.0

Lithology: last sample @ 2830m - 90% Sandstone, 10% Siltstone.
@ 2768m - 2830m 0-10% Claystone, 5-60% Siltstone, 60-95% Sandstone.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	Desander:	
Shaker No 2:	210	210	210	Desilter:	
Shaker No 3:	210	210	210	Degasser:	
Shaker No 4:				Centrifuge No 1:	6 Solids Removal
				Centrifuge No 2:	Solids Removal

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	3624		12551			
BAR 1.5T			18			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 9 **Report for 06:00 AM 18-Nov-05**

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 48

Accident Description:

Meetings/Drills	Time	Description
Safety:		Held 2 x pre-tour mtg's

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Partly cloudy **Visibility:**

Air Temperature: degC **Bar. Pressure:**

Wind Speed/Dir: / **Wind Gusts:**

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 10 **Report for 06:00 AM 19-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	2873.0	**Drilling Days:**	45	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2769.0	**Days On Location:**	50	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	37.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	23.5	**Average ROP:**	1.57	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 2 **Contractor:** 21 **Service:** 13 **Other:** 10 **Total:** 46

Current Operations: Drilling 6" hole in Slide mode.

Planned Operations: POOH change out BHA because of hours.

Toolpusher: Lindsay Baker / Ian Haughey

Wellsite Supervisors: Wayne Stonnell **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:30	0.50	2837	DRILS	Drill 6" hole Slide f/- 2836m to 2837m. WOB 5/6k, GPM 200, psi 2200.
6:30	10:30	4.00	2845	DRILR	Drill 6" hole Rotate f/- 2837m to 2845m. WOB 8/10k, GPM 200, psi 2200, Torque 6/8k, RPM 80/90.
10:30	15:30	5.00	2849	DRILS	Drill 6" hole Slide f/- 2845m to 2849m. WOB 5/8k, GPM 200, psi 2200.
15:30	20:30	5.00	2861	DRILR	Drill 6" hole Rotate f/- 2849m to 2861m. WOB 8/10, GPM 200, psi 2200, Torque 6/8k, RPM 80/90.
20:30	21:00	0.50	2861	SERV	Full rig service, clean pump strainers.
21:00	0:00	3.00	2865	DRILS	Drill 6" hole Slide f/- 2861m to 2865m. WOB 8/10, GPM 200, psi 2200,
0:00	1:00	1.00	2867	DRLR	Drill 6" hole Rotate f/- 2865m to 2867m. WOB 8/10, GPM 200, psi 2200, Torque 6/8k, RPM 80/100
1:00	1:30	0.50	2868	DRILS	Drill 6" hole Slide f/- 2867m to 2868m. WOB 8/10, GPM 200, psi 2400.
1:30	3:00	1.50	2870	DRILR	Drill 6" hole Rotate f/- 2868m to 2870m. WOB 8/10, GPM 200, psi 2400, Torque 6/8k, RPM 80.
3:00	6:00	3.00	2873	DRILS	Drill 6" hole Slide f/- 2868m to 2873m. WOB 8/10, GPM 200, psi 2400.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	1,798	147,623	38,397	484,581	53.2%
	Totals $:	4,658,904	1,798	459,344	38,397	3,171,765	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
19-Nov 02:00 at Depth 2861.0																
8.70	72		2	26	25		5.6	13	79	0.25	2.7	8	18	24	44.0	44.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
BARACARB 150 -	27	338			

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
2836.0	2873.0	2.30	4.50	10	12	80	100	6000	8000	200	200	2450

Annular Velocity: **Drill Collars:** 120.00 **Drill Pipe:** 68.00

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 136000 **Pick Up:** 155000 **Slack Off:** 122000 **Drag Avg/Max:** 19000 / 20000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	58 spm	730 psi	68 spm	900 psi	75 spm	970 psi
Pump 2:	68 spm	680 psi	75 spm	760 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	428.0	**Casing:** 236.0	169.0
Total:	428.0		
Jars:	178.0		

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 10 **Report for 06:00 AM 19-Nov-05**

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Side Track									
MWD	2849.0	8.26	N 62.69 W	2745.5	586	-425.5	S 425.48	E 403.17	0.994

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
8	1	HYC	DSX 519S	6.000	2433.0	379.0	93.2	4.07		10	80	7000	8.70	200	2450	26	57	7	23

Jets: 14 14 14 14 14 Out: 2874.0 Grade: Cutter: 3 / 4 Dull: WT / NO Wear: S Brgs: X Gge: 6 Pull: OTH

BHA - None

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Gas Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2836.0	2873.0	2732.0	2769.0	13	19	2848					9			

Lithology: Last Sample @ 2870M - 40% Sandstone, 30% Siltstone, 30% Claystone.
@2830m - 2870m. 10 - 60% Claystone, 10 - 40% Siltstone, 10 - 80% Sandstone.

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	Desander:	
Shaker No 2:	210	210	210	Desilter:	
Shaker No 3:	210	210	210	Degasser:	
Shaker No 4:				Centrifuge No 1:	3 Solids Removal
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	2249	11847.5	22149.5			
BAR 1.5T			18			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 1240

Accident Description:

Meetings/Drills	Time	Description
Safety:	30	Held 2 X pre-tour safety mtg's w/- both crews

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Morning fog, clear sky **Visibility:**
Air Temperature: degC **Bar. Pressure:**
Wind Speed/Dir: / **Wind Gusts:**

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 11 **Report for 06:00 AM 20-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	2885.0	**Drilling Days:**	46	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2783.0	**Days On Location:**	51	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	12.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	5.0	**Average ROP:**	2.40	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 2 **Contractor:** 21 **Service:** 13 **Other:** 8 **Total:** 44

Current Operations: Drill 6" hole to 2885m.

Planned Operations: Drill 6" hole, Rotate & Slide to target.

Toolpusher: Lindsay Baker / Ian Haughey

Wellsite Supervisors: Wayne Stonnell **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:30	0.50	2874	DRILS	Drill 6" hole Slide f/- 2873m to 2874m. WOB 8/10, GPM 200, psi 2400.
6:30	7:00	0.50	2874	CIRC	Circ & condition shakers clean.
7:00	11:30	4.50	2874	TRPO	Pump slug, flow check, POOH f/- 2874m to BHA.
11:30	14:00	2.50	2874	TOHBHA	Lay out HWDP, brk bit, layout motor.
14:00	17:00	3.00	2874	TIHBHA	P/up new motor, m/up bit #10, set bend to 1.15 deg. Scribe MWD. P/up new HWDP f/- rack.
17:00	21:00	4.00	2874	TRPI	Surface test MWD. RIH drill pipe f/- mast to 2373m. Fill pipe every 30 std's.
21:00	22:00	1.00	2874	CUTDL	Slip & cut drilling line. monitor trip tank.
22:00	22:30	0.50	2874	SERV	Full rig service. monitor trip tank.
22:30	23:00	0.50	2874	TRPI	Con't RIH f/- 2373m to 2414m. Took wt (10,000 lbs)
23:00	0:00	1.00	2874	REAM	Work pipe through tight spot @ 2414m. P/up kelly & oreintate toolface & slide through tite area to 2430m.
0:00	1:00	1.00	2874	TRPI	RIH f/- 2430m to 2858m. fill pipe.
1:00	1:30	0.50	2874	WASH	Wash down f/- 2858m to 2874m. tag 2m fill.
1:30	2:00	0.50	2876	DRLR	Drill 6" hole Rotate f/- 2874m to 2876m, cut new bit profile. WOB 2/4k, GPM 200, psi 2200, RPM 80, Torque 5/7k.
2:00	4:00	2.00	2879	DRLS	Drill 6" hole Slide f/- 2876m to 2879m. WOB 5/6k, GPM 200, psi 2200,
4:00	6:00	2.00	2885	DRLR	Drill 6" hole Rotate f/- 2879m to 2885m. WOB 5/6k, GPM 200, psi 2200, RPM 80, Torque 5/7k.

Comments

Azimuth swing on last survey. Similar occured @ 2734.87m.
Did a check survey 1 sng after last survey & build was @ 8.95 deg. f/- 8.26. Azimuth was 295.47 f/- 297.31 in slide mode! decide to POOH.
At this point we can afford to get out to 9.47 deg. & still hit the target. Azimuth is not a problem.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	1,776	149,399	74,585	559,167	61.4%
	Totals $:	4,658,904	1,776	461,120	74,585	3,246,351	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
20-Nov 02:00 at Depth 2874.0																
8.70	74		2	25	16		5.2	14	78.4	0.25	2.7	8	16	24		

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Barite - 1500 MT	1	316			

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
2873.0	2885.0	2.50	2.50	5	10	80	80	5	7	200	200	2200

Annular Velocity: **Drill Collars:** 117.00 **Drill Pipe:** 68.00

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 11 **Report for 06:00 AM 20-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 120000 **Pick Up:** 135000 **Slack Off:** 110000 **Drag Avg/Max:** 15000 / 15000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	58 spm	880 psi	68 spm	950 psi	75 spm	1080 psi
Pump 2:	68 spm	740 psi	75 spm	800 psi	spm	psi

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	2.4	**Casing:**	240.0	182.0
Total:	2.4			
Jars:	181.0			

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
8	1	HYC	DSX 519S	6.000	2433.0	380.0	93.7	4.06		10000	100	8000	8.70	200	2400	26	57	7	23
Jets:	14	14	14	14	14		Out: 2874.0		Grade:	Cutter:	3 / 4		Dull: WT / NO		Wear: S		Brgs: X	Gge: 6		Pull: OTH
9	1	SMITH	M516	6.000	2874.0	12.0	4	3.00		7000	80	6000	8.70	200	2200	26	56	7	23
Jets:	13	13	13	15	16		Out: 3085.0		Grade:	Cutter:	1 / 4		Dull: WT / WT		Wear: S		Brgs: X	Gge: 1		Pull: TD

BHA - No. 10 - BIT, MMTR, FS, STAB, MWD, 15 HWDP, JAR, 6 HWDP = 216.82

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2873.0	2885.0	2769.0	2783.0	2	11	2874					9			

Lithology: 2873m - 2875m 60% Claystone, 35% Siltstone, 5% sandstone.

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: Been having intermitant pressure loss throughout the night of 200 psi . Mud pump screens cleaned, found drum lid under one suction valve.

Location Condition: Dry & dusty, very small & congested. Can only receive one truck @ a time.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	Barite Recovery
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	2661.5		19488			
BAR 1.5T			18			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 1241

Accident Description:

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre-tour mtg's w/- crews.
Trip:	1	Held trip drill on trip.

☐ **BOP Test** ☑ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 11 **Report for 06:00 AM 20-Nov-05**

Weather

Sky Condition:	Clear sky, no wind.	**Visibility:**	
Air Temperature:	degC	**Bar. Pressure:**	
Wind Speed/Dir:	/	**Wind Gusts:**	

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 12 **Report for 06:00 AM 21-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	2953.0	**Drilling Days:**	47	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2849.0	**Days On Location:**	52	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	68.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	23.5	**Average ROP:**	2.89	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 2 **Contractor:** 21 **Service:** 13 **Other:** 6 **Total:** 42

Current Operations: Drilling 6" hole in Rotate mode. @ 2955m WOB 5/6k, GPM 200, psi 2450, RPM 80/100, Torque 5/7k ft/lbs. ROP 3.7 m/hr

Planned Operations: Drill 6" hole through target & on to section TD.

Toolpusher: Lindsay Baker / Steve Johns

Wellsite Supervisors: Wayne Stonnell **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:30	0.50	2888	DRLR	Drill 6" hole Rotate f/- 2885m to 2888m. WOB 5k, GPM 200, psi 2350, RPM 80, Torque 6k ft/lbs.
6:30	7:00	0.50	2889	DRLS	Drill 6" hole Slide f/- 2888m to 2889m. WOB 5k, GPM 200, psi 2350.
7:00	8:30	1.50	2892	DRLR	Drill 6" hole Rotate f/- 2889m to 2892m. WOB 5k, GPM 200 psi 2350, RPM 80, Torque 6/7k ft/lbs.
8:30	12:00	3.50	2898	DRLS	Drill 6" hole Slide f/- 2892m to 2898m. WOB 5/6k, GPM 200, psi 2350,
12:00	18:30	6.50	2917	DRLR	Drill 6" hole Rotate f/- 2898m to 2917m. WOB 5/6k, GPM 200, psi 2350, RPM 80, Torque 6/7k ft/lbs.
18:30	19:00	0.50	2917	SERV	Full rig service.
19:00	6:00	11.00	2953	DRLR	Drill 6" hole Rotate f/- 2917m to 2953m. WOB 5/6k, GPM 200, psi 2450, RPM 80/100, Torque 5/7k ft/lbs.

Comments

Good responce f/- slide section, able to rotate through target, & on to section TD.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	2,911	152,310	49,317	608,484	66.9%
	Totals $:	4,658,904	2,911	464,031	49,317	3,295,668	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
21-Nov 02:00 at Depth 2921.0																
8.70	72		2	24	17		5.2	14	78.4	0.25	2.7	8	21	28	44.0	44.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	6	866	Barite - 1500 MT	1	316
BARACARB 150 -	18	225	Lime -	5	44

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
2885.0	2953.0	3.50	5.00	5000	6000	80	100	5000	6000	200	200	2450

Annular Velocity: Drill Collars: 115.00 **Drill Pipe:** 65.00

Comments: Ditch magnets recover 600 grms.

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 140000 **Pick Up:** 158000 **Slack Off:** 124000 **Drag Avg/Max:** 18000 / 18000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	58 spm	880 psi	68 spm	950 psi	75 spm	1170 psi
Pump 2:	68 spm	740 psi	75 spm	800 psi	spm	psi

BHA Rotate Hrs	Rotate Hrs	Trip Hrs

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 12 **Report for 06:00 AM 21-Nov-05**

Since Inspection:	26.4	**Casing:**	264.0 182.0
Total:	26.4		
Jars:	205.0		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	616.0	2.02	S 69 E	615.9	3	-1.6	S 1.62	E 2.87	0.022
MWD	667.0	1.98	S 68.85 E	666.8	5	-2.3	S 2.31	E 4.52	0.131
MWD	703.0	6.80	S 26.8500	702.7	8	-4.4	S 4.43	E 6.06	4.575
MWD	720.0	8.98	S 28.88 E	719.5	10	-6.5	S 6.49	E 7.16	3.878
MWD	747.0	11.40	S 37.44 E	746.1	14	-10.5	S 10.46	E 9.80	3.165
MWD	765.0	12.04	S 39.06 E	763.7	18	-13.3	S 13.33	E 12.06	1.199
Side Track									
MWD	2876.4	7.95	N 59.88 W	2772.6	582	-423.6	S 423.63	E 399.79	0.551
MWD	2905.0	6.76	N 62.8900	2801.0	579	-421.9	S 421.87	E 396.58	1.312
MWD	2933.3	7.21	N 63.19 W	2829.1	576	-420.3	S 420.31	E 393.51	0.478

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
9	1	SMITH	M516	6.000	2874.0	80.0	23.3	3.43		5000	80	5000	8.70	200	2450	26	56	7	23

Jets: 13 13 13 15 16 Out: 3085.0 Grade: Cutter: 1 / 4 Dull: VT / WT Wear: S Brgs: X Gge: 1 Pull: TD

BHA - No. 10 - BIT, MMTR, FS, STAB, MWD, 15 HWDP, JAR, 6 HWDP = 216.82

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2885.0	2953.0	2783.0	2848.0	10	28	2913					9			

Lithology: 2885m - 2953m: 25 - 90% Claystone, 5 - 30% Siltstone, 0 - 50% Sandstone.
Last sample @ 2945m = 90% Claystone, 10% Siltstone.

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: No equipment problems, with slow drilling the rig is getting grease & paint a plenty.
Accident reported by BHI logger, lost control of his vehicle on a 2k section of gravel road way while travelling home after a 12 hour shift. No injury to the driver, some damage to the right hand front of the rental vehicle. No other property damage, no other vehicle involved.

Location Condition: Dry & dusty, but with the forcast of rain tomorrow, the dust will be short lived.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	3 Solids Removal
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	3313		16175			
BAR 1.5T	2		16			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 12 **Report for 06:00 AM 21-Nov-05**

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 1242

Accident Description: BHI mud logger (B Berger) lost control of his rental vehicle on a 2k section of gravel road. While travelling North away from the rig on Croydon road after a 12 hour shift. Resulting in some damage to the right front fender of the vehicle. No injury was susstained to the driver, no passanger was in the vehicle at the time. Primary investigator was G Ammundsen.

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre-tour mtgs w/- rig crews.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Cloudy **Visibility:**

Air Temperature: 15.0 degC **Bar. Pressure:**

Wind Speed/Dir: / NW **Wind Gusts:**

Comments: Forcast of heavy rain tomorrow, black clouds already backing up around the mountain. Air temp. is starting to drop. For once the weather man may be correct.

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 13 **Report for 06:00 AM 22-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	2993.0	**Drilling Days:**	48	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2888.0	**Days On Location:**	53	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	40.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	16.5	**Average ROP:**	2.42	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 2 **Contractor:** 21 **Service:** 13 **Other:** 10 **Total:** 46

Current Operations: Attempt to work way out of coal seam. RPM 70, Torque 3/15k ft/lbs, GPM 160, psi 1500. WOB 1k.

Planned Operations: Get out of coal seam, time drill coal, drill to section TD

Toolpusher: Lindsay Baker / Steve Johns

Wellsite Supervisors: Wayne Stonnell **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description	Non-Prod
6:00	22:30	16.50	2993	DRLR	Drill 6" hole Rotate f/- 2953m to 2993m. WOB 5/10k, GPM 200, psi 2450, RPM 80/100, Torque 5/7k ft/lbs.	
22:30	23:00	0.50	2993	STUK	Attempt to p/up & make connection. No go, attempt to rotate. No go. Work pipe free. Slow pump rate to 160 GPM.	X
23:00	0:00	1.00	2993	CIRC	Establish rotary & circ b/up @ GPM 160, psi 1500, RPM 70, still unable to p/up. 100% coal @ shakers.	
0:00	6:00	6.00	2993	CIRC	Con't circ & work pipe down/up to gain larger free spot. Work way out of coal seam.	

Comments

Stuck in coal seam for 1/2 hour last night, managed to regain rotation. Attempting to work out of coal seam.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	3,171	155,481	44,205	652,689	71.7%
	Totals $:	4,658,904	3,171	467,202	44,205	3,339,873	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
22-Nov 02:00 at Depth 2993.0																
8.70	77		2	24	18		5.3	14	78.3	0.25	2.9	8	22	28	44.0	44.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Saraline 185 -	6	866	BARABLOK -	10	320
Barite - 1500 MT	1	316	Calcium chloride 25 kg bag -	20	210

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
2953.0	2993.0	3.10	5.00	8	10	90	100	6000	10000	200	200	2500

Annular Velocity: **Drill Collars:** 115.00 **Drill Pipe:** 65.00

Comments: Drilled into coal seam.

Miscellaneous Drilling Parameters

Hook Loads (lbs); **Off Bottom Rotate:** 140 **Pick Up:** 160 **Slack Off:** 126 **Drag Avg/Max:** 20000 / 30000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	58 spm	830 psi	68 spm	1010 psi	75 spm	1110 psi
Pump 2:	68 spm	660 psi	75 spm	750 psi	spm	psi

BHA Rotate Hrs

Since Inspection: 50.4

Total: 50.4

Jars: 229.0

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 13 **Report for 06:00 AM 22-Nov-05**

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	783.0	13.35	S 40.7 E	781.3	22	-16.4	S 16.36	E 14.60	2.264
MWD	801.0	15.18	S 44.1799	798.8	26	-19.6	S 19.63	E 17.60	3.367
MWD	962.0	19.33	S 48.2899	951.5	77	-52.8	S 52.78	E 55.86	0.772
MWD	989.0	18.58	S 45.61 E	977.1	86	-58.8	S 58.76	E 62.27	1.277
MWD	1016.0	18.94	S 45.0700	1002.6	94	-64.9	S 64.86	E 68.45	0.444
MWD	1043.0	19.46	S 45.38 E	1028.1	103	-71.1	S 71.12	E 74.75	0.589
MWD	1071.0	19.79	S 46.19 E	1054.5	113	-77.7	S 77.67	E 81.49	0.458
MWD	1098.0	19.81	S 47.5700	1079.9	122	-83.9	S 83.92	E 88.17	0.520
MWD	1124.0	19.47	S 46.1000	1104.4	130	-89.9	S 89.90	E 94.54	0.692
MWD	1151.0	18.96	S 42.88 E	1129.9	139	-96.2	S 96.24	E 100.77	1.307
MWD	1178.0	18.89	S 42.1799	1155.4	148	-102.7	S 102.69	E 106.69	0.264
Side Track									
MWD	2962.0	7.37	N 69 W	2857.5	572	-418.8	S 418.84	E 390.19	0.790

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
9	1	SMITH	M516	6.000	2874.0	120.0	29.3	4.10	5.00	8	90	6000	8.70	200	2500	26	56	7	23

Jets: 13 13 13 15 16 Out: 3085.0 Grade: Cutter: 1 / 4 Dull: VT / WT Wear: S Brgs: X Gge: 1 Pull: TD

BHA - No. 10 - BIT, MMTR, FS, STAB, MWD, 15 HWDP, JAR, 6 HWDP = 216.82

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2953.0	2993.0	2849.0	2888.0	15	29	2988					9			

Lithology: 2953m to 2993m: 95 - 100% Claystone, 0 - 5% Siltstone.
Spot sample @ 2993m: 80% coal, 20% Claystone.

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: No equipment problems.

Location Condition: Solid base, damp but draining well.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	210	210	210
Shaker No 2:	210	210	210
Shaker No 3:	210	210	210
Shaker No 4:			

Equipment Usage:	Hrs.
Desander:	
Desilter:	
Degasser:	
Centrifuge No 1:	5 Solids Removal
Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	3317		12858			
BAR 1.5T			16			

Truck/Boat Status: 1 x G J Sole truck delivered 4 x pods of base oil, & back loaded 21 x 3-1/2" HWDP & 1 x mud motor for inspection / rebuild.

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 13 **Report for 06:00 AM 22-Nov-05**

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 1243

Accident Description:

Meetings/Drills **Time** **Description**

Safety: Held 2 x pre-tour safety mtg's

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: heavy cloud cover. **Visibility:**

Air Temperature: degC **Bar. Pressure:**

Wind Speed/Dir: / **Wind Gusts:**

Comments: Rain all day, some heavy falls.

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 14 **Report for 06:00 AM 23-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	3022.0	**Drilling Days:**	49	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2917.0	**Days On Location:**	54	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	29.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	21.0	**Average ROP:**	1.38	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 2 **Contractor:** 21 **Service:** 13 **Other:** 8 **Total:** 44

Current Operations: Time drill 6" hole while wait on sample f/- drill brk @ 3021m. 06:00 depth 3022m

Planned Operations: Drill to section TD, to be advised by Geoligest

Toolpusher: Mike Preston / Steve Johns

Wellsite Supervisors: Wayne Stonnell **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:30	0.50	2993	REAM	Ream f/- 2992.5m to 2993m. WOB 0-1k, GPM 160, psi 1500, RPM 70, Torque 5/15k ft/lbs. 100% coal @ shakers.
6:30	7:00	0.50	2993	REAM	Pull back to 2986m w/- 5k over pull, ream back to 2993m.
7:00	9:00	2.00	2993	CIRC	Pump 10 bbls low vis low wt (base oil), pump 10 bbls 10.7 ppg 74 vis, & circ out of hole. 100% coal @ shakers.
9:00	22:00	13.00	3005	DRLR	Time drill 6" hole Rotate f/- 2993m to 3005m. WOB 2/4k, GPM 160/200, psi 1500/2200. Torque 5/7k ft/lbs. 100/20% coal @ shakers.
22:00	2:00	4.00	3015	DRLR	Drill 6" hole Rotate f/- 3005m to 3015m. Constant WOB 6K, GPM 200, psi 2200, RPM 80, Torque 5/7k ft/lbs. 10% coal @ shakers.
2:00	3:00	1.00	3016	DRLR	Time drill 6" hole Rotate f/-3015m to 3016m. WOB 2/5k, GPM 200, psi 2200, RPM 80, Torque 6k ft/lbs, 15/20% coal @ shakers.
3:00	5:00	2.00	3021	DRLR	Drill 6" hole Rotate f/- 3016m to 3021m. Constant WOB 6k, GPM 200, psi 2300, RPM 80, Torque 5/7k ft/lbs. 20% coal @ shakers, drill brk.
5:00	6:00	1.00	3022	DRLR	Time drill 6" hole Rotate f/- 3021m to 3022m. WOB 4/6k, GPM 200, psi 2300, RPM 80, Torque 5/7k ft/lbs.

Comments

Ditch magnet recovery: 400 grms

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	1,375	156,856	41,709	694,398	76.3%
	Totals $:	4,658,904	1,375	468,577	41,709	3,381,582	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
23-Nov 02:00 at Depth 3004.0																
8.70	76		2	26	16		5.3	14	78.3	0.25	2.8	16	22	28	44.0	44.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
2993.0	3022.0	2.70	16.00	6	10	80	80	5000	7000	200	200	2200

Annular Velocity: Drill Collars: 108.00 **Drill Pipe:** 61.00

Comments: Time drill coal section @ 1m/hr, p/up every 1/2m to check pipe free.

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 140000 **Pick Up:** 163000 **Slack Off:** 129000 **Drag Avg/Max:** 23000 / 25000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	58 spm	760 psi	68 spm	900 psi	75 spm	1020 psi
Pump 2:	68 spm	760 psi	75 spm	810 psi	spm	psi

BHA Rotate Hrs

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 14 **Report for 06:00 AM 23-Nov-05**

Since Inspection:	74.4
Total:	74.4
Jars:	253.0

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	1205.0	19.52	S 43.5 E	1180.9	157	-109.2	S 109.20	E 112.73	0.850
MWD	1232.0	20.14	S 43.53 E	1206.3	166	-115.8	S 115.84	E 119.03	0.689
MWD	1258.0	20.76	S 44.14 E	1230.7	175	-122.4	S 122.39	E 125.33	0.756
MWD	1285.0	20.58	S 44.44 E	1256.0	185	-129.2	S 129.22	E 131.98	0.232
MWD	1312.0	17.63	S 42.41 E	1281.5	194	-135.6	S 135.62	E 138.06	3.359
Side Track									
MWD	2988.3	7.39	N 71.0799	2883.7	569	-417.7	S 417.68	E 387.00	0.305

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
9	1	SMITH	M516	6.000	2874.0	149.0	45.4	3.28	16.00	6	80	6000	8.70	200	2300	26	56	7	23

Jets: 13 13 13 15 16 Out: 3085.0 Grade: Cutter: 1 / 4 Dull: VT / WT Wear: S Brgs: X Gge: 1 Pull: TD

BHA - No. 10 - BIT, MMTR, FS, STAB, MWD, 15 HWDP, JAR, 6 HWDP = 216.82

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
2993.0	3022.0	2700.0	2917.0	10	15	2996					9			

Lithology: 2993m - 3015m: 10-95% Claystone, trace - 90% Coal, 0 - 15% Siltstone, 0 - 15% Sandstone.
Last sample @ 3015m 95% Claystone, 5% Siltstone, trace coal.

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: Pop off by-pass valve vibrated open causing a loss in pump pressure. Also experiencing losses in the active tanks. Several checks found the problem & determand the problem was @ surface not down hole. The valve was tied shut.
BHI added to the problem by not informing the rig floor the losses in the active tank were due to the reserve tank slowly filling! (the pop off lines discharge into the reserve tanks) Rig floor only monitor active tanks.

Location Condition: Small but tidy.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	4 Solids Removal
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	2775		10083			
BAR 1.5T			16			

Truck/Boat Status: 1 x load SPM cuttings out today.

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 14 **Report for 06:00 AM 23-Nov-05**

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 1244

Accident Description:

Meetings/Drills	Time	Description
Safety:	30	held 2 x pre-tour mtg's w/- crews

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: Cloud clearing **Visibility:**

Air Temperature: degC **Bar. Pressure:**

Wind Speed/Dir: / SW **Wind Gusts:**

Comments: Showers this morning, sky clearing w/- long fine intervals.

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 15 **Report for 06:00 AM 24-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	3050.0	**Drilling Days:**	50	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2944.0	**Days On Location:**	55	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	28.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	20.0	**Average ROP:**	1.40	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 2 **Contractor:** 21 **Service:** 21 **Other:** 3 **Total:** 47

Current Operations: Continue to drill 6" hole .Base of ahuroa trust 3034m. TD prognosed 3084m.
GPM 200 ,SPM 160, SPP 2350psi. WOB 3/6K, RPM 80,ROP 2-3.5m/hr.
Back ground gas 6/15 units.Pump sweeps as required.

Planned Operations: Continue to drill 6" hole to TD +/- 3084M

Toolpusher: Mike Preston / Steve Johns

Wellsite Supervisors: Troy Reid Wayne Stonnell **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	6:30	0.50	3022	DRIL	Continue to time drill 1m/hr through coal seam to to 3022m.15% coal.
6:30	8:00	1.50	3025	DRIL	Continue to time drill 1 m/hr to 3025m 100% coal .Pump 5 bbls sweeps to keep well bore clean . maintain 4 bpb barablok in mud system to control coal.GPM 200, SPM 160 SPP=2300psi
8:00	12:00	4.00	3028	DRIL	Time drill at 1m/hr to 3028m .100% coal.Pump 5 bbls sweeps as required
12:00	16:00	4.00	3031	DRIL	Continue to time drill 6" hole to 3031m .Sample 3030m 100% coal ,sample 3031m 70% coal /30% claystone.GPM 200, WOB 2/4k.SPM 160 ,SPP 2300psi.
16:00	17:30	1.50	3031	CIRC	Pump 10 bbls sweep and circulate clean prior to wiper trip.
17:30	18:00	0.50	3031	FLOW	Flow check (static) Pump slug .
18:00	19:00	1.00	2868	WIPE	Wiper trip back to 2868m . No hang ups.
19:00	19:30	0.50	2868	SERV	Rig service . Circulate and condition mud while performing Rig service.
19:30	20:00	0.50	3031	WIPE	TRPI to 3020m wash down last single to 3031m. 1m fill.
20:00	1:30	5.50	3036.5	DRIL	Continue to time drill 6" hole to 3036.5m. 3034m geologist called base of ahuroa trust .GPM 200 ,SPM 160,SPP 2300psi,
1:30	6:00	4.50	3050	DRIL	Continue to drill 6" hole conventionally f/-3036.5m to 3050m Coal percentages dropped of to only traces. GPM 200,WOB 4/6k, Torque 4/5000 ft/lbs,RPM 80 ,SPM 160=SPP 2350psi.,ROP 3.1m/hr. Pump sweeps as required.

Comments

Control drill through coal 100% f/- 3023m to 3032m.
Drill to 3032m hole getting sticky and overpull increasing to 10/12k.Pump sweep and wiper trip back to old hole 2874m.
Check all pressure sensor diaphrams.
Clean out discharge strainers on mud pumps during wiper trip.
Base of ahuroa trust 3034m(Geologist prognosis)

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	1,901	158,757	48,008	742,406	81.6%
	Totals $:	4,658,904	1,901	470,478	48,008	3,429,590	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
24-Nov 02:00 at Depth 3034.0																
8.70	74		2	26	17		5.2	14	78.4	0.25	2.8	12	22	28	44.0	44.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Barite - 1500 MT	1	316	BARACARB 150 -	10	125

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 15 **Report for 06:00 AM 24-Nov-05**

Drilling Parameters

		ROP		WOB		RPM		Torque		Flow		
From	To	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max	PSI
3022.0	3051.0	1.40	3.00	4	6	80	80	3500	5000	200	200	2350

Annular Velocity: **Drill Collars:** 41.50 **Drill Pipe:** 62.90

Comments: Continue time drill until 2036m .Coal samples reduced to traces .Continue to drill conventonally f/- 3036m ROP 3m/hr

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 143000 **Pick Up:** 163000 **Slack Off:** 128000 **Drag Avg/Max:** 15000 / 20000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	58 spm	760 psi	68 spm	900 psi	75 spm	1020 psi	
Pump 2:	68 spm	760 psi	75 spm	810 psi	spm	psi	

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	94.5	**Casing:**	284.0	186.0
Total:	94.5			
Jars:	273.0			

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	1339.0	17.41	S 41.31 E	1307.2	202	-141.7	S 141.68	E 143.49	0.442
MWD	1366.0	17.60	S 41.3999	1333.0	210	-147.8	S 147.77	E 148.85	0.213
MWD	1393.0	17.53	S 41.4299	1358.7	218	-153.9	S 153.88	E 154.24	0.078
MWD	1421.0	18.94	S 43.4600	1385.3	227	-160.3	S 160.34	E 160.16	1.657
MWD	1447.0	19.29	S 44.1000	1409.9	235	-166.5	S 166.49	E 166.05	0.471
MWD	1474.0	19.86	S 44.78 E	1435.3	244	-172.9	S 172.95	E 172.38	0.682
MWD	1501.0	20.16	S 45.52 E	1460.7	253	-179.5	S 179.47	E 178.93	0.436
MWD	1528.0	20.68	S 45.88 E	1486.0	263	-186.0	S 186.04	E 185.68	0.594
MWD	1555.0	21.30	S 46.3 E	1511.2	273	-192.8	S 192.75	E 192.64	0.709
Side Track									
MWD	3019.3	8.03	N 71.6099	2914.3	566	-416.4	S 416.36	E 383.07	0.625

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Pump Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
9	1	SMITH	M516	6.000	2874.0	177.0	65.4	2.71	3.00	5	80	3500	8.70	200	2350	26	56	7	23

Jets: 13 13 13 15 16 Out: 3085.0 Grade: Cutter: 1 / 4 Dull: VT / WT Wear: S Brgs: X Gge: 1 Pull: TD

BHA - No. 10 - BIT, MMTR, FS, STAB, MWD, 15 HWDP, JAR, 6 HWDP = 216.82

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3022.0	3050.0		2944.0	17	47	3029					9			

Lithology: Last sample 100% claystone. at 3031m last sample 100% coal .

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: Mud pump 1 very noisy and vibrating. Checked all strainer .discharge strainer partically plugged. Check pressure sensors .

Location Condition: Continue rig housekeeping.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom
Shaker No 1:	210	210	210
Shaker No 2:	210	210	210
Shaker No 3:	210	210	210
Shaker No 4:			

Equipment Usage:	Hrs.
Desander:	
Desilter:	
Degasser:	
Centrifuge No 1:	4 Solids Removal
Centrifuge No 2:	Barite Recovery

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 15 **Report for 06:00 AM 24-Nov-05**

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	3014	13401.9	20470.9			
BAR 1.5T			16			

Truck/Boat Status: 1 x load of diesel.
1 x load SBM cuttings.

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 1245

Accident Description: No accidents or incidents to report.

Meetings/Drills	Time	Description
Safety:	30	2 x pre-tour safety mtg's w/- both crews.Topics discussd.Working with SBM. Forklift operations.first aid.

☐ **BOP Test** ☑ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 16 **Report for 06:00 AM 25-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	3085.0	**Drilling Days:**	51	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2979.0	**Days On Location:**	56	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	35.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	9.5	**Average ROP:**	3.68	**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 1 **Contractor:** 21 **Service:** 10 **Other:** 2 **Total:** 34

Current Operations: TRPO layout directional equipment.Rig up schlumberger wireline equipment.

Planned Operations: Run TD logs.

Toolpusher: Mike Preston / Steve Johns

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	12:00	6.00	3071	DRIL	Continue drill 6" hole to 3071m .GPM 200, SPM 160 ,SPP 2400psi,Torque 6/7000 ft/bls.
12:00	15:30	3.50	3085	DRIL	Drill 6" hole to target depth 3085m ,50m below the ahuroa thrust basement.GPM 200, ROP 3/4m/hr,Torque 6/7000 ft/bls. 100% claystone formation,SPM 160 ,SPP 2350psi.
15:30	17:00	1.50	3085	CIRC	Pump 10bbls sweep and circulate well clean.
17:00	17:30	0.50	3085	FLOW	Flow check ,(static)Pump slug .
17:30	19:30	2.00	2395	WIPE	Wiper trip back to shoe 2395m .no hang ups.
19:30	21:30	2.00	3085	WIPE	TRPI to 3055m , wash down toTD 3085m .1.2m fill.
21:30	0:00	2.50	3085	FLOW	Sweep 10bbls high vis and circulate clean.Flow check (static) Spot 15 bbls high vis on bottom.
0:00	2:00	2.00	2395	TRPO	TRPO to 7" casing shoe 2395m no hang ups.
2:00	6:00	4.00	216	TRPO	Flow check at 7" casing shoe 5 mins (static) Continue TRPO to BHA.216m.

Comments

Drill 6 " to 3085m TD 50m below the ahuroa trust..
Wiper trip back to old hole good .no hang ups.
Schlumberger on site and inducted.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	3,436	162,193	43,583	785,989	86.4%
	Totals $:	4,658,904	3,436	473,914	43,583	3,473,173	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
25-Nov 02:00 at Depth 3085.0																
8.70	74		2	26	16		5.2	14	78.4	0.25	2.8	12	22	26	44.0	44.0

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
Barite - 1500 MT	3	948	condet - 55 Gal Drum	1	493
BARACARB 150 -	18	225	BARABLOK -	7	224

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
3050.0	3085.0	3.60	6.00	5	8	80	80	5000	6000	200	20	2400

Annular Velocity: **Drill Collars:** 41.50 **Drill Pipe:** 62.90

Comments: TD well at 3085m.

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 16 **Report for 06:00 AM 25-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: 144000 **Pick Up:** 165000 **Slack Off:** 127000 **Drag Avg/Max:** 15000 / 21000

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	58 spm	760 psi	68 spm	900 psi	75 spm	1020 psi
Pump 2:	68 spm	760 psi	75 spm	810 psi	spm	psi

	BHA Rotate Hrs	Rotate Hrs	Trip Hrs
Since Inspection:	104.0	**Casing:** 293.5	196.0
Total:	104.0		
Jars:	283.0		

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	1582.0	20.84	S 45.12 E	1536.4	282	-199.5	S 199.53	E 199.59	0.695
MWD	1609.0	20.57	S 44.92 E	1561.6	292	-206.3	S 206.28	E 206.34	0.310
MWD	1636.0	19.73	S 44.86 E	1587.0	301	-212.9	S 212.86	E 212.91	0.934
MWD	1662.0	20.06	S 44.88 E	1611.4	310	-219.1	S 219.14	E 219.15	0.381
Side Track									
MWD	3047.9	8.34	N 72.22 W	2942.6	562	-415.1	S 415.09	E 379.20	0.338
MWD	3069.2	8.38	N 72.31 W	2963.8	560	-414.1	S 414.15	E 376.24	0.059

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
9	1	SMITH	M516	6.000	2874.0	212.0	74.9	2.83	6.00	5	80	5000	8.70	200	2400	26	56	7	23

Jets: 13 13 13 15 16 Out: 3085.0 Grade: Cutter: 1 / 4 Dull: VT / WT Wear: S Brgs: X Gge: 1 Pull: TD

BHA - No. 10 - BIT, MMTR, FS, STAB, MWD, 15 HWDP, JAR, 6 HWDP = 216.82

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3050.0	3085.0		2979.0	17	29	3071					9			

Lithology: 3040m --3085m 100% claystone

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: Run new genset package and load tested.

Location Condition: Rearrange site for schlumberger truck.
Continue general housekeeping.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	3 Solids Removal
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	4303.9		16167			
BAR 1.5T	6		10			

Truck/Boat Status: 1 x 40ft flatdeck delivered schlumberger equipment

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 16 **Report for 06:00 AM 25-Nov-05**

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 1246

Accident Description: No accidents or incidents to report.

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meeting. Topic discussed. Tripping pipe,Housekeeping.Hand tool operations

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: clear **Visibility:**

Air Temperature: 20.0 degC **Bar. Pressure:**

Wind Speed/Dir: 2 / SE **Wind Gusts:** 5

Comments: Fine clear day

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 17 **Report for 06:00 AM 26-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	3085.0	**Drilling Days:**	52	**RKB Elevation:**		**County:**	Taranaki
Vertical Depth:	2979.0	**Days On Location:**	57	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 1 **Contractor:** 21 **Service:** 0 **Other:** 0 **Total:** 22

Current Operations: Mix and pump cement plug across 7" casing shoe.

Planned Operations: Layout excess drill pipe side ways and run CBL. log with vause wireline services

Toolpusher: Mike Preston / Steve Johns

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:00	1.00	0	TOHBHA	Flow check at BHA and TOHBHA and layout mwd , remove probe ,mud motor ,stab ,bit.
7:00	8:00	1.00	0	LOG	HPJSM Proir to rigging up schlumbereger equipment. Rig up schhlumberger equipment.
8:00	13:00	5.00	3085	LOG	P/up run# 1 PEX -AIT.load source. Run in hole tag bottom W/L MD 3087m. Log up to shoe and Pull out with W/l to surface .
13:00	13:30	0.50	0	LOG	Unload source at surface . Lay out run#1 PEX-AIT.
13:30	14:00	0.50	0	LOG	M/up run # 2 . UBI.
14:00	20:30	6.50	3085	LOG	Run in hole w/- UBI.Log up f/- 3085m.
20:30	22:30	2.00	0	LOG	Wire line at surface . Comfirm logs.ok Lay out UBI tools. Rig down schlumbereger surface equipment
22:30	23:30	1.00	146	TRPI	Rig up floor for 2 7/8 tubing .P/up mule shoe and run cement stinger to 146m
23:30	3:30	4.00	2430	TRPI	Change out handling equipment for 3 1/2 dp.TRPI to 2430m.
3:30	5:30	2.00	2430	CIRC	Circulate and condition mud while mix spacers and prepare cement plug.
5:30	6:00	0.50	2430	CMTPL	Held pre job meeting prior to Cement operations. Rig up cement surface lines.

Comments

Prepare displacement mud .
Site inspection on Kauri F location.
Contact John Molloy from OSH re T&A plan .
Sperry sun DD/MWD prepared equipment for rig move and vacated rig site.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
	No AFE Assigned				0	0	
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	2,879	165,072	26,854	812,843	89.3%
	Totals $:	4,658,904	2,879	476,793	26,854	3,500,027	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
26-Nov 02:00 at Depth 3085.0																
8.70	77		2	26	17		5.2	14	78.4	0.25	2.8	14	24	28		

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
KCl -	2	945	BARAZAN D PLUS - 25KG sxs	2	473

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
3085.0	3085.0											

Comments: TD well at 3085m

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 17 **Report for 06:00 AM 26-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: **Pick Up:** **Slack Off:** **Drag Avg/Max:** /

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	58 spm	760 psi	68 spm	900 psi	75 spm	1020 psi
Pump 2:	68 spm	760 psi	75 spm	810 psi	spm	psi

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	104.0	**Casing:**	293.5	202.0
Total:	104.0			
Jars:	283.0			

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	1689.0	20.17	S 44.84 E	1636.8	319	-225.7	S 225.72	E 225.70	0.123
MWD	1716.0	20.33	S 45.41 E	1662.1	329	-232.3	S 232.31	E 232.32	0.282
MWD	1743.0	20.69	S 46.0399	1687.4	338	-238.9	S 238.91	E 239.10	0.469
MWD	1770.0	20.87	S 46.2100	1712.6	348	-245.6	S 245.55	E 246.00	0.211
MWD	1798.0	20.16	S 45.44 E	1738.9	357	-252.4	S 252.39	E 253.04	0.814
MWD	1826.0	19.74	S 45.16 E	1765.2	367	-259.1	S 259.11	E 259.83	0.461
MWD	1855.0	19.43	S 45.44 E	1792.5	377	-265.9	S 265.95	E 266.74	0.335
MWD	1910.8	18.93	S 45.8 E	1845.2	395	-278.8	S 278.78	E 279.85	0.276
MWD	1938.5	19.02	S 44.7899	1871.4	404	-285.1	S 285.11	E 286.25	0.369
MWD	1967.1	19.08	S 44.5099	1898.4	413	-291.7	S 291.74	E 292.80	0.115
MWD	1995.3	18.90	S 44.2899	1925.2	423	-298.3	S 298.31	E 299.24	0.206
MWD	2023.5	18.59	S 44.48 E	1951.8	432	-304.8	S 304.78	E 305.57	0.336

Bit Information

No	Run	Make	Model	Diam	Depth In	This Run Dist.	This Run Hrs	ROP Avg	ROP Max	WOB	RPM	Torq	Mud Wt	Mud Flow	Pump Press	J. Vel	P.Drp	HHP	JIF
9	1	SMITH	M516	6.000	2874.0	212.0	74.9												

Jets: 13 13 13 15 16 Out: 3085.0 Grade: Cutter: 1 / 4 Dull: VT / WT Wear: S Brgs: X Gge: 1 Pull: TD

BHA - No. 10 - BIT, MMTR, FS, STAB, MWD, 15 HWDP, JAR, 6 HWDP = 216.82

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3085.0	3085.0													

Lithology: No drilling activity .Well TD at 3085m

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	Barite Recovery
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	1480		14687			
BAR 1.5T			10			

Truck/Boat Status: Back load sperry sun directional equipment .

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 17 **Report for 06:00 AM 26-Nov-05**

3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 1247

Accident Description: No accidents or incidents to report

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meeting .Topic discusssed, Logging operations and T @ A operations.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: clear **Visibility:**

Air Temperature: 15.0 degC **Bar. Pressure:**

Wind Speed/Dir: 5 / SE **Wind Gusts:** 5

Comments: Fine clear day

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 18 **Report for 06:00 AM 27-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	3085.0	**Drilling Days:**	53	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2979.0	**Days On Location:**	58	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 1 **Contractor:** 21 **Service:** 4 **Other:** 2 **Total:** 28

Current Operations: TRPO to pick up cement stinger

Planned Operations: Set balanced cement plug across 7" casing shoe

Toolpusher: Mike Preston / Steve Johns

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:00	1.00	2430	PLUG	Pump 10 bbls spacer . Test surface lines to 3000psi ok,Continue pump 20 bbls spacer Total 30 bbls.Mix and pump 11 bbls 17.2ppg slurry . pump 7 bbls spacer to balance plug. Displace with 44 bls SBM. Check back flow .(static).
7:00	7:30	0.50	2283	PLUG	Rig down cement surface lines and TRPO to 2283m slowly.No overpull .
7:30	8:30	1.00	2283	PLUG	Drop wiper ball and Circulate bottoms up .no cement contamination back at surface. Some spacer returns at surface.
8:30	10:30	2.00	1581	LDDP	Lay out excess 3 1/2 drill pipe to 1581m
10:30	13:00	2.50	146	TRPO	Continue to TRPO to 146m 2 7/8 cement stinger
13:00	14:30	1.50	0	LDDP	Layout 2 7/8 cement stinger and handling quipment
14:30	15:00	0.50	0	LOG	HPJSM prior to rigging up vause W/L. R/up vause W/L surface equipment
15:00	17:30	2.50	1500	LOG	Run # 1 CBL .log down to 1500m them log up to 500m to evaluate cement bond.Soilid cement up to 905m .
17:30	18:30	1.00	205	TIHBHA	M/up clean out assy and TIHBHA to 205m
18:30	23:30	5.00	2320	TRPI	Continue TRPI to 2320m filling as required
23:30	0:30	1.00	2450	WASH	Wash down f/- 2320m to 2450m No cement tagged.
0:30	1:30	1.00	2450	CIRC	Circulate bottoms up . No cement contamination at bottoms up
1:30	6:00	4.50	300	TRPO	Pump slug and TRPO to BHA.

Comments

Transfer 422 bbls 70/30 SBM f/- ahuroa st-1 to goss well site.
Back load 68 jnts 3 1/2 dp f/- ahuroa to TOT
TRPI to 2320m, wash down to top of plug no cement tagged continue wash down to 2450m no cement tagged.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
	No AFE Assigned					0	
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	2,060	167,132	100,694	913,537	100.4%
	Totals $:	4,658,904	2,060	478,853	100,694	3,600,721	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
27-Nov 02:00 at Depth 2445.0																
8.50							1.8	98								

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
KCl -	1	473	BARASCAV D - 25kg	2	67
Caustic soda -	2	60			

Drilling Parameters

From	To	ROP Avg	ROP Max	WOB Avg	WOB Max	RPM Avg	RPM Max	Torque Avg	Torque Max	Flow Avg	Flow Max	PSI
3085.0	3085.0											

Comments: Well TD 3085m

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 18 **Report for 06:00 AM 27-Nov-05**

Miscellaneous Drilling Parameters

Hook Loads (lbs); Off Bottom Rotate: **Pick Up:** **Slack Off:** **Drag Avg/Max:** /

Slow Circulation Data: ☑ **Wear Bushing Installed**

Pump 1:	58 spm	760 psi	68 spm	900 psi	75 spm	1020 psi
Pump 2:	68 spm	760 psi	75 spm	810 psi	spm	psi

	BHA Rotate Hrs		Rotate Hrs	Trip Hrs
Since Inspection:	104.0	**Casing:**	293.5	208.0
Total:	104.0			
Jars:	283.0			

Survey Information

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Closure	Vertical Section	Coordinates N-S	Coordinates E-W	D.L.S.
Original Well Bore									
MWD	2052.7	19.21	S 43.23 E	1979.4	441	-311.6	S 311.59	E 312.11	0.762
MWD	2081.2	19.19	S 42.6499	2006.4	450	-318.5	S 318.46	E 318.50	0.202
MWD	2110.1	19.43	S 41.28 E	2033.6	460	-325.6	S 325.56	E 324.88	0.533
MWD	2138.4	20.66	S 40.0399	2060.2	470	-332.9	S 332.93	E 331.21	1.376
MWD	2167.3	20.95	S 39.09 E	2087.2	480	-340.8	S 340.84	E 337.74	0.462
MWD	2195.9	20.97	S 39.06 E	2113.9	490	-348.8	S 348.79	E 344.20	0.024
MWD	2224.2	20.97	S 38.72 E	2140.4	500	-356.7	S 356.66	E 350.55	0.129
MWD	2253.0	20.50	S 40.86 E	2167.3	510	-364.5	S 364.51	E 357.08	0.927
MWD	2291.5	20.35	S 41.17 E	2203.4	524	-374.6	S 374.65	E 365.90	0.144
MWD	2319.6	20.22	S 40.7 E	2229.7	533	-382.0	S 381.99	E 372.27	0.223
MWD	2348.3	19.97	S 39.61 E	2256.7	543	-389.5	S 389.54	E 378.64	0.470
MWD	2378.0	19.93	S 38.9900	2284.6	553	-397.4	S 397.38	E 385.05	0.218

BHA Information

BHA - No. 10 - BIT, MMTR, FS, STAB, MWD, 15 HWDP, JAR, 6 HWDP = 216.82

Mud Log Information

Depth From	Depth To	TVD From	TVD To	Gas Avg	Gas Max	Gas at Depth	Gas Connect.	Trip	Drilling Exp.	Pore Press	Mud Dens.	Shale Dens.	ROP Shale	ROP Sand
3085.0	3085.0										9			

Lithology: well TD no drilling activity

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Location Condition: Transfer excess SBM to storage tanks.
Prepare equipment for rig move.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.
Shaker No 1:	210	210	210	**Desander:**	
Shaker No 2:	210	210	210	**Desilter:**	
Shaker No 3:	210	210	210	**Degasser:**	
Shaker No 4:				**Centrifuge No 1:**	5 Solids Removal
				Centrifuge No 2:	Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	2136		12551			
BAR 1.5T			10			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 18 **Report for 06:00 AM 27-Nov-05**

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 1248

Accident Description: No accidents or incidents to report

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meetings. Topic discussed . Abandon procedures.Forklift operations. Handling SBM.

☐ **BOP Test** ☑ **Crownamatic Check**

Weather

Sky Condition: cleafr **Visibility:**

Air Temperature: 10.0 degC **Bar. Pressure:**

Wind Speed/Dir: 2 / SE **Wind Gusts:** 2

Comments: Fine clear conditions.

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 19 **Report for 06:00 AM 28-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	3085.0	**Drilling Days:**	54	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2979.0	**Days On Location:**	59	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 1 **Contractor:** 21 **Service:** 4 **Other:** 0 **Total:** 26

Current Operations: Layout remaining 3 1/2 DP/HWDP.

Planned Operations: Nipple down BOP's , clean out mud tanks .

Toolpusher: Mike Preston / Steve Johns

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	7:30	1.50	205	TRPO	Continue TRPO to BHA 205m
7:30	8:30	1.00	0	TOHBHA	TOHBHA layout bit ,bit sub,
8:30	9:00	0.50	0	PLUG	M/up EZSV packer assy.
9:00	15:00	6.00	2365	TRPI	TRPI with EZSV as per haliburton engineers parameters to 2365m
15:00	15:30	0.50	2365	CIRC	Circulate and condition mud prior to setting EZSV packer. work string through setting zone
15:30	16:00	0.50	2365	PLUG	Get up/ down weights.122k up 95k down,Set ezsv packer with 35 turns right .Pick up 15k over string weight and let packer element expand.Continue to pull to 170k and shear packer. Set down 20k to confirm packer set ok.
16:00	16:30	0.50	2365	FIT	Establish injectivity rate under EZSV . Break over at 1550psi. pump 1.5bpb = 1340psi.
16:30	17:00	0.50	2365	PLUG	Sting out of EZSV. Pump 5 bbls spacer ,test surface lines to 3000psi ok. continue pump spacer total 10bbls. Mix and pump 12 bbls 15.2ppg cement slurry , pump 1.3 bbls tail spacer for balance. Displace with SBM 32 bbls, sting into EZSV and inject 5 bbls slurry under EZSV1.7bpm= 800psi. Pump 5bbls then unsting out of EZSV. Continue to displace total 48 bbls.displace at 6bpm=450 psi.Stop pumping check back flow .(static)
17:00	18:00	1.00	2235	PLUG	TRPO slowly to 2235m and reverse circulate tubing volume . no cement returns.
18:00	18:30	0.50	2235	P/TEST	Pressure test EZSV against casing to 3000psi 10mins ok.
18:30	19:00	0.50	2235	PLUG	Rig down cementing surface equipment.
19:00	21:00	2.00	2235	CIRC	Displace SBM to caCL brine .Flush all drilling quipment.
21:00	6:00	9.00	200	LDDP	Lay down 3 1/2 DP ,3 1/2 HWDP.Soft break kellly.

Comments

Held pre job meeting prior to setting EZSV, Cementing operations,Laying down 3 1/2 DP.
Injection test on a annulus 1 bpm= 120psi 5bpm=650 psi.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
	No AFE Assigned					0	
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	-77,908	89,224	-29,298	884,239	97.2%
	Totals $:	4,658,904	-77,908	400,945	-29,298	3,571,423	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	Solids %	Water %	Oil %	Sand %	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
28-Nov 02:00 at Depth 2455.0																
8.50								98			14500					

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
SOBM credit - bbls	800	-80,000	Barite - 1500 MT	2	632

BHA Information

BHA - No. 10 - BIT, MMTR, FS, STAB, MWD, 15 HWDP, JAR, 6 HWDP = 216.82

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 19 **Report for 06:00 AM 28-Nov-05**

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: Rig move refurbish M/Pump#2 suction modules.
Change out genset package.

Location Condition: Continue to prepare for rig move.
Clean out mud tanks.

Solids Control Information

Screen Sizes:	Top	Middle	Bottom	Equipment Usage:	Hrs.	
Shaker No 1:	210	210	210	Desander:		
Shaker No 2:	210	210	210	Desilter:		
Shaker No 3:	210	210	210	Degasser:		
Shaker No 4:				Centrifuge No 1:		Barite Recovery
				Centrifuge No 2:		Barite Recovery

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	1546		11005			
BAR 1.5T			10			

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 1249

Accident Description: No accidents or incidents to report

Meetings/Drills	Time	Description
Safety:	30	Held 2 x pre tour safety meeting.Topic discussed .Laying drill pipe . Handling BOP. Truck operations.

☐ **BOP Test** ☑ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 20 **Report for 06:00 AM 29-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	3085.0	**Drilling Days:**	55	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	2979.0	**Days On Location:**	60	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	0.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 2 **Contractor:** 21 **Service:** 2 **Other:** 2 **Total:** 27

Current Operations: Rig move .Rig release at 24:00 hrs on the 28th november

Planned Operations: Rig move to kauri F2

Toolpusher: Mike Preston / Steve Johns

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	8:00	2.00	0	LDDP	Layout 3 1/2 hwdp.
8:00	8:30	0.50	0	OTHER	Retrieve wearbushing and set test plug.
8:30	10:00	1.50	0	OTHER	Layout kelly, L/out RKB ,
10:00	10:30	0.50	0	OTHER	Layout 3 1/2 handling equipment
10:30	17:00	6.50	0	BOPND	Rig down flow line ,blow back koomey lines, l/out annular, rams, spacer spool.
17:00	18:00	1.00	0	OTHER	Nipple up well head valve and pressure test to 3000psi ok.
18:00	0:00	6.00	0	OTHER	Continue cleaning tanks and preparing for rig move
0:00	6:00	6.00	0	RIGD	Release rig at midnight 28th november.

Comments

Production handed over KAURI F2 to drilling 10:00 am 28th November.
Pre job safety meeting prior to rigging down BOPS.
Clean out mud pits with steam cleaner and vacume truck.
Transfer 330 bbls sump waste to spence rd.
Break down mud tanks /remove flow line.
Back load third party rental equipment.
Final fuel dip 38" 8863 ltrs.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
	No AFE Assigned					0	
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019	1,953	91,177	26,098	910,337	100.0%
	Totals $:	4,658,904	1,953	402,898	26,098	3,597,521	

Mud Information

Density	Vis	Filt.	Cake	PV	YP	pH	% Solids	% Water	% Oil	% Sand	Chloride	Gels 10s	Gels 10m	Gels 30m	Temp In	Temp Out
29-Nov 02:00																

Mud Consumable Items

Item Description	Qty.	Cost	Item Description	Qty.	Cost
Engineer -	2	1,400	Mud Storage Tanks -	2	60
condet - 55 Gal Drum	1	493			

BHA Information

BHA - No. 10 - BIT, MMTR, FS, STAB, MWD, 15 HWDP, JAR, 6 HWDP = 216.82

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: Remove modules from mud pump # 2.
Reach crane punctured trye unable to use until repaired

Location Condition: Clean out mud pits witj steam blaster and vacume truck

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 20 **Report for 06:00 AM 29-Nov-05**

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL	2142		8863			
BAR 1.5T			10			

Truck/Boat Status: transfer 330 bbls sump waste to spence rd.
3 x 40 ft flat decks back load third party rental equipment

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 1250

Accident Description:

Meetings/Drills **Time** **Description**

☐ **BOP Test** ☐ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 21 **Report for 06:00 AM 30-Nov-05**

Operator:	Swift Energy New Zealand	**Rig:**	Parker Rig 252	**Proposed TD:**	3270.0	**State:**	TKI
Measured Depth:	0.0	**Drilling Days:**	56	**RKB Elevation:**	5.23	**County:**	Taranaki
Vertical Depth:	0.0	**Days On Location:**	61	**Last Casing:**	7.000 at 2395.0	**Field:**	WAIHAPA
Hole Made:	-3085.0	**Spud Date:**	05-Oct-05	**Next Casing:**	4.500 at 3270.0	**Working Interest:**	100.00%
Drilling Hrs:	0	**Average ROP:**		**Last BOP Test:**	11-Nov-05	**Well Bore:**	Side Track

Personnel: Operator: 1 **Contractor:** 21 **Service:** 1 **Other:** 0 **Total:** 23

Current Operations: Rig move from ahuroa south B-1 ST-1 to Kauri F2.

Planned Operations: Continue to rig move as per parker drilling procedure

Toolpusher: Mike Preston / Steve Johns

Wellsite Supervisors: Troy Reid **Tel No:** 06 762 8743

Operations Summary

From	To	Elapsed	End MD	Code	Operations Description
6:00	19:00	13.00	0	RIGD	Rig move camp 100% rig down rig 25%. Stripped down mud tanks , Undressed rig floor , Scoped mast in and layed over.Steam clean and pressure wash mud tanks. Remove shaker tanks. Backload third party equipment.Backload excess mud chemicals. All lifts over live wells ,production operator to be on site to observe. Mi swaco rigged down there equipment aslo TOT rigged down ther rental equipment.

Comments

Transfered 330 bbls sump waste and taken to spence road for land farming. total removed 660 bbls.
Fuel dip at 39"=8863 ltrs on rig release.

Cost/AFE Information

AFE No	AFE Description	AFE Amount	Daily Mud	Well Mud	Daily Total	Well Total	% Spent
	No AFE Assigned		0	0	0	0	
051203	Dry Hole Cost	2,731,110		311,721		2,687,184	98.4%
051203-C	Completion Cost	1,017,775					0.0%
051203-ST1	Sidetrack Cost	910,019		91,177	23,760	934,097	102.6%
	Totals $:	4,658,904	0	402,898	23,760	3,621,281	

BHA Information

BHA - No. 10 - BIT, MMTR, FS, STAB, MWD, 15 HWDP, JAR, 6 HWDP = 216.82

Rig Information

Rig Name: Parker Rig 252 **RKB Elevation:** 5.23 m

Equipment Problems: Removed modules from Mud pump#2 and sent to town for repair

Logistics Information

Bulk Materials Consumption and Inventory:

	Used This Report Period	Received This Report Period	Inventory	Used This Report Period	Received This Report Period	Inventory
FUEL			8863			
BAR 1.5T			10			

Truck/Boat Status: 3 x 40ft falt decks to remove third party equipment
removed 330 bbls from sump and transfered to speence road.

Drill Pipe Inventory:

DP Size	Joints	Weight	Grade	Thread
3.5	58	15.5	E-75	3.5IF
3.5	106	15.5	G-105	3.5IF
3.5	238	15.5	S-135	3.5IF

Safety Information

First Aid: 0 **Medical:** 0 **Lost Time Accidents:** 0 **Days Since LTA:** 1251

Accident Description:

Meetings/Drills	Time	Description
Safety:	30	Held pre job meeting with all third party contractor prior to commencing operation.Topic discussed Worrking over live well .Production notified of operation over live well and will have a production operator on location while working around live wells. Pre job meeting prior to all lifts around live wells.

☐ **BOP Test** ☐ **Crownamatic Check**

Daily Drilling Report

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Report No: 21 **Report for 06:00 AM 30-Nov-05**

Weather

Sky Condition:	clear	**Visibility:**	
Air Temperature:	20.0 degC	**Bar. Pressure:**	
Wind Speed/Dir:	5 / SE	**Wind Gusts:**	
Comments:	fine clear day		

Casing Report

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Run Date/Time: 21-Oct-05 7:30 **Well Bore:** Original Well Bore
Well Section: INT1 **String Type:** FULL
String Top MD: 5.3 m **String Top TVD:** 7.5 m
Casing Shoe MD: 2395.0 m **Casing Shoe TVD:** 2305.0 m
String Nominal OD: 7.000 ins **String Nominal ID:** 6.184 ins
Bit Diameter: 8.500 ins **Avg. Open Hole Diam.:** 9.200 ins
Centralizers: No: 22 **Manufacturer:** WOOD **Type:** bow spring
Depths: one on first then every 4th jnt for 20 centrilizers
Hanger: Type: wt set **Manufacturer:** WOOD
Comments:
Transferred from Casing Tally Detail on 25-Oct-05 17:26

String Component Details

Joints	Item	Length	O.D.	I.D.	Weight	Grade	Connection	Torque
1	FLOAT S	0.4	7.000	6.184	29.0	L-80	BUTT	
1	JOINT	11.7	7.000	6.184	29.0	L-80	BUTT	
1	FLOAT C	0.4	7.000	6.184	29.0	L-80	BUTT	
203	JOINT	2382.5	7.000	6.184	29.0	L-80	BUTT	
Joints: 206	**Length:**	2395.0						

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1-ST1
Report Date:	**12 Nov 2005**	**Day: 1**	**Report No: 1**
Currently:	**Time drilling @ 2411m to establish kickoff**		**Spud Date: 11th Nov, 2005**

For the period 06:00 to 06:00 hours.

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **06:00 hrs**	2411	2400	11	0.8	1.2	1

Lithology summary

2400-2410m Claystone

CLAYSTONE: nil-25%, medium grey-light olive grey, soft, amorphous- sub blocky, slightly-moderately calcareous, slightly silty in part, trace black specks

CEMENT: 75-100%

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
N/A							

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.15 -0.17						
Max gas @ 2409	0.17	200	0	0	0	0	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
N/a			

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2400	2410	**0**		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2400	8.5	108		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2400	19.96	141.80	2305.27	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki				
McKee				
Mangehewa				
Ahuroa Thrust				
TD				

Additional comments:

Time drill from 2400m to establish kickoff, 25% formation @ 2410m

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1-ST1
Report Date:	**13 Nov 2005**	**Day: 2**	**Report No: 2**
Currently:	**Sliding @ 2428m**		**Spud Date: 11th Nov, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2419	2411	8	0.6	1.1	0.8
@ **06:00 hrs**	2428	2419	9	0.3	1.2	0.9

Lithology summary

2410-2426m Claystone

CLAYSTONE: 70-100%, olive grey, brownish grey, occasionally light olive grey, firm – moderately hard, blocky, occasionally soft, amorphous- sub blocky, slightly-moderately calcareous, slightly silty in part, trace black specks

CEMENT: 0-30%

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
N/A							

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.15 -0.24						
Max gas @ 2418	0.24	87	0	0	0	0	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
N/a			

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2410	2419	1.4		
2419	2428	**0**		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2424	8.5	75		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2400	19.96	141.80	2305.27	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki				
McKee				
Mangehewa				
Ahuroa Thrust				
TD				

Additional comments:

Sliding from 2411m to 2428m, 100% formation by 2420m

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1-ST1
Report Date:	**14 Nov 2005**	**Day: 3**	**Report No: 3**
Currently:	**Drilling @ 2491m**		**Spud Date: 11th Nov, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2433	2428	5	1.2	5.1	2.9
@ **06:00 hrs**	2491	2433	58	2	19	10

Lithology summary

2426-2480m Claystone

CLAYSTONE: 100%, olive grey, brownish grey, occasionally light olive grey, firm – moderately hard, blocky, occasionally soft, amorphous- sub blocky, moderately calcareous, slightly silty in part, trace vein calcite

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
N/A							

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.17 -0.23						
Max gas @ 2479	0.27	19	8	0	0	0	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
N/a			

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2428	2433	5		
2433	2491	0		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2433	8.5	71		
2455	8.55	84		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2450.3	20.66	134.57	2352.07	
2469.33	18.66	135.40	2369.99	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki				
McKee				
Mangehewa				
Ahuroa Thrust				
TD				

Additional comments:

Drilled to 2433m, pulled out of hole to change MWD and bit, run in hole ,continue drilling , 100% claystone @ 2480m

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1-ST1
Report Date:	**15 Nov 2005**	**Day: 4**	**Report No: 4**
Currently:	**Drilling @ 2616m TVD 2514m**		**Spud Date: 11th Nov, 2005**

For the period 06:00 to 06:00 hours.

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2555	2491	64	3.9	20.1	6.3
@ **06:00 hrs**	2616	2555	61	3.6	27	8.5

Lithology summary

2480-2600m Claystone with minor Siltstone

CLAYSTONE: 90-100%, olive grey, brownish grey, occasionally light olive grey, firm – moderately hard, blocky, occasionally soft, amorphous- sub blocky, moderately – occasionally very calcareous, slightly silty in part, trace vein calcite

SILTSTONE: 0-10%, olive grey – brownish black, moderately hard, blocky, moderately calcareous, argillaceous in part grading to silty Claystone

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
N/A							

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.21 -0.30						
Max gas @ 2535	0.36	900	14	0	0	0	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
N/a			

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2491	2555	1.8		
2555	2600	0		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2486	8.5	71		
2566	8.5	70		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2563.69	6.61	140.33	2461.93	
2582.64	4.82	144.36	2480.78	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765			
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD				

Additional comments:

Continued drilling directional hole, 100% claystone @ 2600m

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1-ST1
Report Date:	**16 Nov 2005**	**Day: 5**	**Report No: 5**
Currently:	**Drilling @ 2721m TVD 2618m**		**Spud Date: 11th Nov, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2680	2616	64	2.2	22	9.5
@ **06:00 hrs**	2721	2680	41	1	22	9.6

Lithology summary

2600-2666m Claystone with minor Siltstone

CLAYSTONE: 90-100%, olive grey, brownish grey, occasionally light olive grey, firm – moderately hard, blocky, occasionally soft, amorphous- sub blocky, moderately – occasionally very calcareous, slightly silty in part, trace vein calcite

SILTSTONE: 0-10%, olive grey – brownish black, moderately hard, blocky, moderately calcareous, argillaceous in part grading to silty Claystone

2666-2715m Sandstone with interbedded Siltstone and Claystone

SANDSTONE:10-90% predominantly loose, clear – translucent quartz, very fine upper – medium upper, predominantly fine upper – medium lower, subangular- rounded, well sorted, occasional light grey grain aggregate, friable, trace calcite cement, trace – common argillaceous matrix, rare trace glauconite, trace coal fragments, fair – good porosity, no show.

SILTSTONE:0-30%, olive grey, frm, blky, moderately cacacareous, trace very fine quartz, trace black specks

CLAYSTONE:10-50% light olive grey, yellowish grey, very soft – soft, amorphous, very calcareous, 5 – 10% olive grey as above

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
2669	1.21	12745	690	250	42	0	42
2705	0.64	5329	365	175	39	0	25
2709	0.66	6084	362	174	33	0	24

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.16 -0.29						

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
			Breaks and reverse breaks through Tariki reflecting degree of cementation

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2616	2680	1.3		
2680	2721	0		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2656	8.5	72		
2698	8.6	68		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2677.58	6.06	304.39	2575.57	
2706.24	7.3	302.28	2604.04	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2670	2665	2565	
McKee	3040			
Mangehewa	3060			
Ahuroa Thrust	3160			
TD	3270			

Additional comments:

Continued drilling directional hole, Tariki Sandstone @ 2665m, 60% Sandstone, 30% Siltstone,10% claystone @ 2715m

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1-ST1
Report Date:	**17 Nov 2005**	**Day: 6**	**Report No: 6**
Currently:	**Drilling @ 2768m TVD 2665m**		**Spud Date: 11th Nov, 2005**

For the period 06:00 to 06:00 hours.

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2744	2721	23	1	11.4	5.3
@ **06:00 hrs**	2768	2744	24	1	8	3.3

Lithology summary

2715-2760m Sandstone with interbedded Siltstone and Claystone

SANDSTONE:10-90% predominantly loose, clear – translucent quartz, very fine upper – medium upper, predominantly fine upper, subangular- rounded, well sorted, occasional light grey grain aggregate, friable, trace - common calcite cement, trace – common argillaceous matrix, rare trace glauconite, trace coal fragments, fair – good porosity, no show.

SILTSTONE:5-40%,yellowish grey, olive grey, olive black, firm, blocky, slightly - moderately calcareous, trace very fine quartz grading in part to very fine Sandstone, trace black specks

CLAYSTONE:0-20% light olive grey, yellowish grey, very soft – soft, amorphous, very calcareous, silty in part

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
2739	0.81	7560	370	180	30	0	0
2749	0.75	8100	400	200	40	0	20
2757	0.59	6540	280	170	40	0	20

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.24 -0.35						

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
			Breaks and reverse breaks through Tariki reflecting degree of cementation

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2720	2744	6.6		
2744	2768	4.9		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2723	8.65	68		
2751	8.65	71		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2677.58	6.06	304.39	2575.57	
2706.24	7.3	302.28	2604.04	
2734.87	6.73	299.84	2632.45	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2670	2665	2565	
McKee	3040			
Mangehewa	3060			
Ahuroa Thrust	3160			
TD	3270			

Additional comments:

Continued drilling directional hole, wiper trip at 2762m, hole in good condition, drill ahead sliding to reduce inclination, 90% Sandstone, 10% Siltstone,10% @ 2760m

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1-ST1
Report Date:	**18 Nov 2005**	**Day: 7**	**Report No: 7**
Currently:	**Drilling @ 2836m TVD 2733m**		**Spud Date: 11th Nov, 2005**

For the period 06:00 to 06:00 hours.

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2816	2768	48	1	24	9.7
@ **06:00 hrs**	2836	2816	20	0.7	8	3

Lithology summary

2760-2830m Sandstone with interbedded Siltstone and Claystone

SANDSTONE:40-100%, predominantly loose, clear – translucent quartz, very fine upper – coarse grain upper, predominantly fine upper, subangular- rounded, well sorted, occasional yellowish grey aggregate, friable, trace - common calcite cement, trace – common argillaceous matrix, grades in part to Siltstone rare trace glauconite, fair – good porosity, no show.

SILTSTONE:5-60%, very light grey, yellowish grey, firm, blocky, slightly - moderately calcareous, trace very fine quartz grading in part to very fine Sandstone, rare trace glauconite
From 2820m Siltstone is olive grey – olive black, firm, blocky, slightly – moderately calcareous with traces of carbonaceous fragments

CLAYSTONE:0-30% light olive grey, very soft – soft, amorphous, very calcareous, silty in part

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
2778	1.30	11480	690	320	40	0	10
2791	1.87	15850	1060	460	60	0	20
2807	1.56	13800	900	400	100	0	0

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.24 -0.35						
2794 cxn gas	1.12	8450	620	300	40	0	10

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
2777	2	11	Sandstone with silty matrix

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2744	2816	0		
2816	2836	3.4		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2775	8.65	75		
2818	8.70	72		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2763.61	6.99	303.15	2660.99	
2792.08	7.14	304.10	2689.24	
2820.60	7.90	303.50	2717.51	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2670	2665	2565	
McKee	3040			
Mangehewa	3060			
Ahuroa Thrust	3160			
TD	3270			

Additional comments:

Drilling ahead sliding to reduce inclination, 50% Sandstone, 20% Siltstone,30% Claystone @ 2830m

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1-ST1
Report Date:	**19 Nov 2005**	**Day: 8**	**Report No: 8**
Currently:	**Drilling @ 2873m TVD 2769m**		**Spud Date: 11th Nov, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2853	2836	17	1	14	4
@ **06:00 hrs**	2873	2853	20	1	11	5

Lithology summary

2830-2870m Sandstone with interbedded Siltstone and Claystone

SANDSTONE:10-60%, predominantly loose, clear – translucent quartz, very fine lower – medium lower, predominantly fine upper, subangular- rounded, moderately well sorted, occasional yellowish grey grain aggregate, friable, trace calcite cement, trace – common argillaceous matrix, grades in part to Siltstone, rare trace glauconite trace coal fragments in 2835m sample, poor – good porosity, no show.

SILTSTONE:10-40%, very light grey, yellowish grey, soft, blocky, slightly - moderately calcareous, argillaceous, trace very fine quartz grading in part to very fine Sandstone, rare trace glauconite.
2840m Siltstone is olive grey – olive black, soft - firm, blocky, slightly – moderately calcareous with traces of carbonaceous fragments

CLAYSTONE:10-80% light olive grey, light brown, very soft – soft, amorphous, moderately - very calcareous, silty in part

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.19 -0.37						

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2836	2853	12.1		
2853	2873	0		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2775	8.65	75		
2818	8.70	72		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2792.08	7.14	304.10	2689.24	
2820.60	7.90	303.50	2717.51	
2849.07	8.26	297.31	2745.7	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2670	2665	2565	
McKee	3040			
Mangehewa	3060			
Ahuroa Thrust	3160			
TD	3270			

Additional comments:

Drilling ahead sliding as per directional drillers instruction to reduce holes tendency to build inclination, 30% Sandstone, 70% Claystone @ 2870m

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1-ST1
Report Date:	**20 Nov 2005**	**Day: 9**	**Report No: 9**
Currently:	**Drilling @ 2885m TVD 2781m**		**Spud Date: 11th Nov, 2005**

For the period 06:00 to 06:00 hours.

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2873	2873	0			
@ **06:00 hrs**	2885	2873	12	0.7	5	2.7

Lithology summary

2870-2880m Sandstone with interbedded Siltstone and Claystone

SANDSTONE:40-70%, predominantly loose, clear – translucent quartz, very fine lower – medium lower, predominantly fine upper, subangular- rounded, moderately well sorted, occasional yellowish grey grain aggregate, friable, trace calcite cement, trace – common argillaceous matrix, grades in part to Siltstone, rare trace glauconite trace coal fragments in 2835m sample, poor – good porosity, no show. Samples contain abundant rock flour

SILTSTONE; 10-40%, olive black– brownish black, hard – very hard, blocky, non - slightly calcareous

CLAYSTONE:20% light olive grey, olive grey, very soft – firm, amorphous - blocky, moderately calcareous, silty in part

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.04						
	0.22	255	48	33	31	0	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2873	2853	4.7		
2853	2873	0		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2874	8.7	75		
2874	8.70	74		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2792.08	7.14	304.10	2689.24	
2820.60	7.90	303.50	2717.51	
2849.07	8.26	297.31	2745.7	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2670	2665	2565	
McKee	3040			
Mangehewa	3060			
Ahuroa Thrust	3160			
TD	3270			

Additional comments:

Pulled out of hole to change out BHA and bit. Drilling ahead sliding as per directional drillers instruction 70% Sandstone, 20% Claystone, 10% Siltstone @ 2880m

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1-ST1
Report Date:	**21 Nov 2005**	**Day: 10**	**Report No: 10**
Currently:	**Drilling @ 2953m TVD 2848m**		**Spud Date: 11th Nov, 2005**

For the period 06:00 to 06:00 hours.

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2917	2885	32	0.7	8.2	4.2
@ **06:00 hrs**	2953	2917	36	0.7	5	2.7

Lithology summary

2880-2900m Sandstone with interbedded Siltstone and Claystone

SANDSTONE:30-60%, loose, clear – translucent quartz, very fine lower – fine upper, predominantly very fine upper, subangular- rounded, moderately well sorted, common yellowish grey grain aggregate, friable, trace calcite cement, common silty matrix, grades in part to Siltstone, rare trace glauconite, poor – fair porosity, no show. Samples contain abundant rock flour

SILTSTONE; 20-40%, olive black– brownish black, hard – very hard, blocky, non - slightly calcareous

CLAYSTONE:10-40% light olive grey, olive grey, very soft – firm, amorphous - blocky, moderately calcareous, silty in part

2900-2920m Claystone with interbedded Sandstone and minor Siltstone

CLAYSTONE; 60-70% olive grey, light olive grey, very soft – firm, amorphous – blocky, moderately to occasionally very calcareous

SANDSTONE; 20-60 light grey – yellowish grey, friable – firm, very fine lower – fine upper with common silty matrix, subangular – rounded grains, moderately sorted, trace calcite cement, trace glauconite, poor – fair porosity, no show

SILTSTONE; 10-20%, olive black– brownish black, firm - moderately hard, blocky, non - slightly calcareous

2920-2950m Claystone

CLAYSTONE; 90-100%, olive grey, soft – firm, occasionally moderately hard, blocky, moderately calcareous, slightly silty in part, rare traces black fllecks

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm

Avg Background	0.19-0.30						
Max 2913m	0.55	2240	190	80	40	40	40

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
	2	8	Sandstone into Claystone

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2885	2917	2.0		
2917	2953	4.7		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2895	8.7	77		
2921	8.70	72		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2876.40	7.95	300.12	2772.76	
2904.99	6.76	297.11	2801.11	
2933.32	7.21	296.81	2829.23	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2670	2665	2565	
McKee	3040			
Mangehewa	3060			
Ahuroa Thrust	3160			
TD	3270			

Additional comments:

Drilling ahead at 2953m, formation 100% Claystone (lower Otaraoa)

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1-ST1
Report Date:	**22 Nov 2005**	**Day: 11**	**Report No: 11**
Currently:	**Attempt to work free from coal @ 2993m TVD 2888m**		**Spud Date: 11th Nov, 2005**

For the period 06:00 to 06:00 hours.

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2973	2953	20	1	3	2
@ **06:00 hrs**	2993	2973	20	1.5	20	9.5

Lithology summary

2950-2975m Claystone

CLAYSTONE; 90-100%, olive grey, soft – firm, occasionally moderately hard, blocky, moderately calcareous, slightly silty in part, rare traces black flecks

2975-2980m Claystone with Siltstone

CLAYSTONE; 70%, olive grey, light olive grey, soft – firm, amorphous – subblocky, moderately calcareous

SILTSTONE; 30%, 10% dark greenish grey – greyish black, soft – firm, blocky, moderately calcareous, abundant glauconite.
20% light grey, yellowish grey, soft – firm, blocky, moderately calcareous, trace very fine quartz grains, trace glauconite

2980-2993m Siltstone and Sandstone with Coal

COAL, 50-70%, black, brittle, subvitreous, hackley – subconchoidal fracture

SILTSTONE;20-30%, light olive grey – yellowish grey, soft – firm, blocky, trace calcareous cement, trace quartz grains, grades to silty Sandstone

SANDSTONE; 20-30%, yellowish grey, friable, very fine lower – medium upper, predominantly fine lower, moderately sorted, subangular – rounded, trace calcareous cement, trace glauconite, abundant silty matrix, grades to Siltstone, poor – fair porosity, no show

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
2988	0.57	3785	150	33	9	20	

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm

Avg Background	0.19-0.30						

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
	2	8	Sandstone into Claystone

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2953	2973	9		
2973	2993	0		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2959	8.7	74		
2990	8.70	77		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2933.32	7.21	296.81	2829.23	
2961.96	7.37	291.0	2857.64	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2670	2665	2565	samples
McKee	3040			??
Mangehewa	3060	2983	2878	Samples coal in spot sample
Ahuroa Thrust	3160			
TD	3270			

Additional comments:

Drilled to 2993m, got stuck for 30min in coal, currently circulating and conditioning hole to work free. Mckee sandstone wasn't seen, possible condensed silty section between 2975 – 2983m , drilled coal at 2983m, 2878mTVD. Mangahewa 77m high on prognosis (md).

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1-ST1
Report Date:	**23 Nov 2005**	**Day: 12**	**Report No: 12**
Currently:	**Drilling @ 3022m TVD 2917m**		**Spud Date: 11th Nov, 2005**

For the period 06:00 to 06:00 hours.

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	3002	2993	9	1	1.4	1.2
@ **06:00 hrs**	3022	3002	20	1.5	20	9.5

Lithology summary

2993-3018m Siltstone with coal and carbonaceous Claystone

COAL, Trace-70%, black, hard - brittle, vitreous, hackley – sub-conchoidal fracture

SILTSTONE;5-95%, light olive grey – yellowish grey, soft – firm, blocky, nil -trace calcareous cement, trace carbonaceous specks, trace quartz grains, grades to very fine silty Sandstone

CLAYSTONE; Trace-80%, brownish grey, brownish black, moderately hard – hard, blocky – irregular fracture, non calcareous

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.11-0.30						
Max 2996	0.29	616	32	0	19	5	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2993	3002	12		

3002	3015	3		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2994	8.7	75		
3004	8.70	76		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2961.96	7.37	291.0	2857.64	
2988.33	7.39	288.92	2883.79	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2670	2665	2565	samples
McKee	3040			??
Mangehewa	3060	2983	2878	Samples coal in spot sample
Ahuroa Thrust	3160			
TD	3270			

Additional comments:

Control drilled from 2993m – 3005m to prevent getting stuck in coal, monitored coal percentage taking 1m spot samples. Continued drilling to 3022m, formation at 3018m; Siltstone 85%, Coal 15%

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1-ST1
Report Date:	**25 Nov 2005**	**Day: 1**	**Report No: 14**
Currently:	**Pull out of hole, bit @ 216m**		**Spud Date: 11th Nov, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ 18:00 hrs	3085	3050	35	0.8	7	4.9
@ 06:00 hrs						

Lithology summary

3050-3085mTD Claystone

CLAYSTONE: 100%, medium dark grey, dark grey, firm – moderately hard, blocky, moderately calcareous becoming slightly – non calcareous below 3060m, trace calcite veining

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.13-0.29						
Max 3077	0.29	171	10	0	0	0	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
3050	3085	0		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
3085	8.7	74		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
3047.86	8.34	287.78	2942.75	
3069.23	8.38	287.69	2963.90	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2670	2665	2565	samples
McKee	3040			??
Mangehewa	3060	2983	2878	Samples coal in spot sample
Ahuroa Thrust	3160	3034	2929	samples
TD	3270	3085	2979	

Additional comments:

Continued drilling Manganui claystone to TD @ 3085m MD, TVD 2979.6m. Do wiper trip back to shoe, pull out of hole for wireline logging.

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**12 Oct 2005**	**Day: 8**	**Report No: 1**
Currently:	**Drilling ahead at 983m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 8.5" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **06:00 hrs**	983	659	324	3.81	98.49	42.0

Lithology summary

659-820m Massive Claystone.

CLAYSTONE: 100%, light bluish grey-medium grey, getting greenish grey-dark greenish grey w/ depth, soft, dispersive, amorphous, non calcareous, trace vfL-fL quartz grains, trace shell fragments.

820-980m Predominantly Sandstone with minor Claystone and Limestone stringers.

CLAYSTONE: tr-10%, greenish grey-dark greenish grey w/ depth, soft-firm, dispersive, amorphous to sub-blocky, non-slightly calcareous, trace vfL-fL quartz grains, trace shell fragments.

SANDSTONE: 90-100%, light olive grey-very light grey-light greenish grey, clear-translucent, soft-unconsolidated, vfU-mL, sub rounded to sub angular, well sorted, trace glauconite, good inferred porosity, no show

LIMESTONE: nil-tr, white-very light grey, firm-hard, micro-crystalline, trace vfU-fL quartz grains, grades to very calcareous Sandstone in part, trace shell fragments.

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
N/A							

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.10						
Max gas	0.28	128	0	0	0	0	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
N/A			No significant breaks seen.

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
659	980	**24**	**2-4**	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
659	8.77	39	42,000	

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
935.58	19.86	130.44	926.65	
962.41	19.33	131.71	951.92	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230			
Tikorangi	1940			
Otaraoa	2100			
Tariki	2765			
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Tag cement at 634 m. Drill out cement and casing shoe. Drill new formation to 662m, do LOT. Drill ahead. Currently drilling ahead at 983 m MD.

Geologist: Keith Frankiewicz

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**13 Oct 2005**	**Day: 9**	**Report No: 2**
Currently:	**Drilling ahead at 1273m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 8.5" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **06:00 hrs**	1273	983	290	0.93	72.98	24.89

Lithology summary

820-980m Interbedded Sandstone and Siltstone, with minor Claystone.

CLAYSTONE: tr-5%, greenish grey-dark greenish grey, soft-firm, dispersive, amorphous to sub-blocky, non-slightly calcareous, trace vfL-fL quartz grains, trace shell fragments.

SILTSTONE:30-40%, medium grey-olive grey, soft-moderately firm, sub blocky, non calcareous, trace vfL quartz, grades to very fine grained sandstone in part, trace micromica.

SANDSTONE: 55-65%, light olive grey-very light grey-light greenish grey, clear-translucent, soft-unconsolidated, vfU-mL, sub rounded to sub angular, well sorted, trace glauconite, good inferred porosity, no show

980-1200m Interbedded Claystone and Sandstone w/ trace Siltstone and Limestone stringers.

CLAYSTONE: 5-95%, greenish grey-dark greenish grey-olive grey, soft-firm, dispersive, amorphous to sub-blocky, non calcareous, trace vfL-fL quartz grains, commonly silty, grades to Silty Claystone in parts, rare trace shell fragments.

SILTSTONE: nil-5%, olive grey-olive black, hard-very hard, blocky, non calcareous, trace vfL quartz, trace-common micromica.

SANDSTONE: 10-95%, light olive grey-very light grey-light bluish grey, clear-translucent, soft-unconsolidated, vfL-fL, sub rounded to sub angular, well sorted, common argillaceous matrix, no calcareous, trace glauconite, fair inferred porosity, no show

LIMESTONE: nil-5%, white-very light grey, firm-hard, micro-crystalline, trace vfU-fL quartz grains, grades to very calcareous Sandstone in part, trace shell fragments.

1200-1270m Claystone.

CLAYSTONE: 100%, medium grey-olive grey, soft-firm, dispersive, amorphous to sub-blocky, non calcareous, trace vfL-fL quartz grains, commonly silty, grades to Silty Claystone in parts, trace micromica.

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
N/A							

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.07-0.09						
Max gas	0.096	389	0	0	0	0	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
1141	5-10	1+	Reverse break.

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
980	1273	**23**	**1-2**	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
1069	9.2	39	52,000	
1223	9.15	40	50,000	

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
1204.71	19.52	136.5	1180.66	
1231.46	20.14	136.47	1205.82	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230			
Tikorangi	1940			
Otaraoa	2100			
Tariki	2765			
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Currently drilling ahead at 1273 m MD.

Geologist: Keith Frankiewicz

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**14 Oct 2005**	**Day: 10**	**Report No: 3**
Currently:	**Drilling ahead at 1485m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 8.5" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **06:00 hrs**	1485	1273	212	3.99	47.73	19.08

Lithology summary

1270-1290m Claystone.

CLAYSTONE: 100%, medium grey-olive grey, soft-firm, dispersive, amorphous to sub-blocky, non calcareous, trace vfL-fL quartz grains, commonly silty, grades to Silty Claystone in parts, trace micromica.

1290-1460m Predominantly Claystone w/ minor interbedded Sandstones.

CLAYSTONE: 90-100%, medium grey-medium dark grey, soft, dispersive, amorphous to sub-blocky, slightly-moderately calcareous, trace-common vfL-fL quartz grains, trace micromica. At 1410-1420m, had tr-10% bright yellowish white direct fluorescence, very slow bluish white cut fluorescence, w/ faint-patchy yellowish white residual ring fluorescence, poor show.

SANDSTONE: nil-10%, white-very light grey-clear-translucent-transparent, soft, unconsolidated, predominantly loose quartz, fL-cL, sub angular to sub round, occasionally angular, poorly sorted, trace mica, god inferred porosity, no show.

1460-1485 Interbedded Claystone and Sandstone.

CLAYSTONE: 70%, olive grey, soft, dispersive, amorphous to sub-blocky, moderately calcareous, trace-common vfL-fL quartz grains, trace micromica.

SANDSTONE: 30%, generally as above, white-very light grey-clear-translucent-transparent, soft, unconsolidated, predominantly loose quartz, fL-cL, sub angular to sub round, occasionally angular, poorly sorted, trace mica, god inferred porosity, common mineral fluorescence, no show.

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
N/A							

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.07-0.09						
Max gas	0.11	539	0	0	0	0	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
1350	3.1	5.6	
1419	3.2	9.9	

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
1273	1485	**183**	**7**	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
1280	9.2	45	50,000	
1430	9.2	44	49,000	

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
1420.46	18.94	136.54	1384.78	
1447.30	19.29	135.90	1410.14	
1474.18	19.86	135.22	1435.46	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200		Last sand bed
Tikorangi	1940			
Otaraoa	2100			
Tariki	2765			
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Currently drilling ahead at 1485 m MD.
Had minor hydrocarbon fluorescence in associated with Claystone from 1414-1420m.

Geologist: Keith Frankiewicz

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**15 Oct 2005**	**Day: 11**	**Report No: 4**
Currently:	**Drilling ahead at 1700m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 8.5" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **06:00 hrs**	1700	1485	215	3.62	39.18	15.39

Lithology summary

1485-1630m Interbedded Claystone and Sandstone.

CLAYSTONE: 80-100%, light olive grey-olive grey, soft, dispersive, amorphous to sub-blocky, moderately calcareous, trace vfL-fL quartz grains, trace micromica. Had hydrocarbon fluorescence at: 1485-1530m, 1540-1560m, 1590-1600m, 1610-1620m: predominantly trace to occasionally 5-10% bright yellowish white direct fluorescence, very slow-slow blooming bluish white cut fluorescence, thin patchy bluish white residue ring fluorescence, poor show. From 1637-1640m, and 1650-1660m: trace bright yellowish white direct fluorescence, no cut fluorescence, no show.

SANDSTONE: nil-20%, white-very light grey-clear-translucent-transparent, soft, unconsolidated, predominantly loose quartz, fL-cL, sub angular to sub round, occasionally angular, poorly sorted, trace mica, good inferred porosity, common mineral fluorescence, no show.

1630-1680m Claystone, Siltstone, and Sandstone.

CLAYSTONE: 50-90%, light olive grey, soft, dispersive, amorphous to sub-blocky, moderately calcareous, trace vfL-fL quartz grains. Had fluorescence at: 1650-1680m: trace bright yellowish white direct fluorescence, no cut fluorescence, no show.

SILTSTONE: 5-20%, light olive grey-greenish grey, firm-hard, sub blocky, moderately calcareous, argillaceous, grades to silty Claystone in part.

SANDSTONE: 5-40%, white-very light grey-clear-translucent-transparent, soft, unconsolidated, predominantly loose quartz, vfL-vfU, sub angular to sub round, well sorted, good inferred porosity, common mineral fluorescence, no show.

1680-1700m Claystone.

CLAYSTONE: 100%, medium grey, soft-firm, sub-blocky, moderately calcareous, trace vfL-fL quartz grains, had trace of bright yellowish white direct fluorescence, no cut fluorescence, no show.

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
N/A							

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.07-0.085						
Max gas @ 1555	0.165	600	0	0	0	0	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
1606	1+	6.0	Sst in samples
1651	3.1	9.1	Increase in Sand in cuttings

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
1485	1700	**112**	**4-5**	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
1500	9.3	42	48,000	
1668	9.2	44	49,000	

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
1635.53	19.73	135.14	1586.53	
1662.21	20.06	135.12	1611.62	
1689.11	20.17	135.16	1636.88	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200		Last sand bed
Tikorangi	1940			
Otaraoa	2100			
Tariki	2765			
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Currently drilling ahead at 1700 m MD.
Had minor hydrocarbon fluorescence in associated with Claystone from 1485 down to 1620m. Below that, there was fluorescence but no cut fluorescence. We are not seeing any shows in the sands (possibly because they are all loose and the hydrocarbons have been washed out).

Geologist: Keith Frankiewicz

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**16 Oct 2005**	**Day: 12**	**Report No: 5**
Currently:	**Drilling ahead at 1915m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 8.5" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **06:00 hrs**	1915	1700	215	0.87	38.4	18.55

Lithology summary

1700-1740m Claystone.

CLAYSTONE: 100%, medium grey-dark grey-greenish grey, soft-firm, sub-blocky, moderately calcareous, trace vfL-fL quartz grains.

1740-1911m Predominantly Claystone with minor Siltstone and Sandstones and occasional Limestone stringers.

CLAYSTONE: 75-100%, medium grey-dark grey-greenish grey, soft-firm, sub-blocky, moderately calcareous, getting very calcareous with depth, silty in part, trace vfL-fL quartz grains.

SILTSTONE: nil-10%, dark greenish grey-olive black, firm-hard, sub blocky to blocky, moderately to very calcareous, argillaceous, grades to Claystone in part.

SANDSTONE: nil-10%, light grey-medium grey, translucent, soft, friable, predominantly loose quartz, vfL-fL, well sorted, calcareous matrix, argillaceous, good inferred porosity, no show.

LIMESTONE: nil-25%, light grey-light grey, firm, sub blocky, argillaceous, trace vfL quartz.

1911-1915 Limestone w/ minor Claystone and Siltstone.

LIMESTONE: 25-60%, very light grey-light grey, soft-firm, sub blocky, argillaceous, grades to very calcareous Claystone in part, trace vfL quartz.

CLAYSTONE: 5-60%, medium grey-dark grey-greenish grey, soft-firm, sub-blocky, moderately calcareous, getting very calcareous with depth, silty in part, trace vfL-fL quartz grains.

SILTSTONE: 5-10%, dark greenish grey-olive black, firm-hard, sub blocky to blocky, moderately to very calcareous, argillaceous, grades to Claystone in part.

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
N/A							

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.08						
Max gas @ 1904	0.385	2100	160	70	30		

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
1911	3.8	1+	Top of limestone in samples.

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
1700	1915	**86**	**3-4**	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
1766	9.3	45	44,000	
1854	9.3	44	51,000	

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
1882.71	19.25	135.04	1818.65	
1910.83	18.93	134.20	1845.23	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100			
Tariki	2765			
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Currently drilling ahead at 1915 m MD.
Saw the top Tikorangi at ~ 1911 m MD. Had a decrease in ROP along with Limestone in the samples.

Geologist: Keith Frankiewicz

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**17 Oct 2005**	**Day: 13**	**Report No: 6**
Currently:	**Drilling ahead at 2130m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 8.5" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **06:00 hrs**	2130	1915	215	3.65	29.04	15.63

Lithology summary

1915-2010m Limestone w/ minor Siltstone.

LIMESTONE: 95-100%, white-very light grey-light grey, soft-firm, sub blocky, argillaceous, grades to very calcareous Claystone in part, trace vfL quartz.

SILTSTONE: nil-5%, dark greenish grey-olive black, medium bluish grey in part, firm-hard, sub blocky to blocky, moderately to very calcareous, argillaceous, grades to Claystone in part.

2010-2130m Predominantly Siltstone with occasional interbedded Claystone and Limestone stringers.

SILTSTONE: 20-100%, medium grey-olive grey, soft-firm, sub blocky to occasionally blocky, moderately to very calcareous, argillaceous, grades to Claystone in part, trace black specks.

CLAYSTONE: nil-10%, medium dark grey-olive grey, soft, sub blocky, moderately calcareous, silty, grades to Siltstone in part, trace black specks.

LIMESTONE: nil-5%, white-very light grey-light grey, soft-firm, sub blocky, argillaceous, grades to very calcareous Claystone in part, trace vfL quartz.

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
N/A							

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.05						
Max gas @ 1966	0.967	133	15	5	19		

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
N/a			

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
1915	2130	**153**	**4-6**	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
1957	9.3	45	45,000	
2088	9.35	44	48,000	

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2081.20	19.19	137.35	2006.34	
2110.05	19.43	138.72	2033.56	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765			
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Currently drilling ahead at 2130 m MD.
Saw the base Tikorangi at ~ 2010 m MD.

Geologist: Keith Frankiewicz

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**18 Oct 2005**	**Day: 14**	**Report No: 7**
Currently:	**At 8 ½" td @ 2400m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 8.5" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **06:00 hrs**	2400	2130	270	4.42	34.76	20.99

Lithology summary

2130-2400m Predominantly Siltstone with occasional interbedded Claystone and Limestone stringers.

SILTSTONE: 10-100%, medium grey-olive grey, greenish grey in part, soft-firm, very hard in parts, sub blocky to occasionally blocky, moderately to very calcareous, argillaceous, grades to Claystone in part, trace black specks, trace micromica, trace forams.

CLAYSTONE: nil-10%, medium grey-olive grey, soft, sub blocky, slightly-moderately calcareous, silty, grades to Siltstone in part, trace black specks, trace forams.

LIMESTONE: nil-trace%, white-very light grey-light grey, soft-firm, sub blocky, argillaceous, grades to very calcareous Claystone in part.

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
N/A							

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.06-0.07						
Max gas @ 2246	0.11	155	0	0	0	0	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
N/a			Nothing substantial

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2130	2400	**198**	**6-8**	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2228	9.3	44	44,500	
2370	9.3	45	47,000	

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2348.33	19.97	140.39	2256.70	
2378.0	19.93	141.01	2284.59	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765			
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Drilled to the 8 ½" hole section TD of 2400 m MD. Currently doing wiper trip to shoe.
Will do rig service at shoe, run back to bottom and circulate to condition hole for logs, and then POOH to rig up Schlumberger. Likely logging early AM hours.

Geologist: Keith Frankiewicz

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**24 Oct 2005**	**Day: 20**	**Report No: 8**
Currently:	**Drilling 6" hole @ 2555m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2465	2400	65	0.2	29.2	15.2
@ **06:00 hrs**	2555	2465	90	3.6	28.9	15.8

Lithology summary

2400-2540m, Claystone with minor Siltstone

CLAYSTONE:90 - 100%, olive grey, brownish grey – brownish black, soft – moderately hard, sub blocky - blocky, moderately calcareous, silty in part with trace black specks, trace crystalline calcite, trace fossil fragments (shell, bryazoan).

SILTSTONE: 0-10%, medium grey-olive grey, greenish grey in part, soft-firm, very hard in parts, sub blocky to occasionally blocky, moderately calcareous, argillaceous, grades to Claystone in part, trace black specks, trace micromica

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
N/A							

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Avg Background	0.09-0.15						
Max gas @ 2525	0.15	227	10	0	0	0	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
N/a			Nothing substantial

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2400	2465	4	0.3	
2465	2555	16.8	1.5	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2405	8.55	60		
2486	8.5	56		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2493.65	18.81	135.44	2393.66	
2521.81	18.40	135.69	2420.35	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765			
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Drilled shoe track, rathole and 3m off new formation, performed FIT, continue to drill ahead 6” hole, sliding and rotating as per directional drillers instruction. Currently drilling Claystone.

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**25 Oct 2005**	**Day: 21**	**Report No: 9**
Currently:	**Drilling 6" hole @ 2740m MD.**		**Spud Date: 5th Oct, 2005**

For the period 06:00 to 06:00 hours.

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2660	2555	105	2.9	29.3	16.9
@ **06:00 hrs**	2740	2660	80	2.6	24.8	13.6

Lithology summary

2540 - 2710m, Claystone

CLAYSTONE: 100%, olive grey, brownish grey – brownish black, soft – moderately hard, sub blocky - blocky, moderately calcareous, slightly silty in part, trace crystalline calcite, tr microcrystalline mica, slight colour change below 2590m becoming light olive grey – olive grey, soft, amorphous, moderately – very calcareous and sticky.

2710 – 2735m, Sandstone with minor Siltstone and Claystone

SANDSTONE: 10 – 95%, very light grey – light grey, friable – firm, as loose grains from 2715m – 2725m, clear – translucent quartz, very fine lower – coarse lower grains, poor – moderately sorted, subangular - subrounded, nil – common calcite cement, nil – good porosity dependant on cementation, no shows

SILTSTONE; 0 – 50%, olive grey, firm – moderately hard, blocky, slight – moderately calcareous, trace black specks

CLAYSTONE: 5 - 50%, olive grey, brownish grey – brownish black, firm – moderately hard, sub blocky - blocky, moderately calcareous, slightly silty in part

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
2711	0.25	500	80	30	50	90	0
2717	0.44	2590	220	90	50	60	0

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
2715m Cxn gas	0.576	3820	330	150	50	60	10
2723m Cxn Gas	0.438	2630	190	70	40	50	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks

2713	20	55	Sandstone

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2555	2660	2		
2660	2740	2		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2533	8.5	40		
2690	8.5	58		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2690.57	18.77	134.20	2580.04	
2718.54	19.23	133.96	2606.49	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765	2710	2598	samples
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Drilled Claystone to 2710m, drilled in to Tariki sand at 2710m. Litholgy @ 2735m 30% Sandstone, 50% Siltstone, 20% Claystone.

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**26 Oct 2005**	**Day: 22**	**Report No: 10**
Currently:	**Drilling 6" hole @ 2788m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2775	2740	35	1.3	16.1	5.8
@ **06:00 hrs**	2788	2775	13	0.9	5.2	3.1

Lithology summary

2735 – 2787m, Sandstone with interbedded Siltstone and Claystone

SANDSTONE: Trace – 60%, very light grey – light grey, loose grains , clear – translucent quartz, very fine lower – coarse lower grains, poor – moderately sorted, subangular - subrounded, common strongly calcite cemented grain aggregate, hard, nil – good porosity dependant on cementation, trace coal fragment, trace glauconite, no shows

SILTSTONE; Trace – 40%, olive grey – olive black, firm – moderately hard, blocky, slightly – moderately calcareous, trace black specks

CLAYSTONE: 20 - 100%, light olive grey - olive grey, soft, amorphous - subblocky, moderately - very calcareous, stick

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
2786	0.18	345	74	42	39	62	

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
2776	3	11	sandstone

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2740	2775	0		
2775	2788	3.4		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2737	8.5	59		
2785	8.5	60		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2746.40	18.27	136.72	2632.87	
2773.77	19.19	134.73	2658.79	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765	2710	2598	samples
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Drilled to 2787m and did a wipertrip back to the shoe, drilled ahead.

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**27 Oct 2005**	**Day: 23**	**Report No: 11**
Currently:	**Drilling 6" hole @ 2833m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2815	2788	27	0.9	13	4.6
@ **06:00 hrs**	2833	2815	18	0.9	8.9	3.2

Lithology summary

2787 – 2830m, Sandstone with interbedded Siltstone and Claystone

SANDSTONE: Trace – 90%, very light grey – light grey, loose grains , clear – translucent quartz, very fine lower – coarse lower grains, poor – moderately sorted, subangular - subrounded, common strongly calcite cemented grain aggregate, hard, trace coal fragment, trace glauconite, nil – good porosity dependant on cementation no shows. Samples from 2800 – 2815m have abundant rock flour)

SILTSTONE; Trace – 10%, olive grey – olive black, firm – moderately hard, blocky, slightly – moderately calcareous, trace black specks

CLAYSTONE: trace - 90%, light olive grey - olive grey, soft - firm, amorphous - subblocky, moderately - very calcareous, sticky in part, silty in part grading to Siltstone

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
2804	0.43	594	125	44	8	16	0
2809	0.55	1826	175	93	25	29	0
2822	0.44	1757	109	89	26	56	0

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
2796 cxn gas	0.64	2740	290	120	30	40	0
2806 cxn gas	0.50	746	176	59	15	24	0

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
2797	1	11	Into loose sand
2816	3.3	1	Reverse break into cemented Sanstone

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks

2788	2815	0		
2815	2833	5.5		

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2819	8.6	62		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2746.40	18.27	136.72	2632.87	
2773.77	19.19	134.73	2658.79	
2803.47	18.90	135.14	2686.87	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765	2710	2598	samples
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Drilled to 2833m, slow drilling due to hard cemented sandstone

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**28 Oct 2005**	**Day: 24**	**Report No: 12**
Currently:	**Drilling 6" hole @ 2880m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2852	2833	19	1.2	8.5	3.7
@ **06:00 hrs**	2880	2852	28	1.6	22.1	6.4

Lithology summary

2830 – 2875m, Sandstone with interbedded Siltstone and Claystone

SANDSTONE: 50 – 100%, very light grey – light grey, loose grains , clear – translucent quartz, very fine lower – coarse upper grains, moderately sorted, subangular - subrounded, common strongly calcite cemented grain aggregate, friable – hard, very fine lower – fine upper, nil – common argillaceous matrix, grades in part to Siltstone, nil – good porosity dependant on cementation no shows.

SILTSTONE; 0 – 40%, brownish black – olive grey, firm – moderately hard, blocky, slightly – moderately calcareous, trace black specks, trace very fine quartz, grading to Sandstone

CLAYSTONE: trace - 10%, light olive grey - olive grey, soft - firm, amorphous - subblocky, moderately - very calcareous, sticky in part, silty in part grading to Siltstone

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
2845	0.67	2812	273	140	28	21	0
2871	0.45	2700	200	100	40	20	0

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
2846	1.5	7.0	cemented sandstone into loosely consolidated sandstone
2871	5.0	22	Cemented sandstone into loosely consolidated sandstone

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2833	2852	3.2	0.3	
2852	2852	2880	0.9	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2832	8.6	62		
2864	8.6	55		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2822.15	18.12	135.14	2704.58	
2850.50	18.31	135.26	2731.51	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765	2710	2598	samples
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Continue drilling to 2880m, formation 90% sandstone in last sample(2875m).

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**29 Oct 2005**	**Day: 25**	**Report No: 13**
Currently:	**Run in hole new bit #5**		**Spud Date: 5th Oct, 2005**

For the period 06:00 to 06:00 hours.

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2903	2880	23	1.6	20.9	8.4
@ **06:00 hrs**	2903	2903				

Lithology summary

2875 – 2903m, Sandstone with interbedded Siltstone and Claystone

SANDSTONE: 20 – 100%, very light grey – light grey, loose grains , clear – translucent quartz, very fine lower – coarse upper grains, predominantly fine upper –medium lower, moderately sorted, subangular - subrounded, occasional calcite cemented grain aggregate, friable – hard, very fine lower – fine upper, nil – trace argillaceous matrix, grades in part to Siltstone, trace coal fragments from 2895m, rare glauconite, nil – good porosity dependant on cementation, no shows.

SILTSTONE; 0 – 40%, brownish black – olive grey, firm – moderately hard, blocky, slightly – moderately calcareous, trace black specks, trace very fine quartz, grading to Sandstone

CLAYSTONE: trace - 10%, olive grey, firm, blocky, moderately calcareous, silty in part grading to Siltstone

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
2899	0.48	623	145	70	19	28	0

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
2871	12	72	sandstone
2887	6.8	14	sandstone

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2852	2903	7	0.6	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2880	8.65	61		
2903	8.65	58		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2850.50	18.31	135.26	2731.51	
2879.09	19.21	130.07	2758.58	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765	2710	2598	samples
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Continue drilling sandstone to 2903m, pull out of hole to change the bit due to slow ROP, 0600hrs running in hole, bit at 1650m.

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**31 Oct 2005**	**Day: 27**	**Report No: 14**
Currently:	**Drilling 6" hole @ 2992m**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	2967	2903	64	1.8	27.8	11
@ **06:00 hrs**	2992	2967	25	1.2	11.5	4.3

Lithology summary

2903 – 2985m, Sandstone with interbedded Siltstone and Claystone and minor Limestone

SANDSTONE: 10 – 100%, very light grey – light grey, loose grains , clear – translucent quartz, very fine lower – coarse upper grains, predominantly fine upper –medium lower, moderately sorted, subangular - subrounded, occasional grain aggregate with abundant calcite cement, grading in part to sandy Limestone, friable – hard, very fine lower – fine upper, nil – trace argillaceous matrix, trace coal fragments, rare glauconite, nil – good porosity dependant on cementation, no shows.

LIMESTONE; 0 – 20%, very light grey, soft – moderately hard, predominantly cryptocrystalline, occasionally microcrystalline, trace to common quartz grains, trace glauconite, grades to calcareous sandstone, no show.

SILTSTONE; 0 – 20%, brownish black – olive black, firm – moderately hard, blocky, slightly – moderately calcareous, trace black specks, trace very fine quartz, grading to Sandstone

CLAYSTONE: 5 - 90%, light olive grey – olive grey, soft – moderately hard, amorphous - sub blocky, sticky in part, moderately - very calcareous, rare glauconite, silty in part grading to Siltstone

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
2930	0.68	3896	283	143	37	36	16
2935	0.77	4514	470	228	52	64	21
2948	0.55	3377	230	111	41	46	17
2959	0.72	4228	322	153	35	31	11
2982	0.58	3900	300	100	0	0	0

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
2925 cxn gas	0.5	2081	229	120	25	31	9

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2903	2967	13.8	1.2	
2903	2992	3.6	0.3	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2880	8.65	61		
2903	8.65	58		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
2944.18	21.73	130.24	2758.58	
2972.15	21.26	130.94	2845.47	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765	2710	2598	samples
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Ran in hole new bit, MWD failed, pulled out of holeand replaced MWD, ran back in the hole, drill ahead to 2992m. Formation at 2985m 30% cemented Sanstone, 40% Siltstone, 30% Claystone.

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**31 Oct 2005**	**Day: 27**	**Report No: 15**
Currently:	**Drilling 6" hole @ 3054m**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	3029	2992	37	1.5	22	3.6
@ **06:00 hrs**	3054	3029	25	1.1	9.0	2.9

Lithology summary

2985 – 3015m, Claystone with interbedded Siltstone and Sandstone

CLAYSTONE: 50 - 100%, light olive grey – olive grey, soft – firm, amorphous - sub blocky, sticky in part, moderately - very calcareous, rare glauconite, silty in part grading to Siltstone

SILTSTONE; 0 – 20%, brownish black – olive black, firm – moderately hard, blocky, slightly – moderately calcareous, trace black specks, trace very fine quartz, grading to Sandstone in part

SANDSTONE: 0 – 30%, very light grey – light grey, loose grains , clear – translucent quartz, very fine lower – medium upper grains, predominantly fine lower, moderately well sorted, subangular - subrounded, common grain aggregate with abundant calcite cement, trace argillaceous matrix, friable – firm, very fine lower – fine upper, trace coal fragments, rare glauconite, nil – fair porosity no shows.

3015 – 3050, Sandstone and siltstone with minor Claystone

SANDSTONE; 10 – 90% light grey, firm, occasionally hard, very fine lower – medium lower, predominantly fine lower, subangular - subrounded, moderately well sorted, common calcitic cement, trace argillaceous matrix, trace glauconite, nil – poor visible porosity, no shows

SILTSTONE; 10 – 80%, olive grey, dark grey, soft – firm, sub-blocky – blocky, slightly calcareous, argillaceous in part grading to Claystone

CLAYSTONE; 10 - 80%, light olive grey – olive grey, soft – firm, amorphous - sub blocky, sticky in part, moderately - very calcareous, rare glauconite, silty in part grading to Siltstone

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
3014	0.57	1180	307	106	37	130	46
3038	0.50	2840	254	118	37	47	32

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
2992	3029	9.7	0.8	
3029	3054	5.5	0.5	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
2993	8.65	62		
3037	8.7	63		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
3000.49	20.97	132.92	2871.91	
3029.69	21.95	133.21	2899.09	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765	2710	2598	samples
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

drill ahead to 3054m. Formation at 3050m 80% Siltstone, 10% Sandstone, 10% Claystone.

Geologist: Bill Prin

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**2 Nov 2005**	**Day: 29**	**Report No: 16**
Currently:	**Drilling ahead at 3115m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6.0" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	3089	3054	35	1.3	12.4	5.4
@ **06:00 hrs**	3115	3089	26	1.1	8.6	4.1

Lithology summary

3050-3090m Sandstones and Siltstone with minor Claystone.

SANDSTONE: 20-100%, light grey,fri - firm, occasionally hard cemented grain aggregate, very fine lower – coarse lower, predominantly fine lower, subangular – subrounded, moderately sorted, common calcitic cement, trace - common argillaceous matrix, grades in part to Siltstone, trace glauconite, nil – poor porosity, no shows.

SILTSTONE: 10-60%, olive grey,- dark grey, soft - firm, subblocky, slightly - moderately calcareous, trace very fine quartz, trace glauconite, argillaceous in part grading to Claystone.

CLAYSTONE: 0-80%, light olive grey - olive grey, soft - firm, amorphous - subblocky, sticky in part moderately calcareous, rare glauconite, silty in part grading to Siltstone

3090-3110m Claystone.

CLAYSTONE: 100%, olive grey,- olive black, firm - occasionally moderately hard, moderately calcareous, slightly silty in part

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
3075	0.85	4475	422	219	40	48	14

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
3058	4	9	Loosely consolidated sandstone
3075	2	10	Loosely consolidated sandstone

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
3054	3089	14.7	1.2	
3089	3115	6.5	0.6	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
3058	8.7	65		
3098	8.7	66		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
3057.92	21.95	133.21	2899.09	
3086	22.18	135.33	2951.48	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765	2710	2598	samples
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Drilling ahead at 3115 m MD. Formation at 3110m 100% Claystone (basal Otaoroa)

Geologist: Bill Prin)

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**3 Nov 2005**	**Day: 30**	**Report No: 17**
Currently:	**Drilling ahead at 3172m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6.0" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	3137	3115	22	1.2	6.3	3.5
@ **06:00 hrs**	3171	3137	34	2.2	8.3	4.6

Lithology summary

3110-3140m Claystone with minor Sandstone.

CLAYSTONE: 70-100%, olive grey, soft - firm, occasionally moderately hard, amorphous – subblocky, moderately calcareous, slightly silty in part

SANDSTONE; 10-30%, light grey, friable – hard, very fine lower – fine upper, subangular – subrounded, moderately well sorted, abundant strong calcite cement, common loose grains, trace glauconite, nil – fair porosity, n/s

3140-3165m Claystone.

CLAYSTONE; 100%, olive grey, soft - firm, occasionally moderately hard, blocky, moderately calcareous.

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
3132	0.45	243	100	57	45	125	50

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Background gas	0.16-0.25						

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
3115	3137	14.7	1.2	
3137	3171	4.6	0.4	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
3138	8.7	68		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
3115.04	21.89	138.31	2978.18	
3143.80	21.05	141.58	3004.94	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765	2710	2598	samples
McKee	3180	3060	2927	?? samples
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Drilling ahead at 3172m, no sign of Mckee at prognosed TVD, sand at 3060m possibly McKee TVD 2927m (94m high), Currently drilling 100% claystone

Geologist: Bill Prin)

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**4 Nov 2005**	**Day: 31**	**Report No: 18**
Currently:	**Drilling ahead at 3195m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6.0" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	3182	3171	11	1.2	4.4	2.5
@ **06:00 hrs**	3195	3137	34	2.2	8.3	4.6

Lithology summary

3165-3194m Claystone with minor Siltstone.

CLAYSTONE; 95-100%, light olive grey – olive grey, soft - brittle, occasionally moderately hard, blocky, moderately – very calcareous, trace vein calcite

SILTSTONE; 0-5%, olive black – brownish black, firm, blocky, slightly calcareous

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Background gas	0.2-0.29						
WTG	0.39	110	22	24	57	106	5

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
3171	3182	3.1	0.3	
3182	3195	7.8	0.7	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
3178	8.7	70		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
3143.80	21.05	141.58	3004.94	
3172.54	20.63	144.17	3031.8	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765	2710	2598	samples
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Drilled to 3182m, did wiper trip, Run in hole and attempt to slide, no go, rotary drill with slow ROP to 3195m through calcareous Claystone.

Biostratigraphy @ 3185m – no diagnostic species but is marine and probably Otaraoan

Geologist: Bill Prin)

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**5 Nov 2005**	**Day: 32**	**Report No: 19**
Currently:	**Drilling ahead at 3245m MD.**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6.0" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	3215	3195	20	0.5	2.8	1.8
@ **06:00 hrs**	3245	3215	35	1.1	13.5	4.3

Lithology summary

3194-3225m Claystone.

CLAYSTONE; ,100%, light olive grey – yellowish grey, firm - brittle, occasionally moderately hard, blocky, moderately – very calcareous, occasionally slightly silty, trace vein calcite

3225-3235m Siltstone with minor Sandstone

SILTSTONE; 20-95%, olive grey, olive black becoming light grey-yellow grey from 3230m, soft, blocky, common calcareous cement, trace – common glauconite, trace very fine quartz, grades in part to silty sandstone

SANDSTONE; 5%,loose grains, clear – translucent quartz, very fine lower- medium lower,subangular - subrounded rare silty light grey – yellow grain aggregate (3235m sample), trace glauconite

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Background gas	0.24-0.39						
Max @ 3212m	0.47	84	22	14	37	63	1

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
3227	2.4	4.1	siltstone
3233	7	13	5% loose sand in samples

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
3195	3215	8.2	0.7	
3215	3241	12.5	1.14	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
3197	8.65	77		
3201	8.7	75		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
3201.13	19.54	147.86	3058.66	
3229.81	18.80	151.07	3085.75	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765	2710	2598	samples
McKee	3180			
Mangehewa	3215			
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Drilling at 3245m, lithology change @ 3235m to siltstone with traces of loose sand, indicating close to top of McKee Sandstone

Biostratigraphy @ 3185-3215m – upper Whaingaroan - Otaraoa

Geologist: Bill Prin)

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**6 Nov 2005**	**Day: 33**	**Report No: 20**
Currently:	**Make up BHA. Drilled depth 3296m**		**Spud Date: 5th Oct, 2005**
For the period 06:00 to 06:00 hours.			

Drilling Data: 6.0" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	3289	3245	44	2.4	12.3	5.8
@ **06:00 hrs**	3296	3289	7	3.6	11.4	7.8

Lithology summary

3235-3240m Siltstone with Sandstone

SILTSTONE; 10-100%, light grey-yellow grey, soft, blocky, trace - common calcareous cement, trace glauconite, argillaceous in part, trace very fine quartz, grades in part to silty sandstone

SANDSTONE; 10%, loose grains, clear – translucent quartz, very fine lower- medium lower, subangular - subrounded, rare silty light grey – yellow grain aggregate, friable – firm, calcareous silty matrix, trace glauconite, poor visible porosity

3240-3296m Siltstone and carbonaceous Claystone with Coal and Sandstone

SILTSTONE; 20-95%, light grey-yellow grey, soft, blocky, slightly calcareous, argillaceous in part, trace very fine quartz, grades in part to silty sandstone

CLAYSTONE; 10-40% brownish black, firm – moderately hard, blocky, non calc

COAL; 10-80%, brownish black, black, brittle, earthy – subvitreous, dull – moderately bright, predominanty subfissile

SANDSTONE; 0 – 60%, light grey – yellowish grey, friable, very fine lower – fine lower, subangular - rounded quartz, moderately well sorted, abundant silty matrix, grades to Siltstone, poor visible porosity, no show

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
3257	0.85	5310	340	120	30	30	10
3262	0.93	5520	310	150	30	20	0
3296	0.83	5888	281	146	30	18	0

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Background gas	0.24-0.39						

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks
3292	3.8	8.2	

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
3241	3289	11.8	1.0	
3289	3297	23.2	2.1	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
3246	8.7	75		
3296	8.8	81		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
3229.81	18.80	151.07	3085.75	
3258.74	18.55	152.29	3113.15	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765	2710	2598	samples
McKee	3180	3226	3082	? Possible Siltstone equivalent
Mangehewa	3215	3245	3100	samples
Ahuroa Thrust	3360			
TD	3430			

Additional comments:

Drilled into Mangahewa at 3245m, No significant sand above but siltstone section from 3226m is possible equivalent, no gas increase over this section. Drilled coal at 3294m, pulled out of hole at 3296m and lay out directional assembly

Geologist: Bill Prin)

Swift Energy Company – NZ Ltd.			Daily Geological Report Ahuroa South B1
Report Date:	**7 Nov 2005**	**Day: 34**	**Report No: 21**
Currently:	**Circulating bottoms up @ 3370m TD ; TVD 3219m**		**Spud Date: 5th Oct, 2005**

For the period 06:00 to 06:00 hours.

Drilling Data: 6.0" hole section.

Depths m AH	Depth	Previous	Progress	Drill rate m/hr		
				Minimum	Maximum	Average
@ **18:00 hrs**	3298	3296	2	1.2	3.9	2.7
@ **06:00 hrs**	3370	3298	28	3.9	18.3	9.4

Lithology summary

3296-3220m Predominantly Claystone with minor coal and Siltstone

CLAYSTONE; 10-100% light olive grey, firm – moderately hard, blocky, moderately calcareous

COAL; 40%, brownish black, black, brittle, earthy – subvitreous, dull – moderately bright, predominanty subfissile (finely broken up cuttings, probably cavings)

SILTSTONE; 5%, light grey-yellow grey, soft, blocky, slightly calcareous, argillaceous in part,

3320-3370m Claystone

CLAYSTONE; olive grey – olive black, firm – moderately hard, blocky, moderately calcareous, trace vein calcite, becoming olive black – dark grey below 3330m , moderately hard, occasionally hard, non – slightly calcareous

Gas Shows:

Depth m AH	Total Gas %	Methane ppm	Ethane ppm	Propane ppm	IsoButane ppm	Butane ppm	Pentane ppm
3297	0.62	2922	230	120	40	20	0

Other Gases:

Depth m AH	Total Gas %	C1 ppm	C2 ppm	C3 ppm	IC4 ppm	NC4 ppm	IC5 ppm
Background gas	0.24-0.28						
3296 Trip gas	5.17	43340	4000	1070	180	150	40

Calcimetry:

m AH	max	min	average	Comments
N/A				Not run on this hole section.

Drilling Breaks:

Depth	From	To (m/hr)	Remarks

Fluid Losses:

Depth from	Depth to	total (bbl)	rate (bbl/hr)	Remarks
3296	3298	0		
3298	3370	6	0.3	

Fluid resistivity:

Depth (m)	filtrate Ω-m	mud Ω-m	temp °C	Remarks

Fluid properties:

Depth (m)	Weight ppg	Viscosity	Chlorides	Remarks
3296	8.8	80		
3316	8.8	98		

Last survey:

Depth m AH	Inclination °	Azimuth°	TVD (m)	
3229.81	18.80	151.07	3085.75	
3258.74	18.55	152.29	3113.15	

Formation tops:

Formation	Prognosed	m RKB	m TVD	Basis Of Pick
Mt Messenger	1230	1200	1176	Last sand bed
Tikorangi	1940	1911	1845	Rop/samples
Otaraoa	2100	2010	1940	samples
Tariki	2765	2710	2598	samples
McKee	3180	3226	3082	? Possible Siltstone equivalent
Mangehewa	3215	3245	3100	samples
Ahuroa Thrust Manganui	3360	3320	3171	samples
TD	3430	3370	3219	

Additional comments:

Ran in hole with rotary assembly and new bit, drilled through the thrust plus 50m rat-hole to 3370m MD

Geologist: Bill Prin)

Ahuroa South B-1 - Descriptions

659-820m Massive Claystone. CLAYSTONE: 100%, light bluish grey-medium grey, getting greenish grey-dark greenish grey w/ depth, soft, dispersive, amorphous, non calcareous, trace vfL-fL quartz grains, trace shell fragments.

820-980m Predominantly Sandstone with minor Claystone and Limestone stringers. CLAYSTONE: tr-10%, greenish grey-dark greenish grey w/ depth, soft-firm, dispersive, amorphous to sub-blocky, non-slightly calcareous, trace vfL-fL quartz grains, trace shell fragments. SANDSTONE: 90-100%, light olive grey-very light grey-light greenish grey, clear-translucent, soft-unconsolidated, vfU-mL, sub rounded to sub angular, well sorted, trace glauconite, good inferred porosity, no show LIMESTONE: nil-tr, white-very light grey, firm-hard, micro-crystalline, trace vfU-fL quartz grains, grades to very calcareous Sandstone in part, trace shell fragments.
.**820-980**m Interbedded Sandstone and Siltstone, with minor Claystone.
.CLAYSTONE: tr-5%, greenish grey-dark greenish grey, soft-firm, dispersive, amorphous to sub-blocky, non-slightly calcareous, trace vfL-fL quartz grains, trace shell fragments. SILTSTONE:30-40%, medium grey-olive grey, soft-moderately firm, sub blocky, non calcareous, trace vfL quartz, grades to very fine grained sandstone in part, trace micromica. SANDSTONE: 55-65%, light olive grey-very light grey-light greenish grey, clear-translucent, soft-unconsolidated, vfU-mL, sub rounded to sub angular, well sorted, trace glauconite, good inferred porosity, no show .

980-1200m Interbedded Claystone and Sandstone w/ trace Siltstone and Limestone stringers. CLAYSTONE: 5-95%, greenish grey-dark greenish grey-olive grey, soft-firm, dispersive, amorphous to sub-blocky, non calcareous, trace vfL-fL quartz grains, commonly silty, grades to Silty Claystone in parts, rare trace shell fragments. SILTSTONE: nil-5%, olive grey-olive black, hard-very hard, blocky, non calcareous, trace vfL quartz, trace-common micromica.
.SANDSTONE: 10-95%, light olive grey-very light grey-light bluish grey, clear-translucent, soft-unconsolidated, vfL-fL, sub rounded to sub angular, well sorted, common argillaceous matrix, no calcareous, trace glauconite, fair inferred porosity, no show LIMESTONE: nil-5%, white-very light grey, firm-hard, micro-crystalline, trace vfU-fL quartz grains, grades to very calcareous Sandstone in part, trace shell fragments.

1200-1270m Claystone. .CLAYSTONE: 100%, medium grey-olive grey, soft-firm, dispersive, amorphous to sub-blocky, non calcareous, trace vfL-fL quartz grains, commonly silty, grades to Silty Claystone in parts, trace micromica.

1270-1290m Claystone. CLAYSTONE: 100%, medium grey-olive grey, soft-firm, dispersive, amorphous to sub-blocky, non calcareous, trace vfL-fL quartz grains, commonly silty, grades to Silty Claystone in parts, trace micromica.

1290-1460m Predominantly Claystone w/ minor interbedded Sandstones.
.CLAYSTONE: 90-100%, medium grey-medium dark grey, soft, dispersive, amorphous to sub-blocky, slightly-moderately calcareous, trace-common vfL-fL quartz grains, trace micromica. At 1410-1420m, had tr-10% bright yellowish white direct fluorescence, very slow bluish white cut fluorescence, w/ faint-patchy yellowish white residual ring fluorescence, poor show. SANDSTONE: nil-10%, white-very light grey-clear-translucent-transparent, soft, unconsolidated, predominantly loose quartz, fL-cL, sub angular to sub round, occasionally angular, poorly sorted, trace mica, god inferred porosity, no show.

1460-1485 Interbedded Claystone and Sandstone.CLAYSTONE: 70%, olive grey, soft, dispersive, amorphous to sub-blocky, moderately calcareous, trace-common vfL-fL quartz grains, trace micromica. SANDSTONE: 30%, generally as above, white-very light grey-clear-translucent-transparent, soft, unconsolidated, predominantly loose quartz, fL-cL, sub angular to sub round, occasionally angular, poorly sorted, trace mica, god inferred porosity, common mineral fluorescence, no show. .

1485-1630m Interbedded Claystone and Sandstone. CLAYSTONE: 80-100%, light olive grey-olive grey, soft, dispersive, amorphous to sub-blocky, moderately calcareous, trace vfL-fL quartz grains, trace micromica. Had hydrocarbon fluorescence at: 1485-1530m, 1540-1560m, 1590-1600m, 1610-1620m: predominantly trace to occasionally 5-10% bright yellowish white direct fluorescence, very slow-slow blooming bluish white cut fluorescence, thin patchy bluish white residue ring fluorescence, poor show. From 1637-1640m, and 1650-1660m: trace bright yellowish white direct fluorescence, no cut fluorescence, no show. SANDSTONE: nil-20%, white-very light grey-clear-translucent-transparent, soft, unconsolidated, predominantly loose quartz, fL-cL, sub angular to sub round, occasionally angular, poorly sorted, trace mica, good inferred porosity, common mineral fluorescence, no show.

1630-1680m Claystone, Siltstone, and Sandstone. .CLAYSTONE: 50-90%, light olive grey, soft, dispersive, amorphous to sub-blocky, moderately calcareous, trace vfL-fL quartz grains. Had fluorescence at: 1650-1680m: trace bright yellowish white direct fluorescence, no cut fluorescence, no show. SILTSTONE: 5-20%, light olive grey-greenish grey, firm-hard, sub blocky, moderately calcareous, argillaceous, grades to silty Claystone in part. SANDSTONE: 5-40%, white-very light grey-clear-translucent-transparent, soft, unconsolidated, predominantly loose quartz, vfL-vfU, sub angular to sub round, well sorted, good inferred porosity, common mineral fluorescence, no show.

1680-1700m Claystone. CLAYSTONE: 100%, medium grey, soft-firm, sub-blocky, moderately calcareous, trace vfL-fL quartz grains, had trace of bright yellowish white direct fluorescence, no cut fluorescence, no show.

1700-1740m Claystone. CLAYSTONE: 100%, medium grey-dark grey-greenish grey, soft-firm, sub-blocky, moderately calcareous, trace vfL-fL quartz grains.

1740-1911m Predominantly Claystone with minor Siltstone and Sandstones and occasional Limestone stringers. .CLAYSTONE: 75-100%, medium grey-dark grey-greenish grey, soft-firm, sub-blocky, moderately calcareous, getting very calcareous with depth, silty in part, trace vfL-fL quartz grains. SILTSTONE: nil-10%, dark greenish grey-olive black, firm-hard, sub blocky to blocky, moderately to very calcareous, argillaceous, grades to Claystone in part. SANDSTONE: nil-10%, light grey-medium grey, translucent, soft, friable, predominantly loose quartz, vfL-fL, well sorted, calcareous matrix, argillaceous, good inferred porosity, no show. .LIMESTONE: nil-25%, light grey-light grey, firm, sub blocky, argillaceous, trace vfL quartz.

1911-1915 Limestone w/ minor Claystone and Siltstone. .LIMESTONE: 25-60%, very light grey-light grey, soft-firm, sub blocky, argillaceous, grades to very calcareous Claystone in part, trace vfL quartz. .CLAYSTONE: 5-60%, medium grey-dark grey-greenish grey, soft-firm, sub-blocky, moderately calcareous,

getting very calcareous with depth, silty in part, trace vfL-fL quartz grains. SILTSTONE: 5-10%, dark greenish grey-olive black, firm-hard, sub blocky to blocky, moderately to very calcareous, argillaceous, grades to Claystone in part.

1915-2010m Limestone w/ minor Siltstone. .LIMESTONE: 95-100%, white-very light grey-light grey, soft-firm, sub blocky, argillaceous, grades to very calcareous Claystone in part, trace vfL quartz. .SILTSTONE: nil-5%, dark greenish grey-olive black, medium bluish grey in part, firm-hard, sub blocky to blocky, moderately to very calcareous, argillaceous, grades to Claystone in part.

2010-2130m Predominantly Siltstone with occasional interbedded Claystone and Limestone stringers. SILTSTONE: 20-100%, medium grey-olive grey, soft-firm, sub blocky to occasionally blocky, moderately to very calcareous, argillaceous, grades to Claystone in part, trace black specks. CLAYSTONE: nil-10%, medium dark grey-olive grey, soft, sub blocky, moderately calcareous, silty, grades to Siltstone in part, trace black specks. LIMESTONE: nil-5%, white-very light grey-light grey, soft-firm, sub blocky, argillaceous, grades to very calcareous Claystone in part, trace vfL quartz.

2130-2400m Predominantly Siltstone with occasional interbedded Claystone and Limestone stringers. SILTSTONE: 10-100%, medium grey-olive grey, greenish grey in part, soft-firm, very hard in parts, sub blocky to occasionally blocky, moderately to very calcareous, argillaceous, grades to Claystone in part, trace black specks, trace micromica, trace forams. CLAYSTONE: nil-10%, medium grey-olive grey, soft, sub blocky, slightly-moderately calcareous, silty, grades to Siltstone in part, trace black specks, trace forams. LIMESTONE: nil-trace%, white-very light grey-light grey, soft-firm, sub blocky, argillaceous, grades to very calcareous Claystone in part.

2400-2540m, Claystone with minor Siltstone CLAYSTONE:90 - 100%, olive grey, brownish grey – brownish black, soft – moderately hard, sub blocky - blocky, moderately calcareous, silty in part with trace black specks, trace crystalline calcite, trace fossil fragments (shell, bryazoan). SILTSTONE: 0-10%, medium grey-olive grey, greenish grey in part, soft-firm, very hard in parts, sub blocky to occasionally blocky, moderately calcareous, argillaceous, grades to Claystone in part, trace black specks, trace micromica

2540 - 2710m, Claystone CLAYSTONE: 100%, olive grey, brownish grey – brownish black, soft – moderately hard, sub blocky - blocky, moderately calcareous, slightly silty in part, trace crystalline calcite, tr microcrystalline mica, slight colour change below 2590m becoming light olive grey – olive grey, soft, amorphous, moderately – very calcareous and sticky.

2710 – 2735m, Sandstone with minor Siltstone and Claystone .SANDSTONE: 10 – 95%, very light grey – light grey, friable – firm, as loose grains from 2715m – 2725m, clear – translucent quartz, very fine lower – coarse lower grains, poor – moderately sorted, subangular - subrounded, nil – common calcite cement, nil – good porosity dependant on cementation, no shows .SILTSTONE; 0 – 50%, olive grey, firm – moderately hard, blocky, slight – moderately calcareous, trace black specks CLAYSTONE: 5 - 50%, olive grey, brownish grey – brownish black, firm – moderately hard, sub blocky - blocky, moderately calcareous, slightly silty in part

2735 – 2787m, Sandstone with interbedded Siltstone and Claystone .SANDSTONE: Trace – 60%, very light grey – light grey, loose grains , clear – translucent quartz, very fine lower – coarse lower grains, poor – moderately sorted, subangular - subrounded, common strongly calcite cemented grain

aggregate, hard, nil – good porosity dependant on cementation, trace coal fragment, trace glauconite, no shows SILTSTONE; Trace – 40%, olive grey – olive black, firm – moderately hard, blocky, slightly – moderately calcareous, trace black specks CLAYSTONE: 20 - 100%, light olive gey - olive grey, soft, amorphous - subblocky, moderately - very calcareous, stick

2787 – 2830m, Sandstone with interbedded Siltstone and Claystone .SANDSTONE: Trace – 90%, very light grey – light grey, loose grains , clear – translucent quartz, very fine lower – coarse lower grains, poor – moderately sorted, subangular - subrounded, common strongly calcite cemented grain aggregate, hard, trace coal fragment, trace glauconite, nil – good porosity dependant on cementation no shows. Samples from 2800 – 2815m have abundant rock flour) SILTSTONE; Trace – 10%, olive grey – olive black, firm – moderately hard, blocky, slightly – moderately calcareous, trace black specks .CLAYSTONE: trace - 90%, light olive grey - olive grey, soft - firm, amorphous - subblocky, moderately - very calcareous, sticky in part, silty in part grading to Siltstone

2830 – 2875m, Sandstone with interbedded Siltstone and Claystone .SANDSTONE: 50 – 100%, very light grey – light grey, loose grains , clear – translucent quartz, very fine lower – coarse upper grains, moderately sorted, subangular - subrounded, common strongly calcite cemented grain aggregate, friable – hard, very fine lower – fine upper, nil – common argillaceous matrix, grades in part to Siltstone, nil – good porosity dependant on cementation no shows. SILTSTONE; 0 – 40%, brownish black – olive grey, firm – moderately hard, blocky, slightly – moderately calcareous, trace black specks, trace very fine quartz, grading to Sandstone CLAYSTONE: trace - 10%, light olive grey - olive grey, soft - firm, amorphous - subblocky, moderately - very calcareous, sticky in part, silty in part grading to Siltstone

2875 – 2903m, Sandstone with interbedded Siltstone and Claystone .SANDSTONE: 20 – 100%, very light grey – light grey, loose grains , clear – translucent quartz, very fine lower – coarse upper grains, predominantly fine upper –medium lower, moderately sorted, subangular - subrounded, occasional calcite cemented grain aggregate, friable – hard, very fine lower – fine upper, nil – trace argillaceous matrix, grades in part to Siltstone, trace coal fragments from 2895m, rare glauconite, nil – good porosity dependant on cementation, no shows. SILTSTONE; 0 – 40%, brownish black – olive grey, firm – moderately hard, blocky, slightly – moderately calcareous, trace black specks, trace very fine quartz, grading to Sandstone CLAYSTONE: trace - 10%, olive grey, firm, blocky, moderately calcareous, silty in part grading to Siltstone

2903 – 2985m, Sandstone with interbedded Siltstone and Claystone and minor Limestone SANDSTONE: 10 – 100%, very light grey – light grey, loose grains , clear – translucent quartz, very fine lower – coarse upper grains, predominantly fine upper –medium lower, moderately sorted, subangular - subrounded, occasional grain aggregate with abundant calcite cement, grading in part to sandy Limestone, friable – hard, very fine lower – fine upper, nil – trace argillaceous matrix, trace coal fragments, rare glauconite, nil – good porosity dependant on cementation, no shows. LIMESTONE; 0 – 20%, very light grey, soft – moderately hard, predominantly cryptocrystalline, occasionally microcrystalline, trace to common quartz grains, trace glauconite, grades to calcareous sandstone, no show. SILTSTONE; 0 – 20%, brownish black – olive black, firm – moderately hard, blocky, slightly – moderately calcareous, trace black specks, trace very fine quartz, grading to Sandstone CLAYSTONE: 5 - 90%, light olive grey – olive grey, soft – moderately hard, amorphous - sub

blocky, sticky in part, moderately - very calcareous, rare glauconite, silty in part grading to Siltstone

2985 – 3015m, Claystone with interbedded Siltstone and Sandstone .CLAYSTONE: 50 - 100%, light olive grey – olive grey, soft – firm, amorphous - sub blocky, sticky in part, moderately - very calcareous, rare glauconite, silty in part grading to Siltstone SILTSTONE; 0 – 20%, brownish black – olive black, firm – moderately hard, blocky, slightly – moderately calcareous, trace black specks, trace very fine quartz, grading to Sandstone in part SANDSTONE: 0 – 30%, very light grey – light grey, loose grains , clear – translucent quartz, very fine lower – medium upper grains, predominantly fine lower, moderately well sorted, subangular - subrounded, common grain aggregate with abundant calcite cement, trace argillaceous matrix, friable – firm, very fine lower – fine upper, trace coal fragments, rare glauconite, nil – fair porosity no shows.

3015 – 3050, Sandstone and siltstone with minor Claystone SANDSTONE; 10 – 90% light grey, firm, occasionally hard, very fine lower – medium lower, predominantly fine lower, subangular - subrounded, moderately well sorted, common calcitic cement, trace argillaceous matrix, trace glauconite, nil – poor visible porosity, no shows SILTSTONE; 10 – 80%, olive grey, dark grey, soft – firm, sub-blocky – blocky, slightly calcareous, argillaceous in part grading to Claystone CLAYSTONE; 10 - 80%, light olive grey – olive grey, soft – firm, amorphous - sub blocky, sticky in part, moderately - very calcareous, rare glauconite, silty in part grading to Siltstone

3050-3090m Sandstones and Siltstone with minor Claystone. .SANDSTONE: 20-100%, light grey,fri - firm, occasionally hard cemented grain aggregate, very fine lower – coarse lower, predominantly fine lower, subangular – subrounded, moderately sorted, common calcitic cement, trace - common argillaceous matrix, grades in part to Siltstone, trace glauconite, nil – poor porosity, no shows. SILTSTONE: 10-60%, olive grey,- dark grey, soft - firm, subblocky, slightly - moderately calcareous, trace very fine quartz, trace glauconite, argillaceous in part grading to Claystone. CLAYSTONE: 0-80%, light olive grey - olive grey, soft - firm, amorphous - subblocky, sticky in part moderately calcareous, rare glauconite, silty in part grading to Siltstone

3090-3110m Claystone. CLAYSTONE: 100%, olive grey,- olive black, firm - occasionally moderately hard, moderately calcareous, slightly silty in part 3110-3140m Claystone with minor Sandstone. CLAYSTONE: 70-100%, olive grey, soft - firm, occasionally moderately hard, amorphous – subblocky, moderately calcareous, slightly silty in part SANDSTONE; 10-30%, light grey, friable – hard, very fine lower – fine upper, subangular – subrounded, moderately well sorted, abundant strong calcite cement, common loose grains, trace glauconite, nil – fair porosity, n/s

3140-3165m Claystone. CLAYSTONE; 100%, olive grey, soft - firm, occasionally moderately hard, blocky, moderately calcareous.

3165-3194m Claystone with minor Siltstone. CLAYSTONE; 95-100%, light olive grey – olive grey, soft - brittle, occasionally moderately hard, blocky, moderately – very calcareous, trace vein calcite SILTSTONE; 0-5%, olive black – brownish black, firm, blocky, slightly calcareous

3194-3225m Claystone. CLAYSTONE; ,100%, light olive grey – yllowish grey, firm - brittle, occasionally moderately hard, blocky, moderately – very calcareous, occasionally slightly silty, trace vein calcite

3225-3235m Siltstone with minor Sandstone SILTSTONE; 20-95%, olive grey, olive black becoming light grey-yellow grey from 3230m, soft, blocky, common calcareous cement, trace – common glauconite, trace very fine quartz, grades in part to silty sandstone SANDSTONE; 5%,loose grains, clear – tranlucent quartz, very fine lower- medium lower,subangular - subrounded rare silty light grey – yellow grain aggregate (3235m sample), trace glauconite

3235-3240m Siltstone with Sandstone SILTSTONE; 10-100%, light grey-yellow grey, soft, blocky, trace - common calcareous cement, trace glauconite, argillaceous in part, trace very fine quartz, grades in part to silty sandstone .SANDSTONE; 10%, loose grains, clear – translucent quartz, very fine lower-medium lower, subangular - subrounded, rare silty light grey – yellow grain aggregate, friable – firm, calcareous silty matrix, trace glauconite, poor visible porosity

3240-3296m Siltstone and carbonaceous Claystone with Coal and Sandstone .SILTSTONE; 20-95%, light grey-yellow grey, soft, blocky, slightly calcareous, argillaceous in part, trace very fine quartz, grades in part to silty sandstone .CLAYSTONE; 10-40% brownish black, firm – moderately hard, blocky, non calc .COAL; 10-80%, brownish black, black, brittle, earthy – subvitreous, dull – moderately bright, predominanty subfissile SANDSTONE; 0 – 60%, light grey – yellowish grey, friable, very fine lower – fine lower, subangular - rounded quartz, moderately well sorted, abundant silty matrix, grades to Siltstone, poor visible porosity, no show

3296-3220m Predominantly Claystone with minor coal and Siltstone .CLAYSTONE; 10-100% light olive grey, firm – moderately hard, blocky, moderately calcareous .COAL; 40%, brownish black, black, brittle, earthy – subvitreous, dull – moderately bright, predominanty subfissile (finely broken up cuttings, probably cavings) .SILTSTONE; 5%, light grey-yellow grey, soft, blocky, slightly calcareous, argillaceous in part,

3320-3370m Claystone .CLAYSTONE; olive grey – olive black, firm – moderately hard, blocky, moderately calcareous, trace vein calcite, becoming olive black – dark grey below 3330m , moderately hard, occasionally hard, non – slightly calcareous

.

..

Ahuroa South B1-ST1. Descriptions

2400-2410m Claystone .CLAYSTONE: nil-25%, medium grey-light olive grey, soft, amorphous-sub blocky, slightly-moderately calcareous, slightly silty in part, trace black specks .CEMENT: 75-100% .

2410-2426m Claystone. CLAYSTONE: 70-100%, olive grey, brownish grey, occasionally light olive grey, firm – moderately hard, blocky, occasionally soft, amorphous- sub blocky, slightly-moderately calcareous, slightly silty in part, trace black specks.2426-2480m Claystone .CLAYSTONE: 100%, olive grey, brownish grey, occasionally light olive grey, firm – moderately hard, blocky, occasionally soft, amorphous- sub blocky, moderately calcareous, slightly silty in part, trace vein calcite .

2480-2600m Claystone with minor Siltstone .CLAYSTONE: 90-100%, olive grey, brownish grey, occasionally light olive grey, firm – moderately hard, blocky, occasionally soft, amorphous- sub blocky, moderately – occasionally very calcareous, slightly silty in part, trace vein calcite .SILTSTONE: 0-10%, olive grey – brownish black, moderately hard, blocky, moderately calcareous, argillaceous in part grading to silty Claystone .

2600-2666m Claystone with minor Siltstone .CLAYSTONE: 90-100%, olive grey, brownish grey, occasionally light olive grey, firm – moderately hard, blocky, occasionally soft, amorphous- sub blocky, moderately – occasionally very calcareous, slightly silty in part, trace vein calcite .SILTSTONE: 0-10%, olive grey – brownish black, moderately hard, blocky, moderately calcareous, argillaceous in part grading to silty Claystone.

2666-2715m.Sandstone with interbedded Siltstone and Claystone .SANDSTONE:10-90% predominantly loose, clear – translucent quartz, very fine upper – medium upper, predominantly fine upper – medium lower, subangular- rounded, well sorted, occasional light grey grain aggregate, friable, trace calcite cement, trace – common argillaceous matrix, rare trace glauconite, trace coal fragments, fair – good porosity, no show. .SILTSTONE:0-30%, olive grey, frm, blky, moderately cacacareous, trace very fine quartz, trace black specks .CLAYSTONE:10-50% light olive grey, yellowish grey, very soft – soft, amorphous, very calcareous, 5 – 10% olive grey as above .

2715-2760m Sandstone with interbedded Siltstone and Claystone .SANDSTONE:10-90% predominantly loose, clear – translucent quartz, very fine upper – medium upper, predominantly fine upper, subangular- rounded, well sorted, occasional light grey grain aggregate, friable, trace - common calcite cement, trace – common argillaceous matrix, rare trace glauconite, trace coal fragments, fair – good porosity, no show. .SILTSTONE:5-40%,yellowish grey, olive grey, olive black, firm, blocky, slightly - moderately calcareous, trace very fine quartz grading in part to very fine Sandstone, trace black specks .CLAYSTONE:0-20% light olive grey, yellowish grey, very soft – soft, amorphous, very calcareous, silty in part .

2760-2830m Sandstone with interbedded Siltstone and Claystone .SANDSTONE:40-100%, predominantly loose, clear – translucent quartz, very fine upper – coarse upper, predominantly fine upper, subangular- rounded, well sorted, occasional yellowish grey grain aggregate, friable, trace - common calcite cement, trace – common argillaceous matrix, grades in part to Siltstone rare trace glauconite, fair – good porosity, no show. .SILTSTONE:5-60%, very light grey, yellowish grey, firm, blocky, slightly - moderately calcareous, trace very fine quartz grading in part to very fine Sandstone, rare trace glauconite .From 2820m Siltstone is olive grey – olive black, firm, blocky, slightly – moderately calcareous with traces of carbonaceous fragments .CLAYSTONE:0-30% light olive grey, very soft – soft, amorphous, very calcareous, silty in part .

2830-2870m Sandstone with interbedded Siltstone and Claystone .SANDSTONE:10-60%, predominantly loose, clear – translucent quartz, very fine lower – medium lower, predominantly fine upper, subangular- rounded, moderately well sorted, occasional yellowish grey grain aggregate, friable, trace calcite cement, trace – common argillaceous matrix, grades in part to Siltstone, rare trace glauconite trace coal fragments in 2835m sample, poor – good porosity, no show. .SILTSTONE:10-40%, very light grey, yellowish grey, soft, blocky, slightly - moderately calcareous, argillaceous, trace very fine quartz grading in part to very fine Sandstone, rare trace glauconite. .2840m Siltstone is olive grey – olive black, soft - firm, blocky, slightly – moderately calcareous with traces of carbonaceous fragments .CLAYSTONE:10-80% light olive grey, light brown, very soft – soft, amorphous, moderately - very calcareous, silty in part .

2870-2880m Sandstone with interbedded Siltstone and Claystone .SANDSTONE:40-70%, predominantly loose, clear – translucent quartz, very fine lower – medium lower, predominantly fine upper, subangular- rounded, moderately well sorted, occasional yellowish grey grain aggregate, friable, trace calcite cement, trace – common argillaceous matrix, grades in part to Siltstone, rare trace glauconite trace coal fragments in 2835m sample, poor – good porosity, no show. Samples contain abundant rock flour .SILTSTONE; 10-40%, olive black– brownish black, hard – very hard, blocky, non - slightly calcareous .CLAYSTONE:20% light olive grey, olive grey, very soft – firm, amorphous - blocky, moderately calcareous, silty in part .

2880-2900m Sandstone with interbedded Siltstone and Claystone .SANDSTONE:30-60%, loose, clear – translucent quartz, very fine lower – fine upper, predominantly very fine upper, subangular- rounded, moderately well sorted, common yellowish grey grain aggregate, friable, trace calcite cement, common silty matrix, grades in part to Siltstone, rare trace glauconite, poor – fair porosity, no show. Samples contain abundant rock flour .SILTSTONE; 20-40%, olive black– brownish black, hard – very hard, blocky, non - slightly calcareous .CLAYSTONE:10-40% light olive grey, olive grey, very soft – firm, amorphous - blocky, moderately calcareous, silty in part .

2900-2920m Claystone with interbedded Sandstone and minor Siltstone .CLAYSTONE; 60-70% olive grey, light olive grey, very soft – firm, amorphous – blocky, moderately to occasionally very calcareous .SANDSTONE; 20-60 light grey – yellowish grey, friable – firm, very fine lower – fine upper with common silty matrix, subangular – rounded grains, moderately sorted, trace calcite cement, trace glauconite, poor – fair porosity, no show .SILTSTONE; 10-20%, olive black– brownish black, firm - moderately hard, blocky, non - slightly calcareous .

2920-2950m Claystone .CLAYSTONE; 90-100%, olive grey, soft – firm, occasionally moderately hard, blocky, moderately calcareous, slightly silty in part, rare traces black fllecks .

2950-2975m Claystone .CLAYSTONE; 90-100%, olive grey, soft – firm, occasionally moderately hard, blocky, moderately calcareous, slightly silty in part, rare traces black flecks .

2975-2980m Claystone with Siltstone .CLAYSTONE; 70%, olive grey, light olive grey, soft – firm, amorphous – subblocky, moderately calcareous .SILTSTONE; 30%, 10% dark greenish grey – greyish black, soft – firm, blocky, moderately calcareous, abundant glauconite. .20% light grey, yellowish grey, soft – firm, blocky, moderately calcareous, trace very fine quartz grains, trace glauconite .

2980-2993m Siltstone and Sandstone with Coal .COAL, 50-70%, black, brittle, subvitreous, hackley – subconchoidal fracture .SILTSTONE;20-30%, light olive grey – yellowish grey, soft – firm, blocky, trace calcareous cement, trace quartz grains, grades to silty Sandstone .SANDSTONE; 20-30%, yellowish grey, friable, very fine lower – medium upper, predominantly fine lower, moderately sorted, subangular – rounded, trace calcareous cement, trace glauconite, abundant silty matrix, grades to Siltstone, poor – fair porosity, no show .

2993-3050m Siltstone with coal and carbonaceous Claystone .COAL, Trace-70%, black, hard - brittle, vitreous, hackley – sub-conchoidal fracture .SILTSTONE;5-95%, light olive grey – yellowish grey, soft – firm, blocky, nil -trace calcareous cement, trace carbonaceous specks, trace quartz grains, grades to very fine silty Sandstone .CLAYSTONE; Trace-80%, brownish grey, brownish black, moderately hard – hard, blocky – irregular fracture, non calcareous .

3050-3085mTD Claystone .CLAYSTONE: 100%, medium dark grey, dark grey, firm – moderately hard, blocky, moderately calcareous becoming slightly – non calcareous below 3060m, trace calcite veining .

Composite

SWIFT ENERGY NEW ZEALAND LTD


Paradigm™ THE GEOSCIENCE KNOWLEDGE COMPANY

Well: AHUROA_SOUTH_B-1

COMPANY: Swift Energy NZ Ltd
LOCATION: Ahuroa
LATITUDE: 39.0000
LONGITUDE: 174.0000
X COORDINATE: 2625724.00
Y COORDINATE: 6214674.11
HORIZONTAL UNITS: METRES
DATE PLOTTED: 08–Nov–2005

DATUM FOR ELEVATION: Ground Level
SURFACE ELEVATION: 196.30
MEASUREMENT REF.: Kelly Bushing
ELEVATION MEAS. REF.: 201.84
DRILLED DEPTH: 3370.00
VERTICAL UNITS: METRES
DATE LOGGED: 7–Nov–2005
VERTICAL SCALE: 1:1000

DEPTH (METRES)	RM	RMC	RMF	DFD	BHT	SHT	BIT SIZE
2700.00–3379.78	– @ –	– @ –	– @ –	–	–	–	–



Composite

SWIFT ENERGY NEW ZEALAND LTD


Paradigm™ THE GEOSCIENCE KNOWLEDGE COMPANY

Well: AHUROA_SOUTH_B-1_ST1

COMPANY: Swift Energy NZ Ltd
LOCATION: Onshore Taranaki
LATITUDE: 39.0000
LONGITUDE: 174.0000
X COORDINATE: –
Y COORDINATE: –
HORIZONTAL UNITS: METRES
DATE PLOTTED: 25–Nov–2005

DATUM FOR ELEVATION: MSL
SURFACE ELEVATION: –
MEASUREMENT REF.:
ELEVATION MEAS. REF.: –
DRILLED DEPTH: –
VERTICAL UNITS: METRES
DATE LOGGED: 25–Nov–2005
VERTICAL SCALE: 1:1000

DEPTH (METRES)	RM	RMC	RMF	DFD	BHT	SHT	BIT SIZE
2600.00–3094.00	– @ –	– @ –	– @ –	–	–	–	–



Mud Summary Report

Swift Energy New Zealand Ltd

Date/Time	Depth	Type	Locn	Density	F.Vis	Filt	HTHP	Cake	PV	YP	pH	Sand	LGS	HGS	LCM	Calcium	Chlorides	Gels 10s	10m	30m
Well ID: NZ050091A				**Well Name: Ahuroa South B-1 ST# 1**																
10-Nov-05 02:00	2381.0	SBM	PIT	8.90	108		0.5	2	31	26		0.25	3.1	2.4		3	3	10	17	25
11-Nov-05 02:00	2400.0	SBM	PIT	8.60	112		0.5	2	29	22		0.25	3.4	1.2		3	3.2	9	17	24
12-Nov-05 02:00	2424.0	SBM	PIT	8.50	108		0.5	2	22	16			3	1.3		2.6	2.6	9	20	26
13-Nov-05 02:00	2424.0	SBM	PIT	8.50	75		1	2	23	19		0.25	2.8	1.3		3	2.8	7	14	18
14-Nov-05 02:00	2455.0	SBM	PIT	8.50	84		1.2	2	23	20		0.25	3	1.4		3	2.8	8	17	23
15-Nov-05 02:00	2566.0	SBM	PIT	8.50	70		1.4	2	24	15		0.25	3.8	0.8		3	2.6	8	15	26
16-Nov-05 02:00	2698.0	SBM	PIT	8.60	68		1.4	2	23	13		0.25	3.5	1.3		3	2.2	8	16	22
17-Nov-05 02:00	2751.0	SBM	PIT	8.65	71		1.6	2	23	14		0.25	3.6	1.5		3	2.3	8	18	22
18-Nov-05 02:00	2818.0	SBM	PIT	8.70	72		2	2	25	17		0.2	3.4	1.7		3	2.6	8	17	25
19-Nov-05 02:00	2861.0	SBM	PIT	8.70	72		1.8	2	26	25		0.25	4.3	1.3		3	2.7	8	18	24
20-Nov-05 02:00	2874.0	SBM	PIT	8.70	74		1.8	2	25	16		0.25	3.6	1.6		3	2.7	8	16	24
21-Nov-05 02:00	2921.0	SBM	PIT	8.70	72		1.8	2	24	17		0.25	3.6	1.6		3	2.7	8	21	28
22-Nov-05 02:00	2993.0	SBM	PIT	8.70	77		1.8	2	24	18		0.25	3.8	1.5		3.1	2.9	8	22	28
23-Nov-05 02:00	3004.0	SBM	PIT	8.70	76		1.4	2	26	16		0.25	3.8	1.5		3	2.8	16	22	28
24-Nov-05 02:00	3034.0	SBM	PIT	8.70	74		1.4	2	26	17		0.25	3.6	1.5		3	2.8	12	22	28
25-Nov-05 02:00	3085.0	SBM	PIT	8.70	74		1.4	2	26	16		0.25	3.6	1.6		3	2.8	12	22	26
26-Nov-05 02:00	3085.0	SBM	PIT	8.70	77		1.4	2	26	17		0.25	3.6	1.6		3	2.8	14	24	28
27-Nov-05 02:00	2445.0	KCL	PIT	8.50									2.3	0.5						
28-Nov-05 02:00	2455.0	KCL	PIT	8.50													14500			
29-Nov-05 02:00																				

Printed: 14:31 21-Mar-06

End of Report

Bit Summary Report

Well ID = 'NZ050091' **Bits Ordered By Date Run**

No	Run No	Diam	Manuf.	Model	Serial No	Nozzles - 1/32 in	TFA	Date/Time In	Depth - m In	Depth - m Out	Hole Made	Hrs	ROP	WOB	RPM	Flow	MWt	Grading In	Grading Out	Grading Major	Grading Loc	Grading Brg	Grading Gge	Grading Oth	Grading Pull
Well ID: NZ050091					**Well Name: Ahuroa South B-1**																				
1	1	12.250	SEC	xlc-1	10584831	20 20 20	0.9204	05-Oct-05 18:32	33.0	659.0	626.0	49.0	12.78	15	120	755	9.10	1	1 NO	S	2	1 BU	TD	
2	1	8.500	HYC	DSX104HG	111856	14 14 14	0.451	10-Oct-05 13:42	659.0	2400.0	1741.0	113.0	15.41	5	80	515	9.30	1	3 CT	T	X	1 CT	CSG	
3	1	6.000	HYC	dsx516m-b-	113097	13 13 13 13 13	0.6481	22-Oct-05 4:57	2403.0	2903.0	500.0	119.0	4.20	8	80	195	8.60	3	6 WT	S	N	1 CT	PR	
4	1	6.000	HYC	DSX 516 M	113096	15 15 15 13 13	0.777	29-Oct-05 6:00	2903.0	3296.0	393.0	152.0	2.59	8	80	200	8.80	-2	6 WT	S	X	1 WT	FM	
5	1	6.000	HYC	DSX 413M-	113215	15 15 15 15	0.6903	06-Nov-05 5:30	3296.0	3370.0	74.0	11.5	6.43	5	80	200	8.70	1	1 NO		X	NO	TD	

Printed: 15:37 25-May-07

End of Report

Bit Summary Report

Well ID = 'NZ050091A' **Bits Ordered By Date Run**

No	Run No	Diam	Manuf.	Model	Serial No	Nozzles - 1/32 in	TFA	Date/Time In	Depth - m In	Depth - m Out	Hole Made	Hrs	ROP	WOB	RPM	Flow	MWt	Grading In	Grading Out	Grading Major	Grading Loc	Grading Brg	Grading Gge	Grading Oth	Pull
Well ID: NZ050091A					**Well Name: Ahuroa South B-1 ST# 1**																				
6	1	6.000	HTC	XR PS	PC 0470	32 32 32	2.3562	10-Nov-05 13:30	2385.0	2400.0	15.0							2	2	WT	A	0	1	WT	BHA
7	1	6.000	SMITH	XR+	PC 7092	18 18 18	0.7455	11-Nov-05 17:30	2400.0	2433.0	33.0	36.5	0.90	4	40	200	8.50	1	1	NO		1	1	NO	BHA
8	1	6.000	HYC	DSX 519S	211111	14 14 14 14 14	0.7517	13-Nov-05 14:14	2433.0	2874.0	441.0	93.7	4.71	10000	80	200	8.70	3	4	WT	S	X	6	NO	OTH
9	1	6.000	SMITH	M516	JW3280	13 13 13 15 16	0.7578	19-Nov-05 20:34	2874.0	3085.0	211.0	74.9	2.82	4	80	200	8.70	1	4	WT	S	X	1	WT	TD

Printed: 15:38 25-May-07 *End of Report*

Swift Energy Ltd
New Plymouth
New Zealand

Taranaki - Onshore

Recap of Cementing Services For Ahuroa South B-1 Well Construction

Prepared for Dick Gloger
December, 2005
Version 1

Submitted by Sarah Farnworth
Halliburton New Zealand Pty Ltd
1 Paraite Road, Bell Block,
New Plymouth, New Zealand
Ph: +64 6 7552405

HALLIBURTON

1. TABLE OF CONTENTS

1. TABLE OF CONTENTS 1

2. CEMENTING OPERATIONS WELL REVIEW 3

2.1 CEMENTING OPERATIONS WELL SUMMARY 5
2.2 CEMENTING EVENTS 6
2.3 WELL SCHEMATIC – AS CEMENTED 7
2.4 APPROXIMATE WELL COST 8
2.4.1 Ticket Summary 8
2.4.2 Charges Summary to Date (Approx) 9

3. CEMENT 9-5/8" CASING TO +/- 652M MD 11

3.1 DESIGNED CEMENT PROGRAM 13
3.2 PRIMARY CEMENTING JOB LOG 14
3.3 EJCS 15
3.4 PRESSURE TEST RIG EQUIPMENT, CASING AND FORMATION 16

4. CEMENT 7" INTERMEDIATE CASING TO +/- 2395M MD 19

4.1 DESIGNED CEMENT PROGRAM 21
4.2 PRIMARY CEMENTING JOB LOG 22
4.3 EJCS 23
4.4 PRESSURE TEST BOP'S, RIG EQUIPMENT, CASING AND FORMATION 24

5. PUMP KICK OFF PLUG AT +/- 2526M MD 27

5.1 DESIGNED CEMENT PROGRAM 29
5.2 PRIMARY CEMENTING JOB LOG 30
5.3 EJCS 31
5.4 PRESSURE TEST RIG EQUIPMENT, CASING AND FORMATION 32

6. SUSPEND WELL 35

6.1 DESIGNED CEMENT PROGRAMME 37
6.2 JOB LOG 38
6.3 EJCS 39
6.4 PRESSURE TEST CASING & WELLHEAD 40

APPENDIX A – TICKETS 41

The following report is confidential, and is the property of Halliburton Energy Services. This report is based on sound engineering practices, but because of variable well conditions and other information which must be relied upon, Halliburton makes no warranty, express or implied, as to the accuracy of the data or any of the calculations or opinions expressed herein. You agree that Halliburton shall not be liable for any loss or damage whether due to negligence or otherwise arising out of or in connection with such data, calculations or opinions. This report may not be copied, published or disclosed in whole or in part without the written consent of Halliburton Energy Services.

2. CEMENTING OPERATIONS WELL REVIEW

2.1 Cementing Operations Well Summary

Ahuroa South B-1 was a vertical well drilled with Parker Drilling Rig 252.

The first section of this well was a 12-1/4" hole drilled to 659 mMD. This was cased with 9-5/8", 53.5 lb/ft casing run in hole to 652.2 mMD.
The cement job consisted of a 58 bbl water flush, followed by 191.2 bbls of 11.8 lb/gal Class A lead slurry and 33 bbls of 15.6 lb/gal Class A tail slurry then 152 bbls of mud as the displacement. The cement volumes were based on a gauge hole with 50% excess.

Following the cementation of the 9-5/8" casing, an 8-1/2" hole was drilled to 2403 mMD. A 7", 29 lb/ft production casing was run in hole and cemented to 2395 mMD.
Prior to cementing the casing 58 bbls of water was pumped. The cement slurry was 88.4 bbls of 11.8 lb/gal Class A lead slurry followed by 177.5 bbls of 15.6 lb/gal Class A tail slurry. The cement volumes were based on an open hole caliper of approximately 9.25" diameter with lead including 15% excess and the tail having 25% excess. The cement was displaced down hole with 280 bbls of oil based mud then22 bbls of water and the plug was bumped at 2200psi.


The next cement job was a kick off plug from 2526 mMD to 2380 mMD. Prior to the 21.4 bbl 17.2 lb/gal Class G slurry cement job, 30 bbls of Surfactant Water Flush was pumped. The plug was displaced with 44.6 bbls of synthetic based mud.

The 6" hole drilled from the kick off point was suspended with plugs set at the following depths:
Plug #1 set across the 7" casing shoe at 2425 – 2325m with 11.3 bbls of 17.2 lb/gal slurry. This plug was not tagged due to slippage.
EZ-SV Packer set at 2365m, 30m above the 7" casing shoe.
Plug #2 set on top of EZ-SV from 2365 – 2316m with 12 bbls of 15.8 lb/gal slurry.
Surfactant water flush was pumped before both plug slurries.

2.2 Cementing Events

Event Date	Event Description
08-10-05	Prepare for 9-5/8" Surface Casing cement job.
09-10-05	Cement 9-5/8" Surface Casing 191.2 bbls of 11.8 lb/gal Class A slurry with 3.5 %bwow prehydrated bentonite and 0.3 %bwoc CFR-3 33 bbls of 15.6 lb/gal neat Class A slurry.
10-10-05	Pressure Test BOP's & rig equipment
11-10-05	Formation Integrity Test – EMW = 11.0 lb/gal
20-20-05	Prepare for 7" Intermediate Casing cement job
21-10-05	Cement 7" Intermediate Casing 88.4 bbls of 11.8 lb/gal Class A slurry with 3.5 %bwow prehydrated bentonite, 0.3 %bwoc CFR-3 and 0.2 %bwoc HR-5 177.5 bbls of 15.6 lb/gal Class A slurry with 1.0 %bwoc Halad-322 and 0.25 %bwoc HR-5
22-10-05	Pressure Test BOP's & rig equipment
23-10-05	Casing Integrity Test Formation Integrity Test – EMW = 11.4 lb/gal
09-11-05	Pump Kick Off Plug 21.4 bbls of 17.2 lb/gal Class G slurry including 0.5 %bwoc CFR-3 and 0.06 gal/sk SCR-100L
10-11-05	Pressure Test BOP's & rig equipment
25-11-05	Prepare for well suspension
26-11-05	Pump Suspension Plug #1 11.3 bbls of 17.2 lb/gal Class G slurry containing 0.5 %bwoc CFR-3 and 0.06 gal/sk SCR-100L
27-11-05	Set EZ-SV at 2365 mMD Pump Suspension Plug #2 12 bbls of 15.8 lb/gal Class G slurry with 4 gals/10bbls SCR-100L Pressure Test EZ-SV
28-11-05	Pressure Test Wellhead and Casing

2.3 Well Schematic – As Cemented



2.4 Approximate Well Cost

2.4.1 Ticket Summary

Ticket Number	Ticket Description	Ticket Value (USD)
004394	Ahuroa Sth B1 Cementing Services 30th September to 12th October	$14,690.00
004395	Ahuroa Sth B1 Cement and Chemical Sales for 9 5/8" casing job	$11,300.61
004408	Ahuroa Sth B1 Cementing Services 13th October to 25th October	$12,720.00
004409	Ahuroa Sth B1 Cement and Chemical Sales for 7" casing job	$18,247.38
004416	Ahuroa Sth B1 Cementing Services 26th October to 11th November 2005	$12,534.15
004417	Ahuroa Sth B1 Cement and chemical Sales for Kick off plug 9th November	$10,460.21
004455	Ahuroa Sth B1 ST 1 Cementing Services 12th November 2005 to 28th November 2005	$16,186.47
004456	Ahuroa Sth B1 ST 1 Cement and chemical Sales for Suspension plugs 26th/27th November 2005	$13,054.81
	TOTAL US$	**$ 109,193.63**

2.4.2 Charges Summary to Date (Approx)

Job			Charge (USD)
13-3/8" Production Casing			
Mobilization	$	1,450.00	
Materials	$	8,284.17	
Equipment	$	3,000.00	
Personnel	$	6,340.00	$ 19,074.17
9-5/8" Surface Casing			
Mobilization	$	450.00	
Materials	$	21,263.82	
Equipment	$	5,500.00	
Personnel	$	3,170.00	$ 30,383.82
Kick Off Plug			
Mobilization	$	1,464.15	
Materials	$	10,460.21	
Equipment	$	2,900.00	
Personnel	$	3,820.00	$ 18,644.36
P & A			
Mobilization	$	1,196.47	
Materials	$	13,054.81	
Equipment	$	7,400.00	
Personnel	$	5,040.00	$ 26,691.28
Pressure Testing			
BOP's, Rig Eqpt	$	4,500.00	
FIT's	$	900.00	$ 5,400.00
Equipment Rental			$ 9,000.00
Total			$ 109,193.63

3. CEMENT 9-5/8" CASING TO +/- 652M MD

3.1 Designed Cement Program

Swift Energy
Ahuroa South B1

9-5/8" Casing

Well Data

	ft AH	m AH			
Previous Casing	197	60	Casing Weight	47	lbs/ft
Lead TOC	0	0	BHST	161	°F
Tail TOC	1812	552	BHCT	127	°F
Setting Depth	2140	652	Mud Weight	9.4	ppg
Shoe Track	Single Joint		Equivalent Mud Weight	12.4	ppg
			Est. Final Differential Pressure	332	psi

Calculations

Lead Slurry	**m**		**ft/m**		**cuft/ft**		**cu ft**	***bbl***
13-3/8" Casing X 9-5/8" Casing	60	x	3.2808	x	0.3354	=	66.02	*11.76*
12-1/4" Hole X 9-5/8" Casing	492	x	3.2808	x	0.3132	=	505.76	*90.08*
				Excess	100%	=	505.76	*90.08*
Lead Total						=	**1077.54**	***191.92***
					Actual Volume Pumped (incl excess)			*191.2*
Tail Slurry								
12-1/4" Hole X 9-5/8" Casing	100	x	3.2808	x	0.3132	=	102.75	*18.30*
				Excess	50%	=	51.38	*9.15*
12-1/4" Rat Hole	5	x	3.2808	x	0.8185	=	13.43	*2.39*
9-5/8" 47# Shoe Track	12.2	x	3.2808	x	0.4110	=	16.45	*2.93*
Tail Total						=	**184.01**	***32.77***
					Actual Volume Pumped (incl excess)			*33*
Displacement								
9-5/8" 47# Casing	640	x	3.2808	x	0.4110	=	862.98	*153.70*
Displacement Total						=	**862.98**	***153.70***
						Actual Volume Pumped		*152*
Top Up Slurry								
13-3/8" Casing X 9-5/8" Casing	20	x	3.2808	x	0.3354	=	**22.01**	***3.92***
						Actual Volume Pumped		*4*

Fluid Descriptions

Spacers / Flush

		Volume	
	Drillwater	60	bbls
	Actual Volume Pumped	*58*	*bbls*

Lead Slurry

Cement:	Golden Bay Class A			Slurry Density	11.8	ppg
				Slurry Yield	2.56	ft^3/sk
Additives:	Prehydrated Bentonite	3.5%	BWOW	Mix Water Type	Location Water	
	CFR-3	0.3%	BWOC	Mix Water Req.	15.29	gal/sk
	NF-6	0.5	gal/10bbl	Mix Soln Req.	15.29	gal/sk
				Sack Weight	94.0	lb
				Required Pump Time	2.57	hrs
				Thickening Time (est)	3.00 hrs @	126°F
			24 hr	Compressive Strength (est)	500 psi @	160°F

Tail Slurry

Cement:	Golden Bay Class A			Slurry Density	15.6	ppg
				Slurry Yield	1.17	ft^3/sk
Additives:	NF-6	0.5	gal/10bbl	Mix Water Type	Location Water	
				Mix Water Req.	5.05	gal/sk
				Mix Soln Req.	5.05	gal/sk
				Sack Weight	94.0	lb
				Required Pump Time	2.04	hrs
				Thickening Time (est)	2.5 hrs @	126°F
			24 hr	Compressive Strength (est)	2500 psi @	160°F

Chemical Requirements

The following quantities are based on volumes pumped and do not take into account mixwater tank bottoms.

Material	**Spacer / Flush**	**Lead Slurry**	**Tail Slurry**	**Top Up**	**Total**	***Actual***	**Units**
Golden Bay Class A		421	157	19	597	*597*	sks
Prehydrated Bentonite		1876			1876	*2100*	lbs
CFR-3		119			119	*150*	lbs
NF-6		2	2		4	*5*	gals
Location Water	60	153	19	2	234		bbls

3.2 Primary Cementing Job Log

HALLIBURTON Cementing Job Log			SALES ORDER # (If applicable)		JOB DATE: 9th October 2005		ON SITE HES REP: Greg Dennis	
COUNTRY: New Zealand		BDA: Perth		LOCATION / FIELD NAME: New Plymouth			JOB SITE: Land	
CUSTOMER: Swift Energy		CUSTOMER REPRESENTATIVE: Wallace Suire			WELL NAME & NUMBER: AHUROA STH B1			
PSL GROUP - LEVEL 1: Cementing		PSL GROUP - LEVEL 2: Zonal Isolation			PSL GROUP - LEVEL 3: Cementing Services & Materials			
JOB TYPE CODE: Cement Job		JOB PURPOSE CODE: Surface Casing 7521			WELL TYPE: Development			JOB CLASS: Non-RTO
Special Tools		Complete Only if a Special Tools Job was performed						
JOB TYPE CODE		JOB PURPOSE CODE						

HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS
Greg Dennis	18				
Daniel Dietrich	9				
Kris Roulston	9				

HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES
SK 9178					

Chart #	Date & Time	Volume (BBL)	Pressure (PSI)	Rate (BPM)	JOB DESCRIPTION / REMARKS
					9 5/8" 53.5#/FT CASING
					TD: 659M; FLOAT SHOE: 652.2M; FLOAT COLLAR: 647M
					LEAD VOLUME BASED ON GAUGE HOLE PLUS 100% XS.
	8th Oct				TAIL VOLUME (100M) BASED ON GAUGE HOLE PLUS 50% XS
					Prepare for job, mix chemicals
	9th Oct				
	0:00				Arrive location
	1:00				Hold JSA with rig crew.
					Rig up Compact cementing head. Rig circulate well.
	2:10	20			Pump 20bbls water ahead
			3000		Pressure test lines to 3000psi (OK)
		38	500	4	Pump 38bbls water
	2:25				Release Bottom NR plug (W/Ford)
		2			Pump 2bbls water to kick plug off.
	2:28	191.2	560 max	8 av	Mix and pump Lead slurry
					420 sks Class A cement
					11.8ppg, Yield 2.56cuft/sk, Water ratio 15.29gals/sk
					3.5% PH Aquagel; 0.3% CFR-3
	3:09	33	500 max	5.5 av	Mix and pump Tail slurry
					158 sks Class A cement
					15.6ppg, Yield 1.17cuft/sk, Water ratio 5.05 gals/sk
					Neat
					Release Top NR plug (W/Ford)
	3:20			6 av	Start displacing with WBM
	3:45	152	1500		Bump plug to 1500psi
	3:48				Bleed off, check floats (OK) 1.25bbls bled back
					NB: No cement returns noted at surface (Some spacer water seen)
					(+/- 100bbls XS slurry)
					TOP UP JOB
	5:20	2			Pump 2bbls water ahead
		4			Pump 19sks A cement at 15.6ppg, Neat. (3bbls, 14sks to casing)

3.3 EJCS

HALLIBURTON	CEMENTING END OF JOB CUSTOMER SATISFACTION	SALES ORDER # / TICKET # / JOB # 3977975	JOB DATE 9th October 2005	ON SITE HES REP Greg Dennis
COUNTRY New Zealand	BDA Perth	LOCATION New Plymouth		JOB SITE TYPE Land
CUSTOMER Swift Energy	CUSTOMER REPRESENTATIVE Wallace Suire	WELL NAME & NUMBER AHUROA STH B1		
PSL GROUP - LEVEL 1 Cementing	PSL GROUP - LEVEL 2 Zonal Isolation	PSL GROUP - LEVEL 3 Cementing Services & Materials		
JOB TYPE CODE Cement Job	JOB PURPOSE CODE Surface Casing 7521	WELL TYPE Development		JOB CLASS Non-RTO
Special Tools				
JOB TYPE CODE	JOB PURPOSE CODE			
HSE Incident? (Accident Injury etc) ☐ YES ☑ NO	Operating Time 2	Customer Completed ☑		

Dear Customer,
We hope that you were satisfied with the service quality of this job performed by Halliburton. It is the aim of our management and service personnel to deliver equipment and service of a standard unmatched in the service sector of the energy industry.

Please take the time to let us know if our performance met with your satisfaction. Please be as critical as possible to ensure we constantly improve our service. Your comments are of great value to us and are intended for the exclusive use of Halliburton.

Please indicate your response by placing a " X " in the box underneath the rating that best matches your opinion.

DESCRIPTION	Superior Performance (New quality performance standard - Best Practice) 5	Exceeded Expectations (Provided more than required - Potential Best Practice) 4	Met Expectations (Did what was expected - Prevention/Improvement) 3	Below Expectations (Did not do as expected. Recovery Made - CPI Required) 2	Poor Performance (Job problems/failures, some recovery made - CPI Required) 1
Did our personnel perform the job to your satisfaction?		✓			
Did our equipment perform the job to your satisfaction?		✓			
Did we perform the job to the agreed upon design?		✓			
Did our products and materials perform as you expected?		✓			
Did we perform in a safe & careful manner?		✓			
Did we perform in an environmentally sound manner?		✓			
Was the job performed as scheduled?		✓			
Did the equipment condition & appearance meet you expectations?		✓			
How well did our personnel communicate during mobilisation, rig-up and job execution?		✓			

What can we do to improve our service?

Customer Comments

Customer Signature:

All data collected is for trend analysis and business process improvement only.

3.4 Pressure Test Rig Equipment, Casing and Formation

HALLIBURTON Cementing Job Log			SALES ORDER # (If applicable)		JOB DATE: 10th October 2005		ON SITE HES REP: Greg Dennis
COUNTRY: New Zealand		BDA: Perth		LOCATION / FIELD NAME: New Plymouth		JOB SITE: Land	
CUSTOMER: Swift Energy		CUSTOMER REPRESENTATIVE: Wallace Suire			WELL NAME & NUMBER: AHUROA STH B1		
PSL GROUP - LEVEL 1: Cementing		PSL GROUP - LEVEL 2: Zonal Isolation			PSL GROUP - LEVEL 3: Cementing Services & Materials		
JOB TYPE CODE: Miscellaneous Pumping		JOB PURPOSE CODE: Test Blowout Preventer 15111			WELL TYPE: Development		JOB CLASS: Non-RTO
Special Tools		Complete Only if a Special Tools Job was performed					
JOB TYPE CODE		JOB PURPOSE CODE					

HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS
G Dennis	11				

HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES
9178					

Chart #	Date & Time	Volume (BBL)	Pressure (PSI)	Rate (BPM)	JOB DESCRIPTION / REMARKS
					9 5/8" CASING / BOP AND CHOKE MANIFOLD TESTING
	10th Oct				
	6:45				Arrive location.
Chart #1	7:15		1500		Pressure test 9 5/8" casing to 1500psi (Leaking BOP clamps)
	7:45		1500		Retest 9 5/8" casing (BOP clamp still leaking - Lift BOP's)
					Test Choke manifold
	8:15				Flush manifold to flare pit
Test #1	8:20		250/3000		Poor boy and Flare pit valves 250psi (OK) 3000psi (Leaking choke line)
#1A	8:30		3000		Retest #1 (OK)
#2	8:41		250/5000		Downstream choke valves (OK)
#3	8:57		250/5000		Outside upstream valves (OK)
#4	9:20		250/5000		Inside upstream valves (OK)
Chart #2	11:20		1500		Retest 9 5/8" casing (BOP clamp still leaking)
Test #5	11:50		1500	0.955	Retest 9 5/8" casing (OK)
					BOP's
#6	13:30		250/3000		Annular and 4" mud pump valves 250psi (OK) 3000psi (Leaking)
#6A	13:54		3000		Retest #6 (OK)
#7	14:05		250/3000		Annular and 4" standpipe valve 250psi (OK) 3000psi (Leaking clamp)
#7A	14:37		3000		Retest (Leaking clamp)
#7B	14:50		3000		Retest (Leaking clamp)
#7C	15:27		3000		Retest #7 (OK)
#8	15:45		250/5000		4 1/2" Pipe rams, upper kelly cock, Outer kill, HCR (OK)
#9	16:10		250/5000		Pipe rams, lower kelly cock, inner kill, 4" manual (OK)
#10	16:30		250/5000		TIW (OK)
#11	17:00		250/5000		Gray valve (OK)
#12	17:40		250/5000		Blind rams, kill line NRV (OK)
	17:55				Finish.

HALLIBURTON Cementing Job Log		SALES ORDER # (If applicable)	JOB DATE	ON SITE HES REP
			11th October 2005	Greg Dennis

COUNTRY	BDA	LOCATION / FIELD NAME	JOB SITE
New Zealand	Perth	New Plymouth	Land

CUSTOMER	CUSTOMER REPRESENTATIVE	WELL NAME & NUMBER
Swift Energy	Wallace Suire	AHUROA STH B1

PSL GROUP - LEVEL 1	PSL GROUP - LEVEL 2	PSL GROUP - LEVEL 3
Cementing	Zonal Isolation	Cementing Services & Materials

JOB TYPE CODE	JOB PURPOSE CODE	WELL TYPE	JOB CLASS
Miscellaneous Pumping	Test Casing Seat 7541	Development	Non-RTO

Special Tools	Complete Only if a Special Tools Job was performed
JOB TYPE CODE	JOB PURPOSE CODE

HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS
G Dennis	4				

HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES
9178					

Chart #	Date & Time	Volume (BBL)	Pressure (PSI)	Rate (BPM)	JOB DESCRIPTION / REMARKS
					FORMATION INTEGRITY TEST AFTER DRILLING 9 5/8" SHOE
	11th Oct				
	1:00				Arrive location.
	5:50				F.I.T
					Depth: 652.2m (Shoe) 2140ft
					MW : 8.8ppg
					EMW reqd : 11.5 (300psi)
		0.25	30		
		0.5	270		
		0.537	315		
			297		After 1 minute
			284		After 2 minutes
			270		After 3 minutes
			259		After 4 minutes
			250		After 5 minutes
	6:02				Bleed off, 0.53bbls bled back.

4. CEMENT 7" INTERMEDIATE CASING TO +/- 2395M MD

4.1 Designed Cement Program

Swift Energy
Ahuroa South B1

7" Casing

Well Data

	ft AH	m AH
Lead TOC	1638	499
Previous Casing	2140	652
Tail TOC	4003	1220
Setting Depth	7858	2395
Shoe Track	Two Joint	

Casing Weight	29	lbs/ft
Previous Casing Weight	47.0	lbs/ft
Hole Size	8-1/2	in
BHST	166	°F
BHCT	149	°F
Mud WBM	9.50	ppg
Equivalent Mud Weight	13.3	ppg
Est. Final Differential Pressure	1544	psi

Calculations

									cu ft	*bbl*
Lead Slurry										
9-5/8" Casing X 7" Casing	153	x	3.2808	x	0.1301	=	65.31			*11.63*
9.26" Hole X 7" Casing	568	x	3.2808	x	0.2007	=	373.87			*66.59*
				Excess	15%	=	56.08			*9.99*
Lead Total						=	**495.26**			***88.21***
							Actual Volume Pumped (incl excess)			*88.4*
Tail Slurry										
9.26" Hole X 7" Casing	1175	x	3.2808	x	0.2007	=	773.69			*137.80*
				Excess	25%	=	193.42			*34.45*
9.26" Rat Hole	3	x	3.2808	x	0.4680	=	4.61			*0.82*
7" 29# Casing	24.4	x	3.2808	x	0.2083	=	16.67			*2.97*
Tail Total						=	**988.39**			***176.04***
							Actual Volume Pumped (incl excess)			*177.5*
Displacement										
7" 29# Casing	2371	x	3.2808	x	0.2083	=	1620.05			*288.54*
Displacement Total						=	**1620.05**			***288.54***
							Actual Volume Pumped			*302*

Fluid Descriptions

Spacers / Flush

		Volume	
	Fresh Water	60	bbls
	Actual Volume Pumped	*58*	*bbls*

Lead Slurry

Cement:	Golden Bay Class A			Slurry Density	11.8 ppg
				Slurry Yield	2.56 ft^3/sk
Additives:	Prehydrated Bentonite	3.5%	BWOW	Mix Water Type	Location Water
	CFR-3	0.30%	BWOC	Mix Water Req.	15.29 gal/sk
	HR-5	0.20%	BWOC	Mix Soln Req.	15.29 gal/sk
	NF-6	0.5	gal/10bbl	Sack Weight	94.0 lb
				Required Pump Time	3.13 hrs
				Thickening Time Estimated	5.00 hrs @ 149°F
			24 hr	Compressive Strength Estimated	800 psi @ 166°F

Tail Slurry

Cement:	Golden Bay Class A			Slurry Density	15.8 ppg
				Slurry Yield	1.17 ft^3/sk
Additives:	Halad-322	1.0%	BWOC	Mix Water Type	Location Water
	HR-5	0.25%	BWOC	Mix Water Req.	5.05 gal/sk
	NF-6	0.5	gal/10bbl	Mix Soln Req.	5.05 gal/sk
				Sack Weight	94.0 lb
				Required Pump Time	2.89 hrs
				Thickening Time Estimated	4:30 hrs @ 149°F
			24 hr	Compressive Strength Estimated	3200 psi @ 166°F
				Fluid Loss Estimated	90 ml @ 149°F

Chemical Requirements

The following quantities are based on volumes pumped and do not take into account mixwater tank bottoms.

Slurry Chemicals	Spacer / Flush	Lead Slurry	Tail Slurry	Total	*Actual*	Units
Golden Bay Class A		193	845	1038	*1046*	sks
Prehydrated Bentonite		862		862	*900*	lbs
CFR-3		55		55	*75*	lbs
HR-5		36	199	235	*255*	lbs
NF-6		3.5	5.1	8.6	*10*	gals
Halad-322			794	794	*870*	lbs
Location Water	60.0	70.4	101.6	232		bbls

4.2 Primary Cementing Job Log

HALLIBURTON Cementing Job Log		SALES ORDER # (If applicable)	JOB DATE	ON SITE HES REP
			21st October 2005	Greg Dennis
COUNTRY	BDA	LOCATION / FIELD NAME		JOB SITE
New Zealand	Perth	New Plymouth		Land
CUSTOMER	CUSTOMER REPRESENTATIVE		WELL NAME & NUMBER	
Swift Energy	Wallace Suire		AHUROA STH B1	
PSL GROUP - LEVEL 1	PSL GROUP - LEVEL 2		PSL GROUP - LEVEL 3	
Cementing	Zonal Isolation		Cementing Services & Materials	
JOB TYPE CODE	JOB PURPOSE CODE		WELL TYPE	JOB CLASS
Cement Job	Intermediate Casing 7522		Development	Non-RTO
Special Tools	Complete Only if a Special Tools Job was performed			
JOB TYPE CODE	JOB PURPOSE CODE			

HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS
Greg Dennis	17				
Zahn Leishman	17				
John Williams	10				
HES UNIT NUMBERS	**RT MILES**	**HES UNIT NUMBERS**	**RT MILES**	**HES UNIT NUMBERS**	**RT MILES**
SK 9178					

Chart #	Date & Time	Volume (BBL)	Pressure (PSI)	Rate (BPM)	JOB DESCRIPTION / REMARKS
					7" 29#/FT CASING
					TD: 2403M; FLOAT SHOE:2395M; FLOAT COLLAR:2382.4M
					OH CALIPER AVERAGE 0.2007CUFT/FT (+/- 9 1/4")
					TOP LEAD SLURRY TO 499M 15% XS (150M INSIDE 9 5/8")
					TOP TAIL SLURRY TO 1220M 25% XS (ABOVE MT MESSENGER)
	20th Oct				
	11:00				Arrive location, mix chemicals and prepare for job.
	22:30				Hold JSA with rig crew.
					Rig up Compact cementing head. (8m in air - casing stuck on bottom)
	23:15	20	400 max	2.5	Pump 20bbls water ahead
			4000		Pressure test lines to 4000psi (OK)
	23:30	38	560	2.5	Pump 38bbls water
	23:50				Release Bottom NR plug (W/Ford)
		2			Pump 2bbls water to kick plug off.
	21st Oct				
	0:05	88.4	1200 max	5.9 av	Mix and pump Lead slurry
					194 sks Class A cement
					11.8ppg, Yield 2.56cuft/sk, Water ratio 15.29gals/sk
					3.5% PH Bentonite (MI), 0.3% CFR-3, 0.2% HR-5
	0:25	177.5	900 max	5.5 av	Mix and pump Tail slurry
					852 sks Class A cement
					15.6ppg, Yield 1.17cuft/sk, Water ratio 5.05gals/sk
					1% Halad 322, 0.25% HR-5
	1:10				Release Top NR plug (W/Ford)
		301.75	2000 max	4.3 av	Displace with 280bbls SBM, last 22bbls water
				(6.5 max)	
	2:20	302	2200		Bump plug to 2200psi (Final differential +/-1700psi)
	2:23				Bleed back - Floats holding ok.
					3bbls bled back
					Note: 7" casing average ID = 159mm = 0.038064bbls/ft
					: Mud losses prior to cementing, good returns while cementing
					Final differential higher than estimated.

4.3 EJCS

HALLIBURTON CEMENTING END OF JOB CUSTOMER SATISFACTION	SALES ORDER # / TICKET # / JOB # 3993024	JOB DATE 21st October 2005	ON SITE HES REP Greg Dennis
COUNTRY New Zealand	BDA Perth	LOCATION New Plymouth	JOB SITE TYPE Land
CUSTOMER Swift Energy	CUSTOMER REPRESENTATIVE Wallace Suire	WELL NAME & NUMBER AHUROA STH B1	
PSL GROUP - LEVEL 1 Cementing	PSL GROUP - LEVEL 2 Zonal Isolation	PSL GROUP - LEVEL 3 Cementing Services & Materials	
JOB TYPE CODE Cement Job	JOB PURPOSE CODE Intermediate Casing 7522	WELL TYPE Development	JOB CLASS Non-RTO
Special Tools			
JOB TYPE CODE	JOB PURPOSE CODE		
HSE Incident? (Accident Injury etc) ☐ YES ☑ NO	Operating Time 3	Customer Completed ☑	

Dear Customer,
We hope that you were satisfied with the service quality of this job performed by Halliburton. It is the aim of our management and service personnel to deliver equipment and service of a standard unmatched in the service sector of the energy industry.

Please take the time to let us know if our performance met with your satisfaction. Please be as critical as possible to ensure we constantly improve our service. Your comments are of great value to us and are intended for the exclusive use of Halliburton.

Please indicate your response by placing a " X " in the box underneath the rating that best matches your opinion.

DESCRIPTION	Superior Performance (New quality performance standard - Best Practice) 5	Exceeded Expectations (Provided more than required - Potential Best Practice) 4	Met Expectations (Did what was expected - Prevention/Improvement) 3	Below Expectations (Did not do as expected, Recovery Made - CPI Required) 2	Poor Performance (Job problems/failures, some recovery made - CPI Required) 1
Did our personnel perform the job to your satisfaction?		✓			
Did our equipment perform the job to your satisfaction?		✓			
Did we perform the job to the agreed upon design?		✓			
Did our products and materials perform as you expected?		✓			
Did we perform in a safe & careful manner?		✓			
Did we perform in an environmentally sound manner?		✓			
Was the job performed as scheduled?		✓			
Did the equipment condition & appearance meet you expectations?		✓			
How well did our personnel communicate during mobilisation, rig-up and job execution?		✓			

What can we do to improve our service?

Customer Comments

Customer Signature: [signature]

All data collected is for trend analysis and business process improvement only.

4.4 Pressure Test BOP's, Rig Equipment, Casing and Formation

HALLIBURTON Cementing Job Log			SALES ORDER # (If applicable)		JOB DATE: 22nd October 2005		ON SITE HES REP: Greg Dennis
COUNTRY: New Zealand		BDA: Perth		LOCATION / FIELD NAME: New Plymouth		JOB SITE: Land	
CUSTOMER: Swift Energy		CUSTOMER REPRESENTATIVE: Wallace Suire			WELL NAME & NUMBER: AHUROA STH B1		
PSL GROUP - LEVEL 1: Cementing		PSL GROUP - LEVEL 2: Zonal Isolation			PSL GROUP - LEVEL 3: Cementing Services & Materials		
JOB TYPE CODE: Miscellaneous Pumping		JOB PURPOSE CODE: Test Blowout Preventer 15111			WELL TYPE: Development		JOB CLASS: Non-RTO
Special Tools		Complete Only if a Special Tools Job was performed					
JOB TYPE CODE		JOB PURPOSE CODE					

HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS
G Dennis	10				

HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES
9178					

Chart #	Date & Time	Volume (BBL)	Pressure (PSI)	Rate (BPM)	JOB DESCRIPTION / REMARKS
					BOP AND CHOKE MANIFOLD TESTING FOLLOWING 7" CASING
	22nd Oct				
	5:45				Arrive location.
	10:40				Fill hole
Test #1	10:55		250/3000		Test Poor Boy and Flare pit valves, Annular (OK)
#2	11:15		250/5000		3 1/2" Pipe rams, TIW, Outer kill, Downstream choke valves (OK)
#3	11:36		250/5000		Pipe rams, second TIW, Inner kill, Outside upstream choke valves (OK)
#4	11:52		250/5000		Inside upstream choke valves (OK)
#5	12:28		250/5000		Blind rams, HCR (OK)
#6	12:43		250/5000		4" Manual (OK)
#7	13:20		250/5000		Gray valve, Kill line NRV 250psi (OK) 5000psi (Leaking Gray valve)
#7A	13:47		5000		Retest #7 (OK)
#8	14:38		250/3000		4" Mud pump valves (OK)
#9	14:55		250/3000		4" Standpipe valve (OK)
#10	15:15		250		Upper kelly cock (Passing)
#10A	15:28		250/5000		Retest Upper kelly cock (OK)
	15:40				Finish

HALLIBURTON Cementing Job Log		SALES ORDER # (If applicable)	JOB DATE: 23rd October 2005	ON SITE HES REP: Greg Dennis
COUNTRY: New Zealand	BDA: Perth	LOCATION / FIELD NAME: New Plymouth		JOB SITE: Land
CUSTOMER: Swift Energy	CUSTOMER REPRESENTATIVE: Wallace Suire		WELL NAME & NUMBER: AHUROA STH B1	
PSL GROUP - LEVEL 1: Cementing	PSL GROUP - LEVEL 2: Zonal Isolation		PSL GROUP - LEVEL 3: Cementing Services & Materials	
JOB TYPE CODE: Miscellaneous Pumping	JOB PURPOSE CODE: Test Casing Seat 7541		WELL TYPE: Development	JOB CLASS: Non-RTO
Special Tools	Complete Only if a Special Tools Job was performed			
JOB TYPE CODE	JOB PURPOSE CODE			

HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS
G Dennis	5				

HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES
9178					

Chart #	Date & Time	Volume (BBL)	Pressure (PSI)	Rate (BPM)	JOB DESCRIPTION / REMARKS
					7" CASING PRESSURE TEST / F.I.T AFTER DRILLING 7" SHOE
	23rd Oct				
	4:30				Arrive location.
	6:12	0.25	60		Pressure test 7" casing prior to drilling Float collar
		0.5	246		
		0.75	465		
		1	695		
		1.25	920		
		1.5	1154		
		1.75	1390		
		2	1620		
		2.25	1845		
	6:18	2.45	2000		
	6:23	2.49	2000		Bump up from 1965psi
					Hold for 25 minutes (OK)
	6:50				Bleed off - 2.4bbls bled back.
					Formation Integrity Test.
					TVD: 2305m (7563ft)
					MW : 8.9+ ppg
					EMW reqd: 11.5ppg = 1002psi
	9:16	0.25	240		
		0.5	426		
		0.75	612		
		1	798		
		1.25	984		
	9:20	1.356	1020		
			980		After 1 minute - dropped 40psi immediately
			975		After 2 minutes - dropped 5psi
			972		After 3 minutes - dropped 3psi
			969		After 4 minutes - dropped 3psi
			968		After 5 minutes - dropped 1psi (EMW = 11.4 ppg)

5. PUMP KICK OFF PLUG AT +/- 2526M MD

5.1 Designed Cement Program

Swift Energy

Ahuroa South B1 **Kick Off Plug**

Well Data

	ft AH	m AH
Top of Spacer (with DP)	6007	1831
Plug Length	479	146
TOC	7808	2380
7" Casing Shoe	7858	2395
Setting Depth	8287	2526

Hole Size	6	inch
BHST	171	°F
BHCT	140	°F
7" casing x 2-7/8" tubing	0.157	cuft/ft
6" hole x 2-7/8" tubing	0.151	cuft/ft
Cement plug height in hole with tbg	66	m
Cement plug height in csg with tbg	131	m

Calculations:

Kick Off Plug Slurry										ft³/ft		Vol (ft3)	*Vol (bbl)*
7" 29# Casing	15	x	3.2808	x	0.2083	=	10.25	*1.8*
6" Hole	131	x	3.2808	x	0.1963	=	84.39	*15.0*
				Excess		30%	=	25.32	*4.5*
Slurry Total							=	**119.96**	***21.4***
							Actual Volume Pumped (incl excess)	*21.4*
Displacement													
3-1/2" 13.3# Drill Pipe	2183	x	3.2808	x	0.0417	=	298.46	*53.2*
2-7/8" 6.5# Stinger	146	x	3.2808	x	0.0325	=	15.57	*2.8*
Displacement Total							=	**314.03**	***55.9***
							Actual Volume Pumped	*51.4*

Fluid Descriptions

Spacer and Flush System

System: Surfactant Water Spacer

							Actual
Additives:	KCl (Tech Grade)	7.0%	bwow	Volume	bbls	50	*30*
	WS-36	0.55	gal/bbl	Length	ft	1100	
	Stabiliser 434C	0.40	gal/bbl	Density	ppg	8.70	
	AS-5	0.15	gal/bbl				
	Cleanbore B	0.40	gal/bbl				

Kick Off Plug

Cement: Lafarge Class 'G'

Additives:	SCR-100L	0.06	Gals/Sk	Slurry Density	17.2	ppg
	CFR-3	0.5%	BWOC	Slurry Yield	0.98	ft³/sk
	NF-6	0.5	Gals/10bbls	Mix Water Type	Location	
				Mix Water Req.	3.68	gal/sk
				Mix Soln Req.	3.74	gal/sk
				Required Pump Time	1.76	hrs
				Thickening Time (est)	4.00	hrs @ 140°F
				24 hr Compressive Strength (est)	3000	psi @ 171°F

Chemical Requirements

The following quantities are based on volumes pumped and do not take into account mixwater tank bottoms.

Material	**Spacer**	**Kick Off Plug**	**Total**	***Actual***	**Units**
Lafarge Class 'G'		123	123	*123*	sks
SCR-100L		7	7	*10*	gals
CFR-3		58	58	*70*	lbs
NF-6		1	1		gals
Fresh Water	50	11	61		bbls
KCl (Tech Grade)	1225		1225	*935*	lbs
WS-36	28		28	*20*	gals
Stabiliser 434C	20		20	*15*	gals
AS-5	8		8	*5*	gals
Cleanbore B	20		20	*15*	gals

5.2 Primary Cementing Job Log

HALLIBURTON Cementing Job Log		SALES ORDER # (If applicable)		JOB DATE: 9th Nov 2005		ON SITE HES REP: Greg Dennis	
COUNTRY: New Zealand		BDA: Perth		LOCATION / FIELD NAME: New Plymouth		JOB SITE: Land	
CUSTOMER: Swift Energy		CUSTOMER REPRESENTATIVE: Troy Reid		WELL NAME & NUMBER: AHUROA STH B1			
PSL GROUP - LEVEL 1: Cementing		PSL GROUP - LEVEL 2: Zonal Isolation		PSL GROUP - LEVEL 3: Cementing Services & Materials			
JOB TYPE CODE: Cement Job		JOB PURPOSE CODE: Whipstock/Plug 7529		WELL TYPE: Development		JOB CLASS: Non-RTO	
Special Tools		**Complete Only if a Special Tools Job was performed**					
JOB TYPE CODE		JOB PURPOSE CODE					

HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS
G Dennis	4				
Zahn Leishman	4				

HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES
9178					

Chart #	Date & Time	Volume (BBL)	Pressure (PSI)	Rate (BPM)	JOB DESCRIPTION / REMARKS
					KICK OFF PLUG 2526M TO 2380M (15M INSIDE 7" SHOE)
					OH VOLUME USED: 6" GAUGE HOLE PLUS 30% XS (XS = 4.5 BBLS)
					146M 2 7/8" TUBING STINGER
	8th Nov				
	13:00				Called out for Kick off plug
					Prepare equipment, stand by until confirmation of plug received.
	20:00				Depart rig (No decision made as yet)
	9th Nov				
	11:15				Called out
	12:00				Arrive location, mix chemicals for job.
	13:00				Hold JSA with rig crew
	13:20	10	750	3	Pump 10bbls Surfactant spacer
			3000		Pressure test surface line to 3000psi
		20	800	3.3 av	Pump 20bbls Surfactant spacer
	13:37	21.36	700 max	3 av	Mix and pump Slurry at 17.2ppg
					123 sks Class G cement
					Yield: 0.98cuft/sk, Water ratio: 3.68gals/sk
					0.5% CFR-3, 0.06gals/sk SCR-100L
		6.78		3.5	Pump 6.78bbls Surfactant spacer behind to balance.
	13:58	44.6	750 max	5.5 av	Displace with 44.6bbls SBM
					(0.8bbls underdisplaced, 1bbl added for line volume)
	14:08				Bleed back, plug balanced.
	14:10				Rig pooh above top of cement and circulate bottoms up.
					Surfactant spacer recipe:
					KCL 7% BWOW; WS-36 0.55gals/bbl; Stabiliser 434C 0.4gals/bbl;
					AS-5 0.15gals/bbl; Cleanbore B 0.4gals/bbl.

5.3 EJCS

HALLIBURTON	CEMENTING END OF JOB CUSTOMER SATISFACTION	SALES ORDER # / TICKET # / JOB # 4036627	JOB DATE 9th Nov 2005	ON SITE HES REP Greg Dennis
COUNTRY New Zealand	BDA Perth	LOCATION New Plymouth		JOB SITE TYPE Land
CUSTOMER Swift Energy	CUSTOMER REPRESENTATIVE Troy Reid	WELL NAME & NUMBER AHUROA STH B1		
PSL GROUP - LEVEL 1 Cementing	PSL GROUP - LEVEL 2 Zonal Isolation	PSL GROUP - LEVEL 3 Cementing Services & Materials		
JOB TYPE CODE Cement Job	JOB PURPOSE CODE Whipstock/Plug 7529	WELL TYPE Development		JOB CLASS Non-RTO
Special Tools				
JOB TYPE CODE	JOB PURPOSE CODE			
HSE Incident? (Accident Injury etc) ☐ YES ☑ NO	Operating Time	1	Customer Completed ☑	

Dear Customer,
We hope that you were satisfied with the service quality of this job performed by Halliburton. It is the aim of our management and service personnel to deliver equipment and service of a standard unmatched in the service sector of the energy industry.

Please take the time to let us know if our performance met with your satisfaction. Please be as critical as possible to ensure we constantly improve our service. Your comments are of great value to us and are intended for the exclusive use of Halliburton.

Please indicate your response by placing a " X " in the box underneath the rating that best matches your opinion.

DESCRIPTION	Superior Performance (New quality performance standard - Best Practice) 5	Exceeded Expectations (Provided more than required - Potential Best Practice) 4	Met Expectations (Did what was expected - Prevention/Improvement) 3	Below Expectations (Did not do as expected, Recovery Made - CPI Required) 2	Poor Performance (Job problems/failures, some recovery made - CPI Required) 1
Did our personnel perform the job to your satisfaction?		✓			
Did our equipment perform the job to your satisfaction?		✓			
Did we perform the job to the agreed upon design?		✓			
Did our products and materials perform as you expected?		✓			
Did we perform in a safe & careful manner?		✓			
Did we perform in an environmentally sound manner?		✓			
Was the job performed as scheduled?		✓			
Did the equipment condition & appearance meet you expectations?		✓			
How well did our personnel communicate during mobilisation, rig-up and job execution?		✓			

What can we do to improve our service?

Customer Comments

Customer Signature:

All data collected is for trend analysis and business process improvement only.

5.4 Pressure Test Rig Equipment, Casing and Formation

HALLIBURTON Cementing Job Log					
	SALES ORDER # (If applicable)		JOB DATE: 10th Nov 2005	ON SITE HES REP: Greg Dennis	
COUNTRY: New Zealand	BDA: Perth	LOCATION / FIELD NAME: New Plymouth		JOB SITE: Land	
CUSTOMER: Swift Energy	CUSTOMER REPRESENTATIVE: Troy Reid		WELL NAME & NUMBER: AHUROA STH B1		
PSL GROUP - LEVEL 1: Cementing	PSL GROUP - LEVEL 2: Zonal Isolation		PSL GROUP - LEVEL 3: Cementing Services & Materials		
JOB TYPE CODE: Miscellaneous Pumping	JOB PURPOSE CODE: Test Blowout Preventer 15111		WELL TYPE: Development	JOB CLASS: Non-RTO	
Special Tools	Complete Only if a Special Tools Job was performed				
JOB TYPE CODE	JOB PURPOSE CODE				

HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS
G Dennis	13				
Z Leishman	9				
G Stachurski	3				

HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES
9178					

Chart #	Date & Time	Volume (BBL)	Pressure (PSI)	Rate (BPM)	JOB DESCRIPTION / REMARKS
					BOP AND CHOKE MANIFOLD TESTING FOLLOWING KICK OFF PLUG
Chart #1	9th Nov				
					Choke Manifold
Test #1	17:10		250/3000		Test Poor boy and Flare pit valve (OK)
#2	17:30		250/5000		Downstream valves (OK)
#3	17:55		250/5000		Outside upstream valves (Dropped initially, bumped up OK)
#4	18:27		250/5000		Inside upstream valves (OK)
	18:43				Stop. Standby for BOP's.
	10th Nov				BOP's
	2:05				Fill BOP's
#5	2:10		250/3000		Test Annular and Mud pump valves
					250 (OK)
					3000 (No good)
					Felt we were pressuring up casing, assured casing valve was open.
					Continued to 2000psi, stopped, asked Driller to check casing valve
					again and ensure if open it wasn't plugged. Was assured valve was
					open and clear !
					Continued to 3000psi, slight dribble from flowline.
					Went to bleed down, major jump from Kelly !!
					In hindsight wrong casing valve had been opened and test plug seal
					had been cut. 7" casing had pressured up and Kelly had been lifted.
	3:30				Refill BOP stack
#6	3:35		250		Annular, 4" Mud pump valves (Leaking past test plug)
	3:55				Refill BOP's again
#7	4:03		250/3000		Annular, 4" Mud pump valves (250 OK, 3000 Leaking past test plug)
#8	4:30			11	Flush Wellhead with HNZ pumps
	4:45				Refill BOP's again

HALLIBURTON Cementing Job Log		SALES ORDER # (If applicable)	JOB DATE: 10th Nov 2005	ON SITE HES REP: Greg Dennis
COUNTRY: New Zealand	BDA: Perth	LOCATION / FIELD NAME: New Plymouth		JOB SITE: Land
CUSTOMER: Swift Energy	CUSTOMER REPRESENTATIVE: Troy Reid		WELL NAME & NUMBER: AHUROA STH B1	
PSL GROUP - LEVEL 1: Cementing	PSL GROUP - LEVEL 2: Zonal Isolation		PSL GROUP - LEVEL 3: Cementing Services & Materials	
JOB TYPE CODE: Miscellaneous Pumping	JOB PURPOSE CODE: Test Blowout Preventer 15111		WELL TYPE: Development	JOB CLASS: Non-RTO
Special Tools	Complete Only if a Special Tools Job was performed			
JOB TYPE CODE	JOB PURPOSE CODE			

HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS
G Dennis	13				
Z Leishman	9				
G Stachurski	3				

HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES
9178					

Chart #	Date & Time	Volume (BBL)	Pressure (PSI)	Rate (BPM)	JOB DESCRIPTION / REMARKS
					BOP AND CHOKE MANIFOLD TESTING FOLLOWING KICK OFF PLUG
Chart #1	9th Nov				
#9	4:50		3000		Annular, 4" Mud pump valves
					(Idled up to +/- 1700psi, started leaking past test plug)
	5:25				Decision made to lift BOP's to inspect wellhead.
	5:45				Head to workshop to collect 7" RTTS and SSCV
					(Both tools needed assembly)
	7:30				Told to leave RTTS, discovered Lock down screw still in !!
	8:10				Arrived back at rig.
Chart #2					
#10	8:38		3000		Annular, 4" Mud pump valves (Leaking wash pipe)
#11	8:45		3000		Leaking
#12	8:55		250/3000		250 (OK) 3000 (Leaking)
					Close 4" manual HCR - Holding OK (HCR leaking)
#13	9:15		3000		Annular, 4" Mud pump valves (OK)
					(Also closed against Outer kill and 4" Manual)
#14	9:50		250/3000		Annular, 4" mud pump valves, Outer kill, 4" manual
					250 (OK) 3000 Initially leaking, tighten #2 mud pump valve (OK)
#15	10:10		250/3000		Annular, 4" Standpipe valve
					250 (OK) 3000 Initially dropped to 1900psi, bumped up (OK)
#16	10:32		250/5000		3 1/2" Pipe rams, Upper kelly cock, Outer kill, 4" Manual (OK)
#17	11:04		250/5000		Pipe rams, Lower kelly cock, Inner kill, HCR
					250 (OK) 5000 (Leaking)
#18	11:35		5000		Retest #17 (HCR still passing)
#19	11:50		5000		3 1/2" Pipe rams, Lower kelly cock, Inner kill, 4" Manual (OK)
Chart #3					
#20	12:16		250/5000		Pipe rams, TIW, Inner kill, 4" Manual (OK)
#21	12:30		250/5000		Pipe rams, TIW, Inner kill, HCR (OK)
#22	13:00		250/5000		Blind rams, Kill line NRV, Inside upstream choke valves (OK)
					NB: Gray valve to be tested by TOT in town.
	13:20				Finish

6. SUSPEND WELL

6.1 Designed Cement Programme

Swift Energy
Ahuroa South B1

Suspension Plug *(Completed Twice)*

Well Data

	ft AH	m AH
Top of Spacer (with DP)	6778	2066
Plug Length	328	100
TOC	7693	2345
7" Casing Shoe	7858	2395
Setting Depth	8022	2445

Hole Size	6	inch
BHST	168	°F
BHCT	138	°F
7" casing x 2-7/8" tubing	0.157	cuft/ft
6" hole x 2-7/8" tubing	0.151	cuft/ft
Cement plug height in hole with tbg	74	m
Cement plug height in csg with tbg	50	m

Calculations:

Plug Slurry **x 2**									ft³/ft		Vol (ft3)	*Vol (bbl)*
7" 29# Casing	50	x	3.2808	x	0.2083	=	34.17	*6.1*				
6" Hole	50	x	3.2808	x	0.1963	=	32.21	*5.7*				
			Excess		30%	=	9.66	*1.7*				
Slurry Total						=	**76.04**	***13.5***				
							Actual Volume Pumped (incl excess)	*23.3*				
Displacement												
3-1/2" 13.3# Drill Pipe	2136	x	3.2808	x	0.0417	=	292.05	*52.0*				
2-7/8" 6.5# Stinger	185	x	3.2808	x	0.0325	=	19.72	*3.5*				
Displacement Total						=	**311.77**	***55.5***				
							Actual Volume Pumped	*100.7*				

Fluid Descriptions

Spacer and Flush System

System: Surfactant Water Spacer

						Actual
Additives:	KCl (Tech Grade)	7.0%	bwow	Volume	25 bbls	*40*
	WS-36	0.55	gal/bbl	Length	550 ft	
	Stabiliser 434C	0.40	gal/bbl	Density	8.70 ppg	
	AS-5	0.15	gal/bbl			
	Cleanbore B	0.40	gal/bbl			

Kick Off Plug

Cement: Lafarge Class 'G'

Additives:	SCR-100L	0.06	Gals/Sk	Slurry Density	17.2 ppg
	CFR-3	0.5%	BWOC	Slurry Yield	0.98 ft³/sk
	NF-6	0.5	Gals/10bbls	Mix Water Type	Location
				Mix Water Req.	3.68 gal/sk
				Mix Soln Req.	3.74 gal/sk
				Required Pump Time	1.73 hrs
				Thickening Time (est)	4.00 hrs @ 138°F
			24 hr	Compressive Strength (est)	3000 psi @ 168°F

Chemical Requirements

The following quantities are based on volumes pumped and do not take into account mixwater tank bottoms.

Material	**Spacer**	**Plug Slurry**	**Total**	***Actual***	**Units**
Lafarge Class 'G'		78	78	*123*	sks
SCR-100L		5	5	*8*	gals
CFR-3		37	37	*50*	lbs
NF-6		0	0		gals
Fresh Water	25	7	32		bbls
KCl (Tech Grade)	612		612	*1210*	lbs
WS-36	14		14	*25*	gals
Stabiliser 434C	10		10	*20*	gals
AS-5	4		4	*8*	gals
Cleanbore B	10		10	*20*	gals

6.2 Job Log

HALLIBURTON Cementing Job Log			SALES ORDER # (If applicable)		JOB DATE: 28th Nov 2005		ON SITE HES REP: Greg Dennis	
COUNTRY: New Zealand		BDA: Perth		LOCATION / FIELD NAME: New Plymouth		JOB SITE: Land		
CUSTOMER: Swift Energy		CUSTOMER REPRESENTATIVE: Troy Reid			WELL NAME & NUMBER: AHUROA STH B1 ST1			
PSL GROUP - LEVEL 1: Cementing		PSL GROUP - LEVEL 2: Zonal Isolation			PSL GROUP - LEVEL 3: Cementing Services & Materials			
JOB TYPE CODE: Cement Job		JOB PURPOSE CODE: Plug To Abandon 7528			WELL TYPE: Development		JOB CLASS: Non-RTO	
Special Tools		Complete Only if a Special Tools Job was performed						
JOB TYPE CODE: Special Tools		JOB PURPOSE CODE: Drillable Tool Service 7551						

HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS
G Dennis	34				
Chris Rolston	14				
Daniel Dietrich	14				

HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES
9178					

Chart #	Date & Time	Volume (BBL)	Pressure (PSI)	Rate (BPM)	JOB DESCRIPTION / REMARKS
					SUSPENSION PLUG #1 2425M TO 2325M (7" SHOE AT 2395M)
					OH VOLUME USED: 6" GAUGE HOLE PLUS 30% XS
					146M 2 7/8" TUBING STINGER
	25th Nov				Prepare equipment for plugs
	26th Nov				
	2:30				Called out.
					Mix Spacer and cementing chemicals.
	6:15	10	800	3.8	Pump 10bbls Surfactant spacer (Spacer recipe listed at bottom)
			3000		Pressure test surface line to 3000psi
	6:23	20	800	3.8	Pump 20bbls Surfactant spacer
	6:35	11.34	700 max	2.5	Mix and pump Class G slurry at 17.2ppg
					Yield: 0.98cuft/sk; Water ratio: 3.68gals/sk;
					65 sks cement
					0.5% CFR-3; 0.06gals/sk SCR-100L;
		6.78		3	Pump 6.78bbls Surfactant spacer behind to balance.
	6:45	44	1000 max	5.5	Displace with 44bbls SBM (0.8bbls under displaced)
	6:45				Bleed back - Plug balanced.
	21:30				Arrive back at site for pressure testing plug
					Plug not tagged - slipped down hole.
	27th Nov				SUSPENSION PLUG #2 2365M TO 2315.75M
					7" EZSV PACKER SET AT 2365M (30M ABOVE SHOE)
	9:15				Run in hole with 7" EZSV packer on mechanical setting tool.
	15:30				Set EZSV packer at 2365m
	15:55				Sting into packer and perform injection test
			1550 max	1.5	Formation broke at +/- 1550psi, injected at 1.5bpm at +/- 1340psi
	16:00	5	700	2	Sting out of EZSV packer and pump 5bbls Surfactant spacer
			3000		Pressure test surface line to 3000psi
		5	700	2	Pump 5bbls Surfactant spacer
	16:20	12	750 max	2.5	Mix and pump 12bbls Class G slurry at 15.8ppg
					Yield: 1.16cuft/sk; Water ratio: 5.10gals/sk;
					58 sks cement
					4gals/10bbls mix water SCR-100L
	16:26	1.3			Pump 1.3bbls Surfactant spacer behind to balance
	16:28	32.7	1000	5	Displace 32.7bbls SBM (5bbls Spacer ahead in Annulas)
	16:36				Sting into EZSV packer with 20,000 lbs weight.
		11	850	2	Squeeze with 11bbls SBM
					(5bbls Spacer and 6bbls cement below EZSV)
					Total 43.7bbls SBM pumped so far.
					Unsting from EZSV Packer
		4.3	400	2	Displace further 4.3bbls SBM
					Total 48bbls SBM pumped (0.5bbls under displaced)
	16:59				Bleed back - plug balanced.
	17:00				rig pooh 7 stands and reverse circulate at 2216m

6.3 EJCS

CEMENTING END OF JOB
CUSTOMER SATISFACTION

4055243

COUNTRY: New Zealand	BDA: Perth	LOCATION: New Plymouth	JOB SITE TYPE: Land
JOB DATE: 28th Nov 2005	CSI SITE MGR: Greg Dennis		
CUSTOMER: Swift Energy	CUSTOMER REPRESENTATIVE: Troy Reid	WELL NAME & NUMBER: AHUROA STH B1 ST1	
PSL GROUP - LEVEL 1: Cementing	PSL GROUP - LEVEL 2: Zonal Isolation	PSL GROUP - LEVEL 3: Cementing Services & Materials	
JOB TYPE CODE: Cement Job	JOB PURPOSE CODE: Plug To Abandon 7528	WELL TYPE: Development	JOB CLASS: Non-RTO
Special Tools			
JOB TYPE CODE: Special Tools	JOB PURPOSE CODE: Drillable Tool Service 7551		
HSE Incident? (Accident Injury etc) ☐ YES ☑ NO	Operating Time: 2	Customer Completed ☑	

Dear Customer,
We hope that you were satisfied with the service quality of this job performed by Halliburton. It is the aim of our management and service personnel to deliver equipment and service of a standard unmatched in the service sector of the energy industry.

Please take the time to let us know if our performance met with your satisfaction. Please be as critical as possible to ensure we constantly improve our service. Your comments are of great value to us and are intended for the exclusive use of Halliburton.

Please indicate your response by placing a " X " in the box underneath the rating that best matches your opinion.

DESCRIPTION	Superior Performance (New quality performance standard - Best Practice) 5	Exceeded Expectations (Provided more than required - Potential Best Practice) 4	Met Expectations (Did what was expected - Prevention/Improvement) 3	Below Expectations (Did not do as expected, Recovery Made - CPI Required) 2	Poor Performance (Job problems/failures, some recovery made - CPI Required) 1
Did our personnel perform the job to your satisfaction?		✓			
Did our equipment perform the job to your satisfaction?		✓			
Did we perform the job to the agreed upon design?		✓			
Did our products and materials perform as you expected?		✓			
Did we perform in a safe & careful manner?		✓			
Did we perform in an environmentally sound manner?		✓			
Was the job performed as scheduled?		✓			
Did the equipment condition & appearance meet you expectations?		✓			
How well did our personnel communicate during mobilisation, rig-up and job execution?		✓			

What can we do to improve our service?

Customer Comments

Customer Signature:

All data collected is for trend analysis and business process improvement only.

6.4 Pressure Test Casing & Wellhead

HALLIBURTON Cementing Job Log			SALES ORDER # (If applicable)		JOB DATE: 28th Nov 2005		ON SITE HES REP: Greg Dennis	
COUNTRY: New Zealand		BDA: Perth		LOCATION / FIELD NAME: New Plymouth		JOB SITE: Land		
CUSTOMER: Swift Energy		CUSTOMER REPRESENTATIVE: Troy Reid			WELL NAME & NUMBER: AHUROA STH B1 ST1			
PSL GROUP - LEVEL 1: Cementing		PSL GROUP - LEVEL 2: Zonal Isolation			PSL GROUP - LEVEL 3: Cementing Services & Materials			
JOB TYPE CODE: Cement Job		JOB PURPOSE CODE: Plug To Abandon 7528			WELL TYPE: Development		JOB CLASS: Non-RTO	
Special Tools		Complete Only if a Special Tools Job was performed						
JOB TYPE CODE: Special Tools		JOB PURPOSE CODE: Drillable Tool Service 7551						
HES EMP NAME (EXPOSURE HRS)	HRS	HES EMP NAME (EXPOSURE HRS)	HRS		HES EMP NAME (EXPOSURE HRS)	HRS		
G Dennis	34							
Chris Rolston	14							
Daniel Dietrich	14							
HES UNIT NUMBERS	RT MILES	HES UNIT NUMBERS	RT MILES		HES UNIT NUMBERS	RT MILES		
9178								

Chart #	Date & Time	Volume (BBL)	Pressure (PSI)	Rate (BPM)	JOB DESCRIPTION / REMARKS
	18:00		3000		Pressure test 7" casing to EZSV packer to 3000psi
		0.25	442		
		0.5	618		
		0.75	814		
		1	1030		
		1.25	1258		
		1.5	1496		
		1.75	1715		
		2	1945		
		2.25	2142		
		2.5	2365		
		2.75	2602		
		3	2825		
		3.35	3000		Bump up several times (OK)
					Hold 10 minutes
	18:20				Bleed off. 3.25bbls bled back.
					Stand by for 9 5/8" / 7" annulas injection test (Cellar needed emptying)
	21:30				Injection test on 9 5/8" / 7" annulas
					Took 5 to 6bbls to fill, injecting at 5bpm at 650psi.
	22:00				Depart location.
	28th Nov				
	7:00				EZSV Mechanical Setting tool at surface.
	18:05	0.25	255		Pressure test Wellhead and 7" casing to 3000psi
		0.5	515		
		0.75	745		
		1	987		
		1.25	1250		
		1.5	1484		
		1.75	1740		
		2	1980		
		2.25	2236		
		2.5	2480		
		2.75	2736		
	18:10	3.04	3000		Hold 10 minutes (OK)
	18:20				Bleed off - 3.04bbls bled back.
					Surfactant Spacer recipe:
					7% KCL bwow; 0.55gals/bbl WS-36; 0.4gals/bbl Stabiliser 434C;
					0.15gals/bbl AS-5; 0.4gals/bbl Cleanbore B;

APPENDIX A – TICKETS

HALLIBURTON

NEW ZEALAND LIMITED

FIELD TICKET No. 4394

Send Remittances to :
P.O.BOX 7160, PARAITE ROAD
BELL BLOCK, NEW PLYMOUTH
NEW ZEALAND

CUST NO. 305739
ENTITY
LOCATION
2ND REF

CHARGE TO : SWIFT ENERGY CORP (NZ)
ADDRESS : 16825 NORTH CHASE DRIVE
ADDRESS : SUITE 400, HOUSTON, TEXAS.
COUNTRY USA. POST CODE

SALES ORDER No. 3977975
DELIVERY No
QUOTE No.

CONTRACT NUMBER
DATE 12th October 2005

DEPARTMENT/PSL	INVOICE No :- ACCOUNTS USE ONLY	CUSTOMER ORDER No.	SHIP VIA	DELIVER TO :
ZI, 10003				

PROJECT REF - HALLIBURTON	RIG NAME	RIG TYPE	RIG CONTRACTOR	WELL NAME/No.	WELL OWNER
	Parker 252	Drilling	Parker	AHUROA STH B1	SWIFT ENERGY

WELL TYPE	WELL LOCATION	FIELD NAME	LAND	OFFSHORE	WELL CATEGORY	CASED HOLE	OPEN HOLE
Exploration	Croydon Rd, Tariki		X		Drilling	X	X

TYPE TICKET	JOB TYPE	JOB PURPOSE	CURRENCY
X SERVICE ☐ SALE		Ahuroa Sth B1 Cementing Services 30th September to 12th October	US $

PRICE REFERENCE	PART NUMBER	WHS	DESCRIPTION	UNITS 1 QTY	UNITS 1 U/M	UNITS 2 QTY	UNITS 2 U/M	UNIT PRICE	D/F	AMOUNT
	16113		Service Operator 3rd, 4th, 5th, 6th, 8th, 9th,	Per	Day	6	Days	650.00		3,900.00
	16113		Service Assistant 3rd, 4th, 8th, 9th,	Per	Day	4	Days	610.00		2,440.00
										-
										-
			Contract mobilisation charge - Surface casing	Per	Ea	1	Ea	1,450.00		1,450.00
			Contract mobilisation charge - Production casing	Per	Ea		Ea	1,350.00		-
			Contract mobilisation charge - Small job -	Per	Ea		Ea	450.00		-
			Equipment Rental 30th September to 12th October	Per	Day	13	Days	150.00		1,950.00
			9 5/8" Surface casing cement Job - 9th October	Per	Job	1	Ea	3,000.00		3,000.00
			7" Casing cement Job -	Per	Job		Ea	5,500.00		-
			4 1/2" Liner cement job -	Per	Job		Ea	7,000.00		-
			FI Test - 11th October - (Includes operator)	Per	Ea	1	Ea	450.00		450.00
	238		BOP Test - 10th October - First 6 hours (Includes operator)	Per	Ea	1	Ea	1,200.00		1,200.00
			BOP Tests - Additional hours	Per	Hr	2	Hrs	150.00		300.00
										-
			Pumping Mud/Diesel - - First 12 hrs (Includes operator)	Per	Ea		Ea	3,600.00		-
			Pumping Mud/Diesel-Additional hrs	Per	Hr		Hrs	450.00		
			Plug jobs (Any depth) -	Per	Ea		Ea	900.00		
			Batch mixer -	Per	Ea		Ea	2,000.00		-
			Misc. Pressure testing - - First 6 hours	Per	Ea		Ea	1,200.00		
			Misc. Pressure testing-Additional hours	Per	Hr		Hrs	150.00		

COMMENTS :

CUSTOMER hereby acknowledges r· 0
and/or services listed on this ticket :
CUSTOMER OR CUSTOMER'S AGENT (PLEASE PRINT)

HALLIBURTON ENGINEER/OPERATOR :
M Smith
126968

PAGE TOTAL	14,690.00
CONTINUATION	
TOTAL	
TAX	
INVOICE TOTAL	

PLEASE RATE YOUR LEVEL OF SATISFACTION WITH OUR SERVICE

EXCELLENT	GOOD	ADEQUATE	COULD IMPROVE
4	3	2	1

CUSTOMER OR CUSTOMER'S AGENT (SIGNATURE)

HALLIBURTON APPROVAL :

As consideration, the above-named Customer agrees to pay Halliburton in accord with the rates and terms stated in Halliburton's current price lists. Halliburton warrants only title to the products, supplies and material and that the same are free from de workmanship and materials. THERE ARE NO WARRANTIES, EXPRESS OR IMPLIED, OF MERCHANTABILITY, FITNESS OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. Halliburton's liability and Customer's exclusive remedy in any cause of action (whether in contract, tort, breach of warranty or otherwise) arising out of the sale or use of any products, supplies or materials is expressly limited to the replacement of such products, s or materials on their return to Halliburton or, at Halliburton's option, to the allowance to the Customer of credit for the cost of such items. In no event shall Halliburton be liable for special, incidental, indirect , punitive or consequential damages. Customer's default in the payment of Customer's account 60 days after date of invoice, such account will thereafter be subject to interest until paid. In the event it becomes necessary to employ an attorney to enforce collection of such account, Customer agrees tp pay all collecction costs and attorney fees in the amount of 20 per cent of the unpaid account.

WHITE - ACCOUNTING ; GREEN - LOCATION ; BLUE - DISTRICT WAREHOUSE ; YELLOW - DISTRICT WAREHOUSE ; PINK - CUSTOMER ; OLD GOLD - INTERNAL COPY ; WHITE - INTERNAL COPY

HALLIBURTON

NEW ZEALAND LIMITED

Send Remittances to :
P.O.BOX 7160, PARAITE ROAD
BELL BLOCK, NEW PLYMOUTH
NEW ZEALAND

FIELD TICKET No. 4395

CUST NO.	305739
ENTITY	
LOCATION	
2ND REF	

CHARGE TO :	SWIFT ENERGY CORP (NZ)
ADDRESS :	16825 NORTH CHASE DRIVE
ADDRESS :	SUITE 400, HOUSTON, TEXAS.
COUNTRY	USA.
POST CODE	

SALES ORDER No. 3977976
DELIVERY No
QUOTE No.

CONTRACT NUMBER

DATE: 12th October 2005

DEPARTMENT/PSL	INVOICE No :- ACCOUNTS USE ONLY	CUSTOMER ORDER No.	SHIP VIA	DELIVER TO :
ZI, 10002				

PROJECT REF - HALLIBURTON	RIG NAME	RIG TYPE	RIG CONTRACTOR	WELL NAME/No.	WELL OWNER
	Parker 252	Drilling	Parker	AHUROA STH B1	SWIFT ENERGY

WELL TYPE	WELL LOCATION	FIELD NAME	LAND	OFFSHORE	WELL CATEGORY	CASED HOLE	OPEN HOLE
Exploration	Croydon Rd, Tariki		X		Development	X	X

TYPE TICKET: [ ] SERVICE [X] SALE
JOB TYPE: Cementing
JOB PURPOSE: Ahuroa Sth B1 Cement and Chemical Sales for 9 5/8" casing job.
CURRENCY: US $

PRICE REFERENCE	PART NUMBER	WHS	DESCRIPTION	UNITS 1 QTY	UNITS 1 U/M	UNITS 2 QTY	UNITS 2 U/M	UNIT PRICE	D/F	AMOUNT
	100064243		NF-6	Per	Gal	5	Gals	87.21		436.05
	100003764		Latex 2000L	Per	Gal		Gals	38.09		-
	100064081		Stabilizer 434C	Per	Gal		Gals	55.95		-
	100003653		CFR-3	Per	Lb	150	Lbs	6.23		934.50
			FDP-C634-01	Per	Gal		Gals	60.54		-
	120003193		Gascon 469	Per	Gal		Gals	17.00		-
	100005050		HR-5	Per	Lb		Lbs	5.18		-
	50685		Calcium Chloride	Per	Lb		Lbs	0.38		-
	100003646		Halad-322	Per	Lb		Lbs	10.20		-
	100090929		Pre-Hydrated Bentonite Gel	Per	Lb	2100	Lbs	0.34		714.00
			SCR 100L	Per	Gal		Gals	93.98		-
	100001579		Musol-A	Per	Gal		Gals	42.72		-
	100003871		Hyflo-4	Per	Gal		Gals	60.64		-
	152016		6" Drill pipe foam wiper ball	Per	Ea		Ea	160.00		-
	101318558		Class-A Cement: 44.42 Tonne (23.45 sks per tonne)	Per	sk	1042	sks	8.82		9,190.44
			as per weight dockets : 267060 and 267140							
	100003685		Class-G Cement: Tonne (23.45 sks per tonne)	Per	sk		sks	13.24		
			as per weight docket:							-
			50kg sugar as per Toops invoice: 286716 NZ$36.60 at e.r 0.6999	Per	Ea	1	Ea	25.62		25.62

COMMENTS :

CUSTOMER hereby acknowledges receipt of the materials and/or services listed on this ticket :

CUSTOMER OR CUSTOMER'S AGENT (PLEASE PRINT)

CUSTOMER OR CUSTOMER'S AGENT (SIGNATURE)

HALLIBURTON ENGINEER/OPERATOR : Mike.Smith 126968

HALLIBURTON APPROVAL :

PLEASE RATE YOUR LEVEL OF SATISFACTION WITH OUR SERVICE
EXCELLENT 4 | GOOD 3 | ADEQUATE 2 | COULD IMPROVE 1

PAGE TOTAL	11,300.61
CONTINUATION	
TOTAL	
TAX	
INVOICE TOTAL	

As consideration, the above-named Customer agrees to pay Halliburton in accord with the rates and terms stated in Halliburton's current price lists. Halliburton warrants only title to the products, supplies and material and that the same are free from de workmanship and materials. THERE ARE NO WARRANTIES, EXPRESS OR IMPLIED, OF MERCHANTABILITY, FITNESS OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. Halliburton's liability and Customer's exclusive remedy in any cause of action (whether in contract, tort, breach of warranty or otherwise) arising out of the sale or use of any products, supplies or materials is expressly limited to the replacement of such products, s or materials on their return to Halliburton or, at Halliburton's option, to the allowance to the Customer of credit for the cost of such items. In no event shall Halliburton be liable for special, incidental, indirect, punitive or consequential damages. Customer's default in the payment of Customer's account 60 days after date of invoice, such account will thereafter be subject to interest until paid. In the event it becomes necessary to employ an attorney to enforce collection of such account, Customer agrees tp pay all collecction costs and attorney fees in the amount of 20 per cent of the unpaid account.

WHITE - ACCOUNTING ; GREEN - LOCATION ; BLUE - DISTRICT WAREHOUSE ; YELLOW - DISTRICT WAREHOUSE ; PINK - CUSTOMER ; OLD GOLD - INTERNAL COPY ; WHITE - INTERNAL COPY

HALLIBURTON

NEW ZEALAND LIMITED

Send Remittances to :
P.O.BOX 7160, PARAITE ROAD
BELL BLOCK, NEW PLYMOUTH
NEW ZEALAND

FIELD TICKET No. 4408

CUST NO.	305739
ENTITY	
LOCATION	
2ND REF	

CHARGE TO :	SWIFT ENERGY CORP (NZ)
ADDRESS :	16825 NORTH CHASE DRIVE
ADDRESS :	SUITE 400, HOUSTON, TEXAS.
COUNTRY	USA.
POST CODE	

SALES ORDER No. 3993024
DELIVERY No
QUOTE No.

CONTRACT NUMBER

DATE 25th October 2005

DEPARTMENT/PSL: ZI, 10003	INVOICE No :- ACCOUNTS USE ONLY	CUSTOMER ORDER No.	SHIP VIA	DELIVER TO :	
PROJECT REF - HALLIBURTON	RIG NAME: Parker 252	RIG TYPE: Drilling	RIG CONTRACTOR: Parker	WELL NAME/No.: AHUROA STH B1	WELL OWNER: SWIFT ENERGY
WELL TYPE: Exploration	WELL LOCATION: Croydon Rd, Tariki	FIELD NAME	LAND: X OFFSHORE:	WELL CATEGORY: Drilling	CASED HOLE: X OPEN HOLE: X
TYPE TICKET: X SERVICE SALE	JOB TYPE	JOB PURPOSE: Ahuroa Sth B1 Cementing Services 13th October to 25th October			CURRENCY: US $

PRICE REFERENCE	PART NUMBER	WHS	DESCRIPTION	UNITS 1 QTY	UNITS 1 U/M	UNITS 2 QTY	UNITS 2 U/M	UNIT PRICE	D/F	AMOUNT
	16113		Service Operator 19th, 20th, 21st, October	Per	Day	3	Days	650.00		1,950.00
	16113		Service Assistant 20th, 21st, October	Per	Day	2	Days	610.00		1,220.00
										-
										-
			Contract mobilisation charge - Surface casing	Per	Ea		Ea	1,450.00		-
			Contract mobilisation charge - Production casing	Per	Ea		Ea	1,350.00		-
			Contract mobilisation charge - Small job - 7" casing	Per	Ea	1	Ea	450.00		450.00
			Equipment Rental 13th October to 25th October	Per	Day	13	Days	150.00		1,950.00
			9 5/8" Surface casing cement Job -	Per	Job		Ea	3,000.00		-
			7" Casing cement Job - 20th/21st October	Per	Job	1	Ea	5,500.00		5,500.00
			4 1/2" Liner cement job -	Per	Job		Ea	7,000.00		-
			FI Test - 23rd October - (Includes operator)	Per	Ea	1	Ea	450.00		450.00
	238		BOP Test - 22nd October - First 6 hours (Includes operator)	Per	Ea	1	Ea	1,200.00		1,200.00
			BOP Tests - Additional hours	Per	Hr		Hrs	150.00		-
										-
			Pumping Mud/Diesel - - First 12 hrs (Includes operator)	Per	Ea		Ea	3,600.00		-
			Pumping Mud/Diesel-Additional hrs	Per	Hr		Hrs	450.00		
			Plug jobs (Any depth) -	Per	Ea		Ea	900.00		
			Batch mixer -	Per	Ea		Ea	2,000.00		-
			Misc. Pressure testing - - First 6 hours	Per	Ea		Ea	1,200.00		
			Misc. Pressure testing-Additional hours	Per	Hr		Hrs	150.00		

COMMENTS :

CUSTOMER hereby acknowledges r 0
and/or services listed on this ticket :
CUSTOMER OR CUSTOMER'S AGENT (PLEASE PRINT)

HALLIBURTON ENGINEER/OPERATOR :
M Smith
126968

PAGE TOTAL	12,720.00
CONTINUATION	
TOTAL	
TAX	
INVOICE TOTAL	

PLEASE RATE YOUR LEVEL OF SATISFACTION WITH OUR SERVICE

EXCELLENT	GOOD	ADEQUATE	COULD IMPROVE
4	3	2	1

CUSTOMER OR CUSTOMER'S AGENT (SIGNATURE)

HALLIBURTON APPROVAL :

As consideration, the above-named Customer agrees to pay Halliburton in accord with the rates and terms stated in Halliburton's current price lists. Halliburton warrants only title to the products, supplies and material and that the same are free from de workmanship and materials. THERE ARE NO WARRANTIES, EXPRESS OR IMPLIED, OF MERCHANTABILITY, FITNESS OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. Halliburton's liability and Customer's exclusive remedy in any cause of action (whether in contract, tort, breach of warranty or otherwise) arising out of the sale or use of any products, supplies or materials is expressly limited to the replacement of such products, s or materials on their return to Halliburton or, at Halliburton's option, to the allowance to the Customer of credit for the cost of such items. In no event shall Halliburton be liable for special, incidental, indirect , punitive or consequential damages. Customer's default in the payment of Customer's account 60 days after date of invoice, such account will thereafter be subject to interest until paid. In the event it becomes necessary to employ an attorney to enforce collection of such account, Customer agrees tp pay all collection costs and attorney fees in the amount of 20 per cent of the unpaid account.

WHITE - ACCOUNTING ; GREEN - LOCATION ; BLUE - DISTRICT WAREHOUSE ; YELLOW - DISTRICT WAREHOUSE ; PINK - CUSTOMER ; OLD GOLD - INTERNAL COPY ; WHITE - INTERNAL COPY

HALLIBURTON
NEW ZEALAND LIMITED

FIELD TICKET No. 4409

Send Remittances to :
P.O.BOX 7160, PARAITE ROAD
BELL BLOCK, NEW PLYMOUTH
NEW ZEALAND

CUST NO.	305739
ENTITY	
LOCATION	
2ND REF	

CHARGE TO :	SWIFT ENERGY CORP (NZ)
ADDRESS :	16825 NORTH CHASE DRIVE
ADDRESS :	SUITE 400, HOUSTON, TEXAS.
COUNTRY	USA.
POST CODE	

SALES ORDER No. 3993025
DELIVERY No
QUOTE No.

CONTRACT NUMBER
DATE: 25th October 2005

DEPARTMENT/PSL	INVOICE No :- ACCOUNTS USE ONLY	CUSTOMER ORDER No.	SHIP VIA	DELIVER TO :
ZI, 10002				

PROJECT REF - HALLIBURTON	RIG NAME	RIG TYPE	RIG CONTRACTOR	WELL NAME/No.	WELL OWNER
	Parker 252	Drilling	Parker	AHUROA STH B1	SWIFT ENERGY

WELL TYPE	WELL LOCATION	FIELD NAME	LAND	OFFSHORE	WELL CATEGORY	CASED HOLE	OPEN HOLE
Exploration	Croydon Rd, Tariki		X		Development	X	X

TYPE TICKET	JOB TYPE	JOB PURPOSE	CURRENCY
SERVICE [ ] SALE [X]	Cementing	Ahuroa Sth B1 Cement and Chemical Sales for 7" casing job	US $

PRICE REFERENCE	PART NUMBER	WHS	DESCRIPTION	UNITS 1 QTY	UNITS 1 U/M	UNITS 2 QTY	UNITS 2 U/M	UNIT PRICE	D/F	AMOUNT
	100064243		NF-6	Per	Gal	10	Gals	87.21		872.10
	100003764		Latex 2000L	Per	Gal		Gals	38.09		-
	100064081		Stabilizer 434C	Per	Gal		Gals	55.95		-
	100003653		CFR-3	Per	Lb	75	Lbs	6.23		467.25
			FDP-C634-01	Per	Gal		Gals	60.54		-
	120003193		Gascon 469	Per	Gal		Gals	17.00		-
	100005050		HR-5	Per	Lb	255	Lbs	5.18		1,320.90
	50685		Calcium Chloride	Per	Lb		Lbs	0.38		-
	100003646		Halad-322	Per	Lb	870	Lbs	10.20		8,874.00
	100090929		Pre-Hydrated Bentonite Gel	Per	Lb	900	Lbs	0.34		306.00
			SCR 100L	Per	Gal		Gals	93.98		-
	100001579		Musol-A	Per	Gal		Gals	42.72		-
	100003871		Hyflo-4	Per	Gal		Gals	60.64		-
	152016		6" Drill pipe foam wiper ball	Per	Ea		Ea	160.00		-
	101318558		Class-A Cement: 31.50 Tonne (23.45 sks per tonne)	Per	sk	739	sks	8.67		6,407.13
			as per weight dockets : 269248 (20.88T), 269250 (10.62T)							
	100003685		Class-G Cement: Tonne (23.45 sks per tonne)	Per	sk		sks	13.24		
			as per weight docket:							-

COMMENTS :

CUSTOMER hereby acknowledges receipt of the materials and/or services listed on this ticket :

CUSTOMER OR CUSTOMER'S AGENT (PLEASE PRINT)

HALLIBURTON ENGINEER/OPERATOR : Mike.Smith 126968

PLEASE RATE YOUR LEVEL OF SATISFACTION WITH OUR SERVICE
EXCELLENT 4 | GOOD 3 | ADEQUATE 2 | COULD IMPROVE 1

CUSTOMER OR CUSTOMER'S AGENT (SIGNATURE)

HALLIBURTON APPROVAL :

PAGE TOTAL	18,247.38
CONTINUATION	
TOTAL	
TAX	
INVOICE TOTAL	

As consideration, the above-named Customer agrees to pay Halliburton in accord with the rates and terms stated in Halliburton's current price lists. Halliburton warrants only title to the products, supplies and material and that the same are free from de workmanship and materials. THERE ARE NO WARRANTIES, EXPRESS OR IMPLIED, OF MERCHANTABILITY, FITNESS OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. Halliburton's liability and Customer's exclusive remedy in any cause of action (whether in contract, tort, breach of warranty or otherwise) arising out of the sale or use of any products, supplies or materials is expressly limited to the replacement of such products, s or materials on their return to Halliburton or, at Halliburton's option, to the allowance to the Customer of credit for the cost of such items. In no event shall Halliburton be liable for special, incidental, indirect , punitive or consequential damages. Customer's default in the payment of Customer's account 60 days after date of invoice, such account will thereafter be subject to interest until paid. In the event it becomes necessary to employ an attorney to enforce collection of such account, Customer agrees tp pay all collecction costs and attorney fees in the amount of 20 per cent of the unpaid account.

WHITE - ACCOUNTING ; GREEN - LOCATION ; BLUE - DISTRICT WAREHOUSE ; YELLOW - DISTRICT WAREHOUSE ; PINK - CUSTOMER ; OLD GOLD - INTERNAL COPY ; WHITE - INTERNAL COPY

HALLIBURTON

NEW ZEALAND LIMITED

Send Remittances to :
P.O.BOX 7160, PARAITE ROAD
BELL BLOCK, NEW PLYMOUTH
NEW ZEALAND

FIELD TICKET No. 4416

CUST NO.	305739
ENTITY	
LOCATION	
2ND REF	

CHARGE TO :	SWIFT ENERGY CORP (NZ)
ADDRESS :	16825 NORTH CHASE DRIVE
ADDRESS :	SUITE 400, HOUSTON, TEXAS.
COUNTRY	USA.
POST CODE	

SALES ORDER No. 4036627
DELIVERY No
QUOTE No.

CONTRACT NUMBER	DATE
	11th November 2005

DEPARTMENT/PSL	INVOICE No :- (ACCOUNTS USE ONLY)	CUSTOMER ORDER No.	SHIP VIA	DELIVER TO :
ZI, 10003				

PROJECT REF - HALLIBURTON	RIG NAME	RIG TYPE	RIG CONTRACTOR	WELL NAME/No.	WELL OWNER
	Parker 252	Drilling	Parker	AHUROA STH B1	SWIFT ENERGY

WELL TYPE	WELL LOCATION	FIELD NAME	LAND	OFFSHORE	WELL CATEGORY	CASED HOLE	OPEN HOLE
Exploration	Croydon Rd, Tariki		X		Drilling	X	X

TYPE TICKET	JOB TYPE	JOB PURPOSE	CURRENCY
X SERVICE ___ SALE		Ahuroa Sth B1 Cementing Services 26th October to 11th November 2005	US $

PRICE REFERENCE	PART NUMBER	WHS	DESCRIPTION	UNITS 1 QTY	UNITS 1 U/M	UNITS 2 QTY	UNITS 2 U/M	UNIT PRICE	D/F	AMOUNT
	16113		Service Operator 2nd, 4th, 8th, 9th November	Per	Day	4	Days	650.00		2,600.00
	16113		Service Assistant 8th, 9th November	Per	Day	2	Days	610.00		1,220.00
										-
										-
			Contract mobilisation charge - Surface casing	Per	Ea		Ea	1,450.00		-
			Contract mobilisation charge - Production casing	Per	Ea		Ea	1,350.00		-
			Contract mobilisation charge - Kick off plug 9th Nov (454 sks G)	Per	Ea	1	Ea	1,464.15		1,464.15
			Equipment Rental 26th October to 11th November	Per	Day	17	Days	150.00		2,550.00
			9 5/8" Surface casing cement Job -	Per	Job		Ea	3,000.00		-
			7" Casing cement Job -	Per	Job		Ea	5,500.00		-
			4 1/2" Liner cement job -	Per	Job		Ea	7,000.00		-
			FI Test - - (Includes operator)	Per	Ea		Ea	450.00		-
	238		BOP Test - 10th November - First 6 hours (Includes operator)	Per	Ea	1	Ea	1,200.00		1,200.00
			BOP Tests - Additional hours	Per	Hr	4	Hrs	150.00		600.00
										-
			Pumping Mud/Diesel - - First 12 hrs (Includes operator)	Per	Ea		Ea	3,600.00		-
			Pumping Mud/Diesel-Additional hrs	Per	Hr		Hrs	450.00		
			Plug jobs (Any depth) - Kick off plug 9th November	Per	Ea	1	Ea	900.00		900.00
			Batch mixer - Surfactant Spacer 9th November	Per	Ea	1	Ea	2,000.00		2,000.00
			Misc. Pressure testing - - First 6 hours	Per	Ea		Ea	1,200.00		
			Misc. Pressure testing-Additional hours	Per	Hr		Hrs	150.00		

COMMENTS :

CUSTOMER hereby acknowledges r 0
and/or services listed on this ticket :
CUSTOMER OR CUSTOMER'S AGENT (PLEASE PRINT)

HALLIBURTON ENGINEER/OPERATOR :
M Smith
126968

PAGE TOTAL	12,534.15
CONTINUATION	
TOTAL	
TAX	
INVOICE TOTAL	

PLEASE RATE YOUR LEVEL OF SATISFACTION WITH OUR SERVICE

EXCELLENT	GOOD	ADEQUATE	COULD IMPROVE
4	3	2	1

CUSTOMER OR CUSTOMER'S AGENT (SIGNATURE)

HALLIBURTON APPROVAL :

As consideration, the above-named Customer agrees to pay Halliburton in accord with the rates and terms stated in Halliburton's current price lists. Halliburton warrants only title to the products, supplies and material and that the same are free from de workmanship and materials. THERE ARE NO WARRANTIES, EXPRESS OR IMPLIED, OF MERCHANTABILITY, FITNESS OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. Halliburton's liability and Customer's exclusive remedy in any cause of action (whether in contract, tort, breach of warranty or otherwise) arising out of the sale or use of any products, supplies or materials is expressly limited to the replacement of such products, s or materials on their return to Halliburton or, at Halliburton's option, to the allowance to the Customer of credit for the cost of such items. In no event shall Halliburton be liable for special, incidental, indirect , punitive or consequential damages. Customer's default in the payment of Customer's account 60 days after date of invoice, such account will thereafter be subject to interest until paid. In the event it becomes necessary to employ an attorney to enforce collection of such account, Customer agrees tp pay all collecction costs and attorney fees in the amount of 20 per cent of the unpaid account.

WHITE - ACCOUNTING ; GREEN - LOCATION ; BLUE - DISTRICT WAREHOUSE ; YELLOW - DISTRICT WAREHOUSE ; PINK - CUSTOMER ; OLD GOLD - INTERNAL COPY ; WHITE - INTERNAL COPY

HALLIBURTON

NEW ZEALAND LIMITED

Send Remittances to :
P.O.BOX 7160, PARAITE ROAD
BELL BLOCK, NEW PLYMOUTH
NEW ZEALAND

FIELD TICKET No. 4417

CUST NO.	305739
ENTITY	
LOCATION	
2ND REF	

CHARGE TO :	SWIFT ENERGY CORP (NZ)
ADDRESS :	16825 NORTH CHASE DRIVE
ADDRESS :	SUITE 400, HOUSTON, TEXAS.
COUNTRY	USA.
POST CODE	

SALES ORDER No. 4036628
DELIVERY No
QUOTE No.

CONTRACT NUMBER
DATE: 11th November 2005

DEPARTMENT/PSL: ZI, 10002	INVOICE No :- (ACCOUNTS USE ONLY)	CUSTOMER ORDER No.	SHIP VIA	DELIVER TO :	
PROJECT REF - HALLIBURTON	RIG NAME: Parker 252	RIG TYPE: Drilling	RIG CONTRACTOR: Parker	WELL NAME/No.: AHUROA STH B1	WELL OWNER: SWIFT ENERGY
WELL TYPE: Exploration	WELL LOCATION: Croydon Rd, Tariki	FIELD NAME	LAND [X] OFFSHORE [ ]	WELL CATEGORY: Development	CASED HOLE [X] OPEN HOLE [X]
TYPE TICKET: [ ] SERVICE [X] SALE	JOB TYPE: Cementing	JOB PURPOSE: Ahuroa Sth B1 Cement and Chemical Sales for Kick off plug 9th November			CURRENCY: US $

PRICE REFERENCE	PART NUMBER	WHS	DESCRIPTION	UNITS 1 QTY	UNITS 1 U/M	UNITS 2 QTY	UNITS 2 U/M	UNIT PRICE	D/F	AMOUNT
	100064243		NF-6	Per	Gal		Gals	87.21		-
	100003764		Latex 2000L	Per	Gal		Gals	38.09		-
	100064081		Stabilizer 434C	Per	Gal	15	Gals	62.58		938.70
	100003653		CFR-3	Per	Lb	70	Lbs	6.54		457.80
			KCL (Potasium Cloride)	Per	Lb	935	Lbs	0.47		439.45
	120003193		Gascon 469	Per	Gal		Gals	17.00		-
	100005050		HR-5	Per	Lb		Lbs	5.18		-
			WS - 36	Per	Gal	20	Gals	41.67		833.40
	100003646		Halad-322	Per	Lb		Lbs	10.20		-
	100090929		Pre-Hydrated Bentonite Gel	Per	Lb		Lbs	0.34		-
			SCR 100L	Per	Gal	10	Gals	93.98		939.80
			AS - 5	Per	Gal	5	Gals	22.71		113.55
			Cleanbore B	Per	Gal	15	Gals	37.77		566.55
	152016		6" Drill pipe foam wiper ball	Per	Ea	1	Ea	160.00		160.00
	101318558		Class-A Cement: Tonne (23.45 sks per tonne)	Per	sk		sks	8.67		-
			as per weight dockets :							
	100003685		Class-G Cement: 19.34 Tonne (23.45 sks per tonne)	Per	sk	454	sks	13.24		6,010.96
			as per weight docket: 31152							-

COMMENTS :

CUSTOMER hereby acknowledges receipt of the materials and/or services listed on this ticket :
CUSTOMER OR CUSTOMER'S AGENT (PLEASE PRINT)

HALLIBURTON ENGINEER/OPERATOR :
Mike.Smith
126968

CUSTOMER OR CUSTOMER'S AGENT (SIGNATURE)

HALLIBURTON APPROVAL :

PLEASE RATE YOUR LEVEL OF SATISFACTION WITH OUR SERVICE

EXCELLENT	GOOD	ADEQUATE	COULD IMPROVE
4	3	2	1

PAGE TOTAL	10,460.21
CONTINUATION	
TOTAL	
TAX	
INVOICE TOTAL	

As consideration, the above-named Customer agrees to pay Halliburton in accord with the rates and terms stated in Halliburton's current price lists. Halliburton warrants only title to the products, supplies and material and that the same are free from de workmanship and materials. THERE ARE NO WARRANTIES, EXPRESS OR IMPLIED, OF MERCHANTABILITY, FITNESS OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. Halliburton's liability and Customer's exclusive remedy in any cause of action (whether in contract, tort, breach of warranty or otherwise) arising out of the sale or use of any products, supplies or materials is expressly limited to the replacement of such products, s or materials on their return to Halliburton or, at Halliburton's option, to the allowance to the Customer of credit for the cost of such items. In no event shall Halliburton be liable for special, incidental, indirect , punitive or consequential damages. Customer's default in the payment of Customer's account 60 days after date of invoice, such account will thereafter be subject to interest until paid. In the event it becomes necessary to employ an attorney to enforce collection of such account, Customer agrees tp pay all collecction costs and attorney fees in the amount of 20 per cent of the unpaid account.

WHITE - ACCOUNTING ; GREEN - LOCATION ; BLUE - DISTRICT WAREHOUSE ; YELLOW - DISTRICT WAREHOUSE ; PINK - CUSTOMER ; OLD GOLD - INTERNAL COPY ; WHITE - INTERNAL COPY

HALLIBURTON

NEW ZEALAND LIMITED

FIELD TICKET No. 4455

Send Remittances to :
P.O.BOX 7160, PARAITE ROAD
BELL BLOCK, NEW PLYMOUTH
NEW ZEALAND

CUST NO.	305739
ENTITY	
LOCATION	
2ND REF	

CHARGE TO :	SWIFT ENERGY CORP (NZ)
ADDRESS :	16825 NORTH CHASE DRIVE
ADDRESS :	SUITE 400, HOUSTON, TEXAS.
COUNTRY	USA.
POST CODE	

SALES ORDER No. 4055243
DELIVERY No
QUOTE No.

CONTRACT NUMBER

DATE: 29th November 2005

DEPARTMENT/PSL: ZI, 10003	INVOICE No :- ACCOUNTS USE ONLY	CUSTOMER ORDER No.	SHIP VIA	DELIVER TO :	
PROJECT REF - HALLIBURTON	RIG NAME: Parker 252	RIG TYPE: Drilling	RIG CONTRACTOR: Parker	WELL NAME/No.: AHUROA STH B1 ST 1	WELL OWNER: SWIFT ENERGY
WELL TYPE: Exploration	WELL LOCATION: Croydon Rd, Tariki	FIELD NAME	LAND [X] OFFSHORE [ ]	WELL CATEGORY: Drilling	CASED HOLE [X] OPEN HOLE [X]
TYPE TICKET [X] SERVICE [ ] SALE	JOB TYPE	JOB PURPOSE: Ahuroa Sth B1 ST 1 Cementing Services 12th November 2005 to 29th November 2005			CURRENCY: US $

PRICE REFERENCE	PART NUMBER	WHS	DESCRIPTION	UNITS 1 QTY	UNITS 1 U/M	UNITS 2 QTY	UNITS 2 U/M	UNIT PRICE	D/F	AMOUNT
	16113		Service Operator 25th, 26th, 27th, 29th November	Per	Day	4	Days	650.00		2,600.00
	16113		Service Assistant 25th, 26th, 27th 29th November	Per	Day	4	Days	610.00		2,440.00
	104538		7" EZSV Mechanical setting tool running charges (Per 24 Hrs)	Per	Ea	1	Ea	2,000.00		2,000.00
			Less 20% Discount on setting tool running charges							(400.00)
			Contract mobilisation charge - Surface casing	Per	Ea		Ea	1,450.00		-
			Contract mobilisation charge - Production casing	Per	Ea		Ea	1,350.00		-
			Contract mobilisation charge - Suspension plugs 26th / 27th Nov	Per	Ea	1	Ea	1,196.47		1,196.47
			Equipment Rental 12th November to 29th November	Per	Day	18	Days	150.00		2,700.00
			9 5/8" Surface casing cement Job -	Per	Job		Ea	3,000.00		-
			7" Casing cement Job -	Per	Job		Ea	5,500.00		-
			4 1/2" Liner cement job -	Per	Job		Ea	7,000.00		-
			FI Test - - (Includes operator)	Per	Ea		Ea	450.00		-
	238		BOP Test - - First 6 hours (Includes operator)	Per	Ea		Ea	1,200.00		-
			BOP Tests - Additional hours	Per	Hr		Hrs	150.00		-
										-
			Pumping Mud/Diesel - - First 12 hrs (Includes operator)	Per	Ea		Ea	3,600.00		-
			Pumping Mud/Diesel-Additional hrs	Per	Hr		Hrs	450.00		
			Plug jobs (Any depth) - Suspension plugs 26th / 27th November	Per	Ea	2	Ea	900.00		1,800.00
			Batch mixer - 26th and 27th November	Per	Ea	2	Ea	2,000.00		4,000.00
			Misc. Pressure testing - Wellhead 28th November - First 6 hours	Per	Ea	1	Ea	1,200.00		1,200.00
			Misc. Pressure testing-Additional hours	Per	Hr		Hrs	150.00		

COMMENTS :

CUSTOMER hereby acknowledges r 0
and/or services listed on this ticket :
CUSTOMER OR CUSTOMER'S AGENT (PLEASE PRINT)

HALLIBURTON ENGINEER/OPERATOR :
M Smith
126968

CUSTOMER OR CUSTOMER'S AGENT (SIGNATURE)

HALLIBURTON APPROVAL :

PLEASE RATE YOUR LEVEL OF SATISFACTION WITH OUR SERVICE

EXCELLENT	GOOD	ADEQUATE	COULD IMPROVE
4	3	2	1

PAGE TOTAL	17,536.47
CONTINUATION	
TOTAL	
TAX	
INVOICE TOTAL	

As consideration, the above-named Customer agrees to pay Halliburton in accord with the rates and terms stated in Halliburton's current price lists. Halliburton warrants only title to the products, supplies and material and that the same are free from de workmanship and materials. THERE ARE NO WARRANTIES, EXPRESS OR IMPLIED, OF MERCHANTABILITY, FITNESS OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. Halliburton's liability and Customer's exclusive remedy in any cause of action (whether in contract, tort, breach of warranty or otherwise) arising out of the sale or use of any products, supplies or materials is expressly limited to the replacement of such products, s or materials on their return to Halliburton or, at Halliburton's option, to the allowance to the Customer of credit for the cost of such items. In no event shall Halliburton be liable for special, incidental, indirect , punitive or consequential damages. Customer's default in the payment of Customer's account 60 days after date of invoice, such account will thereafter be subject to interest until paid. In the event it becomes necessary to employ an attorney to enforce collection of such account, Customer agrees tp pay all collecction costs and attorney fees in the amount of 20 per cent of the unpaid account.

WHITE - ACCOUNTING ; GREEN - LOCATION ; BLUE - DISTRICT WAREHOUSE ; YELLOW - DISTRICT WAREHOUSE ; PINK - CUSTOMER ; OLD GOLD - INTERNAL COPY ; WHITE - INTERNAL COPY

HALLIBURTON

SWIFT ENERGY NZ LTD
AHUROA SOUTH B-1
Well Recap

HALLIBURTON

NEW ZEALAND LIMITED

Send Remittances to :
P.O.BOX 7160, PARAITE ROAD
BELL BLOCK, NEW PLYMOUTH
NEW ZEALAND

FIELD TICKET No. 4456

CUST NO.	305739
ENTITY	
LOCATION	
2ND REF	

CHARGE TO :	SWIFT ENERGY CORP (NZ)
ADDRESS :	16825 NORTH CHASE DRIVE
ADDRESS :	SUITE 400, HOUSTON, TEXAS.
COUNTRY	USA.

SALES ORDER No. 4055245
DELIVERY No
QUOTE No.

POST CODE | CONTRACT NUMBER | DATE 28th November 2005

DEPARTMENT/PSL: ZI, 10002	INVOICE No :- ACCOUNTS USE ONLY	CUSTOMER ORDER No.	SHIP VIA	DELIVER TO :
PROJECT REF - HALLIBURTON	RIG NAME: Parker 252	RIG TYPE: Drilling	RIG CONTRACTOR: Parker	WELL NAME/No.: AHUROA STH B1 ST 1
WELL OWNER: SWIFT ENERGY				
WELL TYPE: Exploration	WELL LOCATION: Croydon Rd, Tariki	FIELD NAME	LAND [X] OFFSHORE [ ]	WELL CATEGORY: Development
CASED HOLE [X]	OPEN HOLE [X]			

TYPE TICKET: [ ] SERVICE [X] SALE
JOB TYPE: Cementing
JOB PURPOSE: Ahuroa Sth B1 ST 1 Cement and Chemical Sales for Suspension plugs 26th / 27th November 2005
CURRENCY: US $

PRICE REFERENCE	PART NUMBER	WHS	DESCRIPTION	UNITS 1 QTY	UNITS 1 U/M	UNITS 2 QTY	UNITS 2 U/M	UNIT PRICE	D/F	AMOUNT
	100064243		NF-6	Per	Gal		Gals	87.21		-
	100003764		Latex 2000L	Per	Gal		Gals	38.09		-
	100064081		Stabilizer 434C	Per	Gal	20	Gals	62.58		1,251.60
	100003653		CFR-3	Per	Lb	50	Lbs	6.54		327.00
			KCL (Potassium Chloride)	Per	Lb	1210	Lbs	0.47		568.70
	120003193		Gascon 469	Per	Gal		Gals	17.00		-
	100005050		HR-5	Per	Lb		Lbs	5.18		-
			WS - 36	Per	Gal	25	Gals	41.67		1,041.75
	100003646		Halad-322	Per	Lb		Lbs	10.20		-
	100090929		Pre-Hydrated Bentonite Gel	Per	Lb		Lbs	0.34		-
			SCR 100L	Per	Gal	8	Gals	93.98		751.84
			AS - 5	Per	Gal	8	Gals	22.71		181.68
			Cleanbore B	Per	Gal	20	Gals	37.77		755.40
	152016		6" Drill pipe foam wiper ball	Per	Ea	1	Ea	160.00		160.00
	101318558		Class-A Cement: Tonne (23.45 sks per tonne)	Per	sk		sks	8.67		-
			as per weight dockets :							
	100003685		Class-G Cement: 15.82 Tonne (23.45 sks per tonne)	Per	sk	371	sks	13.24		4,912.04
			as per weight docket: 31397 dated 24th November.							-
	100004370		7" EZSV Packer (Sales prices USD3,881.00 Less 20% Discount)	Per	Ea	1	Ea	3,104.80		3,104.80

COMMENTS :

CUSTOMER hereby acknowledges receipt of the materials and/or services listed on this ticket :
CUSTOMER OR CUSTOMER'S AGENT (PLEASE PRINT)

HALLIBURTON ENGINEER/OPERATOR :
Mike.Smith
126968

CUSTOMER OR CUSTOMER'S AGENT (SIGNATURE)

HALLIBURTON APPROVAL :

PLEASE RATE YOUR LEVEL OF SATISFACTION WITH OUR SERVICE

EXCELLENT	GOOD	ADEQUATE	COULD IMPROVE
4	3	2	1

PAGE TOTAL	13,054.81
CONTINUATION	
TOTAL	
TAX	
INVOICE TOTAL	

As consideration, the above-named Customer agrees to pay Halliburton in accord with the rates and terms stated in Halliburton's current price lists. Halliburton warrants only title to the products, supplies and material and that the same are free from de workmanship and materials. THERE ARE NO WARRANTIES, EXPRESS OR IMPLIED, OF MERCHANTABILITY, FITNESS OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. Halliburton's liability and Customer's exclusive remedy in any cause of action (whether in contract, tort, breach of warranty or otherwise) arising out of the sale or use of any products, supplies or materials is expressly limited to the replacement of such products, s or materials on their return to Halliburton or, at Halliburton's option, to the allowance to the Customer of credit for the cost of such items. In no event shall Halliburton be liable for special, incidental, indirect , punitive or consequential damages. Customer's default in the payment of Customer's account 60 days after date of invoice, such account will thereafter be subject to interest until paid. In the event it becomes necessary to employ an attorney to enforce collection of such account, Customer agrees tp pay all collecction costs and attorney fees in the amount of 20 per cent of the unpaid account.

WHITE - ACCOUNTING ; GREEN - LOCATION ; BLUE - DISTRICT WAREHOUSE ; YELLOW - DISTRICT WAREHOUSE ; PINK - CUSTOMER ; OLD GOLD - INTERNAL COPY ; WHITE - INTERNAL COPY

Cementing Report

Swift Energy New Zealand Ltd

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Start Date/Time: 26-Nov-05 05:30 **Well Bore:** Side Track
Job Type: PLUG

ins

Cementing Co: HALLIBTN
Plug Type: T & A plug
Plug: Top: 2330.0 m **Bottom:** 2430.0 m **Length:** 100.0 m
Calc. Displacement Vol: 44.000 ins **Hole Size at Plug:** ins

	Volume - bbls	Pump Time	Rate - bbls/min	Volume - psi
Conditioning Data:		180	6.0	200.0
Cement Data:	13.2	15	5.6	200
Displacement Data:	44.0	15	6.0	300

Slurry Information:

Type	Density	Yield	Sacks	Volume	Rate	Additives
CL G	17.20	0.98	65	11.3	2.5	0.5% CFR-3, 0.06gals/sk SCR-100L

Liner Top Test: lbs/gal
Shoe Test: lbs/gal
Job Success?: No
CBL Bond Quality:
Actual Top Of Cmt: m
Misc. Comments: Did not get a tag on the cement (failed)

Printed: 14:43 21-Mar-06 *End of Report*

Cementing Report

Well ID: **Well Name:**

Start Date/Time:		**Well Bore:**	
Job Type:			
Well Section:		**String OD:**	ins
String Type:			
Cementing Co:			
Liner Top Test:	lbs/gal		
Shoe Test:	lbs/gal		
Job Success?:			
CBL Bond Quality:			
Actual Top Of Cmt:	m		
Misc. Comments:			

Printed: 12:19 25-May-07 *End of Report*

Cementing Report

Swift Energy New Zealand Ltd

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Start Date/Time: 27-Nov-05 09:15 **Well Bore:** Side Track
Job Type: PLUG

ins

Cementing Co: HALLIBTN
Plug Type: Cement & EZSV
Plug: Top: 2345.0 m **Bottom:** 2445.0 m **Length:** 100.0 m
Calc. Displacement Vol: 32.700 ins **Hole Size at Plug:** ins

	Volume - bbls	Pump Time	Rate - bbls/min	Volume - psi
Conditioning Data:		20	2.0	700.0
Cement Data:	12.0	6	2.5	750
Displacement Data:	32.7	8	5.0	1000

Slurry Information:

Type	Density	Yield	Sacks	Volume	Rate	Additives
CL G	15.80	1.16	58	12.0	2.5	4gals/10bbls SCR-100L

Liner Top Test: lbs/gal
Shoe Test: lbs/gal
Job Success?: Yes
CBL Bond Quality:
Actual Top Of Cmt: 2345.0 m
Misc. Comments: Set EZSV @ 2,365mMD, pumped 6bbls below EZSV, unsting and balanced 6bbls above. Pressure tested Casing to 3,000psi after curing time elapsed.(did not tag with pipe).
The CBL on the 7" Casing good to 900m.

Directional Survey Report

Swift Energy New Zealand Ltd

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Well Bore: Original Well Bore **Plane of Vertical Section: 0.0 degrees**

	Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Coordinates N-S	Coordinates E-W	Closure	Vertical Section	Dog Leg Severity
**	TieIn	0.00	0.00	0.0	0.00				0.00	
	TOTC	33.00	1.00	0.0	33.00	N 0.29		0.29	0.29	0.909
	TOTC	100.00	1.00							
	TOTC	145.00	1.00							
	TOTC	195.00	1.00							
**	TieIn	210.00	1.56	306.0	209.96	N 2.04	E 2.78	3.79	2.04	
	MWD	238.56	1.86	311.2	238.51	N 2.57	E 2.12	3.33	2.57	0.354
	MWD	266.79	1.24	299.5	266.73	N 3.03	E 1.51	3.38	3.03	0.736
	MWD	294.18	0.87	291.0	294.11	N 3.25	E 1.05	3.41	3.25	0.439
	MWD	321.00	0.74	248.0	320.93	N 3.25	E 0.70	3.33	3.25	0.674
	MWD	348.00	0.81	213.1	347.93	N 3.03	E 0.44	3.06	3.03	0.522
	MWD	374.63	0.81	204.3	374.55	N 2.70	E 0.26	2.71	2.70	0.139
	MWD	401.00	0.80	194.3	400.92	N 2.35	E 0.13	2.36	2.35	0.160
	MWD	428.37	0.76	191.1	428.29	N 1.99	E 0.05	1.99	1.99	0.065
	MWD	455.21	1.46	166.4	455.12	N 1.48	E 0.10	1.48	1.48	0.930
	MWD	482.01	1.61	157.6	481.92	N 0.80	E 0.32	0.86	0.80	0.312
	MWD	508.82	1.35	159.1	508.72	N 0.16	E 0.58	0.60	0.16	0.294
	MWD	535.74	1.23	157.4	535.63	S 0.40	E 0.80	0.90	-0.40	0.140
	MWD	562.69	1.70	122.7	562.57	S 0.89	E 1.25	1.53	-0.89	1.094
	MWD	598.41	2.02	110.6	598.27	S 1.39	E 2.29	2.68	-1.39	0.422
	MWD	616.00	2.02	111.0	615.85	S 1.62	E 2.87	3.29	-1.62	0.022
	MWD	640.10	2.03	114.2	639.94	S 1.94	E 3.65	4.14	-1.94	0.141
	MWD	667.00	1.98	111.2	666.82	S 2.31	E 4.52	5.07	-2.31	0.131
	MWD	703.00	6.80	153.1	702.71	S 4.43	E 6.06	7.51	-4.43	4.575
	MWD	720.00	8.98	151.1	719.55	S 6.49	E 7.16	9.67	-6.49	3.878
	MWD	747.00	11.40	142.6	746.12	S 10.46	E 9.80	14.33	-10.46	3.165
	MWD	765.00	12.04	140.9	763.75	S 13.33	E 12.06	17.98	-13.33	1.199
	MWD	783.00	13.35	139.3	781.31	S 16.36	E 14.60	21.93	-16.36	2.264
	MWD	801.00	15.18	135.8	798.75	S 19.63	E 17.60	26.36	-19.63	3.367
	MWD	827.62	16.96	130.4	824.33	S 24.65	E 22.99	33.70	-24.65	2.614
	MWD	854.53	17.41	129.5	850.04	S 29.75	E 29.08	41.60	-29.75	0.586
	MWD	881.45	18.98	130.4	875.61	S 35.16	E 35.52	49.97	-35.16	1.779

Directional Survey Report

Swift Energy New Zealand Ltd

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Coordinates N-S	Coordinates E-W	Closure	Vertical Section	Dog Leg Severity
MWD	908.74	19.55	131.2	901.37	S 41.04	E 42.33	58.96	-41.04	0.679
MWD	935.58	19.86	130.4	926.64	S 46.96	E 49.18	68.00	-46.96	0.442
MWD	962.00	19.33	131.7	951.53	S 52.78	E 55.86	76.85	-52.78	0.772
MWD	989.00	18.58	134.4	977.07	S 58.76	E 62.27	85.62	-58.76	1.277
MWD	1016.00	18.94	134.9	1002.63	S 64.86	E 68.45	94.30	-64.86	0.444
MWD	1043.00	19.46	134.6	1028.13	S 71.12	E 74.75	103.17	-71.12	0.589
MWD	1071.00	19.79	133.8	1054.51	S 77.67	E 81.49	112.58	-77.67	0.458
MWD	1098.00	19.81	132.4	1079.91	S 83.92	E 88.17	121.72	-83.92	0.520
MWD	1124.00	19.47	133.9	1104.40	S 89.90	E 94.54	130.46	-89.90	0.692
MWD	1151.00	18.96	137.1	1129.89	S 96.24	E 100.77	139.34	-96.24	1.307
MWD	1178.00	18.89	137.8	1155.43	S 102.69	E 106.69	148.08	-102.69	0.264
MWD	1205.00	19.52	136.5	1180.93	S 109.20	E 112.73	156.95	-109.20	0.850
MWD	1232.00	20.14	136.5	1206.33	S 115.84	E 119.03	166.10	-115.84	0.689
MWD	1258.00	20.76	135.9	1230.69	S 122.39	E 125.33	175.18	-122.39	0.756
MWD	1285.00	20.58	135.6	1255.95	S 129.22	E 131.98	184.70	-129.22	0.232
MWD	1312.00	17.63	137.6	1281.46	S 135.62	E 138.06	193.53	-135.62	3.359
MWD	1339.00	17.41	138.7	1307.21	S 141.68	E 143.49	201.65	-141.68	0.442
MWD	1366.00	17.60	138.6	1332.96	S 147.77	E 148.85	209.75	-147.77	0.213
MWD	1393.00	17.53	138.6	1358.70	S 153.88	E 154.24	217.88	-153.88	0.078
MWD	1421.00	18.94	136.5	1385.30	S 160.34	E 160.16	226.63	-160.34	1.657
MWD	1447.00	19.29	135.9	1409.86	S 166.49	E 166.05	235.14	-166.49	0.471
MWD	1474.00	19.86	135.2	1435.30	S 172.95	E 172.38	244.19	-172.95	0.682
MWD	1501.00	20.16	134.5	1460.67	S 179.47	E 178.93	253.43	-179.47	0.436
MWD	1528.00	20.68	134.1	1485.98	S 186.04	E 185.68	262.85	-186.04	0.594
MWD	1555.00	21.30	133.7	1511.18	S 192.75	E 192.64	272.52	-192.75	0.709
MWD	1582.00	20.84	134.9	1536.38	S 199.53	E 199.59	282.22	-199.53	0.695
MWD	1609.00	20.57	135.1	1561.63	S 206.28	E 206.34	291.77	-206.28	0.310
MWD	1636.00	19.73	135.1	1586.98	S 212.86	E 212.91	301.07	-212.86	0.934
MWD	1662.00	20.06	135.1	1611.43	S 219.14	E 219.15	309.92	-219.14	0.381
MWD	1689.00	20.17	135.2	1636.78	S 225.72	E 225.70	319.20	-225.72	0.123
MWD	1716.00	20.33	134.6	1662.11	S 232.31	E 232.32	328.55	-232.31	0.282
MWD	1743.00	20.69	134.0	1687.40	S 238.91	E 239.10	338.00	-238.91	0.469
MWD	1770.00	20.87	133.8	1712.65	S 245.55	E 246.00	347.58	-245.55	0.211
MWD	1798.00	20.16	134.6	1738.87	S 252.39	E 253.04	357.39	-252.39	0.814

Directional Survey Report

Swift Energy New Zealand Ltd

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Coordinates N-S	Coordinates E-W	Closure	Vertical Section	Dog Leg Severity
MWD	1826.00	19.74	134.8	1765.19	S 259.11	E 259.83	366.95	-259.11	0.461
MWD	1855.00	19.43	134.6	1792.51	S 265.95	E 266.74	376.67	-265.95	0.335
MWD	1910.83	18.93	134.2	1845.24	S 278.78	E 279.85	395.01	-278.78	0.276
MWD	1938.53	19.02	135.2	1871.44	S 285.11	E 286.25	404.02	-285.11	0.369
MWD	1967.08	19.08	135.5	1898.42	S 291.74	E 292.80	413.33	-291.74	0.115
MWD	1995.35	18.90	135.7	1925.16	S 298.31	E 299.24	422.53	-298.31	0.206
MWD	2023.52	18.59	135.5	1951.83	S 304.78	E 305.57	431.58	-304.78	0.336
MWD	2052.66	19.21	136.8	1979.40	S 311.59	E 312.11	441.02	-311.59	0.762
MWD	2081.20	19.19	137.4	2006.35	S 318.46	E 318.50	450.40	-318.46	0.202
MWD	2110.05	19.43	138.7	2033.58	S 325.56	E 324.88	459.93	-325.56	0.533
MWD	2138.42	20.66	140.0	2060.23	S 332.93	E 331.21	469.62	-332.93	1.376
MWD	2167.28	20.95	140.9	2087.21	S 340.84	E 337.74	479.83	-340.84	0.462
MWD	2195.91	20.97	140.9	2113.94	S 348.79	E 344.20	490.02	-348.79	0.024
MWD	2224.19	20.97	141.3	2140.35	S 356.66	E 350.55	500.09	-356.66	0.129
MWD	2253.04	20.50	139.1	2167.33	S 364.51	E 357.08	510.27	-364.51	0.927
MWD	2291.52	20.35	138.8	2203.39	S 374.65	E 365.90	523.68	-374.65	0.144
MWD	2319.57	20.22	139.3	2229.70	S 381.99	E 372.27	533.39	-381.99	0.223
MWD	2348.33	19.97	140.4	2256.71	S 389.54	E 378.64	543.24	-389.54	0.470
MWD	2378.00	19.93	141.0	2284.60	S 397.38	E 385.05	553.33	-397.38	0.218
MWD	2409.54	19.98	142.1	2314.25	S 405.81	E 391.74	564.04	-405.81	0.370
MWD	2438.25	19.30	141.4	2341.29	S 413.39	E 397.71	573.64	-413.39	0.751
MWD	2466.42	18.89	138.6	2367.91	S 420.45	E 403.63	582.83	-420.45	1.091
MWD	2493.65	18.81	135.4	2393.68	S 426.89	E 409.62	591.63	-426.89	1.121
MWD	2521.81	18.40	135.7	2420.37	S 433.30	E 415.91	600.61	-433.30	0.445
MWD	2549.28	18.54	134.4	2446.42	S 439.46	E 422.06	609.31	-439.46	0.469
MWD	2577.88	18.98	134.6	2473.50	S 445.91	E 428.62	618.51	-445.91	0.467
MWD	2606.78	19.53	134.7	2500.79	S 452.61	E 435.40	628.03	-452.61	0.572
MWD	2634.32	19.03	136.1	2526.78	S 459.09	E 441.78	637.13	-459.09	0.742
MWD	2662.32	18.53	137.1	2553.29	S 465.64	E 447.97	646.14	-465.64	0.641
MWD	2690.57	18.77	134.2	2580.06	S 472.10	E 454.28	655.17	-472.10	1.034
MWD	2718.54	19.23	134.0	2606.51	S 478.43	E 460.82	664.27	-478.43	0.500
MWD	2746.40	18.27	136.7	2632.89	S 484.80	E 467.12	673.22	-484.80	1.407
MWD	2773.77	19.19	134.7	2658.81	S 491.09	E 473.26	682.01	-491.09	1.228
MWD	2803.47	18.90	135.1	2686.88	S 497.93	E 480.12	691.70	-497.93	0.323

Directional Survey Report

Swift Energy New Zealand Ltd

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Coordinates N-S	Coordinates E-W	Closure	Vertical Section	Dog Leg Severity
MWD	2822.15	18.90	135.1	2704.55	S 502.22	E 484.38	697.75	-502.22	0.000
MWD	2850.50	18.31	135.3	2731.42	S 508.64	E 490.76	706.79	-508.64	0.626
MWD	2879.09	19.21	130.1	2758.50	S 514.86	E 497.52	715.96	-514.86	1.989
MWD	2915.60	21.16	130.2	2792.76	S 522.98	E 507.15	728.50	-522.98	1.603
MWD	2944.18	21.73	130.2	2819.36	S 529.72	E 515.13	738.89	-529.72	0.599
MWD	2972.15	21.26	130.9	2845.39	S 536.39	E 522.91	749.10	-536.39	0.574
MWD	3000.49	20.97	132.9	2871.83	S 543.21	E 530.51	759.29	-543.21	0.815
MWD	3029.69	21.95	133.2	2899.00	S 550.50	E 538.31	769.96	-550.50	1.013
MWD	3057.92	22.13	133.9	2925.17	S 557.80	E 545.99	780.54	-557.80	0.329
MWD	3086.24	22.18	135.3	2951.40	S 565.30	E 553.59	791.22	-565.30	0.582
MWD	3115.04	21.89	138.3	2978.09	S 573.18	E 560.99	802.02	-573.18	1.203
MWD	3143.80	21.05	141.6	3004.86	S 581.23	E 567.76	812.51	-581.23	1.525
MWD	3172.54	20.63	144.2	3031.72	S 589.38	E 573.93	822.66	-589.38	1.057
MWD	3201.13	19.54	147.9	3058.57	S 597.51	E 579.43	832.32	-597.51	1.753
MWD	3229.81	18.80	151.1	3085.66	S 605.62	E 584.21	841.47	-605.62	1.347
MWD	3258.74	18.55	152.3	3113.07	S 613.77	E 588.61	850.40	-613.77	0.481

Directional Survey Report

Swift Energy New Zealand Ltd

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

	Survey Type	Meas. Depth	Inc.	Azimuth	TVD	Coordinates N-S	Coordinates E-W	Closure	Vertical Section	Dog Leg Severity
Well Bore: Side Track								**Plane of Vertical Section: 0.0 degrees**		
Kick Off Point: 2405.00 m				**from Well Bore: Original Well Bore**						
**	TieIn	2422.00	21.91	134.5	2325.71	S 408.97	E 395.62	569.01	-408.97	
	MWD	2431.15	22.88	133.9	2334.17	S 411.40	E 398.12	572.49	-411.40	3.295
	MWD	2450.30	20.66	134.6	2351.95	S 416.35	E 403.21	579.59	-416.35	3.503
	MWD	2469.33	18.66	135.4	2369.87	S 420.87	E 407.74	585.99	-420.87	3.183
	MWD	2487.27	16.44	137.2	2386.98	S 424.78	E 411.48	591.40	-424.78	3.818
	MWD	2506.30	13.88	136.7	2405.34	S 428.42	E 414.88	596.38	-428.42	4.041
	MWD	2525.37	11.29	136.4	2423.95	S 431.43	E 417.74	600.53	-431.43	4.076
	MWD	2544.56	8.66	138.6	2442.85	S 433.88	E 419.99	603.85	-433.88	4.157
	MWD	2563.69	6.61	140.3	2461.81	S 435.81	E 421.64	606.39	-435.81	3.234
	MWD	2582.64	4.82	144.4	2480.67	S 437.29	E 422.80	608.27	-437.29	2.902
	MWD	2601.00	2.51	140.1	2498.99	S 438.23	E 423.51	609.43	-438.23	3.798
	MWD	2620.00	0.18	144.6	2517.98	S 438.57	E 423.80	609.87	-438.57	3.680
	MWD	2639.60	2.09	303.5	2537.58	S 438.40	E 423.52	609.56	-438.40	3.457
	MWD	2658.51	3.84	303.5	2556.46	S 437.86	E 422.70	608.60	-437.86	2.776
	MWD	2677.58	6.06	304.4	2575.46	S 436.94	E 421.34	606.99	-436.94	3.494
	MWD	2706.24	7.30	302.3	2603.92	S 435.11	E 418.55	603.74	-435.11	1.323
	MWD	2734.87	6.73	299.8	2632.34	S 433.30	E 415.56	600.37	-433.30	0.674
	MWD	2763.61	6.99	303.1	2660.87	S 431.51	E 412.63	597.05	-431.51	0.494
	MWD	2792.08	7.14	304.1	2689.13	S 429.57	E 409.72	593.63	-429.57	0.200
	MWD	2820.60	7.90	303.5	2717.40	S 427.50	E 406.61	589.99	-427.50	0.804
	MWD	2849.00	8.26	297.3	2745.52	S 425.48	E 403.17	586.16	-425.48	0.994
	MWD	2876.40	7.95	300.1	2772.65	S 423.63	E 399.79	582.48	-423.63	0.551
	MWD	2904.99	6.76	297.1	2801.00	S 421.87	E 396.58	579.00	-421.87	1.312
	MWD	2933.32	7.21	296.8	2829.12	S 420.31	E 393.51	575.76	-420.31	0.478
	MWD	2961.96	7.37	291.0	2857.53	S 418.84	E 390.19	572.43	-418.84	0.790
	MWD	2988.33	7.39	288.9	2883.68	S 417.68	E 387.00	569.41	-417.68	0.305
	MWD	3019.26	8.03	288.4	2914.33	S 416.36	E 383.07	565.77	-416.36	0.625
	MWD	3047.86	8.34	287.8	2942.64	S 415.09	E 379.20	562.22	-415.09	0.338
	MWD	3069.23	8.38	287.7	2963.78	S 414.15	E 376.24	559.53	-414.15	0.059

Calculations using Minimum Curvature Method

BHA Report

Swift Energy New Zealand Ltd

Well ID: NZ050091A **Well Name:** Ahuroa South B-1 ST# 1

Well Bore: Side Track

BHA Number: 7 **BHA Length:** 224.3 m

	Weights in Air	Buoyed Weight at Mud Wt of: 9.30 lbs/gal
BHA Wt:	21177	18166
Drillstring Wt:	21177	18166
Wt Above Jars:	5	
Wt Below Jars:	16	

	In	Out
Depth:	2380.0 m	2400.0 m
Date/Time:	10-Nov-05 13:33	11-Nov-05 05:57
Inclination:		
Azimuth:		

Average RPM: 40 **Drilling Hrs.:** 8.00

Build Rate: **Walk Rate:**

WOB - Min: lbs **WOB - Max:** lbs

Comments:
Clean out assy

BHA Component Details

Item	No. Jnts	Length	I.D.	O.D.	Weight	Grade	Top Connection	P/B	Comment
HWD	15	139.3	2.850	3.500	26.9		3.5IF	Box	
JAR	1	9.0	2.850	3.500	26.9		3.5IF	Box	
HWD	6	56.0	2.850	3.500	26.9		3.5IF	Box	
DC	1	9.5	3.000	4.750	44.0		3.5IF	Box	
DC	1	9.4	2.750	4.750	44.0		3.5IF	Box	
BS	1	0.9	3.000	4.750	118.8		3.5IF	Box	
BIT	1	0.2	0.000	6.000			3.5REG	Box	
Total :		**224.3**							

BHA Report

Swift Energy New Zealand Ltd

Well ID: NZ050091A **Well Name:** Ahuroa South B-1 ST# 1

Well Bore: Side Track

BHA Number: 9 **BHA Length:** 216.8 m

	Weights in Air	Buoyed Weight at Mud Wt of: 9.30 lbs/gal
BHA Wt:	21956	18835
Drillstring Wt:	21956	18835
Wt Above Jars:	5	
Wt Below Jars:	16	

	In	Out
Depth:	2433.0 m	2874.0 m
Date/Time:	05-Nov-19 14:00	19-Nov-05 07:00
Inclination:	8.26	
Azimuth:	297	

Average RPM: **Drilling Hrs.:**

Build Rate: **Walk Rate:**

WOB - Min: lbs **WOB - Max:** lbs

Comments:

BHA Component Details

Item	No. Jnts	Length	I.D.	O.D.	Weight	Grade	Top Connection	P/B	Comment
HWD	6	55.6	2.850	3.500	26.9		3.5IF	Box	
JAR	1	9.0	2.850	3.500	26.9		3.5IF	Box	
HWD	15	139.4	2.850	3.500	26.9		3.5IF	Box	
MWD	1	5.1	2.850	3.500	26.9		3.5IF	Box	
STAB	1	1.5	2.250	4.688	148.1		3.5IF	Box	
FS	1	0.5	1.813	4.625	158.6		3.5IF	Box	
MMT	1	5.5	3.000	4.750	118.8		3.5IF	Box	
BIT	1	0.2	0.000	6.000			3.5REG	Box	
Total :		**216.8**							

Printed: 14:29 21-Mar-06

End of Report

BHA Report

Swift Energy New Zealand Ltd

Well ID: NZ050091A **Well Name:** Ahuroa South B-1 ST# 1
Well Bore: Side Track

BHA Number: 10 **BHA Length:** 216.8 m

	Weights in Air	Buoyed Weight at Mud Wt of: 8.70 lbs/gal
BHA Wt:	21956	19036
Drillstring Wt:	21956	19036
Wt Above Jars:	5	
Wt Below Jars:	16	

	In	Out
Depth:	2874.0 m	m
Date/Time:	19-Nov-05 14:00	
Inclination:	8.26	
Azimuth:	297	

Average RPM: **Drilling Hrs.:**
Build Rate: **Walk Rate:**
WOB - Min: lbs **WOB - Max:** lbs

Comments:
New motor, 21 new HWDP. Reposition float sub below stabilizer as float could slide up into the MWD pin. Replaced float w/- dart type as flapper float had lost it's seals.

BHA Component Details

Item	No. Jnts	Length	I.D.	O.D.	Weight	Grade	Top Connection	P/B	Comment
HWD	6	55.6	2.850	3.500	26.9		3.5IF	Box	
JAR	1	9.0	2.850	3.500	26.9		3.5IF	Box	
HWD	15	139.4	2.850	3.500	26.9		3.5IF	Box	
MWD	1	5.1	2.850	3.500	26.9		3.5IF	Box	
STAB	1	1.5	2.250	4.688	148.1		3.5IF	Box	
FS	1	0.5	1.813	4.625	158.6		3.5IF	Box	
MMT	1	5.5	3.000	4.750	118.8		3.5IF	Box	
BIT	1	0.2	0.000	6.000			3.5REG	Box	
Total :		**216.8**							

BHA Report

Swift Energy New Zealand Ltd

Well ID: NZ050091A **Well Name:** Ahuroa South B-1 ST# 1
Well Bore: Side Track

BHA Number: 8 **BHA Length:** 217.9 m

	Weights in Air	Buoyed Weight at Mud Wt of: 9.30 lbs/gal
BHA Wt:	21246	18226
Drillstring Wt:	21246	18226
Wt Above Jars:	5	
Wt Below Jars:	16	

	In	Out
Depth:	2400.0 m	2433.0 m
Date/Time:	12-Nov-05 05:58	13-Nov-05 14:15
Inclination:		
Azimuth:		

Average RPM: 40 **Drilling Hrs.:** 36.50
Build Rate: **Walk Rate:**
WOB - Min: 5 lbs **WOB - Max:** 2 lbs

Comments:

BHA Component Details

Item	No. Jnts	Length	I.D.	O.D.	Weight	Grade	Top Connection	P/B	Comment
HWD	6	55.6	2.850	3.500	26.9		3.5IF	Box	
JAR	1	9.0	2.850	3.500	26.9		3.5IF	Box	
HWD	15	139.8	2.850	3.500	26.9		3.5IF	Box	
MWD	1	5.1	2.850	3.500	26.9		3.5IF	Box	
FS	1	0.5	3.000	4.750	44.0		3.5IF	Box	
STAB	1	1.5	2.750	4.750	44.0		3.5IF	Box	
MWD	1	6.2	3.000	4.750	118.8		3.5IF	Box	
BIT	1	0.2	0.000	6.000			3.5REG	Box	
Total :		**217.9**							

Printed: 14:30 21-Mar-06

End of Report

RIG 252 INVENTORY

February 2001

Engines

The Carrier and Drawworks are powered by 2 Each x 3408 Turbo Charged Caterpillar engines which are capable of 450 horsepower Each at 1800 RPMs for a total of 900 horsepower. The engines are High mounted on the carrier for convenient accessibility to encourage good preventative maintenance.

Drawworks

The Drawworks is an Ingersoll Rand Model 2346 large diameter Drum barrel with 12inch x 46inch water circulating type brake rims bolted to drum. Full wrap, single point adjusted fully equalized brake bands. Outboard drum clutch for easy maintenance. 60,000 # single line pull. Lebus grooving drum for 1-1/8" IPS drilling and equipped with a Parmac v80 hydromatic brake.

Rig Drive

Torque Converters

Two converters individually matched to engines selected. Automatic lockup feature in each converter for maximum efficiency.

Transmission

Allison CLT 5861 in combination with the converters. Synchronized full load shifting with five forward speeds and one reverse speed. Driller can instantly select the proper gear in any operation. The wide range of speeds available to the drawworks reduces dwell time Between speed ranges and reduces total trip time.

Compound

Integral with final drum drive. Idler adjusted high-speed roller chain in oil bath case compounding each engine drive to drawworks drum Shaft.

Catworks Rotary Drive

Catworks
Hydraulic catworks including high capacity breakout cylinders, Spinning and make up cylinders and planetary gear, self locking handling winch for smooth, safer catheading operations.

Rotary Drive
Propeller shaft via full air rotary clutch, heavy duty reverse gear box, and oil bath roller chain elevated rotary drive, utilised on back face of Mast. This provides simple propeller shaft connection at rig up and rig down stages.
Nominal Max rotary speed = 220 RPM
Nominal table working torque = 30,000 ft.lbs.

Mast and Substructure

Substructure
The substructure has a 17ft floor height and a 14ft rotary beam to ground clearance. The setback capacity of the substructure is 200,000 pounds. And the rotary capacity is 350,000 lbs. with a total Simultaneous of 550,000 lbs.

Mast
The Mast is a 117ft x 350,000 #API rated telescoping mast. Deep derrick section for maximum torsional stability. Patented pawl mechanism assuring positive transfer of load from upper to lower section. Hydraulic cylinder raising and extending system for greater reliability and simplicity. Square tubular construction offers maximum Rigidity and a capability to withstand unplanned abuse. Heavy duty Rigid racking board with side mounted fingers provided with finger Safety locks. Load guylines to carrier.

Hookload capacity = 350,000 lbs. with eight lines
Racking capacity = 10,300ft of 4-1/2" D.P. with 6-1/2" tool joints
Wind Rating = 69 MPH with full setback.

Mud Pumps

Two each, 750 horsepower Gardner Denver PZ-8 Triplex powered by One each per pump Caterpillar D398 providing 975 continuous Horsepower per pump. These pumps can be fitted with 6 inch liner Equals 2385 psi at 2.938 gpm and 5-1/2 inch liners = 2843 psi at 2.468 gpm with a maximum spm of 140. These pumps are precharged by Mission Magnum 5" x 6" centrifugal pumps. The pumps are also equipped with K20-5000 pulsation dampners.

Rotary Table

Continental Emsco 17-1/2" Model T – 1750. Complete with type CU Bowl and 1902 inserts for 7", 9-5/8" and 13-3/8" casing.
Solid and split master bushings.

Travelling Equipment

The block and Hook assembly is a McKissick 200 ton block
With a 150 ton BJ unimatic hook with 4 x 30" sheaves.

Kelly Spinner

One each International Air Model with Right and Left hand operation
With 1800 ft/lbs torque and 150 RPM free spin.

Standpipe and Hose

The Rig is equipped with a 4" x 3,000 psi Standpipe and a 55" gate
By 5,000 psi working pressure Kelly hose.

Swivel

One each Continental Emsco Model 300lb rated at 300 Tons.

Mud Circulating and Treatment Equipment

Mud Tanks

Two each 40ft length x 10ft width x 8ft height with a total surface
Volume capacity of 800 bbls.

One each 60bbls pill tank
One each 50bbls trip tank.

Mixing Pumps

Two each 5" x 6" Mission Magnum centrifugal pumps

Mud Agitators

Three each Brandt Model A – 10 powered by 10 hp electric motors.

Shale Shakers

Not available in the day rate but could be provided as an extra rental
Item at cost plus handling fee.

De-Sander
One each Brandt Model ST2 = 2 x 10" cones. Powered by a 75 HP Electric Motor and fed by a 5" x 6" Mission Magnum centrifugal pump.

De-Silter
One each Brandt Model SE12=14" cones. Powered by a 75 HP Electric motor and fed by a 5" x 6" Mission Magnum centrifugal Pump.

De-Gasser
One each Swaco vacuum type degasser
One each poorboy type gas buster.

Well Control Equipment

BOP's
One each 13-5/8" x 5,000 psi Schaffer Annular.
One each 13-5/8" x 5,000 psi Schaffer double ram preventer C/w 7", 5-1/2", 4-1/2", 3-1/2", 2-7/8" and CSO Rams.

Accumulator
One each Koomey Type 80 x 200 gallon accumulator. 20 cylindrical Bottles. 2 x 20ft hydraulic line extension racks. Equipped with fail-Safe pneumatic pressure reducing and regulating Valves.

Drilling Spools
One each 13-5/8" x 13-5/8" x 5,000 psi c/w 2-1/16" x 5,000 psi Kill line and 3-1/8" x 5,000 psi Choke line outlet.

Double Studded Adapters
One each 13-5/8" 5,000# x 13-5/8" x 3,000#
One each 13-5/8" 5,000# x 11" x 3,000#.
One each 13-5/8" 5,000# x 11' x 5,000#
One each 13-5/8" 5,000# x 7-1/16" 5,000#

Choke / Kill Manifold
One each Cameron Type "F" 3-1/8" and 2-1/16" 3,000/5,000 psi Valves. Swaco super remote choke. Cameron manual adjustable choke. Cameron remote hydraulic HCR valve. Coflex flexible choke hose.

Kill/Choke Lines
One each 2-1/16" x 5,000# Kill line.
One each 3-1/8" x 5,000# Choke line.

Kelly Cocks / Safety Valves
One each Hydril Upper and Lower Kelly Guards
One each Omsco 4" IF and 3-1/2"IF Safety Valves
One each Gray 4" IF and 3-1/2" IF String type BOP

Kelly and Accessories

Kelly
Two each Drilco 5-1/4"hex c/w 4-1/2"IF connections
Two each Drilco 3-1/2"hex c/w 3-1/2"IF connections

Kelly Bushings

One each Varco 17-1/2"HDS Bushing to suit 5-1/4"and
3-1/2"hex kelly.

Drill Pipe

98 joints Premium, Range 2, Grade "E" 16.6 lbs/ft
c/w 4"IF connections.
176 joints Premium Range 2, Grade "S"16.6lbs/ft
c/w 4"IF connections
24 Joints Premium, Range 2, HWDP 40lbs/ft
c/w 4"IF connections

NOTE:
3-1/2"Drill pipe and 4-3/4"Drill Collars are not available in the Dayrate or in our Inventory but can be obtained as an extra rental item from Tasman Oil Tools.

Drill Collars and Subs.

Collars
Eight joints of 8"spiral collars c/w 6-5/8"Reg. Connections.
Fourteen joints of 6-1/4"spiral collars c/w 4"IF connections.

Subs
We carry a very large assortment of various subs to all of our Drilling tools to drill 17-1/2", 14-3/4", 12-1/4", 9-7/8", 8-1/2", 6-3/4", 6" and 5-7/8" hole.

Elevators, Slips and Tongs

Elevators
Two each sets of 4-1/2"x 18 degree x 250 ton BJ type MGG
Drill pipe elevators.
One each set of 13-3/8", 9-5/8", 7"and 4-1/2"BJ 150 ton SXL Side door casing elevators.

One each set of 13-3/8", 9-5/8", 7"and 4-1/2"single joint Casing elevators.

Slips
Two each sets of Varco DC-s slips for the 8"and 6-1/4" Drill Collars.
Two each sets of Varco SDML slips for the 4-1/2" Drill Pipe.

Tongs
Two each BJ Type "B"short lever with jaws from 3-1/2" Up to 13-3/8".

Deviation Instrument

Deviation Instrument
One each Totco 1-5/16"Go devil deviation recorder c/w 0>7 degrees and 0 > 15 degrees recorder clocks.

Wireline Unit

One each Hydraulically driven Mathey traveller unit fitted With 8,000ft of .092"wireline c/w sinker bars and overshot.

Fishing Tools- shared with rig 246

One each 6-1/4"Bowen type "Z"Fishing Jars.
One each 6-1/4"Bowen Bumper Sub c/w 18"stroke.
One each 9-5/8", 8-1/8",
Bowen series 150 overshots c/w all grapples and Controls to catch all contractors drilling tools.
One each 9-5/8"x 15-1/8"oversize lip guide.
One each 8-1/8"x 11"oversize lip guide.
One each 9-5/8"x 36"L overshot extension.
One each 8-1/8"x 36"L overshot extension.

Welding Equipment

One each Lincoln Model K-300 amp welding machine Powered by a diesel engine c/w a full assortment of Associated welding and cutting apparatus.

Drilling Instruments

One each Martin Decker Automatic Driller.
One each Martin Decker four pen Drilling Recorder.
One each Martin Decker Flow Show System.
One each Martin Decker PVT System.

One each Martin Decker Weight Indicator System.
One each Seiger Gas Detection Control System.
One each Swaco Shut in pressure control panel
C/w stroke counters.

Lighting

One lot of Allen Bradley and Northern Rig lights fully
Sealed and gas proof.

Fuel and Water Storage

Fuel
One each 20,000 litres capacity cylindrical tank.
(Fully Bunded)

Water
One each 500 bbls capacity cylindrical Tank c/w a
3"x 4"mission centrifugal transfer pump power with
a 20 hp electric motor.

Drilling Line

One each 3,500ft spool of British Wire Rope IPS x 6 x 19
Construction with IWRC.

Air Hoist

One each Force Five series Model FA 2.5 MR x 2.5 ton capacity
Certified man riding air winch.

Dog House

One each 20ft x 8ft x 8ft steel construction building connected
To substructure and resting on head ache stand;
Doghouse contains Koomey BOP remote control, Martin
Decker pen Recorder, Drillers Knowledge Box, Gas detection
Monitoring system and tool shadow board. The building
Has two points of entry and exists.

Water Transfer Equipment

Pump
One each 5"x 6" Gradner Denver duplex, Model FGF – XGR
Powered by 50 HP diesel engine with a maximum output
Capacity of 160 gpm.

Water Line
One each spool containing 500 meters x 2"quick and easy
Lay flexi line.

Mud Saver
One each Oteco mud bucket fitted with 4-1/2”or 3-1/2” End seals.

Safety Clamp
One each set Varco type MP-R to suit 8”and 6-1/4”drill Collars.
One each set Varco type MP-R to suit 4-3/4”drill collars And other small tools.

Elevator Links
One each set 2-3/4”x 108”with 250 ton rating.
One each set 3-1/2”x 108”with 350 ton rating.

Drill Pipe Spinner
One each Varco SSW-30 Hydraulically operated unit Equipped for 3-1/2”and 4-1/2”drillpipe.

Circulating Hose
One each Gates 60 foot C13 circulating and cementing Hose c/w 2”I.D. and 5,000 psi working pressure.

Electrical Generators
Two each Cat SR4 Rated at 310 KW. Each powered by One each Cat. 3408 engine.

Air Compressors
Three each Ingersoll – Rand Reciprocating Type with a Output capacity of 150 cfpm.

Tool House
One each 40ft long x 8ft wide x 8ft high warehouse and Mechanic and Electrician shop.

Camp Accommodation
One each 40ft L x 8ft W x 8ft H Companyman
skid unit c/w washroom.—**rental charge to operator**
One each 40ft L x 8ft W x 8ft H Toolpushers office
And accommodation skid unit.---Parker
One each 20ft L x 8ft W x 8ft H Ablution skid unit- **Rental charge to operator**
One each 20ft L x 8ft W x 8ft H Smoko / Dry Change
Room skid unit.---**Rental Carge back to operator**

Safety Equipment

One lot Plastic safety hard hats to be worn by all employees
And Visitors on location at all times.
One lot Safety eye protection glasses to be worn by all
Employees and Visitors on location at all times.
One lot steel toe safety footwear to be worn by all employees
On location at all times.
One lot Wet Weather gear supplied to all employees working
On the Rig.
One lot Parker Coveralls and Hand gloves supplied to all
Employees working on the Rig.
One each Chemical shower located mud mixing area.
Two each eye wash stations located at mud mixing area
And Doghouse.
Two each First Aid kits located at Doghouse and Toolpusher
Office.
One each stretcher located at Toolpusher Office.
Four each Scott Air Pak breathing apparatus.
Six each 20kgs Ansul Fire extinguisher.
Two each 25kgs CO2 Fire extinguishers.
One each hand held gas detector.
One each Parker Drilling Company Monkey Board
Lifeline Restraint System located at the Monkey Board.
One each Parker Drilling Company Lad Safe Derrick
Climbing device.
Five each DBI all purpose Safety Harness.
One each Uniscape Derrick device for safe Exit from derrick
One each air horn warning signal alarm system.
One each Ferno communication system and Drillers console
To Monkey Board.
One lot Safety Warning Signs.
One each Wind direction indicator located at the crown.

Pipe Racks and Walkways.

Five sets triangular tumbler type piperacks 25ft long x 3ft high
Two each 20ft long x 4ft wide x 3ft high c/w steel deck.

Four Point Communication System (Optional)

The system is not available on this Rig. The only communication System available is the Ferno Two way system between the Driller And the Derrickman at the monkey board.

Additional Equipment

Computer System
This 466DX 2/T is located in the Toolpushers Office and is Loaded with Windows 95, with Office 97 and the Patent Parker PDS program which consists of Daily drilling report Information (IADC), Well Control, Current Well Parameters, Well information, Formation Testing, Pressure control Forms. Preventative Maintenance, procedures, schedule, analysis and Equipment usage's. Safety, accident reports, incident investigation Reports, job safety analysis, weekly crew safety meetings. Drilling Calculations, oilfield formulas.

Drilling Equipment Maintenance Program

This system is incorporated into the Parker Drilling 'PDS' Computer program.

RIG 252

DRILLING EQUIPMENT

Bit Subs

Parker Drilling can provide all the bit subs required for normal Drilling operations as per the provided drilling program.

X/O Subs

Parker Drilling have a very good X/O sub inventory on the Rig And also have access to all the X/O subs in the Rental Tool Co. Inventory.

Stabilisers 5-7/8”

These are not available in the Dayrate but could be provided As a rental item from Austoil or Tasman.

Drill Collars

Please refer to rig inventory.

Manual Tongs Dies

Please refer to rig inventory.

3-1/2”Drill Pipe

This pipe is not availabel in the Rig inventory but could be supplied As an extra rental item from Tasman Oilfield supplies.

Drill Pipe and Drill Collar Slips

Please refer to Rig Inventory

Proposed Crewing Arrangements

Rig 252

Two Toolpushers

Four Drillers

Two Assistant Drillers

Four Derrickman

Four Lead Floorman

Eight Floor man

Four Leasehands

Two Mechanics

One Electrician (As required)

Two Cooks/Janitors

Each Crew Will Consist of:

One Superintendent
One Driller
One Assistant Driller
One Derrickman
One Lead Floorman
Two Floorman
One Leasehand

Personnel Living On site 24 Hours a Day

One Toolpusher
One Mechanic (Dayshift on call 24 hours per day)
One Electrician (as required)

All personnel working ONE week on shift, ONE weeks off Shift schedule.

Casual Labour over and above crewing arrangements, Requested by Operator at cost, plus 15% Handling Charge.

One Cook/Janitor working two weeks on shift, two weeks Off shift – 12 hours per day.

RATES OF REMUNERATION

Mobilisation:

USD $8,550.00 (95% of Day Rate and cost plus on the trucks and cranes. Plus Handling Fee Of 5%).

DeMobilisation

USD $8,550.00. All Mob / Demob and Inter Well Rig moves will be 95% of the day rate. Cost plus on the trucks and cranes, plus handling fee of 5%.

Operating Rate With Drill Pipe

USD $ 9,000.00 With Drill Pipe.

Operating Rate Without Drill Pipe.

USD $ 8,550.00 Without Drill Pipe (95%)

Repair Rate.

USD $ 7,650 Repair Rate (85%). Repair Rate First 24 hours in any 30 day period Commencing from Spud date (85%) there after (nil)

Mark Up: Percentage handling charge on reimbursables including items provided

USD	**Cost per Order % Handling Charge**
0 – 10,000	15%
10,000 – 50,000	10%
50,000 and above	05%

Operations Time Analysis

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Rig: Parker Rig 252

	Total Hrs	% of Total
Drill		
Drilling Ahead w/ Connections	311.00	32.4
Drilling - Rotating	131.50	13.7
Drilling - Rotating	30.50	3.2
Circulate/Condition Mud	22.50	2.3
Drilling - Sliding	22.00	2.3
Make up-break out BHA	17.50	1.8
Reaming/Underreaming	2.00	0.2
Washing Down	2.00	0.2
Running Survey Tools	1.50	0.2
Directional Work	1.00	0.1
Drilling - Sliding	1.00	0.1
Flow Check	0.50	0.1
Total for Drill:	543.00	56.6
Trip		
Tripping Out	44.50	4.6
Tripping in	40.00	4.2
Pick up DP	12.00	1.3
Wiper Trip	8.50	0.9
Short Trip	5.00	0.5
Tripping Out BHA	5.00	0.5
Tripping BHA	4.00	0.4
Total for Trip:	119.00	12.4
Mobilize/Demob		
Rigging Up	109.50	11.4
Rigging Down	4.50	0.5
Total for Mobilize/Demob:	114.00	11.9
BOP Ops		
BOP Testing	23.00	2.4
BOP Nipple Down	19.00	2.0
BOP Nipple Up	12.50	1.3
Total for BOP Ops:	54.50	5.7
Misc Other		
Lay dn drill pipe	15.00	1.6
Welding Operations	9.50	1.0
Rig Service	7.00	0.7
Other Activity	5.50	0.6
Step rate Test	2.50	0.3
Cut and Slip Drill Line	2.00	0.2
Total for Misc Other:	41.50	4.3
Problem Time		

Operations Time Analysis

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Rig: Parker Rig 252

	Total Hrs	% of Total
Waiting on Orders	30.00	3.1
Rig Repairs	5.00	0.5
Service Company Repairs	1.00	0.1
Total for Problem Time:	36.00	3.8
Cementing		
Waiting On Cement	13.50	1.4
Primary Cement Operations	3.50	0.4
Cement Plug Operations	3.00	0.3
Drilling Cement/Shoe	2.50	0.3
Secondary Cement Operations	0.50	0.1
Total for Cementing:	23.00	2.4
Casing		
Running Casing	19.00	2.0
Total for Casing:	19.00	2.0
Evaluate		
Wireline Logging	10.00	1.0
Total for Evaluate:	10.00	1.0
Total Elapsed Time for Well:	960.00 hrs.	
Total Non-Productive Time for Well:	36.50 hrs.	3.8%
Total Productive Time for Well:	923.50 hrs.	96.2%

Operations Time Analysis

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Rig: Parker Rig 252

	Total Hrs	% of Total
Drill		
Drilling - Rotating	77.00	15.6
Drilling - Rotating	60.50	12.3
Drilling Ahead w/ Connections	53.50	10.9
Drilling - Sliding	50.50	10.2
Circulate/Condition Mud	22.50	4.6
Drilling - Sliding	18.00	3.7
Flow Check	3.50	0.7
Reaming/Underreaming	2.50	0.5
Washing Down	2.00	0.4
Total for Drill:	290.00	58.8
Trip		
Tripping in	36.00	7.3
Tripping Out	28.00	5.7
Tripping BHA	9.00	1.8
Tripping Out BHA	7.00	1.4
Wiper Trip	5.50	1.1
Short Trip	2.00	0.4
Total for Trip:	87.50	17.7
Misc Other		
Lay dn drill pipe	20.50	4.2
Other Activity	10.50	2.1
Rig Service	3.50	0.7
Cut and Slip Drill Line	2.00	0.4
Total for Misc Other:	36.50	7.4
Evaluate		
Wireline Logging	18.50	3.8
Formation Interval Test	0.50	0.1
Total for Evaluate:	19.00	3.9
Mobilize/Demob		
Rigging Down	19.00	3.9
Total for Mobilize/Demob:	19.00	3.9
Problem Time		
Rig Repairs	7.00	1.4
Waiting on Orders	6.00	1.2
Service Company Repairs	2.50	0.5
Stuck Pipe Operations	0.50	0.1
Total for Problem Time:	16.00	3.2
BOP Ops		
BOP Testing	7.50	1.5

Operations Time Analysis

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Rig: Parker Rig 252

	Total Hrs	% of Total
BOP Nipple Down	6.50	1.3
Other BOP Operations	1.00	0.2
Total for BOP Ops:	15.00	3.0
Abandonment		
Plugging Operations	5.50	1.1
Total for Abandonment:	5.50	1.1
Cementing		
Cement Plug Operations	2.00	0.4
Drilling Cement/Shoe	2.00	0.4
Total for Cementing:	4.00	0.8
Casing		
Pressure Testing	0.50	0.1
Total for Casing:	0.50	0.1
Total Elapsed Time for Well:	493.00 hrs.	
Total Non-Productive Time for Well:	16.00 hrs.	3.2%
Total Productive Time for Well:	477.00 hrs.	96.8%

Operations Activity Summary

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Rpt. No.	Date/Time From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product
1	30-Sep-05 6:00	6:00	24	0.0	RIGU	Continue rigging up	
2	01-Oct-05 6:00	18:00	12		RIGU	Rig move	
3	02-Oct-05 6:00	18:00	12	0.0	RIGU	Rig move	
4	03-Oct-05 6:00	6:00	24	0.0	RIGU	Continue rigging up. Break tour. Filled mud tanks with processed water from production facilities (Baroid sampled water OK for spud mud).	
5	04-Oct-05 6:00	6:00	24	0.0	RIGU	Continue rigging up.	
6	05-Oct-05 6:00	9:30	3.5	0.0	RIGU	install rat hole ,r/u d-tank , mix spud mud	
	05-Oct-05 9:30	12:00	2.5	22.0	BHA	p/u 8" bha to 22meter's	
	05-Oct-05 12:00	12:30	0.5	22.0	RIGU	welding in 2" nipple and valve at grd level on riser	x
	05-Oct-05 12:30	13:00	0.5	33.0	BHA	finished p/u 8" bha tag at 33 meter's	
	05-Oct-05 13:00	14:00	1	33.0	REPR	working on rotary tong's	x
	05-Oct-05 14:00	17:00	3	43.0	DRIL	drill from 33 m to 43m	
	05-Oct-05 17:00	17:30	0.5	43.0	SURV	run wire line survey at 33 m 1 degree	
	05-Oct-05 17:30	23:30	6	100.0	DRIL	drill from 43m to 100 m	
	05-Oct-05 23:30	0:00	0.5	100.0	SURV	run wire line survey at 90m 1 degree	
	06-Oct-05 0:00	6:00	6	155.0	DRIL	drill from 100 m to 155 m at 0600 am. prepare to run wire line survey at 145m 1.0 degree	
7	06-Oct-05 6:00	12:30	6.5	200.0	DRIL	drill from 155m to 200 m	
	06-Oct-05 12:30	13:00	0.5	195.0	SURV	run wire line survey at 195m 1.0 degree	
	06-Oct-05 13:00	13:30	0.5	200.0	CIRC	circ btm's up at 200 m while build slug	
	06-Oct-05 13:30	15:30	2	200.0	TRPO	slug d.p. and pooh for directional assembly	
	06-Oct-05 15:30	18:00	2.5	200.0	BHA	p/u directional assembly ,and orient same	
	06-Oct-05 18:00	19:00	1	200.0	REPS	mwd had problem.s spacing out mwd tool with proper compression down time on halco	x
	06-Oct-05 19:00	20:30	1.5	200.0	TRPI	continue tih with bha from derrick	
	06-Oct-05 20:30	21:30	1	200.0	PUDP	p/u 10 joint's of hwdp. from pipe rack and wash to btm. at 200 m took survey at 171m = 1.59 degree's 306 azmt.	
	06-Oct-05 21:30	6:00	8.5	302.0	DRIL	drill from 200 m to 302m at 0600 am.	
8	07-Oct-05 6:00	6:00	24		DRIL	drill from 302 m to 643m at 0600 am.	
9	08-Oct-05 6:00	7:30	1.5	659.0	DRIL	drill from 643m to 659m csg point	
	08-Oct-05 7:30	8:30	1	659.0	CIRC	circ sweep surface to surface , slug dp	
	08-Oct-05 8:30	12:30	4	659.0	WIPE	short trip up to csg shoe had excess drag for 12 stand's	
	08-Oct-05 12:30	14:30	2	659.0	WIPE	tih to 659m	
	08-Oct-05 14:30	15:30	1	659.0	CIRC	circ hole clean slug d.p.	
	08-Oct-05 15:30	19:00	3.5	659.0	TRPO	pooh l/d directional tool's	
	08-Oct-05 19:00	20:00	1	659.0	SERV	service rig ,while r/u csg tool's , held jsa before running csg with all hand's	
	08-Oct-05 20:00	20:30	0.5	659.0	CASE	run two joint;s of 9 5/8" csg and level derrick	
	08-Oct-05 20:30	1:30	5	659.0	CASE	run 55 joint's of 9 5/8" 53.5 p-110 csg to 652meter's	
	09-Oct-05 1:30	2:00	0.5	659.0	CIRC	r/u plug container and circ. csg cap/	
	09-Oct-05 2:00	3:30	1.5	659.0	CMTP	test line's to 3000 psi , pump 60 bbl's wtr spacer. followed with 420 sk's class -a cmt at 11.8 ppg yield= 2.56 wtr= 15.29 slurry volume =191 bbl's plus 158 sk's of class -g cmt at 15.6 ppg yield =1.17 wtr=5.05 slurry volume 33 bbl's	
	09-Oct-05 3:30	4:00	0.5	659.0	CIRC	displace cmt plug at 6.5 bpm had full return's seen only 12 bbl's water back no ctm. job bump plug with 1500 psi cmt in place at 0400 am.	
	09-Oct-05 4:00	4:30	0.5	659.0	CMTS	p/u 1" stinger to 60 feet and cmt with 20 sk's class -g at 15.6 ppg slurry volume of 4 bbl;s 67 feet cap.	
	09-Oct-05 4:30	6:00	1.5	659.0	WOC	woc while prepare bop's to be nippled up	

Operations Activity Summary

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Rpt. No.	Date/Time From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product
10	09-Oct-05 6:00	9:30	3.5	659.0	WOC	attempt to back out landing collar backed out 2" and started backing out down hole	
	09-Oct-05 9:30	12:00	2.5	659.0	BOPNU	made up csg to 10000 and test same to 1500 psi failed 250 psi and leaking at landing collar	
	09-Oct-05 12:00	16:30	4.5	659.0	WELD	cut landing jt. below collar l/d same and cut and remove 13 3/8" riser and removed same , dress off csg top install sow head	
	09-Oct-05 16:30	21:30	5	659.0	WELD	cooling off sow head	
	09-Oct-05 21:30	6:00	8.5	659.0	BOPNU	n/u bop's	
11	10-Oct-05 6:00	7:00	1	659.0	BOPNU	finished n/u bop's ,function test bop's	
	10-Oct-05 7:00	12:00	5	659.0	BOPT	attempt to test csg to 1500 psi bop camlock below cross flange leaking tighten same twice no change leaking started testing choke manifold while changing out ring gasket and bop clamp	
	10-Oct-05 12:00	19:00	7	659.0	BOPT	test csg to 1500 psi ,test all ram's , line's , valve's to 250/5000 test hydrill to 250 / 2500 psi test alll surface equip to 250 /5000 psi r/d test equip.note =camlock clamp's causing leak's	
	10-Oct-05 19:00	21:30	2.5	659.0	BHA	n/u bell nipple , lay down 3- 8" drill collar's & 6-6 1/2 " d.c.'s from derrick	
	10-Oct-05 21:30	2:00	4.5	659.0	BHA	p/u 8 1/2" directional assembly , orient same , and tih tag cmt at 639	
	11-Oct-05 2:00	3:30	1.5	643.0	CMTD	drill cmt float collar , found bop's turned,choke line against sub base	
	11-Oct-05 3:30	4:30	1	643.0	RIGU	realine flow line ; install double line;s on bop's , test bop's and csg to 1500 psi held ok	
	11-Oct-05 4:30	5:30	1	662.0	CMTD	drill shoe track to 652m , drill cmt wash out rat hole and 3 meter's of new hole to 662 meter's	
	11-Oct-05 5:30	6:00	0.5	662.0	CIRC	circ. btm's up, and r/u test line's test form with 8.8 ppg to 310 psi equiv. to 11.5 ppg	
12	11-Oct-05 6:00	6:00	24	986.0	DRIL	drill from 659 m to 986 meter's at 0600 am.	
13	12-Oct-05 6:00	14:00	8	1087.0	DRIL	drill from 986 meter's to 1087 m	
	12-Oct-05 14:00	14:30	0.5	1087.0	SERV	service rig	
	12-Oct-05 14:30	6:00	15.5	1270.0	DRIL	drill from 1087 m to 1270 meter's at 0600 am.	
14	13-Oct-05 6:00	7:00	1	1279.0	DRIL	drill from 1270 m to 1279 m	
	13-Oct-05 7:00	8:00	1	1279.0	CIRC	circ hi vis sweep surface to surface ,flow check and ,slug d.p.	
	13-Oct-05 8:00	9:30	1.5	1279.0	TRPO	pooh to csg shoe from 1279 m up to 650 m no excess drag	
	13-Oct-05 9:30	10:00	0.5	1279.0	SERV	service rig	
	13-Oct-05 10:00	11:30	1.5	1279.0	TRPI	tih to 1279 meter's no excess drag ,& no fill	
	13-Oct-05 11:30	6:00	18.5	1485.0	DRIL	drill from 1279 m to 1340 m mud losses 30 bbl's /hr. pumped 25 bbl sweep losses down to 2 bbl's / hr.continue drilling from 1340 m to 1485 m at 0600 am.	
15	14-Oct-05 6:00	17:00	11	1594.0	DRIL	drill from 1485 m to 1594 m	
	14-Oct-05 17:00	17:30	0.5	1594.0	SERV	service rig	
	14-Oct-05 17:30	6:00	12.5	1700.0	DRIL	drill from 1594 m to 1700 meter's at 0600 am.	
16	15-Oct-05 6:00	14:30	8.5	1787.0	DRIL	drill from 1700 m to 1787 m	
	15-Oct-05 14:30	15:00	0.5	1787.0	SERV	service rig	
	15-Oct-05 15:00	18:30	3.5	1824.0	DRIL	drill from 1787 m to 1824 m drag increased pipe torqued up, drop down and rotate free at 1824m pump sweep	
	15-Oct-05 18:30	19:00	0.5	1824.0	CIRC	circ hole clean ,flow check ,slug d.p.	
	15-Oct-05 19:00	22:30	3.5	1824.0	STRIP	short trip up to 1240 m tih max drag 15 k 1- meter fill on btm max trip gas 11 unit's no mud cut	
	15-Oct-05 22:30	6:00	7.5		DRIL	drill from 1824 m to 1915 m at 0600 am.	
17	16-Oct-05 6:00	17:00	11	2005.0	DRIL	drill from 1915 m to 2005 m	
	16-Oct-05 17:00	17:30	0.5	2005.0	SERV	service rig	

Operations Activity Summary

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Rpt. No.	Date/Time From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product
17	16-Oct-05 17:30	6:00	12.5	2130.0	DRIL	drill from 2005 m to 2130 m at 0600 am.	
18	17-Oct-05 6:00	3:00	21	2400.0	DRIL	drill from 2130 m to 2400 m csg point	
	18-Oct-05 3:00	4:30	1.5	2400.0	CIRC	pump hi- vis sweep surface to surface , flow check , slug d.p.	
	18-Oct-05 4:30	6:00	1.5	2400.0	STRIP	short trip to csg shoe at 652 m	
19	18-Oct-05 6:00	9:00	3	2400.0	TRPO	pooh to 650 m no excess drag hole took proper fill	
	18-Oct-05 9:00	10:00	1	2400.0	CUTDL	slip and cut 127 feet of drill line and rig service	
	18-Oct-05 10:00	14:00	4	2400.0	TRPI	tih filling dp. every 30 stand's to 23841/2 meter's tag fill	
	18-Oct-05 14:00	14:30	0.5	2400.0	CIRC	wash and ream from 2384 m to 2400 m	
	18-Oct-05 14:30	16:00	1.5	2400.0	CIRC	pump 15 bbl's of hi-vis sweep surface to surface , flow check , spot 25 bbl,s 10.0 ppg pill on btm , slug d.p.	
	18-Oct-05 16:00	21:30	5.5	2400.0	TRPO	pooh to directional assembly	
	18-Oct-05 21:30	22:30	1	2400.0	BHA	lay down directional assembly, and mwd tool's	
	18-Oct-05 22:30	23:00	0.5	2400.0	RIGU	spot offshore schl. unit through side of derrick, rigging up with one schl hand , logging crew arrived at 2330 hr's	
	18-Oct-05 23:00	2:30	3.5	2400.0	RIGU	r/u schl tool's pex- hria- sonic	
	19-Oct-05 2:30	6:00	3.5	2400.0	LOG	tih with pex- hr[a -sonic tag btm. at 2400 m run repeat tih tag btm logging up from 2399 m	
20	19-Oct-05 6:00	8:30	2.5	2400.0	RIGD	finished pooh with logging tool's , layed down and load out same	
	19-Oct-05 8:30	9:30	1	2400.0	BHA	p/u new bha	
	19-Oct-05 9:30	10:30	1	2400.0	TRPI	tih to 652 m fill dp. every 30 stand's	
	19-Oct-05 10:30	11:00	0.5	2400.0	CIRC	circ. btm's up at 652'	
	19-Oct-05 11:00	15:30	4.5	2400.0	TRPI	tih circ 20 min's every 30 stand'sto 2384 m tag fill	
	19-Oct-05 15:30	16:00	0.5	2400.0	CIRC	wash and ream from 2384m to 2400	
	19-Oct-05 16:00	16:30	0.5	2403.0	DRIL	drill from 2400 to 2403 m to space out csg	
	19-Oct-05 16:30	17:30	1	2403.0	CIRC	circ hi - vis sweep surface to surface , spot 25 bbl;s of 11.0 ppg mud on btm , slug dp	
	19-Oct-05 17:30	2:30	9	2403.0	LDDP	pooh laying down d.p.to bha	
	20-Oct-05 2:30	3:30	1	2403.0	BHA	driller broke out bit , and rotated off bit pdc breaker lock released and bit fell in hole on top of blind ram's , open pipe ram door above blind ram's and recovered bit ,down time	
	20-Oct-05 3:30	5:00	1.5	2403.0	BOPT	finished l/d bha , pull wear bushing	
	20-Oct-05 5:00	6:00	1	2403.0	BOPT	p/u test plug and test bonnet seal's to 1500 psi ,down time	
21	20-Oct-05 6:00	7:30	1.5	2403.0	RIGU	held prejob safety meeting and r/u csg tool's	
	20-Oct-05 7:30	21:00	13.5	2403.0	CASE	run 204 joint's of 29 # L -80 butt. csg to 2384 m tag up wash from 2384 m to 2395 m would not wash past 2395 m	
	20-Oct-05 21:00	23:00	2	2395.0	RIGD	remove circ swege and install cmt retainer and line's test line's to 4000 psi release btm plug	
	20-Oct-05 23:00	1:00	2	2395.0	CMTP	pump 60 bbl's of water for spacer plus 200 sk's of cl-g at 11.8 ppg yield at 2.56 mix wtr = 15.29 slurry volume = 88 bbl's plus 850 sk's of cl-g at 15.6 ppg yield at 1.17 mix wtr = 5.05 slurry volume = 170	
	21-Oct-05 1:00	2:30	1.5	2395.0	CMTPL	diisplace plug with 280 bbl's of sbm and 20 bbl's of water bump plug with 2200 psi ,bled down pressure float's held ok	
	21-Oct-05 2:30	6:00	3.5	2395.0	BOPND	n/d flow line bell nipple choke & kill line'swhile waiting on cmt	
22	21-Oct-05 6:00	14:30	8.5	2403.0	WOC	while waiting on cmt , changed out liner's in both mud pump's, off loaded 3 1/2" rental's and d.p. washing out mud tank's , clearing way behind mud tank's to run pipe line	
	21-Oct-05 14:30	17:30	3	2403.0	BOPND	r/d plug container and line's ,r/u pick up line's and latch on to bop's n/d flange at a-section set csg slip's with 200 k made rough cut l/dexcess csg	
	21-Oct-05 17:30	6:00	12.5	2403.0	BOPND	make final cut on 7" dress off same, n/d two adaptor spool's and n/u b section and bop's packed and tested well head to 5000 psi , cleaning mud pit's , open bop's changing out	

Operations Activity Summary

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Rpt. No.	Date/Time From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product
						ram's from 4 1/2" to 3 1/2" n/u bell nipple	
23	22-Oct-05 6:00	6:30	0.5	2403.0	BOPNU	finished n/u bell nipple & flow line	
	22-Oct-05 6:30	9:30	3	2403.0	RIGU	changed out 4 1/2" kelly for 3 1/2" kelly	
	22-Oct-05 9:30	10:00	0.5	2403.0	BOPT	p/u test equip.	
	22-Oct-05 10:00	16:00	6	2403.0	BOPT	test annular to 250/ 3000 , test ram's , valve's and line's to bop's and choke manifold to 250 /5000 psi ,test all surface equip. to 250/ 5000 psi	
	22-Oct-05 16:00	18:00	2	2403.0	BHA	p/u directional assembly orient and test same	
	22-Oct-05 18:00	2:30	8.5	2403.0	PUDP	p/u hwdp jar's and drill pipe from pipe rack to 1932 m tighten kelly and broke circ	
	23-Oct-05 2:30	3:30	1	2403.0	SERV	slip and cut 75 feet of drill line and service rig	
	23-Oct-05 3:30	6:00	2.5	2403.0	PUDP	continue tih from 1932 m to 2379 m tag cmt , break circ , test csg to 2000 psi	
24	23-Oct-05 6:00	7:00	1	2403.0	BOPT	test 7" 29 # L-80 butt csg. to 2000 psi for 30 min's	
	23-Oct-05 7:00	9:00	2	2406.0	SRT	drill shoe track to 2395 and wash out rat hole , drill 3 meter's of new hole to 2406 m circ. hole clean	
	23-Oct-05 9:00	9:30	0.5	2406.0	SRT	test formation with 8.9 ppg to 1030 equiv to 11.5 ppg 7562 tvd ft.	
	23-Oct-05 9:30	10:30	1	2409.0	DRIL	drill from 2406 meter's to 2409 m	
	23-Oct-05 10:30	11:30	1	2409.0	OTHER	relevel derrick to center pipe in rotary	
	23-Oct-05 11:30	6:00	18.5	2555.0	DRIL	drill from 2409 m to 2555 m at 0600 am.	
25	24-Oct-05 6:00	6:00	24	2740.0	DRIL	drill from 2555 meter's to 2740 meter's at 0600 am.	
26	25-Oct-05 6:00	0:30	18.5	2787.0	DRIL	Continue to drill 6" hole sliding and rotating .GPM 238, WOB 5/10k, Torque 5/10000 ft/lbs, ROP 1-2m/hr .Hard sandstone stringers unable to slide through .Hole getting sticky.Pump sweeps as required	
	26-Oct-05 0:30	2:00	1.5	2787.0	DRIL	Pump 10 bbls high vis and cirulate clean prior to wiper trip.Take survey	
	26-Oct-05 2:00	3:00	1	2380.0	TRPO	Flow check (static) TRPO f/- 2877m to 2380m no over pull hole in good condition.	
	26-Oct-05 3:00	3:30	0.5	2380.0	SERV	Rig service at 7" casing shoe.	
	26-Oct-05 3:30	4:30	1	2787.0	TRPI	TRPI to 2776m pick up kelly and wash down to 2787m no fill.	
	26-Oct-05 4:30	6:00	1.5	2788.0	DRIL	Continue to drill ahead sliding and rotating to 2788m .GPM 238, WOB 5-10k, Torque 5-9000 ft/lbs MW 8.5ppg.	
27	26-Oct-05 6:00	6:30	0.5	2789.0	DRILS	Continue drill Siding to 2789m.	
	26-Oct-05 6:30	9:30	3	2796.0	DRLR	Continue drill 6" hole rotating to 2796m	
	26-Oct-05 9:30	11:30	2	2802.0	DRILS	Contnue drill 6" hole sliding to 2802m start getting connection gas .increase mw 1 point to 8.6ppg	
	26-Oct-05 11:30	0:00	12.5	2826.0	DRILR	Continue drill 6" hole rotating to 2826m. ROP 1-1.5m/hr,GPM 238,	
	27-Oct-05 0:00	6:00	6	2833.0	DRILR	Continue drill 6"hole rotating to 2833m . ROP reduced to .5-1m/hr very hard cemented sandstones.GPM 238,Torque 6.5/7000 ft/bls,WOB 8-10k.back ground gaas 10-15 units.Pump high vis sweeps as required.	
28	27-Oct-05 6:00	8:00	2	2836.0	DRLR	Contnue to drill 6" hole rotating to 2836m	
	27-Oct-05 8:00	9:30	1.5	2838.0	DRILS	Dill 6" hole sliding to 2838m unable to slide hard formation.	
	27-Oct-05 9:30	16:00	6.5	2847.0	DRILR	Continue to drill 6" hole rotating to 2841m	
	27-Oct-05 16:00	20:30	4.5	2862.0	DRILS	Continue to drill 6 " hole sliding to 2862m	
	27-Oct-05 20:30	21:30	1	2862.0	OTHER	Sudden pressure loss in standpipe pressure reduced 1000 psi.Check pumps ok. All pressure transducers plugged up clean and pump up . Work string during operation, Test run pump pressure ok.	
	27-Oct-05 21:30	23:00	1.5	2868.0	DRILS	Continue to dril 6" hole sliding to 2868m	
	27-Oct-05 23:00	0:00	1	2871.0	DRILR	Drill 6" hole to 2871m. ROP2-4m/hr ,GPM 200. Torque 6-7000 ft/bls.	

Operations Activity Summary

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Rpt. No.	Date/Time From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product
28	28-Oct-05 0:00	2:30	2.5	2876.0	DRILR	Drill 6" hole rotating to 2876m	
	28-Oct-05 2:30	3:30	1	2877.0	DRLS	Drill 6" hole sliding to 2877m. unable to slide weight stacking up .	
	28-Oct-05 3:30	6:00	2.5	2880.0	DRILR	Continure to drill 6" hole to 2880m. GPM 195, WOB 5-12k, Torque 6-7000 ft/bls, rpm 80.Back ground gas 10-25 units.MW 8.6 ppg ,Vis 59. ROP 1-3m/hr. Pump kcl sweeps as required.	
29	28-Oct-05 6:00	7:30	1.5	2884.0	DRLR	Continue to drill 6" hole rotating to 2884m Pump sweeps as required	
	28-Oct-05 7:30	9:00	1.5	2886.0	DRILS	Continue to drill 6" hole sliding to 2886m. Unable to slide .	
	28-Oct-05 9:00	10:00	1	2891.0	DRILR	Continue to drill 6" hole rotating to 2891m.	
	28-Oct-05 10:00	12:00	2	2895.0	DRILS	Continue to drill 6" hole sliding to 2895m GPM 195, ROP 1-2m/hr. Pump sweeps as required	
	28-Oct-05 12:00	14:30	2.5	2903.0	DRILS	Continue drill 6" hole sliding to 2903m .GPM 195,ROP 1-2m/hr .surveys reflect unable to build or maintain angle.	
	28-Oct-05 14:30	16:30	2	2903.0	CIRC	Pump 15 bbls high vis sweep and circulate clean.	
	28-Oct-05 16:30	17:00	0.5	2903.0	FLOW	Flow check (static) Pump slug	
	28-Oct-05 17:00	23:00	6	218.0	TRPO	TRPO out to 7" casing shoe 2390m(static) Continue to TRPO to BHA 218m.	
	28-Oct-05 23:00	0:00	1	22.0	TOHBHA	TROHBHA to directional tools.	
	29-Oct-05 0:00	0:30	0.5	0.0	TOHBHA	Layout Top stabilizer , mlud motor and bit.	
	29-Oct-05 0:30	1:30	1	11.0	DIR	m/up new mud motor , m/up bit, Orientate tool face ok.	
	29-Oct-05 1:30	2:30	1	215.0	TIHBHA	TIHBHA to 215m .Conduct shallow pulse test with MWD ok.	
	29-Oct-05 2:30	6:00	3.5	1650.0	TRPI	Continue TRPI WITH 3 1/2 DP to 1650m	
30	29-Oct-05 6:00	7:00	1	2388.0	TRPI	Continue TRPI to 2388m .filling every 25 stds.	
	29-Oct-05 7:00	7:30	0.5	2388.0	SERV	Rig service	
	29-Oct-05 7:30	8:30	1	2877.0	TRPI	Continue TRPI to 2877m good hole no hang ups.	
	29-Oct-05 8:30	9:30	1	2903.0	WASH	Wash down f/-2877m to 2903m .1m fill	
	29-Oct-05 9:30	11:00	1.5	2903.0	OTHER	Take survey prior to drilling . No pulse signal indentified.Trouble shoot system , recycle pumps, change out transducers, change out link cable . no go. Unable to communicate to MWD tool.	
	29-Oct-05 11:00	18:00	7	281.0	TRPO	Flow check (static) pump slug TRPO. to 7" casing shoe.Flow check at 7" casing shoe (static). continue TRPO to BHA.	
	29-Oct-05 18:00	19:00	1	0.0	TOHBHA	Flow check at BHA. (static).TOHBHA. Lay out MWD pulsing assy.	
	29-Oct-05 19:00	20:00	1	0.0	OTHER	Install new MWDpulsing assy. Install new float.Orientate MWD.	
	29-Oct-05 20:00	21:30	1.5	235.0	TIHBHA	TIHBHA to 235m . Shallow test MWD. All systems operational	
	29-Oct-05 21:30	0:00	2.5	1358.0	TRPI	TRPI to 1358m filling pipe every 25 stds.	
	30-Oct-05 0:00	2:00	2	2378.0	TRPI	Continue TRPI to 7" casing shoe.	
	30-Oct-05 2:00	3:00	1	2378.0	CUTDL	Slip and cut 78ft drilling line . circulate well while slip and cutting drilling line.Install drill piipe screen when circulating	
	30-Oct-05 3:00	4:30	1.5	2378.0	TRPI	Continue TRPI to 2378m . no hang ups.	
	30-Oct-05 4:30	5:00	0.5	2903.0	WASH	Wash down f/- 2378m to 2903m. No fill .	
	30-Oct-05 5:00	6:00	1	2906.0	DRILS	Continue drill 6" hole sliding to 2906m. GPM 200, WOB 2-4k. ROP 6-8m/hr.	
31	30-Oct-05 6:00	6:00	24	2992.0	DRIL	drill from 2906 meter's to 2992 meter's at 0600 am.	
32	31-Oct-05 6:00	7:30	1.5	2995.0	DRILR	Continue drill 6" hole Rotating to 2995m	
	31-Oct-05 7:30	8:00	0.5	2993.0	DRILS	Contnue to drill 6" hole to 2996m sliding Very hard formation unable to make progress	
	31-Oct-05 8:00	10:00	2	3002.0	DRILR	Continue to drill 6" hole to 3002m Rotating.ROP 2-3m/hr	
	31-Oct-05 10:00	12:00	2	3005.0	DRILS	Continue to drill 6" hole to 3005m sliding .	

Operations Activity Summary

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Rpt. No.	Date/Time From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product
32	31-Oct-05 12:00	0:00	12	3047.0	DRILR	Continue drill 6" hole to 3047m rotating. GPM 202, WOB 5-12, SPM 125 = 2200psi. Torque 8-9000 ft/bls	
	01-Nov-05 0:00	6:00	6	3054.0	DRILR	Continue to drill 6" to 30544m Rotating . GPM 202, WOB 8-10k. Torque 8-9000 ft/bls.ROP 1-2m/hr , Very hard siltstone stringers . Pump 5 bbbls sweeps as required.	
33	01-Nov-05 6:00	0:00	18	3105.0	DRLR	Continue drill 6" hole to 3105m. ROP 2.8m/hr,GPM 200, RPM 70/90, Torque 6/7000 ft/bls,	
	02-Nov-05 0:00	6:00	6	3115.0	DRLR	Continue drill 6" hole to 3115m . ROP 1.6m/hr,GPM 200, RPM 70/90, WOB 5-12k, Torque 6/7000 ft/bls.SPM 125 =2100psi.Max gas 58 units at 3074m	
34	02-Nov-05 6:00	0:00	18	3158.0	DRILR	Continue to drill 6' hole to 3158m.Pumping sweeps as required.	
	03-Nov-05 0:00	6:00	6	3172.0	DRILR	Continue to drill 6" hole to 3172m ,GPM 200, WOB 6/12k, Torque 7/9000 ft/bls, SPM 125 = 2250 psi. MW 8.65 ,VIS 69 ,	
35	03-Nov-05 6:00	10:30	4.5	3182.0	DRILR	Continue drill to 3182m Rotating	
	03-Nov-05 10:30	11:30	1	3182.0	CIRC	Pump 10 bbls sweep and circulate clean	
	03-Nov-05 11:30	12:00	0.5	3182.0	OTHER	Take survey ,Flow check 10mins (static), Pump slug	
	03-Nov-05 12:00	13:00	1	2840.0	WIPE	TRPO to 2840 last old hole .hole good correct displacement.	
	03-Nov-05 13:00	13:30	0.5	2840.0	SERV	Rig service .circulate while performing rig service	
	03-Nov-05 13:30	14:00	0.5	3161.0	WIPE	TRPI to 3161m no hang ups.	
	03-Nov-05 14:00	14:30	0.5	3182.0	WASH	Wash down f/-3161m to 3182m No fill .	
	03-Nov-05 14:30	17:00	2.5	3182.5	DRILS	Continue drill 6" hole sliding to 3182.5m Unable to slide due to formation ROP .2m/hr	
	03-Nov-05 17:00	0:00	7	3189.0	DRILR	Continue to drill 6" hole to 3189m . ROP .9-1m/h	
	04-Nov-05 0:00	6:00	6	3195.0	DRILR	Continue to drill 6"hole to 3195m .GPM 200, RPM 60-90,SPM 125= 2300psi WOB 5-12k ,Torque 6/8000 ft/lbs.ROP 1m/hr.Pump 5 bbls kcl sweeps as required	
36	04-Nov-05 6:00	0:00	18	3223.0	DRILR	Continue drill 6" hole to 3223m Rotating ,ROP 1.4m/hr avg.	
	05-Nov-05 0:00	6:00	6	3245.0	DRILR	Continue to drill 6" hole to 3245m. ROP 3.6m/hr avg. rop increased at 3225m max 18m/hr.Formation change to siltstone.,GPM 200,WOB 4-9k, Torque 6/7000 ft/bls. SPM 125=2400psi.	
37	05-Nov-05 6:00	11:00	5	3268.0	DRILR	Continue drill 6" hole rotating to 3268m. Attempt connection very tight.	
	05-Nov-05 11:00	11:30	0.5	3268.0	CIRC	Pump sweep and circulate. work pipe through coal seam until free.	
	05-Nov-05 11:30	19:00	7.5	3296.0	DRILR	Continue drill 6" hole to 3296m .Working through all drilling breaks .Attempt connection at 3296m .tight hole coal seam.	
	05-Nov-05 19:00	20:00	1	3296.0	REAM	Backream 3296 to 3295m 15k overpull well packing off.Pump sweep and circulate while working pipe free. 100% coal at shaker on bottoms up.	
	05-Nov-05 20:00	22:00	2	3296.0	CIRC	Pump 10bbls sweep and circulate clean . Excessive cutting /caving over shakers	
	05-Nov-05 22:00	0:00	2	2311.0	TRPO	Flow check .pump slug .TRPO to 7" casing shoe. hole in good condition	
	06-Nov-05 0:00	3:30	3.5	215.0	TRPO	Flow check at 7" casing shoe (static). Continue TRPO to BHA 215m.Condition active with 4 bpb barablok to held with coal seams.	
	06-Nov-05 3:30	5:30	2	10.0	TOHBHA	Continue TOHBHA. layout jar. MWD, Mud motor ,Bit.	
	06-Nov-05 5:30	6:00	0.5	25.0	TIHBHA	P/UP Bit,bit sub. 2 x 4 3/4 DC.	
38	06-Nov-05 6:00	7:00	1	224.0	TIHBHA	RIH w/- BHA & break circ @ 224m.	
	06-Nov-05 7:00	11:30	4.5	2377.0	TRPI	RIH w/- drill pipe to 2377m.	
	06-Nov-05 11:30	12:00	0.5	2377.0	SERV	Conduct full rig service.	
	06-Nov-05 12:00	13:00	1	2377.0	CIRC	Circ. B/up & condition mud w/- Bareblok	
	06-Nov-05 13:00	15:00	2	3266.0	TRPI	Con't RIH f/- 2377m to 3266m. (fill pipe every 25 stands)	

Operations Activity Summary

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Rpt. No.	Date/Time From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product
38	06-Nov-05 15:00	16:00	1	3297.0	REAM	Wash & ream f/- 3266m to 3297m. (1m fill)	
	06-Nov-05 16:00	17:00	1	3297.0	CIRC	Circ B/up (gas peak 5.2%)	
	06-Nov-05 17:00	4:30	11.5	3370.0	DRIL	Drill 6" hole f/- 3297m to 3370m (TD)	
	07-Nov-05 4:30	6:00	1.5	370.0	CIRC	Circulate bttms up w/ low/hi vis sweeps.	
39	07-Nov-05 6:00	7:00	1	3370.0	WIPE	Flow check TRPO to 3297m. good hole TRPI to 3370m no fill.	
	07-Nov-05 7:00	8:00	1	3370.0	CIRC	Pump 10 bbls sweep and circulate clean	
	07-Nov-05 8:00	8:30	0.5	3370.0	CIRC	Spot 10 bbls high vis on bottom.	
	07-Nov-05 8:30	10:00	1.5	3036.0	TRPO	Flow check TRPO to 3036m wet. no overpull. pump slug at 3036m	
	07-Nov-05 10:00	16:00	6	215.0	TRPO	Continue to TRPO to BHA .	
	07-Nov-05 16:00	16:30	0.5	0.0	TOHBHA	TOHBHA Layout bit ,bit sub.	
	07-Nov-05 16:30	17:00	0.5	0.0	LOG	Held job safety meeting prior to rigging up Schlumberger surface equipment.Rig up surface equipment	
	07-Nov-05 17:00	18:00	1	0.0	LOG	Prepare run#1 PEX,BHC,AIT. Load radioactive sources.	
	07-Nov-05 18:00	22:00	4	3370.0	LOG	RIH with run# 1log up f/- 3370 to 2402m 7" casing .Continue to log up to surface .Schlumberger W/L MD 3374m. Monitor well via trip tank while logging.	
	07-Nov-05 22:00	22:30	0.5	0.0	LOG	Unload radio active sources.Lay out schlumberger tools.	
	07-Nov-05 22:30	23:00	0.5	0.0	LOG	Lay out schlumberger surface equipment.	
	07-Nov-05 23:00	1:00	2	146.0	TRPI	Rig up 2 7/8 handling equipment. M/up mule shoe and p/up 2 7/8 cement stinger f/- catwalk.TRPI to 146m	
	08-Nov-05 1:00	5:00	4	2375.0	TRPI	Change out to 3 1/2 handling equipment and TRPI w/- 3 1/2 DP to 2395m	
	08-Nov-05 5:00	5:30	0.5	2375.0	SERV	Rig service	
	08-Nov-05 5:30	6:00	0.5	2375.0	CIRC	Circululate and condition well while analyze logs.	
40	08-Nov-05 6:00	6:00	24	0.0	WOO	Circulate and condition well while wait on cement plug details.	x
41	09-Nov-05 6:00	12:00	6	0.0	WOO	WOO.	x
	09-Nov-05 12:00	13:00	1	2526.0	TRPI	TRPI to 2526m and circulate while mixing mix water,spacer and prepare for cement job (kick off plug)	
	09-Nov-05 13:00	13:30	0.5	2526.0	CIRC	Continue to mix mix water and spacers..Hold pre job safety meeting .Rig up surface lines.	
	09-Nov-05 13:30	14:00	0.5	2526.0	CMTPL	Pump 10 bbbls spacer .test surface lines to 3000 psi ok.Continue pump remaining 20bbls spacer.	
	09-Nov-05 14:00	15:00	1	2526.0	CMTPL	Pump 21.6 bbls 17.2 ppg Class G cement @ 3.6 bpm.Pump 6.3 bbls tail spacer.Displace balanced plug with 41.6 bbls 8.7ppg OBM. Check for flow back .OK.	
	09-Nov-05 15:00	16:30	1.5	2242.0	TRPI	TRPO f/- 2526m to 2242m .Install wiper sponge and circulate 2 x bottoms up. Slight cement contaminated at bttms/up.	
	09-Nov-05 16:30	20:30	4	2000.0	LDDP	TRPO laying out 104 jnts 3 1/2 DP.	
	09-Nov-05 20:30	22:30	2	1000.0	TRPO	Continue TRPO with 3 1/2 DP to 146m	
	09-Nov-05 22:30	0:30	2	0.0	LDDP	Lay out 2 7/8 tubing	
	10-Nov-05 0:30	1:00	0.5	0.0	OTHER	Retrieve wear bushing	
	10-Nov-05 1:00	2:00	1	0.0	BOPT	Hold pre tour safety meeting prior to rigging up test lines Drain stack set test plug..Fill stack .Test surface lines to 5000 psi.ok. Attempt test # 1 annular .leaking past test plug seal. Drill crew member closed annulus valve.	
	10-Nov-05 2:00	6:00	4	0.0	REPR	Bled of pressure on annulus test.Unseated Test plug lifted string and bent kelly.Trouble shoot open annulus valve .reset test plug .Bypassing test plug.Unable to get test.Drain stack check test plug profile. Junk observed flush well head . Prepare RTTS packer to isolate well bore to enable lifting stack.	x

Operations Activity Summary

Well ID: NZ050091 **Well Name: Ahuroa South B-1**

Rpt. No.	Date/Time	From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product

Printed: 12:16 25-May-07

End of Report

Operations Activity Summary

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Rpt. No.	Date/Time From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product
1	09-Nov-05 6:00	12:00	6	0.0	WOO	WOO.	x
	09-Nov-05 12:00	13:00	1	2526.0	TRPI	TRPI to 2526m and circulate while mixing mix water,spacer and prepare for cement job (kick off plug)	
	09-Nov-05 13:00	13:30	0.5	2526.0	CIRC	Continue to mix mix water and spacers..Hold pre job safety meeting .Rig up surface lines.	
	09-Nov-05 13:30	14:00	0.5	2526.0	CMTPL	Pump 10 bbbls spacer .test surface lines to 3000 psi ok.Continue pump remaining 20bbls spacer.	
	09-Nov-05 14:00	15:00	1	2526.0	CMTPL	Pump 21.6 bbls 17.2 ppg Class G cement @ 3.6 bpm.Pump 6.3 bbls tail spacer.Displace balanced plug with 41.6 bbls 8.7ppg OBM. Check for flow back .OK.	
	09-Nov-05 15:00	16:30	1.5	2242.0	TRPI	TRPO f/- 2526m to 2242m .Install wiper sponge and circulate 2 x bottoms up. Slight cement contaminated at bttms/up.	
	09-Nov-05 16:30	20:30	4	2000.0	LDDP	TRPO laying out 104 jnts 3 1/2 DP.	
	09-Nov-05 20:30	22:30	2	1000.0	TRPO	Continue TRPO with 3 1/2 DP to 146m	
	09-Nov-05 22:30	0:30	2	0.0	LDDP	Lay out 2 7/8 tubing	
	10-Nov-05 0:30	1:00	0.5	0.0	OTHER	Retrieve wear bushing	
	10-Nov-05 1:00	2:00	1	0.0	BOPT	Hold pre tour safety meeting prior to rigging up test lines Drain stack set test plug..Fill stack .Test surface lines to 5000 psi.ok. Attempt test # 1 annular .leaking past test plug seal. Drill crew member closed annulus valve.	
	10-Nov-05 2:00	6:00	4	0.0	REPR	Bled of pressure on annulus test.Unseated Test plug lifted string and bent kelly.Trouble shoot open annulus valve .reset test plug .Bypassing test plug.Unable to get test.Drain stack check test plug profile. Junk observed flush well head . Prepare RTTS packer to isolate well bore to enable lifting stack.	x
2	10-Nov-05 6:00	6:30	0.5	0.0	REPR	Trouble shoot BOP problem. ok.	x
	10-Nov-05 6:30	13:00	6.5	0.0	BOPT	Test BOP as per Parker drilling procedure. 250psi low 5 mins/ 5000psi high 10mins. Annular 250 low 5mins/3000psi high 10mins. ok.	
	10-Nov-05 13:00	14:00	1	0.0	BOPO	Install wear bushing and lock down.	
	10-Nov-05 14:00	15:30	1.5	224.0	TIHBHA	M/up rotary BHA anfd TIHBHA to 224m	
	10-Nov-05 15:30	16:30	1	800.0	TRPI	TRPI with 3 1/2 dp to 800m,	
	10-Nov-05 16:30	19:00	2.5	800.0	REPR	Layout bent 3 1/2 kelly and install new 3 1/2 kelly.	x
	10-Nov-05 19:00	22:30	3.5	2356.0	TRPI	Continue to TRPI with 3 1/2 dp to 2356m Tag cement.	
	10-Nov-05 22:30	0:30	2	2400.0	CMTD	Drill out cement f/- 2356m to 2400m . Cement firm. GPM 175,RPM 40,WOB 4/5k.	
	11-Nov-05 0:30	3:00	2.5	2400.0	CIRC	Circulate and condition well bore to 8.5 ppg.	
	11-Nov-05 3:00	6:00	3	1200.0	TRPO	Flowcheck (static) TRPO. 750m @ 06:00 hrs	
3	11-Nov-05 6:00	8:00	2		TOHBHA	POOH BHA, Lay out 2 HWDP.	
	11-Nov-05 8:00	9:00	1		TIHBHA	P/U Motor w/- 1.5 deg bend. 117 bit. Install MWD probe.	
	11-Nov-05 9:00	10:00	1		TIHBHA	P/U 2 HWDP and run BHA f/- mast.	
	11-Nov-05 10:00	10:30	0.5		OTHER	Test MWD.	
	11-Nov-05 10:30	13:00	2.5		REPS	No pulse observed during testing of MWD. POOH and Change Probe. (orifice upside down) RIH test okay.	x
	11-Nov-05 13:00	17:30	4.5		TRPI	RIH.	
	11-Nov-05 17:30	18:00	0.5	2400.0	REAM	P/U kelly, check MWD, tag cement plug. Orientate.	
	11-Nov-05 18:00	6:00	12	2411.0	DRLS	Directional Drill Time drilling f/- 2400m to 2411m. GPM 203, WOB 4-6k, SPM 125=1980 psi.	
4	12-Nov-05 6:00	0:00	18	2425.0	DRILS	Continue to time drill to 2425m. 95% formation.ROP 1mhr ,WOB 2-3k.	
	13-Nov-05 0:00	6:00	6	2428.0	DRILS	Continue to drill 6" hole to 2428m 95% formation . Slow ROP .5m/hr . Work sting and pump 5 bbls sweeps as required. GPM 202, WOB 6-8k.	

Operations Activity Summary

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Rpt. No.	Date/Time	From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product
5	13-Nov-05	6:00	7:00	1	2433.0	DRILR	Continue to drill 6" hole to 2433m. Check shot survey .inclination and azimuth not on track. Building angle instead of dropping.	
	13-Nov-05	7:00	8:30	1.5	2433.0	CIRC	Pump sweep and circulate and condition mud prior to TRPO to change bit and check BHA.	
	13-Nov-05	8:30	12:30	4	225.0	TRPO	Flow check (static) Pump slug and TRPO to BHA.	
	13-Nov-05	12:30	13:00	0.5	0.0	TOHBHA	Flow check at BHA .continue to TOHBHA. lay out MWD probe and L/out 6" Mill tooth bit.	
	13-Nov-05	13:00	14:30	1.5	225.0	TIHBHA	M/up New MWD Probe ,6" DSX519 PDC BIT AND TIHBHA to 225m	
	13-Nov-05	14:30	17:30	3	2395.0	TRPI	Test MWD OK. Continue TRPI to 2395m.Filling pipe @798,2395m	
	13-Nov-05	17:30	18:30	1	2395.0	CUTDL	Slip and cut 72ft drilling line	
	13-Nov-05	18:30	19:00	0.5	2395.0	SERV	Rig Service	
	13-Nov-05	19:00	19:30	0.5	2428.0	WASH	Continue TRPI to 2400m wash down f/-2400m to 2428m No fill	
	13-Nov-05	19:30	21:00	1.5	2442.0	DRILS	Continue drill 6" hole sliding to 2442m	
	13-Nov-05	21:00	22:30	1.5	2451.0	DRILR	Continue drill 6" hole Rotating to 2451m	
	13-Nov-05	22:30	0:00	1.5	2457.0	DRILS	Continue drill 6" hole Sliding to 2457m. ROP 5m/hr.	
	14-Nov-05	0:00	6:00	6	2492.0	DRILR	Continue drill 6" hole Sliding first 5m of single then rotate the rest. ROP Sliding 5/6m/hr Rotating 14/16m/hr.	
6	14-Nov-05	6:00	0:00	18	2581.0	DRILR	Continue to drill 6" hole sliding and rotating to 2581m ROP 5-7m/hr,	
	15-Nov-05	0:00	6:00	6	2616.0	DRILR	Continue to drill 6" hole sliding and rotating to 2616m. ROP 5-6m/hr,GPM 201,4/6000 ft/bls, WOB 8/10k.Pump sweeps as required.	
7	15-Nov-05	6:00	0:00	18	2703.0	DRIL	Continue to drill 6" hole rotating and sliding to 2703m . ROP 4.8m/hr. Pump 5 bbls sweeps as required	
	16-Nov-05	0:00	6:00	6	2721.0	DRIL	Continue to drill 6" hle sliding and rotating to 2721m. 3m/hr.GPM 202,Torque 5/7000 ft/bs, SPM 125=2200psi, WOB 8/10k.	
8	16-Nov-05	6:00	10:00	4	2727.0	DRILS	Slide 6" hole f/- 2721m to 2727m. WOB 6/8, GPM 198, m/hr 1.6	
	16-Nov-05	10:00	15:00	5	2742.0	DRILR	Rotate 6" hole f/- 2719m to 2742m. WOB 8/10, GPM 198, RPM 80, m/hr 2.6	
	16-Nov-05	15:00	16:00	1	2742.0	STRIP	Flow check, POOH f/- 2742m to shoe.	
	16-Nov-05	16:00	16:30	0.5	2742.0	SERV	Full rig service & adjust brake.	
	16-Nov-05	16:30	17:30	1	2742.0	STRIP	RIH f/- shoe to 2726m, wash down last single to 2742m.	
	16-Nov-05	17:30	22:00	4.5	2751.0	DRILR	Con't rotate 6" hole f/- 2742m to 2751. WOB 8/10, GPM 200, RPM 80, m/hr 2	
	16-Nov-05	22:00	0:00	2	2755.0	DRILS	Slide 6" hole f/- 2751m to 2755m. WOB 5/10, GPM 200, m/hr 2.	
	17-Nov-05	0:00	1:00	1	2756.0	DRILR	Rotate 6" hole f/- 2755m to 2756m. WOB 8/10, GPM 200, RPM 80, m/hr 1	
	17-Nov-05	1:00	3:00	2	2760.0	DRILS	Slide 6" hole f/- 2756m to 2760m. WOB 5/10, GPM 200, m/hr 2.	
	17-Nov-05	3:00	6:00	3	2768.0	DRILR	Rotate 6" hole f/- 2760m to 2768m. WOB 8/10, GPM 200, RPM 80, m/hr 2.5.	
9	17-Nov-05	6:00	14:30	8.5	2803.0	DRILR	Drill 6" hole f/-2768m to 2803m. WOB 8/10, GPM 200, 2200 psi, RPM 100, m/hr 3.1	
	17-Nov-05	14:30	15:00	0.5	2803.0	SERV	Full rig service.	
	17-Nov-05	15:00	3:00	12	2830.0	DRILR	Drill 6" hole f/- 2803m to 2830m. WOB 8/10, GPM 200, 2200 psi, RPM 80/100, Torque 6/8k lbs.	
	18-Nov-05	3:00	6:00	3	2836.0	DRILS	Drill 6" hole Slide f/- 2830m to 2836m. WOB 6/8, GPM 200, 2200psi on bottom / 2100 psi off bottom.	
10	18-Nov-05	6:00	6:30	0.5	2837.0	DRILS	Drill 6" hole Slide f/- 2836m to 2837m. WOB 5/6k, GPM 200, psi 2200.	
	18-Nov-05	6:30	10:30	4	2845.0	DRILR	Drill 6" hole Rotate f/- 2837m to 2845m. WOB 8/10k, GPM	

Operations Activity Summary

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Rpt. No.	Date/Time From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product
						200, psi 2200, Torque 6/8k, RPM 80/90.	
	18-Nov-05 10:30	15:30	5	2849.0	DRILS	Drill 6" hole Slide f/- 2845m to 2849m. WOB 5/8k, GPM 200, psi 2200.	
	18-Nov-05 15:30	20:30	5	2861.0	DRILR	Drill 6" hole Rotate f/- 2849m to 2861m. WOB 8/10, GPM 200, psi 2200, Torque 6/8k, RPM 80/90.	
	18-Nov-05 20:30	21:00	0.5	2861.0	SERV	Full rig service, clean pump strainers.	
	18-Nov-05 21:00	0:00	3	2865.0	DRILS	Drill 6" hole Slide f/- 2861m to 2865m. WOB 8/10, GPM 200, psi 2200,	
	19-Nov-05 0:00	1:00	1	2867.0	DRLR	Drill 6" hole Rotate f/- 2865m to 2867m. WOB 8/10, GPM 200, psi 2200, Torque 6/8k, RPM 80/100	
	19-Nov-05 1:00	1:30	0.5	2868.0	DRILS	Drill 6" hole Slide f/- 2867m to 2868m. WOB 8/10, GPM 200, psi 2400.	
	19-Nov-05 1:30	3:00	1.5	2870.0	DRILR	Drill 6" hole Rotate f/- 2868m to 2870m. WOB 8/10, GPM 200, psi 2400, Torque 6/8k, RPM 80.	
	19-Nov-05 3:00	6:00	3	2873.0	DRILS	Drill 6" hole Slide f/- 2868m to 2873m. WOB 8/10, GPM 200, psi 2400.	
11	19-Nov-05 6:00	6:30	0.5	2874.0	DRILS	Drill 6" hole Slide f/- 2873m to 2874m. WOB 8/10, GPM 200, psi 2400.	
	19-Nov-05 6:30	7:00	0.5	2874.0	CIRC	Circ & condition shakers clean.	
	19-Nov-05 7:00	11:30	4.5	2874.0	TRPO	Pump slug, flow check, POOH f/- 2874m to BHA.	
	19-Nov-05 11:30	14:00	2.5	2874.0	TOHBHA	Lay out HWDP, brk bit, layout motor.	
	19-Nov-05 14:00	17:00	3	2874.0	TIHBHA	P/up new motor, m/up bit #10, set bend to 1.15 deg. Scribe MWD. P/up new HWDP f/- rack.	
	19-Nov-05 17:00	21:00	4	2874.0	TRPI	Surface test MWD. RIH drill pipe f/- mast to 2373m. Fill pipe every 30 std's.	
	19-Nov-05 21:00	22:00	1	2874.0	CUTDL	Slip & cut drilling line. monitor trip tank.	
	19-Nov-05 22:00	22:30	0.5	2874.0	SERV	Full rig service. monitor trip tank.	
	19-Nov-05 22:30	23:00	0.5	2874.0	TRPI	Con't RIH f/- 2373m to 2414m. Took wt (10,000 lbs)	
	19-Nov-05 23:00	0:00	1	2874.0	REAM	Work pipe through tight spot @ 2414m. P/up kelly & oreintate toolface & slide through tite area to 2430m.	
	20-Nov-05 0:00	1:00	1	2874.0	TRPI	RIH f/- 2430m to 2858m. fill pipe.	
	20-Nov-05 1:00	1:30	0.5	2874.0	WASH	Wash down f/- 2858m to 2874m. tag 2m fill.	
	20-Nov-05 1:30	2:00	0.5	2876.0	DRLR	Drill 6" hole Rotate f/- 2874m to 2876m, cut new bit profile. WOB 2/4k, GPM 200, psi 2200, RPM 80, Torque 5/7k.	
	20-Nov-05 2:00	4:00	2	2879.0	DRLS	Drill 6" hole Slide f/- 2876m to 2879m. WOB 5/6k, GPM 200, psi 2200,	
	20-Nov-05 4:00	6:00	2	2885.0	DRLR	Drill 6" hole Rotate f/- 2879m to 2885m. WOB 5/6k, GPM 200, psi 2200, RPM 80, Torque 5/7k.	
12	20-Nov-05 6:00	6:30	0.5	2888.0	DRLR	Drill 6" hole Rotate f/- 2885m to 2888m. WOB 5k, GPM 200, psi 2350, RPM 80, Torque 6k ft/lbs.	
	20-Nov-05 6:30	7:00	0.5	2889.0	DRLS	Drill 6" hole Slide f/- 2888m to 2889m. WOB 5k, GPM 200, psi 2350.	
	20-Nov-05 7:00	8:30	1.5	2892.0	DRLR	Drill 6" hole Rotate f/- 2889m to 2892m. WOB 5k, GPM 200 psi 2350, RPM 80, Torque 6/7k ft/lbs.	
	20-Nov-05 8:30	12:00	3.5	2898.0	DRLS	Drill 6" hole Slide f/- 2892m to 2898m. WOB 5/6k, GPM 200, psi 2350,	
	20-Nov-05 12:00	18:30	6.5	2917.0	DRLR	Drill 6" hole Rotate f/- 2898m to 2917m. WOB 5/6k, GPM 200, psi 2350, RPM 80, Torque 6/7k ft/lbs.	
	20-Nov-05 18:30	19:00	0.5	2917.0	SERV	Full rig service.	
	20-Nov-05 19:00	6:00	11	2953.0	DRLR	Drill 6" hole Rotate f/- 2917m to 2953m. WOB 5/6k, GPM 200, psi 2450, RPM 80/100, Torque 5/7k ft/lbs.	
13	21-Nov-05 6:00	22:30	16.5	2993.0	DRLR	Drill 6" hole Rotate f/- 2953m to 2993m. WOB 5/10k, GPM 200, psi 2450, RPM 80/100, Torque 5/7k ft/lbs.	
	21-Nov-05 22:30	23:00	0.5	2993.0	STUK	Attempt to p/up & make connection. No go, attempt to rotate. No go. Work pipe free. Slow pump rate to 160 GPM.	x
	21-Nov-05 23:00	0:00	1	2993.0	CIRC	Establish rotary & circ b/up @ GPM 160, psi 1500, RPM 70, still unable to p/up. 100% coal @ shakers.	

Operations Activity Summary

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Rpt. No.	Date/Time From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product
13	22-Nov-05 0:00	6:00	6	2993.0	CIRC	Con't circ & work pipe down/up to gain larger free spot. Work way out of coal seam.	
14	22-Nov-05 6:00	6:30	0.5	2993.0	REAM	Ream f/- 2992.5m to 2993m. WOB 0-1k, GPM 160, psi 1500, RPM 70, Torque 5/15k ft/lbs. 100% coal @ shakers.	
	22-Nov-05 6:30	7:00	0.5	2993.0	REAM	Pull back to 2986m w/- 5k over pull, ream back to 2993m.	
	22-Nov-05 7:00	9:00	2	2993.0	CIRC	Pump 10 bbls low vis low wt (base oil), pump 10 bbls 10.7 ppg 74 vis, & circ out of hole. 100% coal @ shakers.	
	22-Nov-05 9:00	22:00	13	3005.0	DRLR	Time drill 6" hole Rotate f/- 2993m to 3005m. WOB 2/4k, GPM 160/200, psi 1500/2200. Torque 5/7k ft/lbs. 100/20% coal @ shakers.	
	22-Nov-05 22:00	2:00	4	3015.0	DRLR	Drill 6" hole Rotate f/- 3005m to 3015m. Constant WOB 6K, GPM 200, psi 2200, RPM 80, Torque 5/7k ft/lbs. 10% coal @ shakers.	
	23-Nov-05 2:00	3:00	1	3016.0	DRLR	Time drill 6" hole Rotate f/-3015m to 3016m. WOB 2/5k, GPM 200, psi 2200, RPM 80, Torque 6k ft/lbs, 15/20% coal @ shakers.	
	23-Nov-05 3:00	5:00	2	3021.0	DRLR	Drill 6" hole Rotate f/- 3016m to 3021m. Constant WOB 6k, GPM 200, psi 2300, RPM 80, Torque 5/7k ft/lbs. 20% coal @ shakers, drill brk.	
	23-Nov-05 5:00	6:00	1	3022.0	DRLR	Time drill 6" hole Rotate f/- 3021m to 3022m. WOB 4/6k, GPM 200, psi 2300, RPM 80, Torque 5/7k ft/lbs.	
15	23-Nov-05 6:00	6:30	0.5	3022.0	DRIL	Continue to time drill 1m/hr through coal seam to to 3022m.15% coal.	
	23-Nov-05 6:30	8:00	1.5	3025.0	DRIL	Continue to time drill 1 m/hr to 3025m 100% coal .Pump 5 bbls sweeps to keep well bore clean . maintain 4 bpb barablok in mud system to control coal.GPM 200, SPM 160 SPP=2300psi	
	23-Nov-05 8:00	12:00	4	3028.0	DRIL	Time drill at 1m/hr to 3028m .100% coal.Pump 5 bbls sweeps as required	
	23-Nov-05 12:00	16:00	4	3031.0	DRIL	Continue to time drill 6" hole to 3031m .Sample 3030m 100% coal ,sample 3031m 70% coal /30% claystone.GPM 200, WOB 2/4k.SPM 160 ,SPP 2300psi.	
	23-Nov-05 16:00	17:30	1.5	3031.0	CIRC	Pump 10 bbls sweep and circulate clean prior to wiper trip.	
	23-Nov-05 17:30	18:00	0.5	3031.0	FLOW	Flow check (static) Pump slug .	
	23-Nov-05 18:00	19:00	1	2868.0	WIPE	Wiper trip back to 2868m . No hang ups.	
	23-Nov-05 19:00	19:30	0.5	2868.0	SERV	Rig service . Circulate and condition mud while performing Rig service.	
	23-Nov-05 19:30	20:00	0.5	3031.0	WIPE	TRPI to 3020m wash down last single to 3031m. 1m fill.	
	23-Nov-05 20:00	1:30	5.5	3036.5	DRIL	Continue to time drill 6" hole to 3036.5m. 3034m geologist called base of ahuroa trust .GPM 200 ,SPM 160,SPP 2300psi,	
	24-Nov-05 1:30	6:00	4.5	3050.0	DRIL	Continue to drill 6" hole conventionally f/-3036.5m to 3050m Coal percentages dropped of to only traces. GPM 200,WOB 4/6k, Torque 4/5000 ft/lbs,RPM 80 ,SPM 160=SPP 2350psi.,ROP 3.1m/hr. Pump sweeps as required.	
16	24-Nov-05 6:00	12:00	6	3071.0	DRIL	Continue drill 6" hole to 3071m .GPM 200, SPM 160 ,SPP 2400psi,Torque 6/7000 ft/bls.	
	24-Nov-05 12:00	15:30	3.5	3085.0	DRIL	Drill 6" hole to target depth 3085m ,50m below the ahuroa thrust basement.GPM 200, ROP 3/4m/hr,Torque 6/7000 ft/bls. 100% claystone formation,SPM 160 ,SPP 2350psi.	
	24-Nov-05 15:30	17:00	1.5	3085.0	CIRC	Pump 10bbls sweep and circulate well clean.	
	24-Nov-05 17:00	17:30	0.5	3085.0	FLOW	Flow check ,(static)Pump slug .	
	24-Nov-05 17:30	19:30	2	2395.0	WIPE	Wiper trip back to shoe 2395m .no hang ups.	
	24-Nov-05 19:30	21:30	2	3085.0	WIPE	TRPI to 3055m , wash down toTD 3085m .1.2m fill.	
	24-Nov-05 21:30	0:00	2.5	3085.0	FLOW	Sweep 10bbls high vis and circulate clean.Flow check (static) Spot 15 bbls high vis on bottom.	
	25-Nov-05 0:00	2:00	2	2395.0	TRPO	TRPO to 7" casing shoe 2395m no hang ups.	

Operations Activity Summary

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Rpt. No.	Date/Time From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product
16	25-Nov-05 2:00	6:00	4	216.0	TRPO	Flow check at 7" casing shoe 5 mins (static) Continue TRPO to BHA.216m.	
17	25-Nov-05 6:00	7:00	1	0.0	TOHBHA	Flow check at BHA and TOHBHA and layout mwd , remove probe ,mud motor ,stab ,bit.	
	25-Nov-05 7:00	8:00	1	0.0	LOG	HPJSM Proir to rigging up schlumbereger equipment. Rig up schhlumberger equipment.	
	25-Nov-05 8:00	13:00	5	3085.0	LOG	P/up run# 1 PEX -AIT.load source. Run in hole tag bottom W/L MD 3087m. Log up to shoe and Pull out with W/l to surface .	
	25-Nov-05 13:00	13:30	0.5	0.0	LOG	Unload source at surface . Lay out run#1 PEX-AIT.	
	25-Nov-05 13:30	14:00	0.5	0.0	LOG	M/up run # 2 . UBI.	
	25-Nov-05 14:00	20:30	6.5	3085.0	LOG	Run in hole w/- UBI.Log up f/- 3085m.	
	25-Nov-05 20:30	22:30	2	0.0	LOG	Wire line at surface . Comfirm logs.ok Lay out UBI tools. Rig down schlumbereger surface equipment	
	25-Nov-05 22:30	23:30	1	146.0	TRPI	Rig up floor for 2 7/8 tubing .P/up mule shoe and run cement stinger to 146m	
	25-Nov-05 23:30	3:30	4	2430.0	TRPI	Change out handling equipment for 3 1/2 dp.TRPI to 2430m.	
	26-Nov-05 3:30	5:30	2	2430.0	CIRC	Circulate and condition mud while mix spacers and prepare cement plug.	
	26-Nov-05 5:30	6:00	0.5	2430.0	CMTPL	Held pre job meeting prior to Cement operations. Rig up cement surface lines.	
18	26-Nov-05 6:00	7:00	1	2430.0	PLUG	Pump 10 bbls spacer . Test surface lines to 3000psi ok,Continue pump 20 bbls spacer Total 30 bbls.Mix and pump 11 bbls 17.2ppg slurry . pump 7 bbls spacer to balance plug. Displace with 44 bls SBM. Check back flow .(static).	
	26-Nov-05 7:00	7:30	0.5	2283.0	PLUG	Rig down cement surface lines and TRPO to 2283m slowly.No overpull .	
	26-Nov-05 7:30	8:30	1	2283.0	PLUG	Drop wiper ball and Circulate bottoms up .no cement contamination back at surface. Some spacer returns at surface.	
	26-Nov-05 8:30	10:30	2	1581.0	LDDP	Lay out excess 3 1/2 drill pipe to 1581m	
	26-Nov-05 10:30	13:00	2.5	146.0	TRPO	Continue to TRPO to 146m 2 7/8 cement stinger	
	26-Nov-05 13:00	14:30	1.5	0.0	LDDP	Layout 2 7/8 cement stinger and handling quipment	
	26-Nov-05 14:30	15:00	0.5	0.0	LOG	HPJSM prior to rigging up vause W/L. R/up vause W/L surface equipment	
	26-Nov-05 15:00	17:30	2.5	1500.0	LOG	Run # 1 CBL .log down to 1500m them log up to 500m to evaluate cement bond.Soilid cement up to 905m .	
	26-Nov-05 17:30	18:30	1	205.0	TIHBHA	M/up clean out assy and TIHBHA to 205m	
	26-Nov-05 18:30	23:30	5	2320.0	TRPI	Continue TRPI to 2320m filling as required	
	26-Nov-05 23:30	0:30	1	2450.0	WASH	Wash down f/- 2320m to 2450m No cement tagged.	
	27-Nov-05 0:30	1:30	1	2450.0	CIRC	Circulate bottoms up . No cement contamination at bottoms up	
	27-Nov-05 1:30	6:00	4.5	300.0	TRPO	Pump slug and TRPO to BHA.	
19	27-Nov-05 6:00	7:30	1.5	205.0	TRPO	Continue TRPO to BHA 205m	
	27-Nov-05 7:30	8:30	1	0.0	TOHBHA	TOHBHA layout bit ,bit sub,	
	27-Nov-05 8:30	9:00	0.5	0.0	PLUG	M/up EZSV packer assy.	
	27-Nov-05 9:00	15:00	6	2365.0	TRPI	TRPI with EZSV as per haliburton engineers parameters to 2365m	
	27-Nov-05 15:00	15:30	0.5	2365.0	CIRC	Circulate and condition mud prior to setting EZSV packer. work string through setting zone	
	27-Nov-05 15:30	16:00	0.5	2365.0	PLUG	Get up/ down weights.122k up 95k down,Set ezsv packer with 35 turns right .Pick up 15k over string weight and let packer element expand.Continue to pull to 170k and shear packer. Set down 20k to confirm packer set ok.	
	27-Nov-05 16:00	16:30	0.5	2365.0	FIT	Establish injectivity rate under EZSV . Break over at 1550psi. pump 1.5bpb = 1340psi.	

Operations Activity Summary

Well ID: NZ050091A **Well Name: Ahuroa South B-1 ST# 1**

Rpt. No.	Date/Time	From	To	Hrs	End MD	Ops Code	Activity Description	Non-Product
19	27-Nov-05	16:30	17:00	0.5	2365.0	PLUG	Sting out of EZSV. Pump 5 bbls spacer ,test surface lines to 3000psi ok. continue pump spacer total 10bbls. Mix and pump 12 bbls 15.2ppg cement slurry , pump 1.3 bbls tail spacer for balance. Displace with SBM 32 bbls, sting into EZSV and inject 5 bbls slurry under EZSV1.7bpm= 800psi. Pump 5bbls then unsting out of EZSV. Continue to displace total 48 bbls.displace at 6bpm=450 psi.Stop pumping check back flow .(static)	
	27-Nov-05	17:00	18:00	1	2235.0	PLUG	TRPO slowly to 2235m and reverse circulate tubing volume . no cement returns.	
	27-Nov-05	18:00	18:30	0.5	2235.0	P/TEST	Pressure test EZSV against casing to 3000psi 10mins ok.	
	27-Nov-05	18:30	19:00	0.5	2235.0	PLUG	Rig down cementing surface equipment.	
	27-Nov-05	19:00	21:00	2	2235.0	CIRC	Displace SBM to caCL brine .Flush all drilling quipment.	
	27-Nov-05	21:00	6:00	9	200.0	LDDP	Lay down 3 1/2 DP ,3 1/2 HWDP.Soft break kellly.	
20	28-Nov-05	6:00	8:00	2	0.0	LDDP	Layout 3 1/2 hwdp.	
	28-Nov-05	8:00	8:30	0.5	0.0	OTHER	Retrieve wearbushing and set test plug.	
	28-Nov-05	8:30	10:00	1.5	0.0	OTHER	Layout kelly, L/out RKB ,	
	28-Nov-05	10:00	10:30	0.5	0.0	OTHER	Layout 3 1/2 handling equipment	
	28-Nov-05	10:30	17:00	6.5	0.0	BOPND	Rig down flow line ,blow back koomey lines, l/out annular, rams, spacer spool.	
	28-Nov-05	17:00	18:00	1	0.0	OTHER	Nipple up well head valve and pressure test to 3000psi ok.	
	28-Nov-05	18:00	0:00	6	0.0	OTHER	Continue cleaning tanks and preparing for rig move	
	29-Nov-05	0:00	6:00	6	0.0	RIGD	Release rig at midnight 28th november.	
21	29-Nov-05	6:00	19:00	13	0.0	RIGD	Rig move camp 100% rig down rig 25%. Stripped down mud tanks , Undressed rig floor , Scoped mast in and layed over.Steam clean and pressure wash mud tanks. Remove shaker tanks. Backload third party equipment.Backload excess mud chemicals. All lifts over live wells ,production operator to be on site to observe. Mi swaco rigged down there equipment aslo TOT rigged down ther rental equipment.	



SWIFT ENERGY COMPANY

SWIFT ENERGY NZ LTD
Drilling Fluids Recap
AHUROA, South B-1 Well

AHUROA Field
Taranaki, New Zealand

HALLIBURTON

Baroid

Cover Page

Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Prepared For	DGloger / NPeri
Title	Drlg Mgr / Engr
Well Name	AHUROA SOUTH B-1
Rig Name	Parker Rig 252
Document Date	11/20/2005
Author	Tom Mitchell
District	New Plymouth
Field Name	Ahuroa
Field or Block	Taranaki
Country	New Zealand
SAP Order #	

Well Name	AHUROA SOUTH B-1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252

Table of Contents

Cover Page

Table of Contents

Executive Summary

Well Summary Report

Time Summary Report

Net Well Cost Breakdown

Total Cost Breakdown

Conclusions & Recommendations

Interval Inventory Recap Report

Interval Summary

Interval Discussion

Interval Cost Breakdown

Interval Inventory Summary

Fluid Volume Record

Fluid Property Recap

Operations Log Recap

Graphs

Deviation

Hydraulics Summary

Personnel Register

Executive Summary

Well Name	AHUROA SOUTH B-1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252

Exec. Summary

The AHOURA B-1 well was started off drilling the 12 ¼" hole section with fresh water spud mud down to 652 meters. At 452 meters Pac-L and Pac-R were added to the system to lower filtrate for casing. After casing was ran and set all of this mud was dumped to the reserve pit and tanks cleaned to the next section of hole.

The 8 ½" section of hole was drilled using a steerable assembly with KCL/PHPA drilling fluids. The KCL was ran at 8-10% by weight. This section of hole was drilled down to 2395 meters with no problems and casing ran and cemented with no problems. Cement was displaced with SBM. All tanks were cleaned and filled with SBM.

Drilled this section of hole using all 175 mesh screens due to all the calcium carbonate that was added into the system. Used a total of 24 screens while drilling this section of hole. Screen breakage was due to all the gumbo drilled in the upper hole. Need some repair kits to fix these screens so that they can be reused.

The 6" hole section of hole was drilled using Coredril-N changed over to SBM. This section of hole was started off at a mud weight of 8.5 ppg and slowly increased the weight up to 8.8 ppg. At 3298-TVD 3149 encountered some coal stringer so the addition of BARABLOK was added to the system. After adding this to the system pulled out of the hole and changed out BHA. Ran back in the hole and drilled to total depth with no further hole problems. Drilled to 3370 meters. Pulled out of the hole and ran two sets of logs with no problems.
This well had one kick off plug set at 2380. Side track #1. Start of new well

Baroid Fluid Services

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Well Summary Report

Well Data

Spud Date		05/10/2005	Fluids/Products: Drilling Cost		$ 178,657.31
TD Date		08/11/2005	Fluids/Products: Completion Cost		$ 0.00
Project			Solids Control/Waste Management Cost		$ 0.00
Days on Well		38	Fluids/Products: Cementing Cost		$ 0.00
From Date		06/10/2005	Prod Lost/Damaged Cost		$ 0.00
To Date		12/11/2005	Engineer Services Cost		$ 28,000.00
Drilling Days		28	Equipment Cost		$ 2,880.00
Rotating / Drilling Hours		461.0/460.0	Transport/Packaging		$ 0.00
Average ROP	m/hr	5.0	Other Cost		$ 1,222.63
Maximum Density	ppg	9.35	Total Well Cost		$ 210,759.94
Total Measured Depth	m	2,403	Planned Cost		$ 186,241.00
True Vertical Depth	m	2,282	Fluid Cost Per Fluid Volume	$/bbl	36.05
Distance Drilled	m	2,303	Fluid Cost Per Length Drilled	$/m	78.83
Maximum Deviation	deg	22.20	Fluid Cost/Vol of Hole Drilled	$/bbl	253.36
Max. Horz. Displacement	m	0	Total Additions/Hole Drilled	bbl/bbl	7.029
Bottom Hole Temp	Deg C	65	Total Additions/Length Drilled	bbl/m	2.187

Casing Design

Description	Set Date & Time	Top MD m	Top TVD m	End MD m	End TVD m	CSG OD in	CSG ID in	Max. Hole Size in	Hole MD m	Hole TVD m
9.625 HCL-80 43.5	10/10/2005 23:59	0		652	652	9.625	8.755		652	652
7 L-80 29.0	21/10/2005 23:59	0		2,395	2,308	7.000	6.184		2,395	2,308

Fluid Program

Int #	Fluid Type	Interval Days	BHT Deg C	Max. Dens ppg	Whole fluid + Mix products	Other material charges	Other charges	Total Interval Cost $		
								Plan	Actual	Variance
1	Spud Mud	4		9.20	19,441.52		180.00	21,059.00	19,621.52	-1,437.48
2	KCl/Polymer	12		9.35	65,857.04	729.39	1,380.00	82,661.00	67,966.43	-14,694.57
	Spud Mud									
3	SHEARDRIL-N	22	65	8.90	93,358.75	493.24	29,320.00	82,521.00	123,171.99	40,650.99
	SOBM									
	Water									
Total Well Cost $					**178,657.31**	**1,222.63**	**30,880.00**	**186,241.00**	**210,759.94**	**24,518.94**

Baroid Fluid Services

Well Name	AHUROA SOUTH B-1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Time Breakdown Summary Report

				Time																			
Rpt No	Rpt Date	Rpt Time	MD	Drilg	Circ	Trip	Rig Serv	Rig Repair	Rig Up/Dn	Run Csg	Core	Ream Time	DST	Test BOP	N. Up BOP	WOC	Fish	Log	Dir Work	Dir Svys	Other	Total Time	Rotate	Avg ROP
			m	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	m/hr
001	06/10/2005	2:00	100.0	10.00																	14.00	24.00	10.00	10.00
002	07/10/2005	2:00	248.0	14.00																	10.00	24.00	14.00	10.58
003	08/10/2005	2:00	589.0	23.00																		23.00	23.00	14.82
004	09/10/2005	2:00	659.0	5.00	2.00					8.00											9.00	24.00	5.00	14.02
005	10/10/2005	2:00	659.0		1.00					8.00											15.00	24.00		
006	11/10/2005	2:00	659.0			4.00								7.00							13.00	24.00		
007	12/10/2005	2:00	946.0	18.00																	6.00	24.00	18.00	15.95
008	13/10/2005	2:00	1,223.0	22.00			1.00														1.00	24.00	22.00	12.58
009	14/10/2005	2:00	1,430.0	15.00		6.00	2.00														1.00	24.00	15.00	13.82
010	15/10/2005	2:00	1,668.0	23.00																	1.00	24.00	23.00	10.34
011	16/10/2005	2:00	1,854.0	18.00		5.00															1.00	24.00	18.00	10.35
012	17/10/2005	2:00	2,088.0	22.00			1.00														1.00	24.00	22.00	10.63
013	18/10/2005	2:00	2,370.0	22.00			1.00														1.00	24.00	22.00	12.83
014	19/10/2005	2:00	2,399.0	4.00	3.00	12.00	1.00					1.00									3.00	24.00	5.00	7.24
015	20/10/2005	2:00	2,403.0	1.00	4.00	16.00	1.00														2.00	24.00	1.00	3.96
016	21/10/2005	2:00	2,403.0		2.00		1.00			18.00											3.00	24.00		
017	22/10/2005	2:00	2,403.0												4.00	15.00					5.00	24.00		
018	23/10/2005	2:00	2,403.0				1.00							4.00	6.00						13.00	24.00		
019	24/10/2005	2:00	2,533.0	14.00		4.50	1.00														4.50	24.00	14.00	9.27
020	25/10/2005	2:00	2,711.0	22.00			1.00														1.00	24.00	22.00	8.09
021	26/10/2005	2:00	2,788.0	22.00			1.00														1.00	24.00	22.00	3.51
022	27/10/2005	2:00	2,828.0	19.00		3.00	1.00														1.00	24.00	19.00	2.10
023	28/10/2005	2:00	2,875.0	22.00			1.00														1.00	24.00	22.00	2.13
024	29/10/2005	2:00	2,903.0	10.50	2.00	9.50	1.00														1.00	24.00	10.50	2.67
025	30/10/2005	2:00	2,903.0		2.00	20.00	1.00														1.00	24.00		

Well Name	AHUROA SOUTH B-1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Time Breakdown Summary Report

				Time																			
Rpt No	Rpt Date	Rpt Time	MD	Drilg	Circ	Trip	Rig Serv	Rig Repair	Rig Up/Dn	Run Csg	Core	Ream Time	DST	Test BOP	N. Up BOP	WOC	Fish	Log	Dir Work	Dir Svys	Other	Total Time	Rotate	Avg ROP
			m	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	m/hr
026	31/10/2005	2:00	2,985.0	21.00			1.00														2.00	24.00	21.00	3.90
027	01/11/2005	2:00	3,048.0	22.00			1.00														1.00	24.00	22.00	2.87
028	02/11/2005	2:00	3,109.0	22.00			1.00														1.00	24.00	22.00	2.77
029	03/11/2005	2:00	3,162.0	22.00			1.00														1.00	24.00	22.00	2.41
030	04/11/2005	2:00	3,191.0	17.00	2.00	3.00	1.00														1.00	24.00	17.00	1.70
031	05/11/2005	2:00	3,227.0	22.00			1.00														1.00	24.00	22.00	1.63
032	06/11/2005	2:00	3,296.0	17.00		3.00	1.00														3.00	24.00	17.00	4.07
033	07/11/2005	2:00	3,345.0	8.00	2.00	10.00	2.00														2.00	24.00	8.00	6.10
034	08/11/2005	2:00	3,370.0	2.50	2.00	13.50	1.00											4.00			1.00	24.00	2.50	10.00
035	09/11/2005	2:00	3,370.0		17.00	5.00	1.00														1.00	24.00		
036	10/11/2005	2:00	2,381.0			9.00															15.00	24.00		
037	11/11/2005	2:00	2,400.0			8.00	1.00									14.00					1.00	24.00		
038	12/11/2005	2:00	2,400.0																		24.00	24.00		
Total Hours :				**460.00**	**39.00**	**131.50**	**28.00**			**34.00**		**1.00**		**11.00**	**10.00**	**29.00**		**4.00**			**163.50**	**38.0 d**	**461.00**	

Well	AHUROA SOUTH B-1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Net Well Cost Breakdown

Cost Breakdown I $	Interval 01	Interval 02	Interval 03	Total
Fluid/Product: Drilling	19,441.52	65,857.04	93,358.75	178,657.31
Fluid/Product: Comp/Filtration				
Solids Control/Waste Management Cost				
Fluids/Products: Cementing Cost				
Engineering Services			28,000.00	28,000.00
Fluid/Product: Lost Damage				
Other Cost		729.39	493.24	1,222.63
Equipment Cost	180.00	1,380.00	1,320.00	2,880.00
Transport/Packaging Cost				
Total Cost	19,621.52	67,966.43	123,171.99	210,759.94

Cost Breakdown II $	Interval 01	Interval 02	Interval 03	Total
Total Products Cost	4,041.52	48,386.43	67,791.99	120,219.94
Total Fluids Cost			26,060.00	26,060.00
Total Charges Cost	15,580.00	18,180.00	30,720.00	64,480.00
Allocated To / From Other Interval		1,400.00	-1,400.00	
Total Cost	19,621.52	67,966.43	123,171.99	210,759.94
Planned Cost	21,059.00	82,661.00	82,521.00	186,241.00
Variance	-1,437.48	-14,694.57	40,650.99	24,518.94

Volume Breakdown bbl	Interval 01	Interval 02	Interval 03	Total
Total Base Fluids Addition			292.0	292.0
Total Chemical Addition	16.0	159.2	68.9	244.1
Total Barite Addition	4.5	18.0	33.7	56.2
Total Water Addition	987.5	2,156.6	253.0	3,397.1
Total Fluid Built	1,008.0	2,333.8	647.6	3,989.4
Total Fluid Received			1,046.7	1,046.7
Total Influx Addition				
Not Used In Interval			-379.5	
Total Fluid Volume	1,008.0	2,964.1	1,694.3	5,036.1

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	SwiftNZ SI/API mix

Total Cost Breakdown

	Unit Size	Quantity	Total Cost
Engineering/Services			
Drilling Fluids Engineer#1	day(s)	44.00	30,800.00
Drilling Fluids Engineer#2	day(s)	44.00	30,800.00
		SubTotal :	**$ 61,600.00**
Equipment Cost			
Mud Storage Tanks	day(s)	96.00	2,880.00
		SubTotal :	**$ 2,880.00**
Fluids/Products: Drilling Cost			
ALDACIDE G	5 gal can	14.00	1,748.04
BARABLOK	50 lb bag	64.00	2,046.72
BARACARB 150	50 lb bag	73.00	913.96
BARACARB 25	50 lb bag	220.00	2,754.40
BARAZAN D	25 kg bag	44.00	10,410.84
barite	1500 kg bag	25.00	7,903.50
BAROFIBRE	25 lb bag	256.00	8,158.72
BDF-303	180 kg drum	7.00	3,020.85
BDF-352	190 kg drum	3.00	
bentonite	25 kg bag	231.00	1,808.73
calcium chloride	25 kg bag	5.00	52.45
Calcium chloride 94%	1000 kg bag	2.00	741.52
caustic soda	25 kg pail	29.00	868.84
Drill Plug Medium	30 lb bag	130.00	
DURATONE HT	50 lb bag	12.00	
EZ MUL NT	190 kg drum	5.00	3,333.70
EZ-MUD DP	50 lb bag	39.00	3,008.85
GELTONE II	50 lb bag	27.00	
lime	25 kg bag	142.00	1,239.66
mica fine	25 kg bag	40.00	680.00
mica medium	25 kg bag	40.00	680.00
PAC-L	25 kg bag	21.00	1,945.02
PAC-R	25 kg bag	46.00	4,260.06
potassium chloride	1000 kg bag	39.00	18,434.13
Returned SOBM	bbl	-782.40	-78,240.00
RM-63 (RM 63)	181.4 kg drum	4.00	2,694.96
Saraline 185	42 gal drum	292.00	42,129.76
SHEARDRIL-N	bbl	293.00	29,300.00
SOBM	bbl	750.00	75,000.00
sodium bicarbonate	25 kg bag	10.00	162.60
		SubTotal :	**$ 145,057.31**
Other			
CON DET	5 gal can	5.00	236.15

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	SwiftNZ SI/API mix

Total Cost Breakdown

CON DET	55 gal drum	2.00	986.48
		SubTotal :	**$ 1,222.63**
		Total Well Cost:	**$ 210,759.94**

Conclusion and Recommendations

It is recommended that all three types of drilling fluid be used in other wells drilled in this area. They all performed as per programmed in drilling this well to completion. In the 6" hole section using the SBM the addition of BARABLOK while drilling the coal stringers seemed to help. These coal stringers were not anticipated in drilling this well. All three sections of hole were drilled with little to no hole problems.

In conclusion Baroid's mud engineers, chemicals and logistical team performed well in drilling this well with no serious hole problems.

Baroid Fluid Services

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Inventory Report

Interval # 01		**From Date**	**06/10/2005**	**Top of Interval**			**100.0 m**
Max. Hole Size / Bit Size	**13.350 / 12.250 in**	**To Date**	**09/10/2005**	**Bottom of Interval**			**659.0 m**
Product Name	**Units**	**Starting**	**Received**	**Used**	**Returned**	**Ending**	**Weight lb**
BARAZAN D	25 kg bag		51.0	3.0		48.0	2,645.55
barite	1500 kg bag		11.0	2.0		9.0	29,762.40
BDF-352	190 kg drum		5.0			5.0	2,094.39
bentonite	25 kg bag		640.0	231.0		409.0	22,542.27
caustic soda	25 kg pail		36.0	5.0		31.0	1,708.58
CON DET	5 gal can		5.0			5.0	213.71
Drill Plug Medium	30 lb bag		384.0	9.0		375.0	11,250.00
DURATONE HT	50 lb bag		12.0			12.0	600.00
GELTONE II	50 lb bag		27.0			27.0	1,350.00
M.E. Glycol	55 gal drum		2.0			2.0	1,009.14
PAC-R	25 kg bag		31.0	8.0		23.0	1,267.66
soda ash	25 kg bag		34.0			34.0	1,873.93
sodium bicarbonate	25 kg bag		10.0			10.0	551.16
					Total Weight of Products in Stock lb		**76,868.79**
					Total Weight of Products in Stock, Metric Tons		**34.87**

Baroid Fluid Services

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Inventory Report

Interval # 02		**From Date**	**10/10/2005**	**Top of Interval**		**659.0 m**	
Max. Hole Size / Bit Size	**9.000 / 8.500 in**	**To Date**	**21/10/2005**	**Bottom of Interval**		**2,403.0 m**	
Product Name	**Units**	**Starting**	**Received**	**Used**	**Returned**	**Ending**	**Weight lb**
ALDACIDE G	5 gal can		30.0	14.0		16.0	733.92
BARACARB 150	50 lb bag		78.0			78.0	3,900.00
BARACARB 25	50 lb bag		200.0	120.0		80.0	4,000.00
BARAZAN D	25 kg bag	48.0	40.0	41.0		47.0	2,590.43
barite	1500 kg bag	9.0	14.0	8.0		15.0	49,604.01
BAROFIBRE	25 lb bag		200.0	95.0		105.0	2,625.00
BDF-352	190 kg drum	5.0				5.0	2,094.39
bentonite	25 kg bag	409.0				409.0	22,542.27
caustic soda	25 kg pail	31.0		24.0		7.0	385.81
CON DET	5 gal can	5.0		5.0			
CON DET	55 gal drum		4.0	1.0		3.0	1,410.50
Drill Plug Medium	30 lb bag	375.0		72.0		303.0	9,090.00
DURATONE HT	50 lb bag	12.0				12.0	600.00
EZ-MUD DP	50 lb bag		55.0	39.0		16.0	800.00
GELTONE II	50 lb bag	27.0				27.0	1,350.00
M.E. Glycol	55 gal drum	2.0				2.0	1,009.14
mica fine	25 kg bag		40.0	40.0			
mica medium	25 kg bag		40.0	40.0			
PAC-L	25 kg bag		60.0	21.0		39.0	2,149.51
PAC-R	25 kg bag	23.0	30.0	38.0		15.0	826.73
potassium chloride	1000 kg bag		50.0	39.0		11.0	24,250.85
soda ash	25 kg bag	34.0				34.0	1,873.93
sodium bicarbonate	25 kg bag	10.0		10.0			
				Total Weight of Products in Stock lb			**131,836.48**
				Total Weight of Products in Stock, Metric Tons			**59.80**

Baroid Fluid Services

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Inventory Report

Interval # 03		**From Date**	**22/10/2005**		**Top of Interval**		**2,403.0 m**	
Max. Hole Size / Bit Size	**6.250 / 6.000 in**	**To Date**	**12/11/2005**		**Bottom of Interval**		**2,400.0 m**	
Product Name	**Units**	**Starting**	**Received**	**Used**	**Returned**	**Ending**	**Weight lb**	
ALDACIDE G	5 gal can	16.0			16.0			
BARABLOK	50 lb bag		100.0	64.0	36.0			
BARACARB 150	50 lb bag	78.0		73.0	5.0			
BARACARB 25	50 lb bag	80.0	160.0	100.0	140.0			
BARAZAN D	25 kg bag	47.0			47.0			
barite	1500 kg bag	15.0	13.0	15.0	13.0			
BAROFIBRE	25 lb bag	105.0	56.0	161.0				
BAROFIBRE COARSE	40 lb bag		65.0		65.0			
BDF-303	180 kg drum		8.0	7.0	1.0			
BDF-352	190 kg drum	5.0	2.0	3.0	4.0			
bentonite	25 kg bag	409.0			409.0			
calcium chloride	25 kg bag		80.0	5.0	75.0			
Calcium chloride 94%	1000 kg bag		2.0	2.0				
caustic soda	25 kg pail	7.0			7.0			
CON DET	5 gal can							
CON DET	55 gal drum	3.0		1.0	2.0			
Drill Plug Medium	30 lb bag	303.0		49.0	254.0			
DURATONE HT	50 lb bag	12.0	33.0	12.0	33.0			
EZ MUL NT	190 kg drum		5.0	5.0				
EZ-MUD DP	50 lb bag	16.0			16.0			
GELTONE II	50 lb bag	27.0	50.0	27.0	50.0			
lime	25 kg bag		222.0	142.0	80.0			
M.E. Glycol	55 gal drum	2.0			2.0			
mica fine	25 kg bag							
mica medium	25 kg bag							
OMC 3	25 kg pail		6.0		6.0			
PAC-L	25 kg bag	39.0			39.0			
PAC-R	25 kg bag	15.0			15.0			
potassium chloride	1000 kg bag	11.0			11.0			
RM-63 (RM 63)	181.4 kg drum		4.0	4.0				
Saraline 185	42 gal drum		292.0	292.0				
soda ash	25 kg bag	34.0			34.0			
sodium bicarbonate	25 kg bag							

Baroid Fluid Services

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Summary

Interval #	**1**	**Max Bit Size: 12.250 in**	**Hole Size Avg/Max**	**12.250 / 13.350 in**

Interval Start Date		06/10/2005	Planned Cost	$	21,059.00
Interval End Date		09/10/2005	Total Interval Cost	$	19,621.52
Interval TD Date		09/10/2005	Program Variance	$	-1,437.48
Drilling Days		4.00	Other material charges		
Rotating/Drilling Hours		52.00 / 52.00	Total Fluids Cost	$	19,441.52
Interval Top MD/TVD	m	100.0 / 100.0	Total Charges Cost	$	180.00
Interval End MD/TVD	m	659.0 / 659.0	Total Cementing Cost	$	0.00
Footage	m	559.0	Fluid Cost Per Vol Unit	$/bbl	19.29
Average ROP	m/hr	10.8	Fluid Cost/Hole Drilled	$/m	34.78
Max Hole Angle	degrees	0.00	Fluid Cost/Vol Drilled	$/bbl	72.72
Casing Size	in	0.000	Fluid Built	bbl	1,008.0
Casing Shoe MD	m	0.0	Total Additions/Vol Drilled	bbl/bbl	3.77
Casing Length	m	0.0	Total Additions/Hole Drilled	bbl/m	1.80
Bottom Hole Temp			Fluid Loss/Vol Drilled	bbl/bbl	0.64
Max Fluid Density	ppg	9.20	Fluid Loss/Hole Drilled	bbl/m	0.31

Interval Product and Base Fluids Usage and Cost

Product Function / Name	**Drilling Fluid**	**Packaging**	**Quantity Used**	**Product Cost**
Viscosifier/Suspension Agent				
BARAZAN D	Spud Mud	25 kg bag	3.000	709.83
bentonite	Spud Mud	25 kg bag	231.000	1,808.73
			Total	**$ 2,518.56**
Weighting Material				
barite	Spud Mud	1500 kg bag	2.000	632.28
			Total	**$ 632.28**
Alkalinity Control				
caustic soda	Spud Mud	25 kg pail	5.000	149.80
			Total	**$ 149.80**
Filtration Control				
PAC-R	Spud Mud	25 kg bag	8.000	740.88
			Total	**$ 740.88**
Lost Circulation/Bridging Agent				
Drill Plug Medium	Spud Mud	30 lb bag	9.000	0.00
			Total	**$ 0.00**

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Summary

Interval # 2	**Max Bit Size: 8.500 in**	**Hole Size Avg/Max**	**8.989 / 9.000 in**

Interval Start Date		10/10/2005	Planned Cost	$	82,661.00
Interval End Date		21/10/2005	Total Interval Cost	$	67,966.43
Interval TD Date		20/10/2005	Program Variance	$	-14,694.57
Drilling Days		9.00	Other material charges	$	729.39
Rotating/Drilling Hours		146.00 / 145.00	Total Fluids Cost	$	65,857.04
Interval Top MD/TVD	m	659.0 / 659.0	Total Charges Cost	$	1,380.00
Interval End MD/TVD	m	2,403.0 / 2,283.3	Total Cementing Cost	$	0.00
Footage	m	1,744.0	Fluid Cost Per Vol Unit	$/bbl	22.22
Average ROP	m/hr	12.0	Fluid Cost/Hole Drilled	$/m	37.76
Max Hole Angle	degrees	21.30	Fluid Cost/Vol Drilled	$/bbl	146.62
Casing Size	in	9.625	Fluid Built	bbl	2,333.8
Casing Shoe MD	m	652.0	Total Additions/Vol Drilled	bbl/bbl	6.60
Casing Length	m	652.0	Total Additions/Hole Drilled	bbl/m	1.70
Bottom Hole Temp			Fluid Loss/Vol Drilled	bbl/bbl	2.10
Max Fluid Density	ppg	9.35	Fluid Loss/Hole Drilled	bbl/m	0.54

Interval Product and Base Fluids Usage and Cost

Product Function / Name	Drilling Fluid	Packaging	Quantity Used	Product Cost
Bactericides				
ALDACIDE G	KCl/Polymer	5 gal can	14.000	1,748.04
			Total	**$ 1,748.04**
Viscosifier/Suspension Agent				
BARAZAN D	KCl/Polymer	25 kg bag	41.000	9,701.01
			Total	**$ 9,701.01**
Weighting Material				
barite	KCl/Polymer	1500 kg bag	8.000	2,529.12
			Total	**$ 2,529.12**
Lost Circulation/Bridging Agent				
BAROFIBRE	KCl/Polymer	25 lb bag	95.000	3,027.65
mica fine	KCl/Polymer	25 kg bag	40.000	680.00
mica medium	KCl/Polymer	25 kg bag	40.000	680.00
BARACARB 25	KCl/Polymer	50 lb bag	120.000	1,502.40
Drill Plug Medium	KCl/Polymer	30 lb bag	72.000	0.00
			Total	**$ 5,890.05**
Alkalinity Control				
caustic soda	KCl/Polymer	25 kg pail	24.000	719.04
sodium bicarbonate	KCl/Polymer	25 kg bag	10.000	162.60
			Total	**$ 881.64**
Detergent/Surfactanct				
CON DET	No Fluid	5 gal can	5.000	236.15
CON DET	No Fluid	5 gal can	1.000	493.24
			Total	**$ 729.39**
Shale Control				
EZ-MUD DP	KCl/Polymer	50 lb bag	39.000	3,008.85
potassium chloride	KCl/Polymer	1000 kg bag	39.000	18,434.13
			Total	**$ 21,442.98**

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Summary

Filtration Control				
PAC-L	KCl/Polymer	25 kg bag	21.000	1,945.02
PAC-R	KCl/Polymer	25 kg bag	38.000	3,519.18
			Total	**$ 5,464.20**

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Summary

Interval #	**3**	**Max Bit Size: 6.000 in**	**Hole Size Avg/Max**	**6.250 / 6.250 in**

Interval Start Date		22/10/2005	Planned Cost	$	82,521.00
Interval End Date		12/11/2005	Total Interval Cost	$	123,171.99
Interval TD Date		08/11/2005	Program Variance	$	40,650.99
Drilling Days		15.00	Other material charges	$	493.24
Rotating/Drilling Hours		263.00 / 263.00	Total Fluids Cost	$	93,358.75
Interval Top MD/TVD	m	2,403.0 / 2,283.3	Total Charges Cost	$	29,320.00
Interval End MD/TVD	m	2,400.0 / 2,281.9	Total Cementing Cost	$	0.00
Footage	m	0.0	Fluid Cost Per Vol Unit	$/bbl	55.10
Average ROP	m/hr	0.0	Fluid Cost/Hole Drilled	$/m	0.00
Max Hole Angle	degrees	22.20	Fluid Cost/Vol Drilled	$/bbl	0.00
Casing Size	in	7.000	Fluid Built	bbl	647.6
Casing Shoe MD	m	2,395.0	Total Additions/Vol Drilled	bbl/bbl	0.00
Casing Length	m	2,395.0	Total Additions/Hole Drilled	bbl/m	0.00
Bottom Hole Temp	Deg C	65	Fluid Loss/Vol Drilled	bbl/bbl	0.00
Max Fluid Density	ppg	8.90	Fluid Loss/Hole Drilled	bbl/m	0.00

Interval Product and Base Fluids Usage and Cost

Product Function / Name	Drilling Fluid	Packaging	Quantity Used	Product Cost
Filtration Control				
BARABLOK	SOBM	50 lb bag	64.000	2,046.72
DURATONE HT	SOBM	50 lb bag	12.000	0.00
BDF-352	SOBM	190 kg drum	3.000	0.00
			Total	**$ 2,046.72**
Weighting Material				
barite	SHEARDRIL-N	1500 kg bag	1.000	316.14
barite	SOBM	1500 kg bag	14.000	4,425.96
calcium chloride	SOBM	25 kg bag	5.000	52.45
Calcium chloride 94%	SOBM	1000 kg bag	2.000	741.52
			Total	**$ 5,536.07**
Lost Circulation/Bridging Agent				
BAROFIBRE	SHEARDRIL-N	25 lb bag	5.000	159.35
BAROFIBRE	SOBM	25 lb bag	156.000	4,971.72
BARACARB 150	SOBM	50 lb bag	73.000	913.96
BARACARB 25	SOBM	50 lb bag	100.000	1,252.00
Drill Plug Medium	SOBM	30 lb bag	49.000	0.00
			Total	**$ 7,297.03**
Detergent/Surfactanct				
CON DET	No Fluid	55 gal drum	1.000	493.24
			Total	**$ 493.24**
Emulsifier				
EZ MUL NT	SOBM	190 kg drum	5.000	3,333.70
BDF-303	SOBM	180 kg drum	7.000	3,020.85
			Total	**$ 6,354.55**
Viscosifier/Suspension Agent				
GELTONE II	SOBM	50 lb bag	27.000	0.00
RM-63 (RM 63)	SOBM	181.4 kg drum	4.000	2,694.96

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Summary

			Total	**$ 2,694.96**
Alkalinity Control				
lime	SOBM	25 kg bag	142.000	1,239.66
			Total	**$ 1,239.66**
Base Fluid				
Saraline 185	SOBM	42 gal drum	292.000	42,129.76
			Total	**$ 42,129.76**
Whole Fluid				
SHEARDRIL-N	SHEARDRIL-N	bbl	293.000	29,300.00
SOBM	SOBM	bbl	750.000	75,000.00
Returned SOBM	SOBM	bbl	782.400	-78,240.00
			Total	**$ 26,060.00**

Interval Discussion

Well Name	AHUROA SOUTH B-1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Interval #	01		From Report	001	Top of Interval	100.0	m
Max. Hole/Bit Size	13.350 / 12.250	in	To Report	004	Bottom of Interval	659.0	m

12-1/4" Hole Section

Section TD: 659 m
Casing: 9-5/8" casing set at 652 m
Drilling Days: 4 days
Average ROP: 10.8 m/hr
Formation: Mt Messenger.

Objectives

- Drill top hole without formation losses or wash-outs.
- Provide a well bore for a successful casing run and cementing operations.

Rig Abstract/Summary

The well was spudded on 5/10/05 at 1300hrs. After rigging up and pressure test all rig surface line a 12 ½ " bit was picked up together with drill collar. All spud mud was mixed using bentonite and caustic soda the day before well spudded in order to give bentonite time to yield. The top hole was planed to drill to 100m but after taking survey it was decided to drill to 200m. POOH to pick up directional BHA as per Sperry sun program. While drilling to 440m PAC R was add to active and pre mix just to tighten the fluid losses. Hi Vis sweep with drill plug were pump every connection to aid in hole cleaning. Continue drilling and slide to build angle to section TD at 659 m. Before POOH 15 bbls of hi Vis sweep was pump and circulate until hole was clean. A wiper trip to shoe was made. There was no tight spots encounter during POOH. BHA was lay down is safely manner. The 9-5/8" casing was set and cemented successfully at the depth of 652m as per program.

Cost Evaluation and Key Performance Indicators

- The added cost was due to rigging up time. Engineer cost was $15,580.00. The cost with out the engineering was $3,775.30

Interval Discussion

Well Name	AHUROA SOUTH B-1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Cost

	Programmed	Actual	Conformance
Volume Used bbl	**1541**	1132	Yes
Dilution Rate bbl/m	**1.2**	0.8	Yes
Cost $/m	**8.71**	6.13	Yes
Cost $/bbl	**3.67**	4.01	No
Total Interval Cost	**$ 5,659.32**	$4200	Yes

This interval was drilled within the programmed amount.

Targets

	Programmed	Actual	Conformance
Time Lost (hole instability)	**0**	0	Y
Reaming (unscheduled)	**0**	0	Y
Differential Sticking	**0**	0	Y
Hole Condition	**0**	0	Y

.

Mud Properties

	Programmed		Actual (Typical)	
	Minimum	Maximum	Minimum	Maximum
Density (ppg)	**8.7**	**9.2**	8.7	9.1
PV (cps)		**15**	3	13
YP (lbs/100ft2)	**20**	**25**	4	8
6rpm dial reading	**8**		2	5
API Fluid Loss		**<12**	8	26
pH	**9.5**		9	10.5

Fluid losses was lowered below 10 ml/30 min at 400 meters as per program

Zero Defects Tracking Summary / Explanation of Non-Conformance

- There were no non-conformance issues in the 12-1/4" section.

Maintenance Treatments

- Spud mud volume was built using bentonite, caustic soda and water.
- Drill and Production water was used to dilute the spud mud while drilling this section.
- PAC R polymer was added to tighten the API fluid loss.
- BARAZAN D PLUS with drill plug use for hi vis/LCM sweep.

Solids Control Evaluation

- The solids control equipment consisted of three DFE shakers, One Swaco 518 HS centrifuges, a desander and a desilter.
- The three DFE shakers were dressed with 110 mesh screens to finish this section of hole.
- Mud tanks were dumped as needed to maintain mud weights as per program.
- Centrifuge was not run for this section.
- Desander could not get to work in this section of hole.
- Desilter was run as needed. Could not run at all times,
- Both the desander and desilter need some work on them.
- Used 9 screens in drilling this section of hole. All 110 mesh

Volumes

- A total of 1168 bbls were used to drill the 12-1/4 inch section.
- All mud was dumped to reserve pit at the end of this section of hole

HSE

- There was no lose time due to HSE issues

Interval Discussion

Well Name	AHUROA SOUTH B-1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Interval #	02		From Report	005	Top of Interval	659.0	m
Max. Hole/Bit Size	9.000 / 8.500	in	To Report	016	Bottom of Interval	2,403.0	m

8.5" Hole Section KCL/PHPA. 10% KCL

Section TD: 659m - 2403m
Casing: 7" casing to 2395m.
Drilling Days: 9
Average ROP: 10 m/hr
Formation: Mt. Messenger. Tikorangi, Otaraoa

Objectives

- Drill 8.5" hole with minimum problems.
- Provide rheology for good hole cleaning at an angle of +/- 35 degrees.
- Provide a well bore for a successful electrical wire line logging program.
- Provide a well bore for a successful casing run and cement operations.

Rig Abstract/Summary

- After picking up 8.5" BHA we ran in the hole and tagged cement at 643 meters. Displaced hole to KCL/PHPA mud (10% KCL by wt.) and drilled out cement and shoe to 662 meters were a LOT was performed. System was per treated with Sodium Bicarbonate for cement contaminates.
- Drilled down to 1278 meters were a wipe trip was made. Pulled back to the shoe with no drag coming out. Ran back in the hole with no fill.
- Drilled down to 1440, meters were we encountered some down hole losses, approximately 30 bbls total. From 1440-1668 we had total losses of approximately 60 bbls.
- Continued drilling while pumping 5 barrel LCM sweeps containing 15 pounds per barrel of Drilplug, (5 lbs/bbl), Barofiber,(10 lbs/bbl) every connection.
- Drilled down to 1826 meters were a wiper trip was made. Pulled 40 stands with no drag in or out, No fill on bottom. Continued to drill while pumping sweeps every 3 to 4 connections.
- Drilled down to 2399 meters, this was called total depth. Pumped a 20 bbls sweep, circulated the hole clean and pumped a slug and pulled out to the shoe. There was no drag coming out of the hole.
- Ran back in the hole and hit a tight spot one stand of bottom. 20 meters. Kelley up and washed the last 20

meters to bottom.

- Circulated the hole clean with no increase of cuttings at the shakers.
- Pulled out of the hole and ran in with wire line log. Logged with no problems.
- Pulled logging tool out of the hole and ran back in the hole with drill pipe. Fill on bottom so wash the last 25 meters to bottom. Noticed at the shakers we were getting some sluffing shale.
- Pumped a 20 bbl LCM sweep and circulated the hole clean while noting still sluffing shale at the shakers.
- Spotted on bottom a weight 25 bbls of 11.3 ppg mud and pulled out of the hole lay down side ways.
- Rigged up and ran in the hole with the 7" casing to a depth of 2395 were the casing packed off and was stuck.
- Rigged up circulating head and circulated while trying to wash casing to bottom. Casing would not wash to bottom. While circulating the casing we had approximately 250 bbls of mud pumped into the formation.
- Rigged up cementers and pumped 88 bbls lead cement at 170 bbls of tail cement was pumped. The cement was displaced with SOBM.
- Waiting on cement and changing out spool and rams on BOP. Set casing slip and cut casing and nipple back up for next section of hole.

Cost Evaluation and Key Performance Indicators

Cost

	Programmed	Actual	Conformance
Volume Rec'd (Last well)	**0**		
New Volume Built	**3158**	1995.6	Yes
Dilution Rate	**1**	.8	Yes
Volume Recovered			
Consumption Rate (bbls/m)	**1.55**	1.1	Yes
Cost / m	**32.41**	29.34	Yes
Cost / bbl	**20.86**	22.22	No
Total Interval Cost	**65,860.93**	51,166	Yes

Targets

	Programmed	Actual	Conformance
Time Lost (hole instability)	0	0	
Reaming (unscheduled)	0	0	
Differential Sticking	0	1	**Casing**
Hole Condition	0	0	

Mud Properties - KCL/PHPA with 10% KCL

	Programmed		Actual (Typical)	
	Minimum	Maximum	Minimum	Maximum
Density (ppg)	**9**	**9.2**	9	9.4
PV (cps)		**< 20**	8	18
YP (lbs/100ft2)	**10**	**20**	10	26
Tau 0 (lbs/100ft2)	**> 4**		2	5.9
Fluid Loss		**< 6***	5	6.8
KCL% by wt.	**8**	**10**	8	11
MBT		**<10**	2.5	10
Solids		**< 5**	2.1	3.4
6 RPM reading	**10**	**14**	5	9

Mud weights ran higher due to the addition of the 10% KCL. <9.4 ppg. This program was figured on the 6% KCL. Calcium Carbonate was added to the system to aid in down hole losses. 12 lbs per barrel

Zero Defects Tracking Summary / Explanation of Non-Conformance

- While running the 7" casing it was landed short due to hole packing off.

Maintenance Treatments

- All chemicals were mixed as per program
-

Solids Control Evaluation

- The three DFE shakers were dressed with 110 mesh screens and changed over to 175 mesh. Drilled this section using just 175 due to all the calcium carbonate and LCM used in this section of hole.
- Used 9 (110 screens) and 24 (175 mesh screens) to drill this section of hole.
- Holes are being punched into the screens due to all the gumbo drilling in this section. Need to have the square plugs to patch these screens and would save a lot of money on screens.

- One Swaco 518 HS centrifuges was in use while drilling this section. It was run almost continuously while

drilling.

- The Desilter was run as needed to help maintain mud weight as per program. Could not run at all times due to the Desilter kicking out to much mud. Does not preform as it should. Desander was not used due to desander kicking out to much mud.

Volumes

- All new mud was build for this section of hole. A total of 1995.6 bbls of mud were build
- Down hole losses 462.8 bbls
- Solids control equipment 416.9
- Miscellaneous losses. Dumped mud and hoses. 915.6 bbls
- 556.2 bbls of mud were dumped at the end of this section of hole.

HSE

- There was no time lost due to HSE issues
- All material was delivered in a timely manner.

Interval Discussion

Well Name	AHUROA SOUTH B-1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Interval #	03		From Report	017	Top of Interval	2,403.0	m
Max. Hole/Bit Size	6.250 / 6.000	in	To Report	038	Bottom of Interval	2,400.0	m

6" Hole Section - Reservoir Section

Section TD: 2395m - 3197m
Casing: Side track.
Drilling Days: 14
Average ROP: 3.7 m/hr
Formation: Tariki, McKeE, Mangahewa, Ahuroa Thrust

Objectives

- Effectively and efficiently displace well to the SBM.
- Provide a rheology for good hole cleaning at an angle of +/- 35 degrees.
- Provide a well bore for a successful electrical wire line logging program.
- Provide a well bore for a successful casing run and cement operations.

Rig Abstract/Summary

- After running in the 7" casing and displace cement with SBM the mud tanks were cleaned and filled with Oil base mud form the PIAKAU A-2 well. 974 bbls of mud were shipped over.
- Ran in the hole with new 6" BHA and tagged cement at 2379 meters. Test casing and shoe.
- Drilled form 2379-2828 meters were a wipe trip was ran. There were no tight spots or drag during this wiper trip.
- At 2828 meters it was decided to increase the mud weight form 8.5 ppb to 8.6 ppb. Here we were showing .5% connection gas.
- Drilled form 2828-2903 meters. Pulled out of the hole for new BHA. Ran back in the hole with no drag or tight spots. No fill on bottom. Sweeps were being pumped every three to four connections to aid in hole cleaning.(5ppb of Barofiber fine and 15 ppb CaCo3)
- When on bottom the MWD failed so we pulled out of the hole to change out MWD.
- Drilled form 2903-3109 meters were we increased the mud weight form 8.6 ppb to 8.7 ppb. Still showing about .5% connection gas.
- Drilled down to 3191 meters were a wiper tip back to 2849 meters. The hole was still in good shape. No drag or

fill on bottom.

- Drilled down to 3296 and a TVD of 3148 meters were we encountered some sluffing shale. Hole packed of but working the pipe and pumping two sweeps this cleaned up. Shakers showed large amounts of coal at the shakers. Here it was decided to add 4 lbs/bbl BARABLOK and increase the mud weight to 8.8 ppb.
- Here it was decided to pull out of the hole and change out the BHA.
- Ran back in the hole circulating at the shoe while adding the 4 lbs/bbl Barablok. One complete bottom up. Ran back to 3 joints off bottom and circulated while adding in the rest of the BARABLOK. Washed the last three joint to bottom with no tight spots or fill. Continued to drill.
- Drilled down to the Ahuroa fault and 50 meters for rat hole. 3370 meters and TVD of 3219 meters. Pumped sweep and circulated shakers clean. Pulled up 4 stands to 3700 and spotted a weight pill on bottom and pumped slug and pulled out of the hole to run logs.
- Ran in hole with two sets of logs, No problems
- Pick up cement stinger and ran back in the hole to the shoe. Circulating waiting on orders.
- Set kick off plug at 2380 meters.
- Start of side track #1 AHOURA B-1

Cost Evaluation and Key Performance Indicators

	Programmed	Actual	Conformance
Volume Rec'd (Last well)	**750**	974	
New Volume Built	**438**	436.4	Yes
Dilution Rate	**.5**	.25	Yes
Volume Recovered		782	
Consumption Rate (bbl/m)	**1.59**	.71	Yes
Cost / m	**71.12**	117	No
Cost / bbl	**121.10**	88.04	Yes
Total Interval Cost	**53201.10**	93,851	No

Cost

Note: 141 bbls of SBM lost down-hole and 129 bbls lost behind casing contributed to the cost over-run for this interval. In addition the SBM was treated with BARABLOK to control the unexpected coal seams.

Targets

Interval Discussion

Well Name	AHUROA SOUTH B-1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

	Programmed	Actual	Conformance
Time Lost (hole instability)	0	1	**N**
Reaming (unscheduled)	0	0	**Y**
Differential Sticking	0	0	**Y**
Hole Condition	0	0	**Y**

Mud Properties - SOBM

	Programmed		Actual (Typical)	
	Minimum	Maximum	Minimum	Maximum
Density (ppg)	**8.4**	**9.2**	8.5	8.9
PV (cps)		**< 40**	21	32
YP (lbs/100ft2)	**9**	**13**	14	26
Tau 0 (lbs/100ft2)	**> 4**		2.51	7.21
HTHP Fluid Loss		**< 4***	.5	4.8
Electrical Stability	**> 500**		895	1336
Water Content		**<30**	10	16
LGS		**< 5**	1.8	5.1

* HTHP Fluid Loss results at 180F
** Actual HTHP Fluid Loss tested at 250F

Zero Defects Tracking Summary / Explanation of Non-Conformance

- There were no non-conformance in this section of hole.

Maintenance Treatments

- All chemicals were mixed as per program
- Saraline base oil was added to the system to control rheology properties as per program.

- The addiction of BARABLOK was added to the system due to the coal stringer that were encountered while drilling this section on hole.
- RM-63 was added to the system to aid in low end rheology. This was due to running the lower viscosity and lower mud weights for drilling this section of hole. Controlling ECD in the 6" hole.
- Sweeps were pumped every three to four connections to aid in hole clean.(5 ppb Barafiber fine and 15 ppb Baracarb #25 were used in these sweeps). Showing no fill to little to no tight spots in this section of hole.

Solids Control Evaluation

- The three DFE shakers were dressed with 210 mesh screens throughout the section. Only two shakers were used to drill this section of hole due to the slow pump rate. 6" hole

- One Swaco 518 HS centrifuges were in use while drilling this section. it was run 4 to 5 hours per tour to lower LGS due to using used SBM. This maintained the LGS less than 5% while drilling this section of hole

Volumes

- 974 bbls of COREDRIL-N volume was received from Piakani North A-2 well. This Coredril-N had 12% water when transferred to this well. This mud is to be made into SOMB. Charged off at $100.00 bbls
- 251 bbls of SOBM (70/30) were mixed at the BAROID LMP and delivered to the location.
- 782 bbls of SBM remained at the end of the section. Transferred to side track well

HSE

- There was no time lost due to HSE issues
- All material was delivered in a timely manner.

Baroid Fluid Services

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Cost Breakdown

Interval #	**01**	**From Date**	**06/10/2005**	**Top of Interval**	**100.0 m**
Max. Hole Size / Bit Size	**13.350 / 12.250 in**	**To Date**	**09/10/2005**	**Bottom of Interval**	**659.0 m**

Material	Unit Size	Quantity		Total Cost
Engineering/Services				
Drilling Fluids Engineer#1		11.00	$	7,700.00
Drilling Fluids Engineer#2		11.00	$	7,700.00
		SubTotal	**$**	**15,400.00**
Equipment Cost				
Mud Storage Tanks		6.00	$	180.00
		SubTotal	**$**	**180.00**
Prod/Fluids: Drilling				
BARAZAN D	25 kg bag	3.00	$	709.83
barite	1500 kg bag	2.00	$	632.28
bentonite	25 kg bag	231.00	$	1,808.73
caustic soda	25 kg pail	5.00	$	149.80
Drill Plug Medium	30 lb bag	9.00	$	0.00
PAC-R	25 kg bag	8.00	$	740.88
		SubTotal	**$**	**4,041.52**
		Interval Total Cost	**$**	**19,621.52**

Charged To/From Other Interval	**$**	
Net Interval Total Cost	**$**	**19,621.52**
Programmed Cost	**$**	**21,059.00**
Program Variance	**$**	**-1,437.48**

Baroid Fluid Services

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Cost Breakdown

Interval # 02		**From Date**	**10/10/2005**	**Top of Interval**	**659.0 m**
Max. Hole Size / Bit Size	**9.000 / 8.500 in**	**To Date**	**21/10/2005**	**Bottom of Interval**	**2,403.0 m**

Material	Unit Size	Quantity		Total Cost
Engineering/Services				
Drilling Fluids Engineer#1		12.00	$	8,400.00
Drilling Fluids Engineer#2		12.00	$	8,400.00
		SubTotal	**$**	**16,800.00**
Equipment Cost				
Mud Storage Tanks		46.00	$	1,380.00
		SubTotal	**$**	**1,380.00**
Prod/Fluids: Drilling				
ALDACIDE G	5 gal can	14.00	$	1,748.04
BARACARB 25	50 lb bag	120.00	$	1,502.40
BARAZAN D	25 kg bag	41.00	$	9,701.01
barite	1500 kg bag	8.00	$	2,529.12
BAROFIBRE	25 lb bag	95.00	$	3,027.65
caustic soda	25 kg pail	24.00	$	719.04
Drill Plug Medium	30 lb bag	72.00	$	0.00
EZ-MUD DP	50 lb bag	39.00	$	3,008.85
mica fine	25 kg bag	40.00	$	680.00
mica medium	25 kg bag	40.00	$	680.00
PAC-L	25 kg bag	21.00	$	1,945.02
PAC-R	25 kg bag	38.00	$	3,519.18
potassium chloride	1000 kg bag	39.00	$	18,434.13
sodium bicarbonate	25 kg bag	10.00	$	162.60
		SubTotal	**$**	**47,657.04**
Other Cost				
CON DET	5 gal can	5.00	$	236.15
CON DET	55 gal drum	1.00	$	493.24
		SubTotal	**$**	**729.39**
		Interval Total Cost	**$**	**66,566.43**
		Charged To/From Other Interval	**$**	**1,400.00**
		Net Interval Total Cost	**$**	**67,966.43**
		Programmed Cost	**$**	**82,661.00**
		Program Variance	**$**	**-14,694.57**

Baroid Fluid Services

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Cost Breakdown

Interval # 03		**From Date**	**22/10/2005**	**Top of Interval**	**2,403.0 m**
Max. Hole Size / Bit Size	**6.250 / 6.000 in**	**To Date**	**12/11/2005**	**Bottom of Interval**	**2,400.0 m**

Material	Unit Size	Quantity		Total Cost
Engineering/Services				
Drilling Fluids Engineer#1		21.00	$	14,700.00
Drilling Fluids Engineer#2		21.00	$	14,700.00
		SubTotal	**$**	**29,400.00**
Equipment Cost				
Mud Storage Tanks		44.00	$	1,320.00
		SubTotal	**$**	**1,320.00**
Prod/Fluids: Drilling				
BARABLOK	50 lb bag	64.00	$	2,046.72
BARACARB 150	50 lb bag	73.00	$	913.96
BARACARB 25	50 lb bag	100.00	$	1,252.00
barite	1500 kg bag	15.00	$	4,742.10
BAROFIBRE	25 lb bag	161.00	$	5,131.07
BDF-303	180 kg drum	7.00	$	3,020.85
BDF-352	190 kg drum	3.00	$	0.00
calcium chloride	25 kg bag	5.00	$	52.45
Calcium chloride 94%	1000 kg bag	2.00	$	741.52
Drill Plug Medium	30 lb bag	49.00	$	0.00
DURATONE HT	50 lb bag	12.00	$	0.00
EZ MUL NT	190 kg drum	5.00	$	3,333.70
GELTONE II	50 lb bag	27.00	$	0.00
lime	25 kg bag	142.00	$	1,239.66
RM-63 (RM 63)	181.4 kg drum	4.00	$	2,694.96
Saraline 185	42 gal drum	292.00	$	42,129.76
SHEARDRIL-N	bbl	293.00	$	29,300.00
Returned SOBM	bbl	1,532.40	$	-3,240.00
		SubTotal	**$**	**93,358.75**
Other Cost				
CON DET	55 gal drum	1.00	$	493.24
		SubTotal	**$**	**493.24**
		Interval Total Cost	**$**	**124,571.99**
	Charged To/From Other Interval		**$**	**-1,400.00**
	Net Interval Total Cost		**$**	**123,171.99**
	Programmed Cost		**$**	**82,521.00**
	Program Variance		**$**	**40,650.99**

Baroid Fluid Services

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Inventory Report

Interval # 01		**From Date**	**06/10/2005**	**Top of Interval**			**100.0 m**
Max. Hole Size / Bit Size	**13.350 / 12.250 in**	**To Date**	**09/10/2005**	**Bottom of Interval**			**659.0 m**
Product Name	**Units**	**Starting**	**Received**	**Used**	**Returned**	**Ending**	**Weight lb**
BARAZAN D	25 kg bag		51.0	3.0		48.0	2,645.55
barite	1500 kg bag		11.0	2.0		9.0	29,762.40
BDF-352	190 kg drum		5.0			5.0	2,094.39
bentonite	25 kg bag		640.0	231.0		409.0	22,542.27
caustic soda	25 kg pail		36.0	5.0		31.0	1,708.58
CON DET	5 gal can		5.0			5.0	213.71
Drill Plug Medium	30 lb bag		384.0	9.0		375.0	11,250.00
DURATONE HT	50 lb bag		12.0			12.0	600.00
GELTONE II	50 lb bag		27.0			27.0	1,350.00
M.E. Glycol	55 gal drum		2.0			2.0	1,009.14
PAC-R	25 kg bag		31.0	8.0		23.0	1,267.66
soda ash	25 kg bag		34.0			34.0	1,873.93
sodium bicarbonate	25 kg bag		10.0			10.0	551.16
					Total Weight of Products in Stock lb		**76,868.79**
					Total Weight of Products in Stock, Metric Tons		**34.87**

Baroid Fluid Services

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Inventory Report

Interval # 02		**From Date**	**10/10/2005**	**Top of Interval**		**659.0 m**	
Max. Hole Size / Bit Size	**9.000 / 8.500 in**	**To Date**	**21/10/2005**	**Bottom of Interval**		**2,403.0 m**	
Product Name	**Units**	**Starting**	**Received**	**Used**	**Returned**	**Ending**	**Weight lb**
ALDACIDE G	5 gal can		30.0	14.0		16.0	733.92
BARACARB 150	50 lb bag		78.0			78.0	3,900.00
BARACARB 25	50 lb bag		200.0	120.0		80.0	4,000.00
BARAZAN D	25 kg bag	48.0	40.0	41.0		47.0	2,590.43
barite	1500 kg bag	9.0	14.0	8.0		15.0	49,604.01
BAROFIBRE	25 lb bag		200.0	95.0		105.0	2,625.00
BDF-352	190 kg drum	5.0				5.0	2,094.39
bentonite	25 kg bag	409.0				409.0	22,542.27
caustic soda	25 kg pail	31.0		24.0		7.0	385.81
CON DET	5 gal can	5.0		5.0			
CON DET	55 gal drum		4.0	1.0		3.0	1,410.50
Drill Plug Medium	30 lb bag	375.0		72.0		303.0	9,090.00
DURATONE HT	50 lb bag	12.0				12.0	600.00
EZ-MUD DP	50 lb bag		55.0	39.0		16.0	800.00
GELTONE II	50 lb bag	27.0				27.0	1,350.00
M.E. Glycol	55 gal drum	2.0				2.0	1,009.14
mica fine	25 kg bag		40.0	40.0			
mica medium	25 kg bag		40.0	40.0			
PAC-L	25 kg bag		60.0	21.0		39.0	2,149.51
PAC-R	25 kg bag	23.0	30.0	38.0		15.0	826.73
potassium chloride	1000 kg bag		50.0	39.0		11.0	24,250.85
soda ash	25 kg bag	34.0				34.0	1,873.93
sodium bicarbonate	25 kg bag	10.0		10.0			
				Total Weight of Products in Stock lb			**131,836.48**
				Total Weight of Products in Stock, Metric Tons			**59.80**

Baroid Fluid Services

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Inventory Report

Interval # 03		**From Date**	**22/10/2005**		**Top of Interval**		**2,403.0 m**	
Max. Hole Size / Bit Size	**6.250 / 6.000 in**	**To Date**	**12/11/2005**		**Bottom of Interval**		**2,400.0 m**	
Product Name	**Units**	**Starting**	**Received**	**Used**	**Returned**	**Ending**	**Weight lb**	
ALDACIDE G	5 gal can	16.0			16.0			
BARABLOK	50 lb bag		100.0	64.0	36.0			
BARACARB 150	50 lb bag	78.0		73.0	5.0			
BARACARB 25	50 lb bag	80.0	160.0	100.0	140.0			
BARAZAN D	25 kg bag	47.0			47.0			
barite	1500 kg bag	15.0	13.0	15.0	13.0			
BAROFIBRE	25 lb bag	105.0	56.0	161.0				
BAROFIBRE COARSE	40 lb bag		65.0		65.0			
BDF-303	180 kg drum		8.0	7.0	1.0			
BDF-352	190 kg drum	5.0	2.0	3.0	4.0			
bentonite	25 kg bag	409.0			409.0			
calcium chloride	25 kg bag		80.0	5.0	75.0			
Calcium chloride 94%	1000 kg bag		2.0	2.0				
caustic soda	25 kg pail	7.0			7.0			
CON DET	5 gal can							
CON DET	55 gal drum	3.0		1.0	2.0			
Drill Plug Medium	30 lb bag	303.0		49.0	254.0			
DURATONE HT	50 lb bag	12.0	33.0	12.0	33.0			
EZ MUL NT	190 kg drum		5.0	5.0				
EZ-MUD DP	50 lb bag	16.0			16.0			
GELTONE II	50 lb bag	27.0	50.0	27.0	50.0			
lime	25 kg bag		222.0	142.0	80.0			
M.E. Glycol	55 gal drum	2.0			2.0			
mica fine	25 kg bag							
mica medium	25 kg bag							
OMC 3	25 kg pail		6.0		6.0			
PAC-L	25 kg bag	39.0			39.0			
PAC-R	25 kg bag	15.0			15.0			
potassium chloride	1000 kg bag	11.0			11.0			
RM-63 (RM 63)	181.4 kg drum		4.0	4.0				
Saraline 185	42 gal drum		292.0	292.0				
soda ash	25 kg bag	34.0			34.0			
sodium bicarbonate	25 kg bag							

Company	**Swift Energy NZ Ltd**
Well Name	**AHUROA SOUTH B-1**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Fluid Volume Record Report

			Additions								Losses						Volumes			
Report No	Date	Initial Volume	Received	Mixed	Base	Water	Barite	Chemicals	Other	Daily Total	SCE	Downhole	Misc	Mixed	Returned	Daily Total	Hole Volume	Active Pit Volume	Reserve Volume	Final Volume
		bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl
Interval # 01																				
Fluid Name: Spud Mud																				
001	6/10/2005					597.9		9.0		606.9	12.0					12.0	19.9	416.0	159.0	594.9
002	7/10/2005	594.9				213.0	2.2	1.5		216.7	47.4	8.0	145.0			200.4	104.2	380.0	127.0	611.2
003	8/10/2005	611.2				140.7		3.4		144.1	48.2	10.0	42.0			100.2	260.1	365.0	30.0	655.1
004	9/10/2005	655.1				35.9	2.2	2.1		40.2	36.0	6.0	23.1			65.1	315.2	295.0	20.0	630.2
Cumulative Volume						987.5	4.4	16.0		1,007.9	143.6	24.0	210.1			377.7				

Company	**Swift Energy NZ Ltd**
Well Name	**AHUROA SOUTH B-1**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Fluid Volume Record Report

			Additions								Losses						Volumes			
Report No	Date	Initial Volume	Received	Mixed	Base	Water	Barite	Chemicals	Other	Daily Total	SCE	Downhole	Misc	Mixed	Returned	Daily Total	Hole Volume	Active Pit Volume	Reserve Volume	Final Volume
		bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl
Interval # 02																				
Fluid Name:		**KCl/Polymer**																		
005	10/10/2005					453.5		21.5		475.0									475.0	475.0
006	11/10/2005	475.0				63.4		0.6		64.0			24.0			24.0			515.0	515.0
007	12/10/2005	515.0				235.9		21.1		257.0	45.0	15.0				60.0	207.0	390.0	115.0	712.0
008	13/10/2005	712.0				152.0		11.0		163.0	48.8	15.0	70.0			133.8	272.2	389.0	80.0	741.2
009	14/10/2005	741.2				197.9		16.1		214.0	52.0	18.0	59.4			129.4	320.9	410.0	95.0	825.9
010	15/10/2005	825.9				177.8		21.2		199.0	53.7	75.2				128.9	376.9	395.0	124.0	895.9
011	16/10/2005	895.9				168.5		19.8		188.3	38.5	15.0	30.0			83.5	420.7	398.0	182.0	1,000.7
012	17/10/2005	1,000.7				166.6		13.3		179.9	53.0	16.0	85.0			154.0	477.6	413.0	136.0	1,026.6
013	18/10/2005	1,026.6				124.9		23.3		148.2	54.0	15.6	60.0			129.6	542.2	408.0	95.0	1,045.2
014	19/10/2005	1,045.2				178.9	6.7	7.4		193.0	48.9	26.0	19.0			93.9	610.3	415.0	119.0	1,144.3
015	20/10/2005	1,144.3				0.2	9.0	3.8		13.0	23.0	17.0	12.0			52.0	611.3	364.0	130.0	1,105.3
016	21/10/2005	1,105.3				76.0	2.2			78.2		250.0	556.2			806.2	377.3			377.3
Cumulative Volume						1,995.6	17.9	159.1		2,172.6	416.9	462.8	915.6			1,795.3				
Fluid Name:		**Spud Mud**																		
005	10/10/2005	630.2											628.3			628.3				
006	11/10/2005					161.0				161.0							161.1			161.1
007	12/10/2005	161.1											161.0			161.0				
Cumulative Volume						161.0				161.0			789.3			789.3				

Baroid Fluid Services

Company	Swift Energy NZ Ltd
Well Name	AHUROA SOUTH B-1
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Fluid Volume Record Report

			Additions								Losses						Volumes			
Report No	Date	Initial Volume	Received	Mixed	Base	Water	Barite	Chemicals	Other	Daily Total	SCE	Downhole	Misc	Mixed	Returned	Daily Total	Hole Volume	Active Pit Volume	Reserve Volume	Final Volume
		bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl
Interval # 03																				
Fluid Name:	**KCl/Polymer**																			
017	22/10/2005	377.3											377.2			377.2				
Cumulative Volume													377.2			377.2				
Fluid Name:	**SHEARDRIL-N**																			
017	22/10/2005		292.9							292.9			0.9	292.0		292.9				
018	23/10/2005						2.2	0.3		2.5			2.5			2.5				
Cumulative Volume			292.9				2.2	0.3		295.4			3.4	292.0		295.4				
Fluid Name:	**SOBM**																			
017	22/10/2005		1.8	292.0						293.8			0.9			0.9	292.9			292.9
018	23/10/2005	292.9	752.0		214.0			17.5		983.5			51.5			51.5	292.9	255.0	677.0	1,224.9
019	24/10/2005	1,224.9						4.1		4.1	22.0	4.0	9.9			35.9	263.1	332.0	598.0	1,193.1
020	25/10/2005	1,193.1						2.6		2.6	35.0	15.4	3.0			53.4	282.2	337.0	523.0	1,142.2
021	26/10/2005	1,142.2			8.0			1.3		9.3	30.0	12.0	4.0			46.0	290.5	324.0	491.0	1,105.5
022	27/10/2005	1,105.5			6.0		4.5	4.5		15.0	19.7	14.0				33.7	294.8	345.0	447.0	1,086.8
023	28/10/2005	1,086.8			6.0			4.2		10.2	20.0	6.2	1.0			27.2	299.9	326.0	444.0	1,069.9
024	29/10/2005	1,069.9			6.0		4.5	1.1		11.6	17.0	8.0				25.0	348.5	282.0	426.0	1,056.5
025	30/10/2005	1,056.5					4.5	0.8		5.3	8.4	4.0	8.0			20.4	315.4	315.0	411.0	1,041.4
026	31/10/2005	1,041.4					4.5	4.3		8.8	17.4	12.0	1.0			30.4	311.8	343.0	365.0	1,019.8
027	1/11/2005	1,019.8			6.0			2.6		8.6	17.6	7.0	1.2			25.8	318.6	338.0	346.0	1,002.6
028	2/11/2005	1,002.6									16.0	10.0	1.4			27.4	325.1	329.0	321.0	975.1
029	3/11/2005	975.1			12.0			3.9		15.9	26.7	10.0	1.5			38.2	330.8	335.0	287.0	952.8
030	4/11/2005	952.8						4.2		4.2	18.0	4.1	1.0			23.1	334.0	343.0	257.0	934.0
031	5/11/2005	934.0			8.0		2.2	1.3		11.5	19.7	8.0				27.7	337.8	324.0	256.0	917.8
032	6/11/2005	917.8			6.0		4.5	5.8		16.3	12.7	10.0	6.0			28.7	346.4	344.0	215.0	905.4

Company	**Swift Energy NZ Ltd**
Well Name	**AHUROA SOUTH B-1**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Fluid Volume Record Report

			Additions								Losses						Volumes			
Report No	Date	Initial Volume bbl	Received bbl	Mixed bbl	Base bbl	Water bbl	Barite bbl	Chemicals bbl	Other bbl	Daily Total bbl	SCE bbl	Downhole bbl	Misc bbl	Mixed bbl	Returned bbl	Daily Total bbl	Hole Volume bbl	Active Pit Volume bbl	Reserve Volume bbl	Final Volume bbl
033	7/11/2005	905.4			6.0			5.6		11.6	3.0	2.5	6.0			11.5	342.6	350.0	213.0	905.6
034	8/11/2005	905.6			14.0		2.2	0.7		16.9	5.0	6.0	6.2			17.2	413.3	285.0	207.0	905.3
035	9/11/2005	905.3									4.0	4.0	5.0			13.0	374.3	314.0	204.0	892.3
036	10/11/2005	892.3					2.2			2.2	2.0	4.0	134.4			140.4	257.5	295.0	248.0	800.5
037	11/11/2005	800.5						2.5		2.5	16.0		4.6			20.6	253.0	296.6	232.8	782.4
038	12/11/2005	782.5					2.2	1.3		3.5					785.9	785.9				
Cumulative Volume			753.8	292.0	292.0		31.3	68.3		1,437.4	310.2	141.2	246.6		785.9	1,483.9				

Fluid Name: Water

038	12/11/2005					253.0				253.0							253.0			253.0
Cumulative Volume						253.0				253.0										

Baroid Fluid Services

Operator	Swift Energy NZ Ltd
Well Name	AHUROA SOUTH B-1
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Fluid Property Recap : Water-Based Fluid

Date	Depth	FL Temp	Density	Funn Visc	Rheology 49 Deg C					Filtration					Filtrate Analysis						MBT	Sand	Retort Analysis				Rheometer Dial Readings					
					PV	lbs/100 ft2				API	HTHP	Cake API	Cake HTHP	Temp	pH	Pm	Pf	Mf	Cl	Total Hardness	ppb Eq.	% by vol	% by vol				600	300	200	100	6	3
	m	Deg C	ppg	sec/qt	cP	YP	10S	10M	30M	ml/30 min	ml/30 min	32nd in		Deg C		ml	ml	ml	mg/l	mg/l			Corr Solid	LGS	NAP Base	Water						
Interval # 01										**From Date**				**06/10/2005**						**Top of Interval**			**100.0**		**m**						
Max. Hole Size / Bit Size 13.350 / 12.250 in										**To Date**				**09/10/2005**						**Bottom of Interval**			**659.0**		**m**						
06/10/2005	20	22	8.70	42	8	16	18	22	30	18.0		3			9.50	1.80	0.90	1.40	800	120	12.0		1.73	0.694		98	32.0	24.0	20.0	18.0	12.0	8.0
06/10/2005	90	20	9.00	44	11	8	16	20	24	22.0		3			9.50	0.15	0.12	0.50	720	110	20.0	0.15	2.94	0.854		96.8	30.0	19.0	15.0	12.0	10.0	8.0
07/10/2005	173	20	9.20	43	8	14	11	21	26	24.0		3			9.50	0.20	0.10	0.40	800	120	20.0	0.20	4.24	1.966		95.5	30.0	22.0	19.0	15.0	12.0	10.0
08/10/2005	589	25	9.10	42	6	18	12	23	28	10.0		3			9.50	0.25	0.15	0.35	750	100	22.0	0.20	4.04	2.313		95.7	30.0	24.0	20.0	18.0	12.0	10.0
09/10/2005	659	25	9.20	42	8	17	12	22	27	8.0		2			9.50	0.20	0.15	0.40	650	110	22.0		4.34	2.164		95.4	33.0	25.0	20.0	17.0	13.0	10.0
Interval # 02										**From Date**				**10/10/2005**						**Top of Interval**			**659.0**		**m**						
Max. Hole Size / Bit Size 9.000 / 8.500 in										**To Date**				**21/10/2005**						**Bottom of Interval**			**2,403.0**		**m**						
10/10/2005	659	22	8.77	38	11	14	3	5	8	10.2		1			7.20				45,200	100	5.0		0.6	1.559		95.6	36.0	25.0	18.0	12.0	4.0	3.0
11/10/2005	659		8.77	39	10	16	4	5		10.2		1			7.20	0.05	0.02	0.08	42,000	100	5.0		0.67	1.453		95.8	36.0	26.0	18.0	12.0	4.0	3.0
12/10/2005	946	42	9.05	48	8	16	5	6	8	6.2		1			11.90	0.50	0.20	0.40	40,000	110	5.0	0.50	1.26	0.357		95.4	32.0	24.0	18.0	12.0	5.0	3.0
13/10/2005	1,069	41	9.20	39	9	14	3	5	7	5.5		1			9.50	0.20	0.15	0.30	52,000	120	5.0	0.25	2.09	1.779		93.6	32.0	23.0	17.0	12.0	4.0	3.0
14/10/2005	1,430	42	9.20	44	12	23	6	12	17	5.8		1			9.20	0.15	0.10	0.24	49,000	120	5.0	0.25	2.45	2.271		93.5	47.0	35.0	29.0	20.0	8.0	6.0
15/10/2005	1,668	42	9.20	44	14	23	9	15	18	5.8		1			9.50	0.10	0.10	0.20	49,000	120	7.5	0.25	2.45	2.271		93.5	51.0	37.0	30.0	21.0	8.0	7.0
16/10/2005	1,854	42	9.30	44	13	24	8	16	19	6.0		1		1	9.50	0.10	0.10	0.20	51,000	120	7.5	0.25	2.8	2.355		93	50.0	37.0	30.0	21.0	9.0	6.0
17/10/2005	2,088	42	9.35	44	14	24	8	14	18	5.2		1		1	9.50	0.10	0.10	0.18	48,000	120	7.5	0.40	3.27	2.674		92.8	52.0	38.0	31.0	22.0	9.0	7.0
18/10/2005	2,370	43	9.30	45	14	26	8	15	19	6.0		1		1	9.50	0.15	0.12	0.24	47,000	100	7.5	0.50	3.15	2.733		93	54.0	40.0	33.0	24.0	9.0	7.0
19/10/2005	2,399	43	9.30	45	16	22	8	16	24	6.0		1		1	9.50	0.15	0.14	0.26	46,000	120	7.5	0.25	3.23	2.826		93	54.0	38.0	30.0	23.0	9.0	8.0
20/10/2005	2,403	42	9.30	45	15	24	9	16	23	5.6		1		1	9.00	0.10	0.08	0.16	49,500	120	10.0	0.25	3.35	3.317		92.6	54.0	39.0	32.0	24.0	9.0	7.0
21/10/2005	2,403		9.30	44	15	25	8	17	23	5.8		1		1	9.20	0.12	0.10	0.24	51,000	120	10.0	0.25	3.01	2.765		92.8	55.0	40.0	32.0	25.0	9.0	8.0
Interval # 03										**From Date**				**22/10/2005**						**Top of Interval**			**2,403.0**		**m**						
Max. Hole Size / Bit Size 6.250 / 6.000 in										**To Date**				**12/11/2005**						**Bottom of Interval**			**2,400.0**		**m**						
12/11/2005	2,400		8.50	108	22	16	9	20	26		0.5		2	121		2.50				3			4.3	3.027	78	15.5	60.0	38.0	29.0	18.0	8.0	7.0

Baroid Fluid Services

Operator	**Swift Energy NZ Ltd**
Well Name	**AHUROA SOUTH B-1**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Fluid Property Recap : NAP-Based Fluid (Baroid Titrations)

Date	Depth	FL Temp	Density	Funn Visc	Rheology 49 Deg C					Filtration			Elec. Stability	Excess Lime Content	Alk (Pom)	Water Phase Salinity	CaCl2	NaCl Sol	NaCl Insol	Sand	Retort Analysis % by vol				NAP/Water Ratio	Rheometer Dial Readings					
					PV	lbs/100 ft2				HTHP	Cake	Temp									Corr Solid	LGS	NAP	Water		600	300	200	100	6	3
	m	Deg C	ppg	sec/qt	cP	YP	10S	10M	30M	ml/30 min	32nd in	Deg C	volt	ppb	ml	ppm	ppb	ppb	ppb	% by vol											
Interval # 01										**From Date**				**06/10/2005**						**Top of Interval**				**100.0**	**m**					
Max. Hole Size / Bit Size 13.350 / 12.250 in										**To Date**				**09/10/2005**						**Bottom of Interval**				**659.0**	**m**					
Interval # 02										**From Date**				**10/10/2005**						**Top of Interval**				**659.0**	**m**					
Max. Hole Size / Bit Size 9.000 / 8.500 in										**To Date**				**21/10/2005**						**Bottom of Interval**				**2,403.0**	**m**					
Interval # 03										**From Date**				**22/10/2005**						**Top of Interval**				**2,403.0**	**m**					
Max. Hole Size / Bit Size 6.250 / 6.000 in										**To Date**				**12/11/2005**						**Bottom of Interval**				**2,400.0**	**m**					
22/10/2005	2,403		8.90	80	26	19	8	15	20	5.8	2		1620	3.11	2.40	268,307	6.26	9.16	21.80	0.3	6.5	2.8	80.0	12.0	87/13	71.0	45.0	35.0	25.0	9.0	7.0
23/10/2005	2,403		8.70	55	15	15	5	8	13	4.4	2		1427	2.85	2.20	360,943	22.77	0.99	6.82	0.2	4.0	0.2	82.0	12.0	87.2/12.8	45.0	30.0	22.0	13.0	6.0	4.0
24/10/2005	2,405	25	8.55	60	24	10	5	6	7	5.0	2		1326	2.46	1.90	360,943	22.77	0.99	3.93	0.3	4.0	1.4	82.0	12.0	87.2/12.8	58.0	34.0	26.0	16.0	4.0	3.0
24/10/2005	2,486	42	8.50	56	20	16	6	8	12	4.0	2		1159	4.40	3.40	368,509	23.74	0.81	8.87	0.3	4.0	1.7	82.0	12.0	87.2/12.8	56.0	36.0	26.0	17.0	7.0	6.0
25/10/2005	2,533	28	8.50	40	23	18	6	8	9	4.8	2		895	4.27	3.30	342,562	23.74	1.83	9.29	0.3	3.9	1.9	80.0	14.0	85.1/14.9	64.0	41.0	31.0	20.0	6.0	5.0
25/10/2005	2,690	42	8.50	58	22	21	6	9	12	4.2	2		1012	4.14	3.20	355,116	25.68	1.34	6.29	0.3	3.8	1.8	80.0	14.0	85.1/14.9	65.0	43.0	34.0	25.0	7.0	6.0
26/10/2005	2,737	40	8.50	59	29	17	7	10	12	5.0	2		925	4.53	3.50	381,150	29.56	0.66	4.32	0.3	3.5	1.6	80.0	14.0	85.1/14.9	75.0	46.0	35.0	22.0	6.0	5.0
26/10/2005	2,785	42	8.50	60	21	21	6	9	13	4.0	2		1008	4.53	3.50	399,366	27.62	0.35	8.13	0.3	3.6	1.5	82.0	12.0	87.2/12.8	63.0	42.0	32.0	21.0	7.0	6.0
27/10/2005	0	42	8.50	65	28	20	7	12	14	4.0	2		921	4.53	3.50	383,857	25.68	0.53	5.66	0.3	3.8	1.6	82.0	12.0	87.2/12.8	76.0	48.0	37.0	24.0	7.0	6.0
27/10/2005	2,819	42	8.60	62	23	19	7	10	15	4.0	2		1063	4.53	3.50	383,857	25.68	0.53	9.99	0.3	4.8	2.9	81.0	12.0	87.1/12.9	65.0	42.0	33.0	25.0	8.0	7.0
28/10/2005	2,832	42	8.60	62	22	19	6	10	11	4.0	2	49	966	4.14	3.20	383,857	25.68	0.53	7.10	0.3	4.8	2.9	81.0	12.0	87.1/12.9	63.0	41.0	32.0	21.0	6.0	5.0
28/10/2005	2,864	42	8.60	55	19	19	7	9	14	4.0	2	49	1004	4.53	3.50	383,857	25.68	0.53	9.99	0.3	4.8	2.9	81.0	12.0	87.1/12.9	57.0	38.0	30.0	22.0	8.0	6.0
29/10/2005	2,880	42	8.65	61	20	16	6	9	10	4.0	2	49	1044	4.14	3.20	376,154	24.71	0.65	9.44	0.3	4.5	1.8	81.4	12.0	87.2/12.8	56.0	36.0	27.0	18.0	6.0	5.0
29/10/2005	2,903	42	8.65	58	18	25	8	11	15	4.4	2	49	1021	4.66	3.60	383,857	25.68	0.53	7.54	0.3	4.6	2.1	81.2	12.0	87.1/12.9	61.0	43.0	34.0	25.0	9.0	7.0
30/10/2005	2,903	42	8.65	62	21	14	5	9		4.0	2	49	991	3.63	2.80	399,366	27.62	0.35	6.68	0.3	4.0	1.2	81.6	12.0	87.2/12.8	56.0	35.0	27.0	17.0	5.0	4.0
30/10/2005	2,903		8.70	64	22	19	8	14	18	4.4		64.99	991	3.89	3.00	399,366	27.62	0.35	8.13	0.3	4.8	2.5	80.8	12.0	87.1/12.9	63.0	41.0	33.0	24.0	8.0	7.0
31/10/2005	2,941	42	8.75	62	21	15	6	9	10	4.0	2	64.99	1017	3.63	2.80	400,000	23.37		9.79	0.3	6.0	3.8	82.0	10.0	89.1/10.9	57.0	36.0	28.0	18.0	6.0	5.0
31/10/2005	2,975	42	8.65	62	22	21	8	13	17	4.4		64.99	998	3.63	2.80	387,325	25.68	0.47	10.05	0.3	4.8	2.5	81.2	11.8	87.3/12.7	65.0	43.0	34.0	25.0	8.0	7.0
01/11/2005	2,993	42	8.65	62	21	14	7	11	12	4.2	2	64.99	1068	4.27	3.30	400,000	25.70		10.20	0.3	4.3	1.4	82.5	11.0	88.2/11.8	56.0	35.0	26.0	17.0	8.0	7.0
01/11/2005	3,037	42	8.70	63	22	19	7	13	15	4.2		64.99	1358	4.40	3.40	400,000	23.37		15.57	0.3	4.8	1.7	83.2	10.0	89.3/10.7	63.0	41.0	31.0	22.0	8.0	7.0
02/11/2005	3,058	42	8.70	65	22	18	6	13	14	4.2	2	121	1122	3.63	2.80	400,000	23.37		12.68	0.3	4.8	1.7	83.2	10.0	89.3/10.7	62.0	40.0	31.0	20.0	7.0	5.0

Baroid Fluid Services

Operator	**Swift Energy NZ Ltd**
Well Name	**AHUROA SOUTH B-1**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Fluid Property Recap : NAP-Based Fluid (Baroid Titrations)

Date	Depth	FL Temp	Density	Funn Visc	Rheology 49 Deg C					Filtration			Elec. Stability	Excess Lime Content	Alk (Pom)	Water Phase Salinity	CaCl2	NaCl Sol	NaCl Insol	Sand	Retort Analysis					Rheometer Dial Readings					
					PV	lbs/100 ft2				HTHP	Cake	Temp									% by vol				NAP/Water Ratio	600	300	200	100	6	3
	m	Deg C	ppg	sec/qt	cP	YP	10S	10M	30M	ml/30 min	32nd in	Deg C	volt	ppb	ml	ppm	ppb	ppb	ppb	% by vol	Corr Solid	LGS	NAP	Water							
02/11/2005	3,098	42	8.70	66	23	18	7	12	15	4.6		121	1187	3.37	2.60	400,000	23.37		9.79	0.3	5.0	2.1	83.0	10.0	89.2/10.8	64.0	41.0	32.0	20.0	7.0	6.0
03/11/2005	3,116	42	8.70	66	23	17	6	13	14	4.0	2	121	1325	2.33	1.80	395,431	23.74	0.34	9.34	0.3	5.0	2.1	82.5	10.5	88.7/11.3	63.0	40.0	31.0	19.0	7.0	5.0
03/11/2005	3,138	42	8.70	68	23	18	7	12	15	4.8	2	121	1289	2.85	2.20	395,431	23.74	0.34	10.78	0.3	5.0	2.1	82.5	10.5	88.7/11.3	64.0	41.0	32.0	21.0	8.0	7.0
04/11/2005	3,178	42	8.70	70	23	20	7	14	18	4.8	2	121	1237	4.79	3.70	384,682	24.71	0.49	8.16	0.3	4.9	2.2	81.5	11.5	87.6/12.4	66.0	43.0	32.0	22.0	7.0	6.0
04/11/2005	0	42	8.75	76	27	21	8	14	19	3.0	2	121	1257	5.44	4.20	386,569	22.77	0.43	16.05	0.3	5.6	2.8	82.0	10.5	88.6/11.4	75.0	48.0	36.0	25.0	8.0	7.0
05/11/2005	3,197	42	8.65	77	28	18	7	15	18	3.4	2	121	1247	4.14	3.20	376,154	24.71	0.65	10.89	0.3	4.9	2.6	81.0	12.0	87.1/12.9	74.0	46.0	35.0	24.0	7.0	6.0
05/11/2005	3,201	42	8.70	75	27	19	8	14	18	3.0	2	121	1324	4.66	3.60	383,857	25.68	0.53	12.88	0.3	4.8	2.2	81.0	12.0	87.1/12.9	73.0	46.0	35.0	24.0	8.0	3.0
06/11/2005	3,246	42	8.70	75	28	20	7	15	22	3.0	2	121	1184	5.57	4.30	376,154	24.71	0.65	9.44	0.3	4.9	2.2	81.0	12.0	87.1/12.9	76.0	48.0	37.0	24.0	8.0	7.0
06/11/2005	3,296	42	8.80	81	29	18	7	14	19	2.0	2	121	1351	5.44	4.20	368,509	23.74	0.81	14.64	0.3	5.5	2.6	80.5	12.0	87/13	76.0	47.0	36.0	24.0	8.0	6.0
07/11/2005	3,296	35	8.80	80	28	20	8	15	21	1.0	2	121	1288	5.44	4.20	368,509	23.74	0.81	10.31	0.3	5.5	2.6	80.5	12.0	87/13	76.0	48.0	37.0	25.0	8.0	7.0
07/11/2005	3,316	42	8.80	98	30	20	9	17	23	0.5	2	121	1301	5.18	4.00	383,857	25.68	0.53	11.44	0.3	5.8	3.5	80.0	12.0	87/13	80.0	50.0	38.0	26.0	9.0	7.0
08/11/2005	3,370	42	8.85	90	29	21	7	17	21	1.0	2	121	1088	5.18	4.00	368,509	23.74	0.81	13.20	0.3	6.0	3.3	80.0	12.0	87/13	79.0	50.0	39.0	25.0	7.0	6.0
08/11/2005	3,370		8.85	92	31	20	8	16	20	0.5	2	121	1361	5.18	4.00	383,857	25.68	0.53	12.88	0.3	5.8	3.2	80.0	12.0	87/13	82.0	51.0	38.0	27.0	8.0	7.0
09/11/2005	3,370	42	8.85	90	29	21	7	17	24	0.5	2	121	1185	5.18	4.00	360,943	22.77	0.99	14.04	0.3	6.0	3.3	80.0	12.0	87/13	79.0	50.0	39.0	25.0	7.0	6.0
09/11/2005	3,370	42	8.85	88	30	20	8	17	23	0.5	2	121	1336	5.18	4.00	376,154	24.71	0.65	13.78	0.3	5.9	3.2	80.0	12.0	87/13	80.0	50.0	38.0	26.0	9.0	7.0
10/11/2005	3,370		8.85	98	31	20	8	17	24	0.5	2	121	1362	5.18	4.00	376,154	24.71	0.65	13.78	0.3	5.9	3.2	80.0	12.0	87/13	82.0	51.0	40.0	28.0	8.0	7.0
10/11/2005	2,380		8.90	108	31	26	10	17	25	0.5	2	121	789	5.70	4.40	345,308	27.62	1.96	12.29	0.3	5.6	3.1	76.0	16.0	82.6/17.4	88.0	57.0	45.0	30.0	10.0	8.0
11/11/2005	2,381		8.90	106	32	22	10	17	26	1.0	2	121	867	2.59	2.00	345,308	27.62	1.96	12.29	0.3	6.6	5.2	75.0	16.0	82.4/17.6	86.0	54.0	43.0	28.0	9.0	7.0
11/11/2005	2,356		8.60	112	29	22	9	17	24	0.5	2	121	1030	6.48	5.00	350,338	27.62	1.68	15.46	0.3	4.7	3.4	77.4	15.5	83.3/16.7	80.0	51.0	40.0	28.0	10.0	8.0

Operations Log Recap

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval #	**01**		**From Report**	**001**	**Top of Interval**	**100.0**	**m**
Max. Hole/Bit Size	**13.350 / 12.250**	**in**	**To Report**	**004**	**Bottom of Interval**	**659.0**	**m**

For Report	**# 001**	**On**	**06/10/2005**	**Operation at Depth**	**100.0 m**
Rig Activity				Nipple up. Pick up DC with bit and Spud well @ 13:00 hrs. Drill 12.25" hole to 100 m. Pump sweep and run log. Continue drilling.	
Activity				Drilling 12.25" hole	
Fluid Treatment				Start build up spud mud with Bentonite. Received one load of chemicals from warehouse. Dress all shaker screen with 110 mesh screens. 5 new screens and 4 used screens. Pump 5 bbl Hi vis sweep with drill plug every connection. Losses: SCE: Shaker 12 bbls.	
For Report	**# 002**	**On**	**07/10/2005**	**Operation at Depth**	**248.0 m**
Rig Activity				Drill from 100m to 200m.	
Activity				Drilling 12.25"	
Fluid Treatment				Maintain mud weight and viscosity through dump and dilute.	
For Report	**# 003**	**On**	**08/10/2005**	**Operation at Depth**	**589.0 m**
Rig Activity				Drill from 248m to 589m.	
Activity				Drill 12.25" hole	
Fluid Treatment				Change shaker #3.....	
For Report	**# 004**	**On**	**09/10/2005**	**Operation at Depth**	**659.0 m**
Rig Activity				Drill to section TD @ 659m. Pump sweep, circulate hole clean. Pump slug and make wiper trip. RIH to bottom and circulate bottoms up. Slug pipe and pooh. Rig up casing equipment and RIH with 9 5/8" casing.	
Activity				Run 9 5/8" casing	
Fluid Treatment				Maintain mud weight through dump and dilute. Pump sweeps as required to aid hole cleaning. Make up a hi-vis sweep and slug. COREDRIL-N on location: 545 bbl Losses: DH 6 bbl, shakers 14 bbl, desilter 22 bbl, dump 20 bbl, tripping 3.1 bbl.	

Operations Log Recap

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval #	**02**		**From Report**	**005**	**Top of Interval**	**659.0**	**m**
Max. Hole/Bit Size	**9.000 / 8.500**	**in**	**To Report**	**016**	**Bottom of Interval**	**2,403.0**	**m**

For Report	**# 005**	**On**	**10/10/2005**	**Operation at Depth**	**659.0 m**
Rig Activity				Land 9 5/8" casing at 652 meters, Cir casing volume and pump cement as per HALCO program. 60 bbls water, 191 bbls of lead and 33 bbls tail and displaced with 152 bbls of mud. No cement returns to surface. Top up cement WOC. Weld on well head, Nipple up BOP	
Activity				Wait on cement/Nipple up	
Fluid Treatment				Dump all mud and start tank cleaning Building new KCL/PHPA mud Returned 400 sx bentonite today Received chemicals today Cordril-N on location 545 bbls	
For Report	**# 006**	**On**	**11/10/2005**	**Operation at Depth**	**659.0 m**
Rig Activity				Nipple up BOP adn pressure test. P/U and RIH with 8.8" directional BHA	
Activity				RIH 8.5 Dir BHA	
Fluid Treatment				Mix spacer for displacment. Coredril-N on location 545 bbls	
For Report	**# 007**	**On**	**12/10/2005**	**Operation at Depth**	**946.0 m**
Rig Activity				Displace well to KCL, Tag cement at 643 and drill down to 662 andf perform a LOT, Dril	
Activity				Drlg 8.5" hole	
Fluid Treatment				Mix sodium bicar to treat out cement. Mixed pac to control filtrate and Barazan for rheology Running all solids control equipment. Changed out all screens to 175	
For Report	**# 008**	**On**	**13/10/2005**	**Operation at Depth**	**1,223.0 m**
Rig Activity				Drill and slideing form 946-1223	
Activity				Drlg 8.5" hole	
Fluid Treatment				Pumping Hi vis sweeps every 2 connections. Running all solids equipment. Dumping sand trap as needed. Mixing all chemicals as per program Replaced new screens with Swaco screen	
For Report	**# 009**	**On**	**14/10/2005**	**Operation at Depth**	**1,430.0 m**
Rig Activity				Drill and slide form 1223-1278. Pump sweep and make wipe trip to shoe. Repair trans on rig, Drlg 1278-1430	
Activity				Drlg	
Fluid Treatment				Pumping Hi-Vis sweeps to aid in hole cleaning. Running all solids control equipment. Adding all chemicals as per program building LCM sweeps: 15 lbs/bbls. Pumping every other connection	
For Report	**# 010**	**On**	**15/10/2005**	**Operation at Depth**	**1,668.0 m**
Rig Activity				Losses at 1440m, approx 30 bbls, Pump 25 bbls LCM sweep, Lost a total of 60 bbls. Drlg 1450-1668	

Operations Log Recap

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval #		**02**		**From Report**	**005**	**Top of Interval**	**659.0**	**m**
Max. Hole/Bit Size		**9.000 / 8.500**	**in**	**To Report**	**016**	**Bottom of Interval**	**2,403.0**	**m**
Activity				Drlg				
Fluid Treatment				Running all solids equipment. Pumping 5 bbls sweeps every connection to control seepage. Mixing all chemical as per program				
For Report	**# 011**	**On**	**16/10/2005**	**Operation at Depth**		**1,854.0 m**		
Rig Activity				Drlg 1668-1826. Pull 40 stand wiper trip, No problems in or out, Drlg to 1854				
Activity				Drlg				
Fluid Treatment				Run all solids control equipment. Pump LCM sweeps every 3rd connection, Added 10% oil to sweeps to aid in torque and drag. All chemical mixes as per program.				
For Report	**# 012**	**On**	**17/10/2005**	**Operation at Depth**		**2,088.0 m**		
Rig Activity				Drlg 1854-2088				
Activity				Drlg				
Fluid Treatment				Run all solids control equipment. Pumping 5 bbl LCM sweeps every 3 connection. Replaced one new screen. All chemicals mixed as per program.				
For Report	**# 013**	**On**	**18/10/2005**	**Operation at Depth**		**2,370.0 m**		
Rig Activity				Drlg 2088-2370 Cordril-N on location 511 bbls on other location 435 bbls				
Activity				Drlg				
Fluid Treatment				Pumping sweep every 3 to 4 connections. Dumping sand trap as needed to maintain mud wt. Mixing all chemicals as per program				
For Report	**# 014**	**On**	**19/10/2005**	**Operation at Depth**		**2,399.0 m**		
Rig Activity				Drlg to TD. 2399, Pump 20 bbls sweep and cir hole clean, pump slug, wiper trip to shoe, Slip and cut line, RIH, hit tight spot one stand of bottom, Work tight spot and pump LCM sweep. Cir hole clean Pump slug and POOH, Rig up and run wire line long,				
Activity				RIH with wire line log				
Fluid Treatment				Mixing all chemical as per program, LCM sweeps 18 lbs/bbl Cordril-N on location 511 bbls other location 435				
For Report	**# 015**	**On**	**20/10/2005**	**Operation at Depth**		**2,403.0 m**		
Rig Activity				RIH with logging tool to section TD with no problems, Log hole, RIH, Fill on bottom, Wash 3 joints to bottom, Pump 20 bbls LCM sweep and cir hole clean. Pump 25 bbls 11.3 ppg to spot on bottom. Slug pipe and pull out of the hole				
Activity				POOH laying down DP				
Fluid Treatment				Mix up sweep at 16 lbs/bbl, Build new mud in per-Mix				
For Report	**# 016**	**On**	**21/10/2005**	**Operation at Depth**		**2,403.0 m**		
Rig Activity				RIH with 7" casing. Hung up at 2395m. Try to wash to bottom, Cemented in. Pumped 88 bbls lead and 170 bbls tail. Displaced with SBM				

Operations Log Recap

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval #	**02**		**From Report**	**005**	**Top of Interval**	**659.0**	**m**
Max. Hole/Bit Size	**9.000 / 8.500**	**in**	**To Report**	**016**	**Bottom of Interval**	**2,403.0**	**m**

Activity	Cement 7" casing
Fluid Treatment	Barite was mixed for slug Cordril-N on location 511 bbls, on other location 435 bbls.

Operations Log Recap

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval #	**03**		**From Report**	**017**	**Top of Interval**	**2,403.0**	**m**
Max. Hole/Bit Size	**6.250 / 6.000**	**in**	**To Report**	**038**	**Bottom of Interval**	**2,400.0**	**m**

For Report	**# 017**	**On**	**22/10/2005**	**Operation at Depth**	**2,403.0 m**
Rig Activity				Nipple down to set casing slips Cleaning mud tanks	
Activity				Setting casing slips	
Fluid Treatment				Cleaning tank, Ordered chemical for this section of hole.	
For Report	**# 018**	**On**	**23/10/2005**	**Operation at Depth**	**2,403.0 m**
Rig Activity				Set casing slips, Nipple up and test lines and BOP. Pressure test casing. Pick up 3.5 Drill pipe	
Activity				RIH with 3.5 DP	
Fluid Treatment				Cleaned all pits for transfer of OBM. Received chemicals for new hole section. Recieved all COREDRIL-N from Piakau site. Total 943 bbls trans form old location.Old recap shows 974 bbls, (31 bbls lost in trans). Will be adding water to this so will not be Cordril-N.	
For Report	**# 019**	**On**	**24/10/2005**	**Operation at Depth**	**2,533.0 m**
Rig Activity				TIH with 3.5" DP. Tag cement @ 2379m. Test csg to 2000psi, ok. Drill out shoe track and 3m of new hole. Continue drilling 6" hole from 2403-2533m.	
Activity				Drill 6" hole	
Fluid Treatment				Replaced 175 mesh screens on shakers #1, #2 and #3 with 210screens. Used all swaco screens to start this section of hole. Added 2 drums of BDF-303 to emulsify water content and increase low end rheology. Sweeping hole every 3 to 4 connections to aid in hole cleaning. The new charge for Saraline V185 is $144.28, the old price is $131.98. This was to reconciliate so the additional cost of $1,636.51 was added in todays cost. Losses: SCE 22 bbl, trips 6 bbl, DH 4 bbl, surface 2.7 bbl, other 1.2 bbl	
For Report	**# 020**	**On**	**25/10/2005**	**Operation at Depth**	**2,711.0 m**
Rig Activity				Continue to rotate and slide drill 6" hole from 2533-2711m.	
Activity				Drill 6" hole	
Fluid Treatment				Ran centrifuge to maintain a MW of 8.5ppg. Pumped 5 bbl sweeps every 3-4 connections to aid in hole cleaning and to aid in seepage losses. Losses: shakers lost on cuttings 20 bbl, DH 15.43 bbl, centrifuge 15 bbl, evaporation 2 bbl, pumps/hoses 1 bbl.	
For Report	**# 021**	**On**	**26/10/2005**	**Operation at Depth**	**2,788.0 m**
Rig Activity				Continue to rotate and slide drill 6" hole from 2711-2788m.	
Activity				Drill 6" hole	
Fluid Treatment				Pumped 5 bbl sweeps (@ 15 ppb) every 3-4 connections to clean hole and minimise DH losses. Running centrifuge for 4-5 hours per tour to lower LGS.	

Operations Log Recap

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval #		**03**		**From Report**	**017**	**Top of Interval**	**2,403.0**	**m**
Max. Hole/Bit Size		**6.250 / 6.000**	**in**	**To Report**	**038**	**Bottom of Interval**	**2,400.0**	**m**
				Losses: shakers lost on cuttings 18 bbl, DH 12 bbl, centrifuge 12 bbl, pumps/hoses 2 bbl, evaporation 2 bbl.				
For Report	**# 022**	**On**	**27/10/2005**	**Operation at Depth**		**2,828.0 m**		
Rig Activity				Make wiper trip back to shoe, no tight spots and no fill. Continue to rotate and slide drill 6" hole from 2788-2828m.				
Activity				Drill 6" hole				
Fluid Treatment				Increased mud weight to 8.6 ppg as per Company Man's request. Ran centrifuge for 4-5 hours per tour to lower LGS. Continued to pump 5 bbls sweeps (@ 20 ppb) every 3-4 connections to aid in hole cleaning and to minimise DH losses. Mixed barite as needed to maintain mud wt. Bled in base oil to help control rheology. Added in Baracarb #25 to aid in seepage and to improve filter cake. Losses: DH 14 bbl, centrifuge 11.7 bbl, shakers lost on cuttings 8 bbl				
For Report	**# 023**	**On**	**28/10/2005**	**Operation at Depth**		**2,875.0 m**		
Rig Activity				Continue to rotate and slide drill 6" hole from 2828m-2875m.				
Activity				Drill 6" hole				
Fluid Treatment				Ran centrifuge for 4-5 hours per tour to lower LGS. Continued to pump 5 bbl sweeps (@ 20 ppb) every 3-4 connections to aid hole cleaning and to minimise DH losses. Bled in base oil to control rheology. Mixed in RM-63 for low-end rheology. Added Baracarb #25 to minimse seepage losses and to improve filter cake. Losses: shakers on cuttings 10 bbl, centrifuge 10 bbl, DH 6.15 bbl, evaporation 1 bbl.				
For Report	**# 024**	**On**	**29/10/2005**	**Operation at Depth**		**2,903.0 m**		
Rig Activity				Continue to rotate and slide drill 6" hole from 2875m-2903m. Pump 15 bbl sweep, circulate hole clean, pump slug, POOH.				
Activity				Drill 6" hole				
Fluid Treatment				Ran centrifuge for 4-5 hours per tour to lower LGS. Continued to pump 5 bbl sweeps (@ 20 ppb) every 3-4 connections to aid hole cleaning and to minimise DH losses. Losses: shakers lost on cuttings 12 bbl, DH 8 bbl, centrifuge 5 bbl.				
For Report	**# 025**	**On**	**30/10/2005**	**Operation at Depth**		**2,903.0 m**		
Rig Activity				RIH with new bit and BHA, circulate bottoms up. MWD tool failure. Pump sweep and cir hole clean, Pump slug, POOH. Change out MWD, RIH				
Activity				RIH				
Fluid Treatment				Pumped a 10 bbl sweep (@ 20 ppb) . Pumped slug. Ran centrifuge to maintain mud wt of 8.6+ ppg. Losses: centrifuge 6 bbl, tripping 6 bbl, DH 4 bbl, shakers lost on cuttings 2 bbl, miscellaneous 2 bbl.				
For Report	**# 026**	**On**	**31/10/2005**	**Operation at Depth**		**2,985.0 m**		
Rig Activity				RIH with new MWD tool. Continue to rotate and slide drill 6" hole from 2903m-2985m.				
Activity				Drill 6" hole				
Fluid Treatment				Pumped 5 bbl weighted sweeps every 3-4 connections to clean hole (9.6 ppg, 15 ppb LCM). Ran centrifuge for 3-4 hours per tour to lower LGS and to maintain a mud weight of				

Interval #		**03**		**From Report**	**017**	**Top of Interval**	**2,403.0**	**m**
Max. Hole/Bit Size		**6.250 / 6.000**	**in**	**To Report**	**038**	**Bottom of Interval**	**2,400.0**	**m**

	8.6+ ppg. Mixed in barite as needed to maintain mud wt. Mixed in RM-63 for low end rheology. Losses: DH 12 bbl, shakers lost on cuttings 11.38 bbl, centrifuge 6 bbl, evaporation 1 bbl.
For Report # 027 On 01/11/2005	**Operation at Depth 3,048.0 m**
Rig Activity	Continue to rotate and slide drill 6" hole from 2985m-3048m.
Activity	Drill 6" hole
Fluid Treatment	Suspected balled bit - spotted a 5 bbl CaCl2 pill on bottom. Pumped 5 bbl weighted sweeps every 3-4 connections to clean hole (9.6 ppg, 15 ppb LCM). Ran centrifuge for 3-4 hours per tour to lower LGS and to maintain a mud weight of 8.6+ ppg. Dusted in barite to maintain a mud weight of 8.6+ ppg. Bled in base oil to maintain a funnel viscosity < 65 sec/qt. Added RM63 for low-end rheology. Losses: shakers lost on cuttings 10.6 bbl, DH 7 bbl, centrifuge 7 bbl, evaporation 1 bbl.
For Report # 028 On 02/11/2005	**Operation at Depth 3,109.0 m**
Rig Activity	Continue to rotate and slide drill 6" hole from 3048m-3109m. Received load of chemicals today.
Activity	Drill 6" hole
Fluid Treatment	Pumped 5 bbl weighted sweeps every 3-4 connections to clean hole (9.6 ppg, 15 ppb LCM). Ran centrifuge for 4-5 hours per tour to lower LGS and to maintain a mud weight of 8.6+ ppg. Dusted in barite to maintain a mud weight of 8.6+ ppg. Losses: DH 10 bbl,shakers lost on cuttings 8 bbl, centrifuge 8 bbl, miscellaneous 1.5 bbl.
For Report # 029 On 03/11/2005	**Operation at Depth 3,162.0 m**
Rig Activity	Continue to rotate and slide drill 6" hole from 3109m-3162m.
Activity	Drill 6" hole
Fluid Treatment	Pumped 5 bbl weighted sweeps every 3-4 connections to clean hole (9.6 ppg, 15 ppb LCM). Ran centrifuge for 4-5 hours per tour to lower LGS and to maintain a mud weight of 8.7 ppg. Dusted in barite to maintain a mud weight of 8.7 ppg. Bled in base oil to maintain a funnel viscosity < 70 sec/qt. Mixed lime for alkalinity. Losses: centrifuge 13.74 bbl, shakers lost on cuttings 13 bbl, DH 10 bbl, miscellaneous 1.5 bbl.
For Report # 030 On 04/11/2005	**Operation at Depth 3,191.0 m**
Rig Activity	Continue to rotate and slide drill 6" hole from 3162m-3182m. Pump 10 bbl sweep 1m before kelly down. Circulate hole clean, pump slug, make wiper trip back to 2849m. RIH (no fill), continue to rotate and slide 6" hole from 3182m-3191m.
Activity	Drill 6" hole
Fluid Treatment	Pumped 5 bbl weighted sweeps as requested by Driller (9.6 ppg, 15 ppb LCM). Ran centrifuge for 4-5 hours per tour to lower LGS and to maintain a mud weight of

Interval #	**03**		**From Report**	**017**	**Top of Interval**	**2,403.0**	**m**
Max. Hole/Bit Size	**6.250 / 6.000**	**in**	**To Report**	**038**	**Bottom of Interval**	**2,400.0**	**m**

	8.7 ppg. Dusted in barite to maintain a mud weight of 8.7 ppg. Added RM-63 to increase low-end rheology. Mixed in BDF-352 to lower filtrate losses. (Increase in PV and viscosity due to addition of BDF-352). Losses: centrifuge 10 bbl, shakers lost on cuttings 8 bbl, DH 4 bbl, evaporation 1 bbl.
For Report # 031 On 05/11/2005	**Operation at Depth 3,227.0 m**
Rig Activity	Continue to rotate and slide drill 6" hole from 3191m-3227m. Received chemicals today.
Activity	Drill 6" hole
Fluid Treatment	Pump 5 bbl weighted sweeps as requested by the Driller (9.6 ppg, 15 ppb LCM). Ran centrifuge for 4-5 hours per tour to lower LGS and to maintain a mud weight of 8.7 ppg. Dusted in barite to maintain a mud weight of 8.7 ppg. Replaced one screen on shaker #2 with a new Pacific 210 mesh screen. Losses: shakers lost on cuttings 10 bbl, centrifuge 10 bbl, DH 8 bbl.
For Report # 032 On 06/11/2005	**Operation at Depth 3,296.0 m**
Rig Activity	Continue to rotate and slide drill 6" hole from 3227m-3296.8m. Encountered sluffing shale at 3296.8m MD, 3149.8m TVD. Worked tight spot, pumped two sweeps. First sweep carried 15% more shale over the shakers. The last sweep showed no increase. No additional torque was recorded thereafter. Pumped slug and pulled out to change BHA.
Activity	POOH for BHA
Fluid Treatment	Increased mud weight to 8.8 ppg as requested by Company Man. Pump 5 bbl weighted sweeps as requested by the Driller (9.6 ppg, 15 ppb LCM). Ran centrifuge for 4-5 hours per tour to lower LGS and to maintain a mud weight of 8.8 ppg. Dusted in barite to maintain a mud weight of 8.8 ppg. Received a load of chemicals today. Losses: DH 10 bbl, centrifuge 8 bbl, tripping 5 bbl, shakers lost on cuttings 4.71 bbl, evaporation 1 bbl.
For Report # 033 On 07/11/2005	**Operation at Depth 3,345.0 m**
Rig Activity	RIH with new BHA to shoe, circulate bottoms up. RIH to 3290m. Break circulation and wash the last three joints to bottom. No tight spots. Had 5% gas to surface. Continue drilling 6" hole from 3296m-3345m.
Activity	Drill 6" hole
Fluid Treatment	Added 4 ppb of Barablok to the active system to improve shale stability and fluid loss. Mixed a 50 bbl sweep in the slug @ 15 ppb to clean the hole. Bled in base oil to control viscosity. Losses: tripping 5 bbl, shakers lost on cuttings 3 bbl, DH 2.5, evaporation 1 bbl.
For Report # 034 On 08/11/2005	**Operation at Depth 3,370.0 m**
Rig Activity	Drill to a final depth of 3370.1m MD, 3219m TVD. Pump consecutive sweeps (low then high visc.), circulate bottoms up, pull back 4 stands. RIH (3 stands) and wash down the last. Pump sweep and circulate bottoms up. Pull back 4 stands, spot pill on bottom, pump slug, POOH for wireline logs. Rig up and run wire line. Rig down wire line. RIH to casing shoe with cement stinger.

Operations Log Recap

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval #		**03**		**From Report**	**017**	**Top of Interval**	**2,403.0**	**m**
Max. Hole/Bit Size		**6.250 / 6.000**	**in**	**To Report**	**038**	**Bottom of Interval**	**2,400.0**	**m**
Activity				RIH				
Fluid Treatment				Pumped a 15 bbl low visc. sweep (37 sec/qt) followed by a 15 bbl high visc. sweep (80 sec/qt) to clean hole. Pumped another high visc. sweep and spotted a weighted LCM on bottom. Losses: DH 6 bbl, shakers lost on cuttings 5 bbl, tripping 5 bbl, evaporation 1 bbl.				
For Report	**# 035**	**On**	**09/11/2005**	**Operation at Depth**		**3,370.0 m**		
Rig Activity				Pull out of hole with logging tools. No problems logging. RIH OE with cement stinger to shoe and circulate well @ 68 spm.				
Activity				Wait on orders				
Fluid Treatment				No chemicals mixed. Losses: DH 4 bbl, shakers lost on cuttings 4 bbl, tripping 4 bbl, evaporation 1 bbl.				
For Report	**# 036**	**On**	**10/11/2005**	**Operation at Depth**		**2,381.0 m**		
Rig Activity				Wait on orders. RIH to 2526. Pump 30 bbls spacer followed by 21.3 bbls of 17.3 ppg cement followed by 7 bbls of spacer. Pull up to 2380, Cir bottoms up, No spacer to surface. Trace of cement. Cir hole volume. Pull out of the hole. Dumped 12 bbls mud in desilter tank, water cement				
Activity				Testing BOP				
Fluid Treatment				One bag barite mixed for slug. Losses. 129.41 bbls left behind cement plug DH 4 bbls, Shakers 2 bbls, Evaporation 1 bbls, tripping 4 bbls.				
For Report	**# 037**	**On**	**11/11/2005**	**Operation at Depth**		**2,400.0 m**		
Rig Activity				Pressure test BOP and casing. RIH and tag cement at 2356. Drlg cement				
Activity				Drlg cement.				
Fluid Treatment				Running centrifuge to low mud wt to 8.5 ppg. Mixed BDF 303 for emulsion Losses: SCE 16 bbls centrifuge . Trip 3.59 bbls Evap. 1 bbls				
For Report	**# 038**	**On**	**12/11/2005**	**Operation at Depth**		**2,400.0 m**		
Rig Activity				Drill out cement to 2400m. Circulate to a mud weight of 8.5ppg in/out. Pump slug POOH. P/U and RIH 6" drilling BHA. Last report. Hole shows water but this is just to show transfer of mud to side track #2				
Activity				Side Track				
Fluid Treatment				Mixed BDF-303 for emulsion.				

Well Name	AHUROA SOUTH B-1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Deviation Actual

Survey Date	MD m	TVD m	Angle	Direction	Horiz Displ. m
08/10/2005	1,662	1,611	20.00	135.1	
13/10/2005	962	951	19.30	131.7	
13/10/2005	1,015	1,002	18.90	134.9	
13/10/2005	1,151	1,130	18.90	137.1	
13/10/2005	1,231	1,205	20.00	136.4	
14/10/2005	1,285	1,256	20.50	135.5	
14/10/2005	1,365	1,332	17.60	138.6	
14/10/2005	1,392	1,358	17.50	138.5	
15/10/2005	1,474	1,460	19.20	135.9	
15/10/2005	1,555	1,511	21.30	133.7	
16/10/2005	1,689	1,636	20.10	135.1	
16/10/2005	1,769	1,712	20.80	133.7	
16/10/2005	1,826	1,765	19.70	134.8	
18/10/2005	2,110	2,033	19.40	139.9	
18/10/2005	2,224	2,140	20.90	141.2	
18/10/2005	2,348	2,256	19.90	140.3	
24/10/2005	2,410	2,314	20.00	142.1	
24/10/2005	2,438	2,341	19.30	141.5	
24/10/2005	2,466	2,368	18.90	138.6	
24/10/2005	2,494	2,394	18.80	135.4	
24/10/2005	2,549	2,446	18.50	134.4	
24/10/2005	2,578	2,474	19.00	134.6	
24/10/2005	2,607	2,501	19.50	134.7	
24/10/2005	2,634	2,527	19.00	136.1	
27/10/2005	2,774	2,659	19.20	134.7	
27/10/2005	2,804	2,687	18.90	135.1	
31/10/2005	2,879	2,759	19.20	130.1	
31/10/2005	2,916	2,793	21.20	130.2	
31/10/2005	2,944	2,820	21.70	130.2	
31/10/2005	2,972	2,846	21.30	130.9	
02/11/2005	3,001	2,872	21.00	132.9	
02/11/2005	3,030	2,899	22.00	133.2	
02/11/2005	3,058	2,925	22.10	133.9	
03/11/2005	3,086	2,952	22.20	135.3	
03/11/2005	3,115	2,978	21.90	138.3	
03/11/2005	3,144	3,005	21.10	141.6	

Baroid Fluid Services

Well Name	AHUROA SOUTH B-1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Hydraulics Summary Report

Rpt No	Rpt Date	Hole MD	Max. Hole Size	ECD @ Csg Shoe	ECD @ Bit	Flow Rate	Btms Up Time	Total Circ Time	Press Drop DP	Press Drop @ Bit	Press Drop An	Total Press Drop	Hyd Meth	Circ Press	Ann Vel Riser	AV min DP	AV max DC	Bit HHSI	Bit Jet Vel	Bit Imp Force
		m	in	ppg	ppg	gpm	Min	Min	psi	psi	psi	psi		psi	ft/min	ft/min	ft/min	hhp/in2	m/sec	lbf
001	06/10/2005	100.0	13.350		9.04	399	2	46	93	235	1	454	HB	110			85.6	0.46	52.2	318.0
002	07/10/2005	248.0	12.250		9.34	553	7	37	197	462	6	984	HB	1,100		104.4	157.4	1.26	72.3	624.2
003	08/10/2005	589.0	12.250																	
004	09/10/2005	659.0	12.250											110						
005	10/10/2005	659.0	9.000																	
006	11/10/2005	659.0	9.000																	
007	12/10/2005	946.0	9.000	9.27	9.27	445	16	56	331	289	35	944	HB	1,250		179.3	259.8	1.32	57.7	393.9
008	13/10/2005	1,223.0	9.000																	
009	14/10/2005	1,430.0	9.000	9.56	9.56	467	23	66	512	325	85	1,221	HB	1,428		188.5	273.1	1.56	60.6	442.5
010	15/10/2005	1,668.0	9.000	9.57	9.56	473	27	69	630	333	101	1,375	HB	1,371		190.8	276.4	1.62	61.4	453.4
011	16/10/2005	1,854.0	9.000	9.69	9.68	504	28	68	739	382	117	1,556	HB	1,600		203.5	294.8	1.98	65.4	521.1
012	17/10/2005	2,088.0	9.000	9.75	9.73	499	31	73	796	376	129	1,622	HB	1,937		201.2	291.4	1.93	64.7	512.1
013	18/10/2005	2,370.0	9.000	9.71		459	40	87	772	316	157	1,545	HB	1,847		185.1	268.1	1.49	59.5	431.1
014	19/10/2005	2,399.0	9.000																	
015	20/10/2005	2,403.0	9.000																	
016	21/10/2005	2,403.0	8.755																	
017	22/10/2005	2,403.0	6.250																	
018	23/10/2005	2,403.0	6.250																	
019	24/10/2005	2,533.0	6.250	9.16	9.17	220	39	114	1,165	89	276	1,720	HB	2,492		200.8		0.40	33.1	104.8
020	25/10/2005	2,711.0	6.250	9.36	9.37	222	41	117	1,184	91	387	1,848	HB	2,550		202.6		0.42	33.4	106.7
021	26/10/2005	2,788.0	6.250	9.32	9.33	234	40	110	1,355	101	377	2,025	HB	2,800		213.4		0.49	35.1	118.5
022	27/10/2005	2,828.0	6.250	9.42	9.43	237	40	113	1,540	104	432	2,273	HB	2,956		217.1		0.51	35.7	122.5
023	28/10/2005	2,875.0	6.250	9.33	9.34	200	49	131	1,099	75	348	1,704	HB	2,405		183.1		0.31	30.2	88.2
024	29/10/2005	2,903.0	6.250																	
025	30/10/2005	2,903.0	6.250									150								
026	31/10/2005	2,985.0	6.250	9.39	9.39	200	51	137	1,152	60	312	1,708	HB	2,050		183.1		0.25	26.6	79.3
027	01/11/2005	3,048.0	6.250	9.27	9.28	202	51	136	1,226	60	313	1,784	HB	2,422		184.6		0.25	26.8	79.6
028	02/11/2005	3,109.0	6.250	9.42	9.43	202	52	136	1,216	60	368	1,828	HB	2,433		184.6		0.25	26.8	80.1

Well Name	**AHUROA SOUTH B-1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Hydraulics Summary Report

Rpt No	Rpt Date	Hole MD	Max. Hole Size	ECD @ Csg Shoe	ECD @ Bit	Flow Rate	Btms Up Time	Total Circ Time	Press Drop DP	Press Drop @ Bit	Press Drop An	Total Press Drop	Hyd Meth	Circ Press	Ann Vel Riser	AV min DP	AV max DC	Bit HHSI	Bit Jet Vel	Bit Imp Force
		m	in	ppg	ppg	gpm	Min	Min	psi	psi	psi	psi		psi	ft/min	ft/min	ft/min	hhp/in2	m/sec	lbf
029	03/11/2005	3,162.0	6.250	9.45	9.45	200	54	139	1,241	59	387	1,872	HB	3,000		183.1		0.25	26.6	78.8
030	04/11/2005	3,191.0	6.250	9.46	9.47	202	54	141	1,265	60	399	1,909	HB	2,340		184.6		0.25	26.8	80.1
031	05/11/2005	3,227.0	6.250	9.46	9.46	202	54	138	1,345	60	427	2,019	HB	2,550		184.6		0.25	26.8	79.6
032	06/11/2005	3,296.0	6.250									150								
033	07/11/2005	3,345.0	6.250	9.99	10.06	202	55	144	1,313	69	686	2,157	HB	1,911		184.6		0.29	28.5	86.2
034	08/11/2005	3,370.0	6.250																	
035	09/11/2005	3,370.0	6.250	9.45	9.46	109	75	217	312	20	235	631	HB	570		89.1		0.20	15.4	25.2
036	10/11/2005	2,381.0	6.184																	
037	11/11/2005	2,400.0	6.250																	
038	12/11/2005	2,400.0	6.250																	

Well Name	AHUROA SOUTH B-1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252

Personnel Register

New Zealand Manager:
Tom Mitchell

Engineers	From	To	Days	Costs
Pg Osmera	09/29/05	10/09/05	11	$ 7,700.00
Sandy Chiew	09/29/05	10/18/05	21	$14,700.00
Cal Urbatsch	10/10/05	11/11/05	33	$23,100.00
Oliver Winchester	10/19/05	11/09/05	21	$14,700
Sandy Chiew	11/10/05	11/11/05	2	$1,400.00



SWIFT ENERGY NZ LTD

Drilling Fluids Recap

AHUROA, South B-1, ST-1

AHUROA Field

Taranaki, New Zealand

HALLIBURTON

Baroid

Cover Page

Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Prepared For	D Gloger / N Peri
Title	DRG MGR/ DRG ENGR
Well Name	AHUROA B-1 ST#1
Rig Name	Parker Rig 252
Document Date	12/25/2005
Author	Pg Osmera / T Mitchell
District	New Plymouth
Field Name	Ahuroa
Field or Block	N - Taranaki
Country	New Zealand
SAP Order #	

Well Name	AHUROA B-1 ST#1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252

Table of Contents

Cover Page

Table of Contents

Well Summary Report

Time Summary Report

Net Well Cost Breakdown

Total Cost Breakdown

Conclusions and Recommendations

Interval Summary

Interval Discussion

Interval Cost Breakdown

Interval Inventory Summary

Fluid Volume Record

Fluid Property Recap

Operations Log Recap

Graphs

Deviation

Hydraulics Summary

Personnel Register

Baroid Fluid Services

Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Well Summary Report

Well Data

Spud Date		11/11/2005	Fluids/Products: Drilling Cost	$	62,430.93
TD Date		11/25/2005	Fluids/Products: Completion Cost	$	0.00
Project			Solids Control/Waste Management Cost	$	0.00
Days on Well		18	Fluids/Products: Cementing Cost	$	0.00
From Date		11/12/2005	Prod Lost/Damaged Cost	$	0.00
To Date		11/29/2005	Engineer Services Cost	$	25,200.00
Drilling Days		13	Equipment Cost	$	1,080.00
Rotating / Drilling Hours		233.0/233.0	Transport/Packaging	$	0.00
Average ROP	m/hr	2.8	Other Cost	$	2,466.20
Maximum Density	ppg	8.70	Total Well Cost	$	91,177.13
Total Measured Depth	m	3,085	Planned Cost	$	0.00
True Vertical Depth	m	2,956	Fluid Cost Per Fluid Volume	$/bbl	43.49
Distance Drilled	m	661	Fluid Cost Per Length Drilled	$/m	96.08
Maximum Deviation	deg	22.88	Fluid Cost/Vol of Hole Drilled	$/bbl	771.77
Max. Horz. Displacement	m	606	Total Additions/Hole Drilled	bbl/bbl	17.746
Bottom Hole Temp	Deg C	69	Total Additions/Length Drilled	bbl/m	2.209

Casing Design

Description	Set Date & Time	Top MD m	Top TVD m	End MD m	End TVD m	CSG OD in	CSG ID in	Max. Hole Size in	Hole MD m	Hole TVD m
7 L-80 23.0	10/22/2005 23:59	0		2,395	2,311	7.000	6.366		2,395	2,311

Fluid Program

Int #	Fluid Type	Interval Days	BHT Deg C	Max. Dens ppg	Whole fluid + Mix products	Other material charges	Other charges	Total Interval Cost $		
								Plan	Actual	Variance
1	SOBM	15	69	8.70	59,780.08	1,972.96	21,900.00		83,653.04	
2	SOBM KCl Brine	3		8.50	2,650.85	493.24	4,380.00		7,524.09	
Total Well Cost $					**62,430.93**	**2,466.20**	**26,280.00**		**91,177.13**	**91,177.13**

Baroid Fluid Services

Well Name	AHUROA B-1 ST#1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Time Breakdown Summary Report

				Time																		
Rpt No	Rpt Date	Rpt Time	MD	Drilg	Circ	Trip	Rig Serv	Rig Repair	Rig Up/Dn	Run Csg	Core	Ream Time	DST	Test BOP	N. Up BOP	WOC	Fish	Log	Dir Work	Dir Svys	Other	Total Time	Rotate	Avg ROP
			m	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	(Hr)	m/hr
001	11/12/2005	2:00	2,424.0	5.00		8.00															11.00	24.00	5.00	484.81
002	11/13/2005	2:00	2,425.0	21.00			1.00														2.00	24.00	21.00	0.04
003	11/14/2005	2:00	2,461.0	15.00		7.00	1.00														1.00	24.00	15.00	2.40
004	11/15/2005	2:00	2,595.0	21.00																	3.00	24.00	21.00	6.39
005	11/16/2005	2:00	2,710.0	22.00			1.00														1.00	24.00	22.00	5.22
006	11/17/2005	2:00	2,758.0	19.00		3.00	1.00														1.00	24.00	19.00	2.53
007	11/18/2005	2:00	2,827.0	21.00			1.00														2.00	24.00	21.00	3.28
008	11/19/2005	2:00	2,867.0	18.00																2.00	4.00	24.00	18.00	2.22
009	11/20/2005	2:00	2,874.0			19.00															5.00	24.00		
010	11/21/2005	2:00	2,941.0	21.00																	3.00	24.00	21.00	3.19
011	11/22/2005	2:00	2,993.0	20.00			1.00														3.00	24.00	20.00	2.61
012	11/23/2005	2:00	3,013.0	16.00																	8.00	24.00	16.00	1.24
013	11/24/2005	2:00	3,038.0	18.00		4.00															2.00	24.00	18.00	1.39
014	11/25/2005	2:00	3,085.0	16.00		5.00															3.00	24.00	16.00	2.93
015	11/26/2005	2:00	3,085.0															11.00			13.00	24.00		
016	11/27/2005	2:00	2,445.0													6.00					18.00	24.00		
017	11/28/2005	2:00	2,365.0																		24.00	24.00		
018	11/29/2005	2:00	2,365.0						24.00													24.00		
Total Hours :				**233.00**		**46.00**	**6.00**		**24.00**							**6.00**		**11.00**		**2.00**	**104.00**	**18.0 d**	**233.00**	

Well	AHUROA B-1 ST#1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Net Well Cost Breakdown

Cost Breakdown I $	Interval 01	Interval 02	Total
Fluid/Product: Drilling	59,780.08	2,650.85	62,430.93
Fluid/Product: Comp/Filtration			
Solids Control/Waste Management Cost			
Fluids/Products: Cementing Cost			
Engineering Services	21,000.00	4,200.00	25,200.00
Fluid/Product: Lost Damage			
Other Cost	1,972.96	493.24	2,466.20
Equipment Cost	900.00	180.00	1,080.00
Transport/Packaging Cost			
Total Cost	83,653.04	7,524.09	91,177.13

Cost Breakdown II $	Interval 01	Interval 02	Total
Total Products Cost	64,971.60	1,725.53	66,697.13
Total Fluids Cost	-1,800.00		-1,800.00
Total Charges Cost	21,900.00	4,380.00	26,280.00
Allocated To / From Other Interval	-1,418.56	1,418.56	
Total Cost	83,653.04	7,524.09	91,177.13
Planned Cost			
Variance			

Volume Breakdown bbl	Interval 01	Interval 02	Total
Total Base Fluids Addition	284.0		284.0
Total Chemical Addition	41.6	3.6	45.1
Total Barite Addition	24.7	4.5	29.2
Total Water Addition	204.5	115.5	320.0
Total Fluid Built	554.8	123.5	678.3
Total Fluid Received	782.0		782.0
Total Influx Addition			
Not Used In Interval	-211.0		
Total Fluid Volume	1,125.7	1,276.5	1,460.3

Baroid Fluid Services

Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	SwiftNZ SI/API mix

Total Cost Breakdown

	Unit Size	Quantity	Total Cost
Engineering/Services			
Drilling Fluids Engineer#1	day(s)	18.00	12,600.00
Drilling Fluids Engineer#2	day(s)	18.00	12,600.00
		SubTotal :	**$ 25,200.00**
Equipment Cost			
Storage tanks	day(s)	36.00	1,080.00
		SubTotal :	**$ 1,080.00**
Fluids/Products: Drilling Cost			
BARABLOK	50 lb bag	17.00	543.66
BARACARB 150	50 lb bag	191.00	2,391.32
BARACARB 25	50 lb bag	60.00	751.20
BARASCAV D	25 kg bag	2.00	67.42
BARAZAN D	25 kg bag	2.00	473.22
barite	1500 kg bag	13.00	4,109.82
BDF-303	180 kg drum	7.00	3,020.85
BDF-352	190 kg drum	3.00	2,048.22
calcium chloride	25 kg bag	40.00	419.60
caustic soda	25 kg pail	2.00	59.92
GELTONE II	50 lb bag	29.00	1,358.65
lime	25 kg bag	24.00	209.52
M.E. Glycol	55 gal drum	8.00	6,384.00
potassium chloride	1000 kg bag	3.00	1,418.01
Returned SOBM	bbl	-800.00	-80,000.00
Saraline 185	42 gal drum	284.00	40,975.52
SOBM	bbl	782.00	78,200.00
		SubTotal :	**$ 62,430.93**
Other			
CON DET	55 gal drum	5.00	2,466.20
		SubTotal :	**$ 2,466.20**
		Total Well Cost:	**$ 91,177.13**

Conclusion and Recommendations

It is recommended that this type of drilling fluid be used in other wells drilled in this area. This mud performed as per programmed in drilling this side track well to completion. In the 6" hole section using the SBM the addition of BARABLOK while drilling the coal stringers seemed to help. These coal strings were not anticipated in drilling this well.

In conclusion Baroid's mud engineers, chemical and logistical team performed well in drilling this well with little to no serious hole problems.

Baroid Fluid Services

Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Summary

Interval # 1	**Max Bit Size: 6.000 in**	**Hole Size Avg/Max**	**6.250 / 6.250 in**

Interval Start Date		11/12/2005	Planned Cost	$	0.00
Interval End Date		11/26/2005	Total Interval Cost	$	83,653.04
Interval TD Date		11/25/2005	Program Variance	$	83,653.04
Drilling Days		13.00	Other material charges	$	1,972.96
Rotating/Drilling Hours		233.00 / 233.00	Total Fluids Cost	$	59,780.08
Interval Top MD/TVD	m	2,424.0 / 2,424.0	Total Charges Cost	$	21,900.00
Interval End MD/TVD	m	3,085.0 / 2,955.9	Total Cementing Cost	$	0.00
Footage	m	661.0	Fluid Cost Per Vol Unit	$/bbl	53.10
Average ROP	m/hr	2.8	Fluid Cost/Hole Drilled	$/m	90.44
Max Hole Angle	degrees	22.88	Fluid Cost/Vol Drilled	$/bbl	726.43
Casing Size	in	7.000	Fluid Built	bbl	554.8
Casing Shoe MD	m	2,395.0	Total Additions/Vol Drilled	bbl/bbl	13.68
Casing Length	m	2,395.0	Total Additions/Hole Drilled	bbl/m	1.70
Bottom Hole Temp	Deg C	69	Fluid Loss/Vol Drilled	bbl/bbl	2.36
Max Fluid Density	ppg	8.70	Fluid Loss/Hole Drilled	bbl/m	0.29

Interval Product and Base Fluids Usage and Cost

Product Function / Name	Drilling Fluid	Packaging	Quantity Used	Product Cost
Filtration Control				
BARABLOK	SOBM	50 lb bag	17.000	543.66
BDF-352	SOBM	190 kg drum	3.000	2,048.22
			Total	**$ 2,591.88**
Weighting Material				
barite	SOBM	1500 kg bag	11.000	3,477.54
calcium chloride	SOBM	25 kg bag	40.000	419.60
			Total	**$ 3,897.14**
Detergent/Surfactanct				
CON DET	No Fluid	55 gal drum	4.000	1,972.96
			Total	**$ 1,972.96**
Viscosifier/Suspension Agent				
GELTONE II	SOBM	50 lb bag	29.000	1,358.65
			Total	**$ 1,358.65**
Lost Circulation/Bridging Agent				
BARACARB 150	SOBM	50 lb bag	191.000	2,391.32
BARACARB 25	SOBM	50 lb bag	60.000	751.20
			Total	**$ 3,142.52**
Alkalinity Control				
lime	SOBM	25 kg bag	24.000	209.52
			Total	**$ 209.52**
Other				
M.E. Glycol	SOBM	55 gal drum	8.000	6,384.00
			Total	**$ 6,384.00**
Base Fluid				
Saraline 185	SOBM	42 gal drum	284.000	40,975.52
			Total	**$ 40,975.52**
Emulsifier				

Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Summary

BDF-303	SOBM	180 kg drum	7.000		3,020.85
			Total	**$**	**3,020.85**
Whole Fluid					
SOBM	SOBM	bbl	782.000		78,200.00
Returned SOBM	SOBM	bbl	800.000		-80,000.00
			Total	**$**	**-1,800.00**

Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Summary

Interval #	**2**	**Max Bit Size: 6.000 in**	**Hole Size Avg/Max**	**6.250 / 6.250 in**

Interval Start Date		11/27/2005	Planned Cost	$	0.00
Interval End Date		11/29/2005	Total Interval Cost	$	7,524.09
Interval TD Date			Program Variance	$	7,524.09
Drilling Days		0.00	Other material charges	$	493.24
Rotating/Drilling Hours		0.00 / 0.00	Total Fluids Cost	$	2,650.85
Interval Top MD/TVD	m	3,085.0 / 2,955.9	Total Charges Cost	$	4,380.00
Interval End MD/TVD	m	3,085.0 / 2,955.9	Total Cementing Cost	$	0.00
Footage	m	0.0	Fluid Cost Per Vol Unit	$/bbl	2.08
Average ROP	m/hr	0.0	Fluid Cost/Hole Drilled	$/m	0.00
Max Hole Angle	degrees	0.00	Fluid Cost/Vol Drilled	$/bbl	0.00
Casing Size	in	0.000	Fluid Built	bbl	123.5
Casing Shoe MD	m	2,365.0	Total Additions/Vol Drilled	bbl/bbl	0.00
Casing Length	m	2,365.0	Total Additions/Hole Drilled	bbl/m	0.00
Bottom Hole Temp			Fluid Loss/Vol Drilled	bbl/bbl	0.00
Max Fluid Density	ppg	8.50	Fluid Loss/Hole Drilled	bbl/m	0.00

Interval Product and Base Fluids Usage and Cost

Product Function / Name	Drilling Fluid	Packaging	Quantity Used	Product Cost
Corrosion Inhibitor				
BARASCAV D	Potassium Chloride brine	25 kg bag	2.000	67.42
			Total	**$ 67.42**
Viscosifier/Suspension Agent				
BARAZAN D	Potassium Chloride brine	25 kg bag	2.000	473.22
			Total	**$ 473.22**
Weighting Material				
barite	Potassium Chloride brine	1500 kg bag	1.000	316.14
barite	SOBM	1500 kg bag	1.000	316.14
			Total	**$ 632.28**
Alkalinity Control				
caustic soda	Potassium Chloride brine	25 kg pail	2.000	59.92
			Total	**$ 59.92**
Detergent/Surfactanct				
CON DET	No Fluid	55 gal drum	1.000	493.24
			Total	**$ 493.24**
Shale Control				
potassium chloride	Potassium Chloride brine	1000 kg bag	3.000	1,418.01
			Total	**$ 1,418.01**

Interval Discussion

Well Name	AHUROA B-1 ST#1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Interval #	01		From Report	001	Top of Interval	2,424.0	m
Max. Hole/Bit Size	6.250 / 6.000	in	To Report	015	Bottom of Interval	3,085.0	m

6" Hole Section - Reservoir Section

Section: **2356 to 3085** m MD, TVD 2979m
Casing: 4" liner was not set.
Drilling Days: 14
Average ROP: 2.5 m/hr
Formation: Tariki
McKee
Mangahewa
Ahuroa Thrust

Objectives

- Effectively and efficiently displace well to the SOBM.
- Provide a rheology for good hole cleaning at an angle of +/- 35 degrees.
- Provide a well bore for a successful electrical wire line logging program.
- Provide a well bore for a successful casing run and cement operations.

Rig Abstract/Summary

On this well a total of 782 bbls of SOBM were carried on from AHOURA B - 1 and treated. The BHA was picking up as per Sperry program and ran in the hole to tag cement at 2356 meters and drill slowly to assure kick off point. The well was drilled ahead and while drilling 5 bbls of CaCo3 was pump every connection to aid hole cleaning. A plan wiper trip was made at 2742m to 2358 where there is no tight hole nor losses were experience during tripping. While back on bottom and continue drilling a back ground gas was occur at 1.2% it was decided to increase mud wt from 8.6 ppg to 8.7 ppg. A POOH was made at 2874m in order to change mud motor. While running back with new BHA a pipe work was made due pipe held up at kick off point at 2414m and manage to get through and continue drilling. While attempt to make connection at 2993m, there was 15K over pull. Hole packing off in the annulus, work pipe free and establish rotation. At this point circulate bottom up and wash down to bottom without applying any weight on bit. A time drilling was made and all drilling parameters were monitor closely. As drilling continues BARABLOK was added to the system to control sloughing of coal beds. A plan wiper trip was made at 3034m. Continue drilling to section TD at 3085m and TVD 2979m. Circulate hole clean and wiper trip to shoe. Hi Vis sweep of 10 bbls was spot on bottom when running back to bottom. POOH and lay down BHA to run log. Two logs were run in this hole, both logs went to bottom.

Interval Discussion

Well Name	AHUROA B-1 ST#1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Cost Evaluation and Key Performance Indicators

	Programmed	Actual	Conformance	Cost
Volume Rec'd (Last well)		782		
New Volume Built		673.8		
Dilution Rate				
Volume Recovered		800		
Consumption Rate (bbl/m)				
Cost / m		$90.44		
Cost / bbl		$53.00		
Total Interval Cost		$83,653.04		

Targets

	Programmed	Actual	Conformance
Time Lost (hole instability)	0	0	**Y**
Reaming (unscheduled)	0	0	**Y**
Differential Sticking	0	0	**Y**
Hole Condition	0	0	**Y**

Mud Properties - SOBM

	Programmed		Actual (Typical)	
	Minimum	Maximum	Minimum	Maximum
Density (ppg)	**8.4**	**9.2**	8.5	8.7
PV (cps)		**< 40**	22	26
YP (lbs/100ft2)	**9**	**13**	13	20
Tau 0 (lbs/100ft2)	**> 4**		4.79	7.07
HTHP Fluid Loss		**< 4***	0.5	2
Electrical Stability	**> 500**		898	1303
Water Content		**<30**	13	15
LGS		**< 5**	2.8	4.3

* HTHP Fluid Loss results at 180F
** Actual HTHP Fluid Loss tested at 250F

Zero Defects Tracking Summary / Explanation of Non-Conformance

- There was no non-conformance in this section of hole. Except the mud wt were lower then the program due control drilling to coal formation.
- The cost was high due to building new mud for the side track and high dilution rate on base oil to get the viscosity lower.
- Another $1725.53 was the cost to built brine for displacement

Maintenance Treatments

- All chemicals were mixed as per program
- Saraline base oil was added to the system to control rheology properties as per program.
- Sweeps were pumped every three to four connections to aid in hole cleaning. (5 ppb Baracarb 150 and 15 ppb Baracarb #25 were used in these sweeps). Showing no fill to little to no tight spots in this section of

hole.

- 4.5 ppb of BARABLOK was added to the system when drilling coal formation.
- 3 % KCL brine was mixed with BARASCAV D for displacement the hole.

Solids Control Evaluation

- The three DFE shakers were dressed with 210 mesh screens throughout the section. Only two shakers were used to drill this section of hole due to the low pump rate.

- One Swaco 518 HS centrifuge was in use while drilling this section. it was run 4 to 5 hours per tour to lower the LGS content less than 5%.

Volumes

- 782 bbls of SOBM volume was received from AHUROA B- well. .
- 275 bbls of COREDRILL N were mixed at the BAROID LMP and delivered to rig and treat to 70 / 30.
- 554.8 bbls through direct and chemicals.
- Another 94 bbls of Diesel cement Spacer add in the mud.
- 800 bbls of mud from this section was recovered and stored.
- 253.8 bbls mud losses during this interval.
- 75 bbls SOBM left behind casing.

HSE

- There was no time lost due to HSE issues
- All material was delivered in a timely manner.

Interval Discussion

Well Name	AHUROA B-1 ST#1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Interval #	02		From Report	016	Top of Interval	3,085.0	m
Max. Hole/Bit Size	6.250 / 6.000	in	To Report	018	Bottom of Interval	3,085.0	m

Completion section - Plug back Section

Section TD: **3085** m to 2365m

Objectives

- To set cement plug at casing shoe.
- Effectively and efficiently displace well to 3% KCL brine..

Rig Abstract/Summary

Cement stinger were pick up and RIH to 2430m, circulate to condition mud prior to set cement plug. Set a balance plug from 2445m to 2345m. 7" CBL was run from 1500m to 500 m inside 9 5/8" casing shoe @ 650m. Trip in hole to 2420m, no cement. Slug pipe and POOH. A packer was run in to the depth of 2365m and well was cement as per HALCO program. Pull out 7 stands and reverse out no cement to surface. A pressure test was done and displace hole to 3 % KCL brine. Received all the mud in the hole and back to storage. tAll the mud pump and surface line were flush with brine.

Cost Evaluation and Key Performance Indicators

	Programmed	Actual	Conformance	Cost
New Volume Built		320		
Cost / bbl		$2.08		
Total Interval Cost		$7,524.09		

Targets

	Programmed	Actual	Conformance
Time Lost (hole instability)	0	0	**Y**

Reaming (unscheduled)	0	0	**Y**
Differential Sticking	0	0	**Y**
Hole Condition	0	0	**Y**

Mud Properties - SOBM

	Programmed		Actual (Typical)	
	Minimum	Maximum	Minimum	Maximum
Density (ppg)	**8.4**	**8.6**	8.4	8.5
PH	**9**	**11.5**		11
Chloride	**14000**	**15000**		15000

Zero Defects Tracking Summary / Explanation of Non-Conformance

- There was no non-conformance in this section of hole.

Maintenance Treatments

- All chemicals were mixed as per program
- All rig tanks were clean prior mixing KCL brine.
- BARASCAV D was mix in the system for oxygen scavenger.
- Caustic was added to increase the PH level.

Solids Control Evaluation

- One Swaco 518 HS centrifuges were in use while receiving all the return mud to bring down the weight 8.3 ppg before storage.

Volumes

- 320 bbls 3% by wt of KCL brine was mix on the rig side.

- 274 bbls of SOBM received back from the well during displacement.

HSE

- There was no time lost due to HSE issues
- All material was delivered in a timely manner.

Baroid Fluid Services

Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Cost Breakdown

Interval # 01		**From Date**	**11/12/2005**	**Top of Interval**	**2,424.0 m**
Max. Hole Size / Bit Size	**6.250 / 6.000 in**	**To Date**	**11/26/2005**	**Bottom of Interval**	**3,085.0 m**

Material	Unit Size	Quantity		Total Cost
Engineering/Services				
Drilling Fluids Engineer#1		15.00	$	10,500.00
Drilling Fluids Engineer#2		15.00	$	10,500.00
		SubTotal	**$**	**21,000.00**
Equipment Cost				
Storage tanks		30.00	$	900.00
		SubTotal	**$**	**900.00**
Prod/Fluids: Drilling				
BARABLOK	50 lb bag	17.00	$	543.66
BARACARB 150	50 lb bag	191.00	$	2,391.32
BARACARB 25	50 lb bag	60.00	$	751.20
BARAZAN D	25 kg bag	2.00	$	473.22
barite	1500 kg bag	11.00	$	3,477.54
BDF-303	180 kg drum	7.00	$	3,020.85
BDF-352	190 kg drum	3.00	$	2,048.22
calcium chloride	25 kg bag	40.00	$	419.60
GELTONE II	50 lb bag	29.00	$	1,358.65
lime	25 kg bag	24.00	$	209.52
M.E. Glycol	55 gal drum	8.00	$	6,384.00
potassium chloride	1000 kg bag	2.00	$	945.34
Saraline 185	42 gal drum	284.00	$	40,975.52
Returned SOBM	bbl	1,582.00	$	-1,800.00
		SubTotal	**$**	**61,198.64**
Other Cost				
CON DET	55 gal drum	4.00	$	1,972.96
		SubTotal	**$**	**1,972.96**
		Interval Total Cost	**$**	**85,071.60**
		Charged To/From Other Interval	**$**	**-1,418.56**
		Net Interval Total Cost	**$**	**83,653.04**
		Programmed Cost	**$**	**0.00**
		Program Variance	**$**	**83,653.04**

Baroid Fluid Services

Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Cost Breakdown

Interval # 02		**From Date**	**11/27/2005**	**Top of Interval**	**3,085.0 m**
Max. Hole Size / Bit Size	**6.250 / 6.000 in**	**To Date**	**11/29/2005**	**Bottom of Interval**	**3,085.0 m**

Material	Unit Size	Quantity		Total Cost
Engineering/Services				
Drilling Fluids Engineer#1		3.00	$	2,100.00
Drilling Fluids Engineer#2		3.00	$	2,100.00
		SubTotal	**$**	**4,200.00**
Equipment Cost				
Storage tanks		6.00	$	180.00
		SubTotal	**$**	**180.00**
Prod/Fluids: Drilling				
BARASCAV D	25 kg bag	2.00	$	67.42
barite	1500 kg bag	2.00	$	632.28
caustic soda	25 kg pail	2.00	$	59.92
potassium chloride	1000 kg bag	1.00	$	472.67
		SubTotal	**$**	**1,232.29**
Other Cost				
CON DET	55 gal drum	1.00	$	493.24
		SubTotal	**$**	**493.24**
		Interval Total Cost	**$**	**6,105.53**
		Charged To/From Other Interval	**$**	**1,418.56**
		Net Interval Total Cost	**$**	**7,524.09**
		Programmed Cost	**$**	**0.00**
		Program Variance	**$**	**7,524.09**

Baroid Fluid Services

Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval Inventory Report

Interval # 01		**From Date 11/12/2005**		**Top of Interval 2,424.0 m**			
Max. Hole Size / Bit Size 6.250 / 6.000 in		**To Date 11/26/2005**		**Bottom of Interval 3,085.0 m**			
Product Name	**Units**	**Starting**	**Received**	**Used**	**Returned**	**Ending**	**Weight lb**
ALDACIDE G	5 gal can		24.0		8.0	16.0	733.92
BARABLOK	50 lb bag		36.0	17.0		19.0	950.00
BARACARB 150	50 lb bag		285.0	191.0		94.0	4,700.00
BARACARB 25	50 lb bag		140.0	60.0		80.0	4,000.00
BARAZAN D	25 kg bag		47.0	2.0		45.0	2,480.20
barite	1500 kg bag		21.0	11.0		10.0	33,069.34
BAROFIBRE COARSE	40 lb bag		65.0			65.0	2,600.00
BDF-303	180 kg drum		11.0	7.0		4.0	1,587.33
BDF-352	190 kg drum		6.0	3.0		3.0	1,256.63
bentonite	25 kg bag		9.0			9.0	496.04
calcium chloride	25 kg bag		75.0	40.0		35.0	1,929.04
caustic soda	25 kg pail		7.0			7.0	385.81
CON DET	55 gal drum		6.0	4.0		2.0	940.33
Drill Plug Medium	30 lb bag		254.0			254.0	7,620.00
DURATONE HT	50 lb bag		33.0			33.0	1,650.00
EZ-MUD DP	50 lb bag		16.0			16.0	800.00
GELTONE II	50 lb bag		79.0	29.0		50.0	2,500.00
lime	25 kg bag		99.0	24.0		75.0	4,133.67
M.E. Glycol	55 gal drum		10.0	8.0		2.0	1,009.14
OMC 3	25 kg pail		6.0			6.0	330.69
PAC-L	25 kg bag		39.0			39.0	2,149.51
PAC-R	25 kg bag		15.0			15.0	826.73
potassium chloride	1000 kg bag		11.0	2.0		9.0	19,841.60
Saraline 185	42 gal drum		304.0	284.0		20.0	5,884.70
soda ash	25 kg bag		34.0			34.0	1,873.93
					Total Weight of Products in Stock lb		**103,748.63**
					Total Weight of Products in Stock, Metric Tons		**47.06**

Well Name	AHUROA B-1 ST#1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Interval Inventory Report

Interval # 02		From Date 11/27/2005		Top of Interval		3,085.0 m	
Max. Hole Size / Bit Size 6.250 / 6.000 in		To Date 11/29/2005		Bottom of Interval		3,085.0 m	
Product Name	**Units**	**Starting**	**Received**	**Used**	**Returned**	**Ending**	**Weight lb**
ALDACIDE G	5 gal can	16.0			16.0		
BARABLOK	50 lb bag	19.0			19.0		
BARACARB 150	50 lb bag	94.0			94.0		
BARACARB 25	50 lb bag	80.0			80.0		
BARASCAV D	25 kg bag		2.0	2.0			
BARAZAN D	25 kg bag	45.0			45.0		
barite	1500 kg bag	10.0		2.0	8.0		
BAROFIBRE COARSE	40 lb bag	65.0			65.0		
BDF-303	180 kg drum	4.0			4.0		
BDF-352	190 kg drum	3.0			3.0		
bentonite	25 kg bag	9.0			9.0		
calcium chloride	25 kg bag	35.0			35.0		
caustic soda	25 kg pail	7.0		2.0	5.0		
CON DET	55 gal drum	2.0		1.0	1.0		
Drill Plug Medium	30 lb bag	254.0			254.0		
DURATONE HT	50 lb bag	33.0			33.0		
EZ-MUD DP	50 lb bag	16.0			16.0		
GELTONE II	50 lb bag	50.0			50.0		
lime	25 kg bag	75.0			75.0		
M.E. Glycol	55 gal drum	2.0			2.0		
OMC 3	25 kg pail	6.0			6.0		
PAC-L	25 kg bag	39.0			39.0		
PAC-R	25 kg bag	15.0			15.0		
potassium chloride	1000 kg bag	9.0		1.0	8.0		
Saraline 185	42 gal drum	20.0			20.0		
soda ash	25 kg bag	34.0			34.0		

Company	**Swift Energy NZ Ltd**
Well Name	**AHUROA B-1 ST#1**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Fluid Volume Record Report

			Additions								Losses						Volumes			
Report No	Date	Initial Volume	Received	Mixed	Base	Water	Barite	Chemicals	Other	Daily Total	SCE	Downhole	Misc	Mixed	Returned	Daily Total	Hole Volume	Active Pit Volume	Reserve Volume	Final Volume
		bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl
Interval # 01																				
Fluid Name:	**SOBM**																			
001	12/11/2005		782.0		122.0			8.9		912.9	6.3		4.0			10.3	269.6	307.0	326.0	902.6
002	13/11/2005	902.6			26.0		2.2			28.2	6.4	1.0	1.0			8.4	269.4	327.0	326.0	922.4
003	14/11/2005	922.4						2.4		2.4	7.0	1.4	3.0			11.4	273.4	329.0	311.0	913.4
004	15/11/2005	913.4			6.0					6.0	8.2	2.0				10.2	287.2	331.0	291.0	909.2
005	16/11/2005	909.2					4.5	5.7		10.2	8.8	3.0				11.8	299.6	328.0	280.0	907.6
006	17/11/2005	907.6			112.0		2.2	7.8		122.0	6.8	1.0				7.8	304.7	327.0	390.0	1,021.7
007	18/11/2005	1,021.7			6.0			2.4		8.4	13.0	3.0				16.0	312.2	331.0	371.0	1,014.2
008	19/11/2005	1,014.2						1.4		1.4	10.1	5.0	2.0			17.1	316.5	331.0	351.0	998.5
009	20/11/2005	998.5					2.2			2.2	5.7	3.0	6.0			14.7	316.9	332.0	337.0	985.9
010	21/11/2005	985.9			6.0		2.2	1.3		9.5	7.3	4.0	1.0			12.3	324.2	332.0	327.0	983.2
011	22/11/2005	983.2			6.0		2.2	2.8		11.0	14.9	4.5				19.4	329.7	329.0	316.0	974.7
012	23/11/2005	974.7									10.9	5.0	1.0			16.9	331.9	327.0	299.0	957.9
013	24/11/2005	957.9					2.2	0.5		2.7	12.0	4.0	2.0			18.0	334.6	332.0	276.0	942.6
014	25/11/2005	942.6					6.7	2.0		8.7	8.6	3.0	2.0			13.6	344.6	351.0	242.0	937.6
015	26/11/2005	937.6											6.4			6.4	395.2	293.0	243.0	931.2
Cumulative Volume			782.0		284.0		24.4	35.2		1,125.6	126.0	39.9	28.4			194.3				
Fluid Name:	**KCl Brine**																			
015	26/11/2005					204.5		6.5		211.0									211.0	211.0
Cumulative Volume						204.5		6.5		211.0										

Company	**Swift Energy NZ Ltd**
Well Name	**AHUROA B-1 ST#1**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Fluid Volume Record Report

			Additions								Losses						Volumes			
Report No	Date	Initial Volume	Received	Mixed	Base	Water	Barite	Chemicals	Other	Daily Total	SCE	Downhole	Misc	Mixed	Returned	Daily Total	Hole Volume	Active Pit Volume	Reserve Volume	Final Volume
		bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl	bbl
Interval # 02																				
Fluid Name: SOBM																				
016	27/11/2005	931.2									18.0		83.0		422.0	523.0	315.6		92.7	408.3
017	28/11/2005	408.3					2.2			2.2	5.0		30.5			35.5			375.0	375.0
018	29/11/2005	375.0													135.0	135.0			240.0	240.0
Cumulative Volume							2.2			2.2	23.0		113.5		557.0	693.5				
Fluid Name: KCl Brine																				
016	27/11/2005	211.0				115.5		3.5		119.0									330.0	330.0
017	28/11/2005	330.0					2.2			2.2	26.7					26.7	305.5			305.5
Cumulative Volume						115.5	2.2	3.5		121.2	26.7					26.7				

Baroid Fluid Services

Operator	Swift Energy NZ Ltd
Well Name	AHUROA B-1 ST#1
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Fluid Property Recap : NAP-Based Fluid (Baroid Titrations)

Date	Depth	FL Temp	Density	Funn Visc	Rheology 49 Deg C					Filtration			Elec. Stability	Excess Lime Content	Alk (Pom)	Water Phase Salinity	CaCl2	NaCl Sol	NaCl Insol	Sand	Retort Analysis					Rheometer Dial Readings					
					PV	lbs/100 ft2				HTHP	Cake	Temp									% by vol				NAP/Water Ratio	600	300	200	100	6	3
	m	Deg C	ppg	sec/qt	cP	YP	10S	10M	30M	ml/30 min	32nd in	Deg C	volt	ppb	ml	ppm	ppb	ppb	ppb	% by vol	Corr Solid	LGS	NAP	Water							
Interval # 01										**From Date**				**11/12/2005**						**Top of Interval**			**2,424.0**		**m**					
Max. Hole Size / Bit Size	**6.250 / 6.000 in**									**To Date**				**11/26/2005**						**Bottom of Interval**			**3,085.0**		**m**					
11/12/2005	2,400		8.50	108	26	18	8	17	24	0.5	2	121	1117	5.18	4.00	368,015	27.62	0.96	10.41	0.3	4.4	3.4	79.2	14.0	85/15	70.0	44.0	36.0	24.0	8.0	7.0
11/12/2005	2,424	35	8.50	89	26	16	8	17	23	0.5	2	121	1135	5.18	4.00	368,015	27.62	0.96	10.41	0.3	4.6	3.8	79.0	14.0	84.9/15.1	68.0	42.0	34.0	23.0	8.0	6.0
11/13/2005	2,424	40	8.50	75	26	16	7	18	26	0.5	2	121	1206	5.44	4.20	355,773	27.62	1.42	12.84	0.3	4.1	2.9	78.5	15.0	84/16	68.0	42.0	32.0	20.0	9.0	7.0
11/13/2005	2,424	40	8.50	75	23	19	7	14	18	1.0		121	898	5.31	4.10	361,651	27.62	1.18	10.19	0.3	4.1	2.8	79.0	14.5	84.5/15.5	65.0	42.0	32.0	21.0	8.0	6.0
11/14/2005	2,433	39	8.50	71	22	19	7	18	24	1.0	2	121	980	5.44	4.20	368,015	27.62	0.96	10.41	0.3	4.1	2.8	79.5	14.0	85/15	63.0	41.0	32.0	23.0	8.0	7.0
11/14/2005	2,455	39	8.55	84	23	20	8	17	23	1.2	2	121	1018	5.18	4.00	368,015	27.62	0.96	10.41	0.3	4.4	3.0	79.2	14.0	85/15	66.0	43.0	35.0	24.0	8.0	6.0
11/15/2005	2,486	40	8.50	71	23	17	7	15	25	1.4	2	121	1135	5.18	4.00	368,015	27.62	0.96	7.52	0.3	4.6	3.8	79.0	14.0	84.9/15.1	63.0	40.0	30.0	20.0	8.0	6.0
11/15/2005	2,566	38	8.50	70	24	15	8	15	26	1.4	2	49	1022	4.66	3.60	368,015	27.62	0.96	7.52	0.3	4.6	3.8	79.0	14.0	84.9/15.1	63.0	39.0	31.0	20.0	8.0	6.0
11/16/2005	2,656	44	8.50	72	22	16	8	17	24	1.4	2	49	1152	5.18	4.00	368,015	27.62	0.96	1.74	0.3	4.4	3.4	79.2	14.0	85/15	60.0	38.0	30.0	19.0	8.0	6.0
11/16/2005	2,698	40	8.60	68	23	13	8	16	22	1.4	2	49	1125	4.92	3.80	368,015	27.62	0.96	1.74	0.3	4.8	3.5	78.8	14.0	84.9/15.1	59.0	36.0	29.0	18.0	8.0	6.0
11/17/2005	2,723	44	8.65	68	23	15	7	19	24	1.6	2	49	1177	4.92	3.80	368,015	27.62	0.96	1.74	0.3	5.1	3.8	78.5	14.0	84.9/15.1	61.0	38.0	29.0	18.0	8.0	7.0
11/17/2005	2,751	44	8.65	71	23	14	8	18	22	1.6	2	49	1103	3.63	2.80	368,015	27.62	0.96	3.19	0.3	5.0	3.6	78.6	14.0	84.9/15.1	60.0	37.0	29.0	19.0	8.0	6.0
11/18/2005	2,775	44	8.65	75	25	18	8	19	26	2.0	2	49	1152	3.63	2.80	382,399	27.62	0.59	9.33	0.3	5.0	3.4	79.6	13.0	86/14	68.0	43.0	33.0	21.0	8.0	6.0
11/18/2005	2,818	42	8.70	72	25	17	8	17	25	2.0	2	49	1025	3.63	2.80	368,015	27.62	0.96	7.52	0.3	5.1	3.4	78.5	14.0	84.9/15.1	67.0	42.0	32.0	21.0	8.0	6.0
11/19/2005	2,838	42	8.70	75	25	17	7	19	26	1.8	2	121	1152	3.50	2.70	382,399	27.62	0.59	9.33	0.3	5.6	4.3	79.0	13.0	85.9/14.1	67.0	42.0	32.0	20.0	8.0	6.0
11/19/2005	2,861	44	8.70	72	26	15	8	18	24	1.8	2	121	1034	3.63	2.80	382,399	27.62	0.59	9.33	0.3	5.6	4.3	79.0	13.0	85.9/14.1	67.0	41.0	32.0	21.0	8.0	6.0
11/20/2005	2,874	44	8.70	75	26	16	8	18	25	1.8	2	121	1278	3.63	2.80	368,015	27.62	0.96	8.96	0.3	5.3	3.8	78.3	14.0	84.8/15.2	68.0	42.0	33.0	20.0	8.0	6.0
11/20/2005	2,874	30	8.70	74	25	16	8	16	24	1.8	2	121	1272	3.63	2.80	368,015	27.62	0.96	8.96	0.3	5.2	3.6	78.4	14.0	84.8/15.2	66.0	41.0	31.0	20.0	8.0	6.0
11/21/2005	2,895	44	8.70	77	26	17	8	17	25	1.8	2	121	1181	3.37	2.60	368,015	27.62	0.96	4.63	0.3	5.4	4.0	78.2	14.0	84.8/15.2	69.0	43.0	33.0	21.0	8.0	6.0
11/21/2005	2,921	44	8.70	72	24	17	8	21	28	1.8	2	121	1128	4.01	3.10	368,015	27.62	0.96	8.96	0.3	5.2	3.6	78.4	14.0	84.8/15.2	65.0	41.0	32.0	20.0	8.0	6.0
11/22/2005	2,959	44	8.70	74	26	15	8	19	27	2.0	2	121	1241	3.89	3.00	381,150	29.56	0.66	8.66	0.3	5.3	3.9	78.2	14.0	84.8/15.2	67.0	41.0	32.0	20.0	8.0	6.0
11/22/2005	2,990	44	8.70	77	24	18	16	22	28	1.8	2	121	1151	3.89	3.00	374,560	28.59	0.80	10.99	0.3	5.3	3.8	78.3	14.0	84.8/15.2	66.0	42.0	33.0	21.0	8.0	6.0
11/23/2005	2,994	44	8.70	75	26	16	12	20	24	2.0	2	121	1214	3.89	3.00	381,150	29.56	0.66	8.66	0.3	5.3	3.9	78.2	14.0	84.8/15.2	68.0	42.0	32.0	20.0	8.0	6.0
11/23/2005	3,004	44	8.70	76	26	16	16	22	28	1.4	2	121	1159	4.01	3.10	368,015	27.62	0.96	10.41	0.3	5.3	3.8	78.3	14.0	84.8/15.2	68.0	42.0	33.0	21.0	8.0	6.0
11/24/2005	3,023	44	8.70	75	26	18	8	17	24	1.4	2	121	1303	3.76	2.90	368,015	27.62	0.96	10.41	0.3	5.3	3.8	78.3	14.0	84.8/15.2	70.0	44.0	34.0	22.0	8.0	6.0

Baroid Fluid Services

Operator	**Swift Energy NZ Ltd**
Well Name	**AHUROA B-1 ST#1**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Fluid Property Recap : NAP-Based Fluid (Baroid Titrations)

Date	Depth	FL Temp	Density	Funn Visc	Rheology 49 Deg C					Filtration			Elec. Stability	Excess Lime Content	Alk (Pom)	Water Phase Salinity	CaCl2	NaCl Sol	NaCl Insol	Sand	Retort Analysis					Rheometer Dial Readings					
					PV	lbs/100 ft2				HTHP	Cake	Temp									% by vol				NAP/Water Ratio	600	300	200	100	6	3
	m	Deg C	ppg	sec/qt	cP	YP	10S	10M	30M	ml/30 min	32nd in	Deg C	volt	ppb	ml	ppm	ppb	ppb	ppb	% by vol	Corr Solid	LGS	NAP	Water							
11/24/2005	3,034	44	8.70	74	26	17	12	22	28	1.4	2	121	1146	3.89	3.00	368,015	27.62	0.96	10.41	0.3	5.2	3.6	78.4	14.0	84.8/15.2	69.0	43.0	34.0	22.0	8.0	6.0
11/25/2005	3,085	44	8.70	74	26	16	12	22	26	1.4	2	121	1149	3.89	3.00	368,015	27.62	0.96	10.41	0.3	5.2	3.6	78.4	14.0	84.8/15.2	68.0	42.0	33.0	21.0	8.0	6.0
11/26/2005	3,085	30	8.70	77	26	17	14	24	28	1.4	2	121	1149	3.89	3.00	368,015	27.62	0.96	10.41	0.3	5.2	3.6	78.4	14.0	84.8/15.2	69.0	43.0	34.0	22.0	8.0	6.0
Interval # 02										**From Date**				**11/27/2005**						**Top of Interval**				**3,085.0**	**m**					
Max. Hole Size / Bit Size			**6.250 / 6.000 in**							**To Date**				**11/29/2005**						**Bottom of Interval**				**3,085.0**	**m**					
11/27/2005	2,445		8.50																	0.3	1.8	2.3		98.0	0/100						

Baroid Fluid Services

Operations Log Recap

Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval #	**01**		**From Report**	**001**	**Top of Interval**	**2,424.0**	**m**
Max. Hole/Bit Size	**6.250 / 6.000**	**in**	**To Report**	**015**	**Bottom of Interval**	**3,085.0**	**m**

For Report	**# 001**	**On**	**11/12/2005**	**Operation at Depth**	**2,424.0 m**
Rig Activity				Pick up BHA RIH tag cement. Time drill to kick off	
Activity				Drlg side track	
Fluid Treatment				Received one load SOBM. Received one load of chemicals. Adding base oil to lower viscosity. Baracarb #150 used in sweeps. Pumping sweeps as needed. (20 ppb CaCo3) Losses: Shakers 4.25 bbls, Centrifuge 2 bbls. Mis: Pumps 1 bbl. Trans 2 bbls, Evaporation 1 bbl	
For Report	**# 002**	**On**	**11/13/2005**	**Operation at Depth**	**2,425.0 m**
Rig Activity				Continue kicking off to new formation.Drill to 2425m at report time.	
Activity				Drill 6" hole	
Fluid Treatment				Bled in base oil to lower rheology. Run centrifuge to lower LGS. Pumping sweeps as needed to aid in hole cleaning. Added barite to maintain mud wt. Losses: Downhole-1bbls Shakers-2.09bbls Centrifuge-4.34bbls	
For Report	**# 003**	**On**	**11/14/2005**	**Operation at Depth**	**2,461.0 m**
Rig Activity				Drill and slide from 2425m to 2433m. Pump slug, flow check POOH. Change BHA, RIH, Drlg to 2461m.	
Activity				Drill 6" hole	
Fluid Treatment				Mixed BDF-303 for emulsion. Run centrifuge to lower LGS. Pump sweep as needed to aid hole cleaning.(20 lbs/bbl CaCo3). .. Losses: Downhole-1.41bbls Shakers-3bbls Centrifuge-4bbls Tripping-3bbls	
For Report	**# 004**	**On**	**11/15/2005**	**Operation at Depth**	**2,595.0 m**
Rig Activity				Drill and slide from 2461m to 2595m.	
Activity				Drill 6" hole	
Fluid Treatment				Run centrifuge to control mud weight and lower LGS. Bleed in base oil to control rheology. Pump BARACARB sweep(20ppb) as needed to aid hole cleaning. Losses: DH-2bbls Shaker-4bbls centrifuge-4.2bbls	
For Report	**# 005**	**On**	**11/16/2005**	**Operation at Depth**	**2,710.0 m**
Rig Activity				Drill and slide from 2595m to 2710m. Background gas 0.2%.	
Activity				Drill and Slide 6" hole	
Fluid Treatment				Bleed in base oil to control rheology. Run centrifuge to lower LGS. Pump BARACARB sweep as needed to aid hole cleaning. Weight up active pits to 8.6ppg with CaCo3 to increase CaCo3 concentration.	

Operations Log Recap

Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval #		**01**		**From Report**	**001**	**Top of Interval**	**2,424.0**	**m**
Max. Hole/Bit Size		**6.250 / 6.000**	**in**	**To Report**	**015**	**Bottom of Interval**	**3,085.0**	**m**
				Losses: DH: 3bbls, shaker: 4.83bbls, centrifuge: 4bbls.				
For Report	**# 006**	**On**	**11/17/2005**	**Operation at Depth**	**2,758.0 m**			
Rig Activity				Continue to drill ahead from 2710m to 2742m. Circulate well clean,flow check. Pump slug and wiper trip to 2358m. RIH and Drill ahead from 2742m to 2758m.				
Activity				Drill and Slide 6" hole				
Fluid Treatment				Bleed in base oil and premix to control rheology and mud weight. Pump sweep as needed to aid hole cleaning. Run centrifuge to lower mud wt and LGS. Mix slug with barite. Received 1 load of SOBM from Baroid LMP Losses: DH-1bbls, Shaker-3bbls, Centrifuge-3.84bbls.				
For Report	**# 007**	**On**	**11/18/2005**	**Operation at Depth**	**2,827.0 m**			
Rig Activity				Drill and slide from 2758m to 2827m.				
Activity				Drill and slide 6" hole				
Fluid Treatment				Bleed in premix into active system to control mud weight and Rheology. Run centrifuge to reduce LGS. Mixed BDF-352 to tighten fluid loss. Pump sweep as needed to aid hole cleaning and control seepage loss. Weight up active to 8.7 ppg with CaCo3. Losses: DH-3bbl Shaker-6bbl Centrifuge-6.98bbl				
For Report	**# 008**	**On**	**11/19/2005**	**Operation at Depth**	**2,867.0 m**			
Rig Activity				Continue rotate / slide from 2827m to 2867m.				
Activity				Slide and Drill 6" hole				
Fluid Treatment				Bleed in premix to active system to control rheology and make up volume. Run centrifuge to lower LGS. Pump sweep as needed to aid hole cleaning. Change shaker#2 with 1xused 210mesh screen. Losses: DH-5bbl, Shaker-5.79bbl, Centrifuge-4.31bbl Evaporation-2bbl				
For Report	**# 009**	**On**	**11/20/2005**	**Operation at Depth**	**2,874.0 m**			
Rig Activity				Drill to 2874m, Pump slug, flow check and POOH to change out new mud motor and bit. Make up BHA and RIH. Held up at kick off point-2414m. Circulate, work on pipe, get through 2414m continue RIH. Wash down single, continue drill ahead.				
Activity				Drilling 6" hole				
Fluid Treatment				Bleed in premix to active system to maintain volume and control weight. Pump sweep as needed to aid hole cleaning. MIx slug for POOH Losses: DH-3bbl, Shaker-5.71bbl Pump/hoses-1bbl Tripping-5bbl				
For Report	**# 010**	**On**	**11/21/2005**	**Operation at Depth**	**2,941.0 m**			

Operations Log Recap

Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval #	**01**		**From Report**	**001**	**Top of Interval**	**2,424.0**	**m**
Max. Hole/Bit Size	**6.250 / 6.000**	**in**	**To Report**	**015**	**Bottom of Interval**	**3,085.0**	**m**

Rig Activity	Drill and slide from 2874m to 2941m at report time
Activity	Drilling 6" hole
Fluid Treatment	Bleed in premix into active system for volume. Mixed BARACARB sweep @ 20ppb. Pump sweep as needed to aid hole cleaning. Run centrifuge to lower LGS. Bleed base oil for dilution and mix Lime to active for alkalinity. Change 2 used and 1 new 210 mesh screen on shaker # 2 Losses: DH-4bbl Shaker-5bbl Centrifuge-2.3 Evaporation-1bbl

For Report	**# 011**	**On**	**11/22/2005**	**Operation at Depth**	**2,993.0 m**

Rig Activity	Continue drill from 2959m to 2993m. Attempt to work pipe for connection(2993m), 15K over pull, slack-off. Work pipe free and establish rotation, circulate bottom up. Drill back to bottom, monitor drilling parameters.
Activity	Drill / slide 6" hole
Fluid Treatment	Bleed pre mix and base oil to active to control viscosity and volume. Add CaCl2 directly to active. Run centrifuge to control mud wt and lower Lgs. Pump CaCo3 sweep as needed to aid hole cleaning. Start adding BARABLOK at 0.5 ppb, total in the circulating system 4.5 ppb. Losses: DH-4.5bbl, Shaker-7bbl, centrifuge-7.91bbl.

For Report	**# 012**	**On**	**11/23/2005**	**Operation at Depth**	**3,013.0 m**

Rig Activity	Continue drilling from 2993 to 3013m. 5% coal on cuttings sample on report time.
Activity	Drill 6" hole
Fluid Treatment	Add BARABLOK to active. Pump 10bbl Low Vis sweep followed by 10bbl Hi Wt sweep at bottom, circulate bottom up before back to drilling. Run centrifuge to control mud wt and lower lgs. Losses: DH-5bbl, Shakers-6bbl Centrifuge-4.85bbl Evaporation-1bbl

For Report	**# 013**	**On**	**11/24/2005**	**Operation at Depth**	**3,038.0 m**

Rig Activity	Continue drill ahead from 3013m to 3034m. pump sweep and circulate hole clean. survey and slug pipe. Wiper trip to 2876m. RIH and continue drilling to 3038m.
Activity	Drilling 6" hole
Fluid Treatment	Bleed in premix to active for volume. Pump sweep as needed to aid hole cleaning. Make up slug with barite. Run centrifuge to control mud wt and lower Lgs. Losses: DH-4bbl, Shaker-8bbl Centrifuge-4bbl, Tripping-1bbl, Evaporation-1bbl

For Report	**# 014**	**On**	**11/25/2005**	**Operation at Depth**	**3,085.0 m**

Operations Log Recap

Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Interval #	**01**		**From Report**	**001**	**Top of Interval**	**2,424.0**	**m**
Max. Hole/Bit Size	**6.250 / 6.000**	**in**	**To Report**	**015**	**Bottom of Interval**	**3,085.0**	**m**
Rig Activity	Continue drill ahead from 3038 to TD @ 3085m. Pump Hi vis sweep and circulate hole clean. Flow check and slug pipe. Wiper trip to shoe and RIH. Pump sweep circulate hole clean and spot 10 bbls Hi Vis sweep on bottom. Slug pipe and POOH for log.						
Activity	POOH						
Fluid Treatment	Bleed in premix to active for volume. Pump sweep as needed to aid hole cleaning. Run centrifuge to lower mud wt and LGS. Make up slug with barite. Losses: DH-3bbl, Centrifuge-3.64bbl, Shakers-5bbl, Tripping-2bbls.						
For Report	**# 015**	**On**	**11/26/2005**	**Operation at Depth**	**3,085.0 m**		
Rig Activity	Rig up for logs as per program. Two log were run, both logs to bottom. Rig down and lay down logging tool. RIH with OE and cement stinger to bottom and circulate.						
Activity	RIH with cement stinger						
Fluid Treatment	Transfer mud to storage tank. Add BARASCAV-D for oxygen scavenger. Mix 3% KCL brine in premix and Desilter tank. ready for displacement. (KCL Brine vol 211 bbls). Losses: Misc: Pit residue 4.4 bbls. Left in hoses 2 bbls.						

Operations Log Recap

Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**


Interval #	**02**		**From Report**	**016**	**Top of Interval**	**3,085.0**	**m**
Max. Hole/Bit Size	**6.250 / 6.000**	**in**	**To Report**	**018**	**Bottom of Interval**	**3,085.0**	**m**

For Report	**# 016**	**On**	**11/27/2005**	**Operation at Depth**	**2,445.0 m**
Rig Activity				RIH Cement Stinger and DP to 2430m. Circulate to condition mud prior to set cement plug.Pump 30 bbls spacer and 13 bbls cement follow by 7 bbls spacer. POOH 8 stand and circulate bottom up and slug pipe. No cement to surface. POOH to run CBL log. RIH to 2420m, no cement. Pump slug and POOH.	
Activity				Displace hole to KCL brine	
Fluid Treatment				Centrifuge down all surface mud to 8.4 ppg. transfer mud to other loaction (Goss). Continue mixing KCL brine. All chemical are used for mix up KCL brine Total vol on (Goss) location 422 bbls for storage. Losses: Shaker-4bbl, Centrifuge-12bbl, Left behind csg-75bbl, pit residual-8bbl.	
For Report	**# 017**	**On**	**11/28/2005**	**Operation at Depth**	**2,365.0 m**
Rig Activity				RIH with cement stinger and packer. Set packer at 2365mand pump cement as per HALCO program. POOH 7 stand and reverse out. Pressure test well. Dispalce well to KCL brine. pump slug and POOH. Lay down single.	
Activity				POOH	
Fluid Treatment				Barite for slug. SOBM on location 378 bbls. SOBM on Goss location 422 bbls SOBM credit :800 bbls @$100.00 = $80000.00 Losses: SCE shaker 5 bbls. Tripping 2 bbls Pit residue 15 bbls. Displacement: 13.5 bbls	
For Report	**# 018**	**On**	**11/29/2005**	**Operation at Depth**	**2,365.0 m**
Rig Activity				Rigging down. Move to new location.	
Activity				Rig Down, Rig Move	
Fluid Treatment				Clean out mud tanks. Use CONDET E to clean all tank and flush all tank lines. Return all chemical to warehouse. Transfer SOBM to Goss location 135 bbl. Total vol at Goss location 560 bbls. Total at location (AHUROA B1 ST 1) 240 bbls.	

Hydraulics vs Depth Set 1

Well : AHUROA B-1 ST#1


Operator : Swift Energy NZ Ltd



Hydraulics vs Depth Set 2

Well : AHUROA B-1 ST#1


Operator : Swift Energy NZ Ltd



Recap Properties NAP Based Baroid Method ax_length

Well : AHUROA B-1 ST#1

Operator : Swift Energy NZ Ltd



Well Name	**AHUROA B-1 ST#1**
Operator	**Swift Energy NZ Ltd**
Contractor	**Parker Drilling Co**
Rig No	**Parker Rig 252**
Unit System	**SwiftNZ SI/API mix**

Deviation Actual

Survey Date	MD m	TVD m	Angle	Direction	Horiz Displ. m
11/15/2005	2,431	2,327	22.88	133.8	568.3
11/15/2005	2,450	2,352	20.66	134.5	575.4
11/15/2005	2,469	2,370	18.66	135.4	581.8
11/15/2005	2,487	2,387	16.44	137.1	587.2
11/15/2005	2,506	2,405	13.88	136.6	592.2
11/15/2005	2,525	2,424	11.29	136.3	596.3
11/15/2005	2,545	2,443	8.66	138.6	599.7
11/15/2005	2,564	2,462	6.61	140.3	602.2
11/15/2005	2,602	2,500	2.51	140.1	605.3
11/15/2005	2,621	2,519	0.18	144.6	605.7
11/18/2005	2,640	2,538	20.90	303.5	605.4
11/18/2005	2,659	2,557	3.84	303.5	604.5
11/18/2005	2,678	2,576	6.06	304.3	602.8
11/18/2005	2,706	2,604	7.30	302.2	599.6
11/18/2005	2,735	2,604	6.73	299.8	596.2
11/18/2005	2,764	2,661	6.99	303.1	592.9
11/18/2005	2,792	2,689	7.14	304.1	589.5
11/19/2005	2,821	2,746	8.26	297.3	582.0
11/19/2005	2,849	2,746	8.26	297.3	582.0
11/23/2005	2,876	2,773	7.95	300.1	578.3
11/23/2005	2,905	2,801	6.76	297.1	574.8
11/23/2005	2,933	2,829	7.21	296.8	571.6
11/23/2005	2,962	2,858	7.37	291.0	568.2
11/23/2005	2,988	2,884	7.39	288.9	565.2
11/24/2005	3,048	2,943	8.34	287.7	557.9
11/24/2005	3,069	2,964	8.38	287.6	555.2

Well Name	AHUROA B-1 ST#1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252
Unit System	SwiftNZ SI/API mix

Hydraulics Summary Report

Rpt No	Rpt Date	Hole MD	Max. Hole Size	ECD @ Csg Shoe	ECD @ Bit	Flow Rate	Btms Up Time	Total Circ Time	Press Drop DP	Press Drop @ Bit	Press Drop An	Total Press Drop	Hyd Meth	Circ Press	Ann Vel Riser	AV min DP	AV max DC	Bit HHSI	Bit Jet Vel	Bit Imp Force
		m	in	ppg	ppg	gpm	Min	Min	psi	psi	psi	psi		psi	ft/min	ft/min	ft/min	hhp/in2	m/sec	lbf
001	11/12/2005	2,424.0	6.250	9.23	9.23	243	36	99	1,296	83	292	1,869	HB	2,810		211.0		0.42	31.8	111.8
002	11/13/2005	2,425.0	6.250	9.21	9.22	247	36	101	1,319	85	287	1,890	HB	2,000		214.4		0.44	32.3	115.5
003	11/14/2005	2,461.0	6.250	9.33		247	36	101	1,320	85	314	1,914	HB	2,184		214.4		0.43	32.1	115.2
004	11/15/2005	2,595.0	6.250	9.16	9.19	247	38	105	1,483	84	293	2,060	HB	2,906		214.4		0.43	32.1	114.5
005	11/16/2005	2,710.0	6.250	9.15	9.17	200	49	131	1,092	56	253	1,586	HB	2,183		173.7		0.23	26.0	76.0
006	11/17/2005	2,758.0	6.250	9.21	9.24	200	50	132	1,110	56	265	1,616	HB	2,239		173.7		0.23	26.0	76.5
007	11/18/2005	2,827.0	6.250	9.32	9.35	200	52	135	1,164	56	300	1,707	HB	2,171		173.7		0.23	26.0	76.9
008	11/19/2005	2,867.0	6.250	9.33	9.36	214	49	127	1,323	64	311	1,889	HB	2,576		185.2		0.28	27.7	87.5
009	11/20/2005	2,874.0	6.250	9.31	9.34	210	50	130	1,286	319	301	2,096	HB	2,607		181.8		1.38	61.8	191.5
010	11/21/2005	2,941.0	6.250	9.32	9.35	208	52	133	1,263	313	313	2,078	HB	2,464		180.1		1.34	61.2	187.9
011	11/22/2005	2,993.0	6.250	9.24	9.26	162	67	171	875	191	276	1,518	HB	1,482		140.6		0.64	47.8	114.6
012	11/23/2005	3,013.0	6.250	9.31	9.34	194	57	143	1,175	273	317	1,999	HB	2,272		168.1		1.09	57.1	163.7
013	11/24/2005	3,038.0	6.250	9.35	9.37	200	55	140	1,234	290	336	2,046	HB	2,388		173.2		1.20	58.9	173.9
014	11/25/2005	3,085.0	6.250																	
015	11/26/2005	3,085.0	6.250																	
016	11/27/2005	2,445.0	6.250																	
017	11/28/2005	2,365.0	6.366																	
018	11/29/2005	2,365.0	6.366																	


Well Name	AHUROA B-1 ST#1
Operator	Swift Energy NZ Ltd
Contractor	Parker Drilling Co
Rig No	Parker Rig 252

Personnel Register

New Zealand Manager:
Tom Mitchell

Engineers	From	To	Days	Costs
Cal Urbatsch	11/11/05	11/14/05	3	$2,100.00
Sandy Chiew	11/11/05	11/29/05	18	$12,600.00
PG Osmera	11/15/05	11/29/05	14	$9,800.00

Ahuroa South B-1



SWIFT ENERGY
NEW ZEALAND LTD

Seismic Line PC94-06

AHUROA-PIAKAU

2624300M E | 2625000M E | PC94-01 | WH85-28 | 2626500M E | SENZ06-07 | MK-40 | 2628000M E

6215500M N | WH85-15S | WH85-16 | PC94-06 | 6214500M N | WH85-17S | WH85-18 | SENZ06-03_PSTM | WH85-19N | WH85-19S | PC959-02 | 6213000M N | WH85-20 | SENZ06-02_PSTM | WH85-21N | SENZ06-01_PSTM | WH85-21S | WH85-22 | PC94-18 | 6211500M N | WH85-23S | PC959-24 | PC959-09 | 6210000M N

3000 | 3250 | 3500 | 3750 | 2750 | 2500

Ahuroa-1
-2980
Ahuroa South B-1 ST1
Ahuroa South B-1
-2666
Base Otaraoa unconf.,
Sand not present
-2888
Piakau North A-2
Piakau North A-1 ST1
-2772
Piakau North A-1
-2580
Piakau-1
FO
Wharehuia-1
-3071

AHUROA
PML 38139

NGA3D-1240X | NGA3D-1260X | NGA3D-1280X | NGA3D-1300X | NGA3D-1320X | NGA3D-1340X | NGA3D-1360X | NGA3D-1380X | NGA3D-1400X

LEGEND

- Well surface location
- Well bottomhole location
- Top McKee Formation
- Ahuroa Thrust Fault Trace relation to Mckee P/out
- Mckee Strat. Pinchout
- Thrust Fault
- Permit boundary
- Seismic line

1:10000

0 — 1 KILOMETRES

0 — 0.50 MILES

NEW ZEALAND MAP GRID
CENTRAL MERIDIAN 173 00 00E
Mapsheet datum: "New Zealand Geodetic Datum 1949"

Meters Subsea

SWIFT ENERGY
NEW ZEALAND LTD

Ahuroa-Piakau Fields

Top McKee

Depth Structure Map

Geology : R. Henderson	Date : October 2, 2007
Scale : 1:10000	Cont. Int. 50m
DrawnBy :	Ref: 809753

BAKER HUGHES

INTEQ

SWIFT ENERGY NEW ZEALAND LTD

Compan	Swift Energy New Zealand LTD
Well	Ahuroa South B-1
Permit	PEP 38719
Region	Taranaki, NZ
Designation	Exploration / Appraisal
Coordinates	NZMG: 6214665.80 mN 2625724.00 mE
Spud date	5th October 2005
Spud depth	50m BRKB
Reference Elevation	169.20m
Total Depth	3370m
Contractor	Parker Drilling Company
Rig	Rig 252
Typ	Land Rig

LOG

Depth	659m to 3370m MD AH BRKB
Date	5th Oct – 10th Nov 2005
Scale	1:500
Loggers	G. Ammundsen, G. Minaro, R Farmer G. Lindsay, D. Barrel, B. Berger


INTEQ LOG SUITE


Formation Evaluation Log	1:500
Drill Data Plot	1:2500
Gas Ratio Plot	1:500


ABBREVIATION

NB	New Bit	SG	Swab Gas
RR	Rerun Bit	SVG	Survey Gas
CB	Core Bit	C	Carbide Test
WOB	Weight on Bit	W	Mud Density ppg
RPM	Revs per Minute	V	Funnel
FLC	Flow Check	F	Filtrate - API
CR	Circulate Returns	FC	Filter Cake
PR	Poor Returns	PV	Plastic Viscosity
NR	No Returns	YP	Yield Point
LAT	Logged after trip	SOL	Solids %
BG	Background Gas	Sd	Sand %
TG	Trip Gas	Cl	Chlorides ppm
STG	Short trip Gas	RM	Mud Resistivity
CG	Connection Gas	RMF	Filtrate Resistivty

LITHOLOGY







BAKER HUGHES INTEQ

Company : Swift Energy
Well : Ahuroa South B1 ST1
Interval : 2396.00 - 3088.48 meters
Created : 1/17/2006 2:43:30 PM

SWIFT ENERGY NEW ZEALAND LTD

FORMATION EVALUATION LOG

ROP (reverse logarithmic) 1000 | 100 | 10 m/hr
WOB Avg (linear) 20 | 40 | 60 klbf
MD meters 1:500
SLIDE / ROTATE
Cuttings Lithology
DIRECT FLUORESCENCE
CUT FLUORESCENCE
Interpreted Lithology
CORE
TEST
Total Gas (%) 0.1 | 1 | 10 | 100
Methane (%)
Ethane (%)
Propane (%)
iso-Butane (%)
n-Butane (%)
iso-Pentane (%)
n-Pentane (%) 0.1 | 1 | 10 | 100

NB8 6" SMITH XR+
3x18 jets
IN:2400m
OUT:2433m
HRS:31.6

11/12/2005

WOB 1-11klbf
RPM 112-199
GPM 200
SPP 2045-2295psi

NB9 6" REED DSX519S-A3
5x14 Jets
IN: 2433m
OUT: 2874m
HRS:100.2hrs

11/13/2005

WOB 1-11klbf
RPM 112-197
GPM 200
SPP 2030-2200psi

WOB 1-11klbf
RPM 106-225
GPM 190-235
SPP 2070-2850psi

2400
2450
2500
2550

REMARKS

Ahuroa South B1-ST1 Kick-Off @ 2400m
1800 hrs 11 November 2005

Survey @ 2400.00m
Inc 19.96deg, Azi 141.80deg
TVD 2305.27m

CLAYSTONE: brnsh gy-olv gy, sft-frm, sbblky-blky, mod calc, grd to SLTST

Survey @ 2422.80m
Inc 21.91deg, Azi 134.54deg
TVD 2326.56m

Survey @ 2431.15m
Inc 22.88deg, Azi 133.85deg
TVD 2334.26m

CLAYSTONE: olv gy, frm, blky, sli calc

SILTSTONE: lt olv gy, sft-mod frm, sbblky, mod calc

Survey @ 2450.30m
Inc 20.66deg, Azi 134.57deg
TVD 2352.07m

Survey @ 2469.33m
Inc 18.66deg, Azi 135.40deg
TVD 2369.99m

CLAYSTONE: olv gy, sft-frm, sbblky-blky, sli-mod calc i/p

Survey @ 2487.27m
Inc 16.44deg, Azi 137.17deg
TVD 2387.09m

SILTSTONE: gnsh gy-olv gy, frm, sbblky, mod calc

Survey @ 2506.30m
Inc 13.88deg, Azi 136.69deg
TVD 2405.46m

Survey @ 2525.37m
Inc 11.29deg, Azi 136.36deg
TVD 2424.07m

CLAYSTONE: dk yel brn-olv gy, sft-mod frm, sbblky, calc

Survey @ 2544.56m
Inc 8.66deg, Azi 138.64deg
TVD 2442.97m

SILTSTONE: olv gy-olv blk, mod frm-frm, mod calc

11/14/2005

WOB 2-9klbf
RPM 110-213
GPM 195-200
SPP 2040-2260psi

WOB 1-6klbf
RPM 125-210
GPM 215-225
SPP 2500-2610psi

WOB 2-14klbf
RPM 112-222
GPM 200-235
SPP 2120-2820psi

11/15/2005

WOB 3-15klbf
RPM 111-214
GPM 170-200
SPP 1880-2340psi

11/16/2005

2600
2650
2700
2750

FG 1.21% / 0.3% BG

FG 0.81% / 0.4% BG

FG 1.3% / 0.38% BG

Survey @ 2563.69m
Inc 6.61deg, Azi 140.33deg
TVD 2461.93m

Survey @ 2582.64m
Inc 4.82deg, Azi 144.36deg
TVD 2480.78m

CLAYSTONE: olv gy, sft-frm, sbblky-blky, mod-v calc

Survey @ 2601.65m
Inc 2.51deg, Azi 140.10deg
TVD 2499.75m

CLAYSTONE: lt olv gy-olv gy, v sft-frm, sbblky-blky, mod calc

Survey @ 2620.61m
Inc 0.18deg, Azi 144.65deg
TVD 2518.70m

Survey @ 2639.60m
Inc 2.09deg, Azi 303.51deg
TVD 2537.69m

CLAYSTONE: lt olv gy-olv gy, v sft-frm, sbblky-blky, v calc

Survey @ 2658.51m
Inc 3.84deg, Azi 303.52deg
TVD 2556.57m

SANDSTONE: sl cldy trnsp-trnsl qtz, vfU-mU, sbang-rnd, uncons, w srtd, occ olv gy agg, tr calc cmt, rr gluac, fr inf por

CLAYSTONE: lt olv gy-yel gy, v sft-sft, amor, v calc, mnr coal frag

Survey @ 2677.58m
Inc 6.06deg, Azi 304.39deg
TVD 2575.57m

Survey @ 2706.24m
Inc 7.30deg, Azi 302.28deg
TVD 2604.04m

SANDSTONE:pred lse, clr-trnsl qtz, vfL-cL, pred mL, sbang-rdd, mod srtd, occ lt gy agg, fri, tr calc cmt, tr arg mtx, tr coal frg, tr glauc, fr inf por, NS

SILTSTONE:md lt gy-md dk gy, fm-hd, bblky-sbblky, lt calc, grd to CLST

6 Stands Wiper Trip @2742m

Survey @ 2734.87m
Inc 6.73deg, Azi 299.28deg
TVD 2632.45m

SILTSTONE: olv gy-olv blk, mod frm-frm, blky, mod calc, rr coal frag, mnr grd to SST

SANDSTONE: pred lse, clr-trnsl qtz, vfL-mU, sbang-rnd, mod w srt, tr-com calc cmt, tr glauc, tr coal frg, fr inf por, NS

SANDSTONE: pred lse, clr-trnsl qtz, vfL-mL, pred fU, sbang-rdd, mod w srtd, occ lt olv gy- yel gy agg, tr-com calc cmt, tr glauc, tr coal frg, f inf por, NS

MW 8.65 FV 68 PV/YP 23/15
GELS 7/19/24

Survey @ 2763.61m
Inc 6.99deg, Azi 303.15deg
TVD 2660.99m

SANDSTONE: pred lse, clr-trnsl qtz, vfU-mU, pred fU, sbang-rdd, mod w srtd, occ lt olv gy- yel gy agg, tr-com calc cmt, slty mtx, grd to SLTST, tr glauc, tr coal frg, f inf por, NS

2800

2850

2900

2950

FG 1.87% / 0.46% BG

FG 1.56% / 0.6% BG

WOB 4-14klb
RPM 111-212
GPM 200-200
SPP 2125-2312psi

11/17/2005

WOB 3-10klbf
RPM 120-210
GPM 195-220
SPP 1970-2650psi

11/18/2005

11/19/2005
NB10 6" Smith Geo M516LYPX
1x16 1x15 3x13 Jets
IN: 2874m
OUT: 3085m
HRS: 80.0

WOB 2-13klbf
RPM 109-200
GPM 135-215
SPP 1140-2750psi

11/20/2005

WOB 2-8klb
RPM 152-209
GPM 165-205
SPP 1610-2555psi

11/21/2005

Survey @ 2792.08m
Inc 7.14deg, Azi 304.10deg
TVD 2689.24m

Flowcheck @ 2797m (Static)

SILTSTONE: lt gy, lt yel gy, occ dk gy, sft, blky, calc cmt, aren ip, grd to vf SST

Survey @ 2820.60m
Inc 7.90deg, Azi 303.50deg
TVD 2717.51m

SILTSTONE: brnsh gy-olv gy, mod frm-mod hd, sbblky-blky, sli calc, tr coal frag, mnr grd to SST

MW 8.65 FV 75 PV/YP 25/18
GELS 8/19/26

CLAYSTONE: lt olv gy, v sft- frm, abd amor, blky i/p, v calc, mnr grd to SLTST

Survey @ 2849.07m
Inc 8.26deg, Azi 297.31deg
TVD 2745.70m

SANDSTONE: trnsl, sft-v hd, sbblky-blky, vfU-mU, ang-sbang, mod w srtd, gd inf por, NS

CLAYSTONE: lt olv gy, sft-v sft, amor, mod-v calc, grd to SLST

MW 8.70 FV 75 PV/YP 25/17
GELS 7/19/26

Survey @ 2876.40m
Inc 7.95deg, Azi 300.12deg
TVD 2772.76m

MW 8.70 FV 75 PV/YP 26/16
GELS 8/18/25

SILTSTONE: lt olv gy-brnsh gy, frm-mod hd, blky, mod calc, com grd to SST

Survey @ 2904.99m
Inc 6.76deg, Azi 297.11deg
TVD 2801.11m

CLAYSTONE: lt olv gy, v sft-sft, amor, mod-v calc

Survey @ 2933.32m
Inc 7.21deg, Azi 296.81deg
TVD 2829.23m

MW 8.70 FV 77 PV/YP 26/17
GELS 8/17/25

CLAYSTONE:olv gy, mod frm-frm, blky, mod-v calc


Survey @ 2961.96m
Inc 7.37deg, Azi 291.00deg
TVD 2857.64m

SILTSTONE: 60% grnsh blk-olv blk, sft-frm, blky, com glauc
40% lt olv gy-yel gy, frm, blky, tr vf qtz, tr blk spks

COAL: blk, brit, vit lstr, sub conch frac

SANDSTONE:clr-trans qtz, fri, vfL-mU, sbang-rnd, p-mod srtd, abt slty mtx, tr calc cmt, com yel gy agg, tr glauc, grds to sltst, p vis por

Drillstring momentarily stuck @ 2993m.



Add barablok to mud system, circulate to condition hole.
Controlled drilling F/2994m - T/3005m

SILTSTONE: lt olv gy, sft-frm, occ mod hd, blky, non-sli calc, tr vf qtz

Survey @ 3019.26m
Inc 8.03deg, Azi 288.39deg
TVD 2914.44m

SILTSTONE: lt ol gy, lt brnsh gy, sft-frm, blky, tr blk flks, tr vfL qtz, grds to vf silty SST

MW 8.70 FV 75 PV/YP 26/16
GELS 12/20/24

Wiper Trip from 3031m-2868m

CLAYSTONE:lt olv gy-olv gy, sft frm, blky, mod calc, tr SLST

MW 8.70 FV 75 PV/YP 26/18
GELS 8/17/24


Survey @ 3047.86m
Inc 8.34deg, Azi 287.78deg
TVD 2942.75m

Survey @ 3069.23m
Inc 8.38deg, Azi 287.69deg
TVD 2963.90m

TD 3085m MD, 2979m TVD
@ 1520hrs 11/24/2005

Wireline runs:
Log 1: PEX-AIT-BHC
Log 2: UBI

FORMATION EVALUATION LOG



REMARKS

BAKER HUGHES

INTEQ

SWIFT ENERGY NEW ZEALAND LTD

Company	**Swift Energy New Zealand Ltd**
Well	**Ahuroa South B-1**
Permit	**PEP 38719**
Region	**Taranaki, NZ**
Designation	**Exploration / Appraisal**
Coordinates	**NZMG: 6214665.80 mN 2625724.00 mE**
Spud date	**5th October 2005**
Spud depth	**50m BRKB**
Reference Elevation	**169.20m AMSL**
Total Depth	**3370m**
Contractor	**Parker Drilling Company**
Rig	**Rig 252**
Type	**Land Rig**

LOG INTERVAL

Depth	**659m to 3370m MD AH BRKB**
Date	**5th Oct – 10th Nov 2005**
Scale	**1:500**
Loggers	**G. Ammundsen, G. Minaro, R Farmer G. Lindsay, D. Barrel, B. Berger**


INTEQ LOG SUITE


Formation Evaluation Log	1:500
Drill Data Plot	1:2500
Gas Ratio Plot	1:500

ABBREVIATIONS

NB	New Bit	SG	Swab Gas
RR	Rerun Bit	SVG	Survey Gas
CB	Core Bit	C	Carbide Test
WOB	Weight on Bit	W	Mud Density ppg
RPM	Revs per Minute	V	Funnel Viscosity
FLC	Flow Check	F	Filtrate - API
CR	Circulate Returns	FC	Filter Cake
PR	Poor Returns	PV	Plastic Viscosity
NR	No Returns	YP	Yield Point
LAT	Logged after trip	SOL	Solids %
BG	Background Gas	Sd	Sand %
TG	Trip Gas	Cl	Chlorides ppm
STG	Short trip Gas	RM	Mud Resistivity
CG	Connection Gas	RMF	Filtrate Resistivty

LITHOLOGY SYMBOLS





BAKER HUGHES INTEQ

Company : Swift Energy
Well : Ahuroa South B1
Interval : 645.00 - 3370.00 meters
Created : 1/30/2006 3:04:19 PM

SWIFT ENERGY NEW ZEALAND LTD

FORMATION EVALUATION LOG

ROP (reverse logarithmic) 1000 | 100 | 10 m/hr
WOB Avg (linear) 20 | 40 | 60 klbf
MD meters 1:500
SLIDE / ROTATE
Cuttings Lithology
DIRECT FLUORESCENCE
CUT FLUORESCENCE
Interpreted Lithology
CORE
TEST
Total Gas (%) 0.1 | 1 | 10 | 100
Methane (%)
Ethane (%)
Propane (%)
iso-Butane (%)
n-Butane (%)
iso-Pentane (%)
n-Pentane (%) 0.1 | 1 | 10 | 100

REMARKS

650

NB3 Reed DSX104HG
8.5" 5x14 Jets
In 659m Out 2399m
1740m/113.0hrs
Not Graded

NB3 Reed DSX104HG
8.5" 5x14 Jets
In 659m Out 2399m
1740m/113.0hrs
Not Grad

Ahuroa South B1 spudded 5 October 2005

Drill 12.25" hole to 659m
Set 9.625" casing shoe @652m

BHI logging unit online from 652m

WOB 3-9klbf
RPM 176-229
GPM 495-635
SPP 1000-1245psi

MW 8.8 FV 39 PV/YP 10/146
Gels 4/5/-Cl 42k

700

WOB 4-9klbf
RPM 184-230
GPM 185-220
SPP 1200-1255psi

CLAYSTONE: lt bl gy-m gy, sft, amor, mnr-com vfL-fL sd gr, tr shl frag, n calc

CLAYSTONE: lt bl gy-m gy, sft, amor-sbblky, com vfL-fU sd gr, tr shl frag, n calc

CLAYSTONE: gn gy, sft, amor-blky, rr-mnr sd gr, sli calc

750

WOB 2-15klb
RPM 131-183
GPM 280-460
SPP 970-1255psi

CLAYSTONE: gn gy-dk gn gy, sft, amor-blky, mnr-com vfL-fL sd gr, n calc

MW 8.9 FV 48 PV/YP 11/10
Gels 3/6/7 Cl 40k

CLAYSTONE: gn gy-dk gn gy, sft-frm, amor-blky, com glauc pel, rr-mnr shl frag, tr-rr qtz gr, sli calc

800

WOB 1-9klb
RPM 176-186
GPM 435-460
SPP 905-1075psi

WOB 1-9klbf
RPM 236-241
GPM 435-450
SPP 930-1115psi

850

CLAYSTONE: gn gy-dk gn gy, sft-frm, amor-blky, rr-mnr shl frag, v calc i/p

SANDSTONE: lt olv gy-gn gy, trnsp-trnsl qtz, sft-uncons, vfU-mL, sbang-sbrnd, wl srt, mod calc, mnr-com glauc, n vis por, mod inf por, NS

SANDSTONE: lt olv gy-gn gy, trnsp-trnsl qtz, sft-uncons, vfU-mL, sbang-sbrnd, wl srt, mod-v calc, mnr-com glauc, tr shl frag, n vis por, mod inf por, NS

LIMESTONE: wh-v lt gy, frm-hd agg, vfU-fL sd gr, mnr shl frag, grd to SST

WOB 1-9klb
RPM 176-181
GPM 435-450
SPP 930-1115psi

900

SANDSTONE: lt olv gy-gn gy, trnsp-trnsl qtz, pred uncons, frm-hd agg, vfL-mL, sbang-sbrnd, wl srt, mnr glauc, tr mic, n vis por, NS

Survey @ 908.74m
Inc 19.55deg, Azi 901.38deg
TVD 901.38m

Survey @ 935.58m
Inc 19.86deg, Azi 130.44deg
TVD 926.65m

MW 9.1 FV 48 PV/YP 8/16
Gels 5/6/8 Cl 40k

WOB 4-7klbf
RPM 127-208
GPM 440-490
SPP 920-1210psi

950

Survey @ 962.41m
Inc 19.33deg, Azi 131.71deg
TVD 951.9m

Survey @ 989.18m
Inc 18.58deg, Azi 134.39deg
TVD 977.2m

WOB 4-8klbf
RPM 185-207
GPM 455-495
SPP 1065-1250psi

1000

SILTSTONE: olv gy, sft, sbblky-amor, n calc, grd to SST

SANDSTONE: olv gy, v sft, blky-uncons, vfL-fL sd gr, sbang-sbrnd, mod-wl srt, tr mic, NS

Survey @ 1015.89m
Inc 18.94deg, Azi 134.93deg
TVD 1002.5m

1050

WOB 3-8klbf
RPM 173-199
GPM 450-505
SPP 1065-1345psi

Survey @ 1042.82m
Inc 19.46deg, Azi 134.62deg
TVD 1028.0m

CLAYSTONE: dk gn gy-olv gy, sft, sbblky-amor, n calc

SANDSTONE: m bl gy-olv gy, sft-uncons, vfL-fL, sbrnd-rnd, wl srt, arg cmt, pr vis por, NS

Survey @ 1070.64m
Inc 19.79deg, Azi 133.81deg
TVD 1054.2m

1100

WOB 2-11klbf
RPM 106-200
GPM 365-495
SPP 1165-1355psi

LIMESTONE: wh-v lt gy, frm-hd, sbblky, aren, grd to SST

Survey @ 1097.43m
Inc 19.81deg, Azi 132.43deg
TVD 1079.4m

CLAYSTONE: gn gy-dk gn gy, sft, sbblky, mnr-com vfL-fL sd gr, n calc

Survey @ 1124.27m
Inc 19.47deg, Azi 133.90deg
TVD 1104.65m

1150

WOB 1-6klbf
RPM 136-198
GPM470-490
SPP1090-1215psi

Survey @ 1151.11m
Inc 18.96deg, Azi 137.12deg
TVD 1130.00m

SANDSTONE: olv gy, uncons, vfL-vfU, arg cmt, n calc, NS

Survey @ 1178.00m
Inc 18.89deg, Azi 137.82deg
TVD 1155.43m


CLAYSTONE: m gy-olv gy, sft, blky-amor, tr-rr sd gr, n calc

1200

WOB 2-4klbf
RPM 187-199
GPM 470-480
SPP 1185-1280psi

Survey @ 1204.71m
Inc 19.52deg, Azi 136.50deg
TVD 1180.66m

Survey @ 1231.46m
Inc 20.14deg, Azi 136.47deg
TVD 1205.82m



CLAYSTONE: m dk gy, sft, sbblky, vfU sd gr, mod calc

Survey @ 1258.25m
Inc 20.76deg, Azi 135.86deg
TVD 1230.95m

Survey @ 1285.30m
Inc 20.58deg, Azi 135.56deg
TVD 1256.23m

CLAYSTONE: m dk gy, sft, sbblky, mnr vfL sd gr, sli calc

SANDSTONE: trnsp-trnsl qtz stn or, uncons, fL-cL, sbang-sbrnd, tr mic, NS

Survey @ 1312.05m
Inc 17.63deg, Azi 137.59deg
TVD 1281.51m

Survey @ 1338.88m
Inc 17.41deg, Azi 138.69deg
TVD 1307.09m

CLAYSTONE: dk gn gy-m bl gy, sft, sbblky-amor, mnr vfL-vfU sd gr, n calc

Survey @ 1365.74m
Inc 17.6deg, Azi 138.60deg
TVD 1332.71m

CLAYSTONE: olv gy-dk gn gy, sft-frm, sbblky-blky, tr sd gr, sli calc

Survey @ 1392.60m
Inc 17.53deg, Azi 138.57deg
TVD 1358.32m

CLAYSTONE:olv gy-dk gn gy, sft-frm, sbblky-blky, aren, sli calc, SHOW

FLUORESCENCE: In CLST @ 1410m, 10% yel wh dir fluor, slw blmg, cut fluor, pr shw

CLAYSTONE: m dk gy, sft-frm, sbblky-blky, sli calc, SHOW

Survey @ 1420.46m
Inc 18.94deg, Azi 136.54deg
TVD 1384.78m

MW 9.2 FV 45 PV/YP 13/24
Gels 7/12/16 Cl 50k

Survey @ 1447.30m
Inc 19.29deg, Azi 135.90deg
TVD 1410.14m

CLAYSTONE: olv gy, sft-frm, mnr sd, sbblky-blky,

mod calc, tr qtz, SHOW

Survey @ 1474.18m
Inc 19.86deg, Azi 135.22deg
TVD 1435.46m

Survey @ 1500.90m
Inc 20.16deg, Azi 134.48deg
TVD 1460.57m

1500

WOB 2-6klbf
RPM 156-217
GPM 285-475
SPP 1245-1350psi

CLAYSTONE: olv gy, v sft-frm, sbblky-blky, mod calc, tr qtz, SHOW

CLAYSTONE: m gy, v sft-frm, sbblky-blky, tr SLTST, sli calc, SHOW

SANDSTONE: trsnp-trnsl qtz stn or, uncons, fL-vcL, ang-sbrnd, pr srt, n vis por, mod inf por, NS

CLAYSTONE: lt olv gy, sft-frm, sbblky-blky, mod calc, SHOW

1550

WOB 1-10klbf
RPM 103-248
GPM 230-630
SPP 1260-1560psi

FLUORESCENCE: in CLST @ 1540-1560m, 5% yelsh wh dir fluor, slw blmg blsh wh cut fluor, thk bl res ring

CLAYSTONE: lt olv gy, sft-frm, sbblky-blky, sli calc, SHOW

1600

WOB 3-10klbf
RPM 142-226
GPM 475-500
SPP 1385-1555psi

TRACE FLUORESCENCE: in CLST @ 1590-1610m, yelsh wh dir fluor, n cut

SANDSTONE: trnsp-trnsl, uncons, vfL-fL, sbang-sbrnd, wl srt, NS

CLAYSTONE: lt olv gy, sft-frm, sbblky-blky, arg, sli calc, SHOW

FLUORESCENCE: in Clst @ 1610-1620, 5% yel wh dir fluor, v slw blmg bl wh cut, tr res rng

SILTSTONE: lt olv gy-gnsh gy, frm-hd, sbblky, mod-v calc, grd to CLST

1650

WOB 4-7klbf
RPM 220-230
GPM 500-520
SPP 1465-1640psi

CLAYSTONE:lt olv gy, sft, sbblky-blky, arg, sli calc i/p, grd to SLTST, SHOW

FLUORESCENCE: in Clst @ 1637-1640m, tr yel wh dir fluor, n cut

SANDSTONE: lt gy-dk gy, frm-hd, mod calc, fL-mU, sbang, mod srt

CLAYSTONE: m gy, sft-frm, sbblky, mod calc, tr sd, SHOW

FLUORESCENCE: in Clst @ 1650-1680m, tr yel wh dir fluor, n cut

1700

WOB 3-6klbf
RPM 201-231
GPM 450-425
SPP 1295-1605psi

CLAYSTONE: m gy, sft-frm, sbblky, mod calc, tr sc

1750

WOB 4-11klbf
RPM 143-233
GPM 445-510
SPP 1375-1745psi

SILTSTONE: dk gnsh gy-olv bk, frm-hd, sbblky, mod-v calc, grd to CLST

CLAYSTONE: gnsh gy-dk gnsh gy, sft-frm, sbblky-blky, mod calc, grd to SLTST

1800

WOB 2-7klbf
RPM 78-232
GPM 170-515
SPP 635-1770psi

LIMESTONE: lt olv gy, frm-hd, sbblky, aren, grd to CLST

1850

WOB 3-5klbf
RPM 197-238
GPM 500-520
SPP 1715-1840psi

CLAYSTONE:dk gn gy, v sft- frm, sbblky, mod calc, grd to SLTST

SILTSTONE:dk gnsh gy, frm-hd, sbblky-blky, mod calc

1900

WOB3-9klbf
RPM151-239
GPM 495-520
SPP1770-1880psi

1950

WOB 4-14klbf
RPM 191-225
GPM 410-525
SPP 1535-2345psi

LIMESTONE: wh-olv gy, v sft-frm, sbblky-blky, grd to SLTST

2000

WOB 5-14klb
RPM 141-246
GPM 475-515
SPP 1740-2340psi

SILTSTONE: md gy-dk gnsh gy, frm, sbblky, mod-v calc, grd to LST

LIMESTONE: wh-lt gy, v sft-frm, sbblky-blky, aren i/p, grd to SLTST


2050


WOB 5-14klb
RPM 190-250
GPM 475-505
SPP 1770-2030psi

SILTSTONE: gnsh gy-dk gnsh gy, md blsh gy i/p, frm-hd, sbblky-blky, mod-v calc, grd to LST

2100

WOB 6-12klb
RPM 142-230
GPM 490-505
SPP 1850-1935psi


2150
2200
2250
2300
WOB 5-9klb
RPM 212-239
GPM 490-515
SPP 1820-1935psi
WOB 4-25klb
RPM 137-244
GPM 460-505
SPP 1680-2000psi
WOB 3-9klb
RPM 205-222
GPM 450-470
SPP 1775-1905psi
WOB 3-8klb
RPM 212-220
GPM 450-470
SPP 1805-1935psi
SILTSTONE: gnsh gy-olv gy, sft-frm, sbblky, mod-v calc, arg, grd to CLST i/p
SILTSTONE: lt olv gy-olv gy, sft-frm, sbblky-blky, mod-v calc
SILTSTONE: lt olv gy-olv gy, sft-frm, sbblky-blky, mod-v calc



SILTSTONE: olv gy, sft-frm, sbblky-blky, mod calc

LIMESTONE: md gy, v sft, sbblky-blky, sli aren

SILTSTONE: olv gy, sft-hd, sbblky-blky, sli calc, grd to CLST

Mud changed from KCl WBM to 80% SBM

CLAYSTONE:med gy, sft-frm, sbblky-bblky, sli calc, grd SLTST.

CLAYSTONE: brnsh gy-olv gy, sft-frm, sbblky-blky, mod calc, grd to SLTST

Survey @ 2438.25m
Inc19.30, Azi141.45deg
TVD 2341.27m

SILTSTONE: lt olv gy, sft-mod frm, sbblky, mod calc

Survey @ 2450.30m
Inc 20.66deg, Azi 134.57deg
TVD 2352.07m

SILTSTONE:olv gy, frm-hd, sbblky-bblky, sli calc

Survey@2466.42m
Inc18.89, Azi 138.58 deg
TVD 2367.89m

CLAYSTONE: olv gy, sft-frm, sbblky-blky, sli-mod calc i/p
CLAYSTONE: dk gnsh gy, sft, sbblky-blky, mod srt, sli calc

Survey @ 2469.33m
Inc 16.44deg, Azi 137.17deg
TVD 2387.09m

SILTSTONE: gnsh gy-olv gy, frm, sbblky, mod calc

Survey @ 2506.30m
Inc 13.88deg, Azi 136.69deg
TVD 2405.46m

SILTSTONE: olv gy, frm-hd, sbblky-blky, sli calc i/p

Survey @ 2525.37m
Inc 11.29deg, Azi 136.36deg
TVD 2424.07m

MW 8.6, FV60, PV/YP 24/10
Gels 5/6/7

Survey@2540.28m

WOB 1-11klbf
RPM 106-225
GPM 190-235
SPP 2070-2850psi

2550

2600

WOB 1-11
RPM 116-205
GPM 175-220
SPP 2350-2650psi

2650

WOB 1-6
RPM121-217
GPM215-220
SPP 2430-2560psi

2700

10/25/2005

WOB 1-14klb
RPM 123-209
GPM 220-225
SPP 2490-2655psi

2750

WOB 1-11
RPM175-123
GPM220-245
SPP2520-3060

F.G. 0.245/0.19% bg

C.G. 0.576/0.19% bg

F.G. 0.438/0.32% bg

C.G. 0.438/0.20% bg

Survey@2549.28m
Inc18.54, Azi134.41deg
TVD2446.41m

CLAYSTONE: olv bk, sft-frm, sbblkk-blky, sli-mod calc

CLAYSTONE: olv gy-olv bk, sft-frm, sbblky-blky, mnr-com calc vn, mod-v calc

SILTSTONE: lt olv gy-olv gy, sft-frm, sbblky-blky, sli-mod calc

Survey @ 2577.88m
Inc 19.98deg, Azi 134.62deg
TVD 2473.49

Survey @ 2606.78m
Inc 19.53deg, Azi134.73deg
TVD2500.77m

CLAYSTONE:lt olv gy, v sft-sft, sbblky, mod-v calc

Survey@2634.32m
Inc 19.03, Azi136.13deg
TVD 2526.77m

SILTSTONE:dk gnsh gy, frm, sbblky, sli calc

CLAYSTONE: lt olv gy, v sft-sft, sbblky, mod calc

Survey @ 2662.32m
Inc 18.53deg, Azi 137.15deg
TVD 2553.28m

MW 8.5, FV40, PV/YP 23/18
Gels 6/8/9

Survey @ 2690.57m
Inc 18.77deg, Azi 134.20deg
TVD 2580.04m

CLAYSTONE: olv gy, sft-frm, sbblky, mod-v calc, tr-rr calc vn
SANDSTONE: pred trnsp-trnsl qtz, v lt gy-yelsh gy, uncons-frm, fU-cL, sbang-sbrnd, pr-mod srt, calc cmt, n-gd inf por, NS

SANDSTONE: pred trnsp-trnsl qtz, v lt gy-yelsh gy, uncons-frm pred uncons, vfL-cU, sbang-sbrnd, pr srt, calc cmt, n-gd inf por, NS

Survey @ 2718.54m
Inc 19.23deg, Azi 133.96deg
TVD 2606.49m

SILTSTONE: olv gy-olv bk, sft-frm, sbblky-blky, sli-mod calc

Survey @ 2746.40m
Inc 18.27deg, Azi 136.72deg
TVD 2632.87m

CLAYSTONE: olv gy, sft-frm, sbblky, mod-v calc, grd to SLTST

10/26/2005

WOB 2-15klb
RPM 132-219
GPM 190-240
SPP 2145-3130psi

2800

F.G. 0.43/0.17% bg
C.G. 0.50/0.40% bg
F.G. 0.55/0.40% bg

F.G. 0.44/0.30% bg

10/27/2005

WOB 1-14klb
RPM 110-193
GPM 190-240
SPP 1955-2900psi

2850

F.G. 0.67/0.45% bg

10/28/2005

F.G. 0.49/0.27% bg

NB5 Reed DSX516M-B1
6" 3x13 2x15 Jets
In 2903m Out 3296
393m/123.8hrs
2-6-WT-S-X-1-WT-FM
WOB 1-12klb
RPM 110-200
GPM 198-200
SPP 1830-2675psi

2900

SWAB: 0.41/0.17 % bg

F.G. 0.51/0.28% bg

F.G 0.77/0.35% bg

WOB 1-11klb
RPM 113-199
GPM 200
SPP 1830-2660psi

2950

F.G 0.55/0.4% bg

F.G 0.72/0.4% bg

SANDSTONE: lt gnsh gy, vfL-cU, pr srt, tr coal, grd SLST

Survey @ 2773.77m
Inc 19.19deg, Azi 134.73deg
TVD 2658.79m

23 Stand Wiper Trip @ 2787m

SANDSTONE: trnsp-trnsl qtz, wh-lt gy, hd, mL-cL, sbang-sbrnd, mod srt, calc cmt, mnr glauc, tr carb mat, com rk flr, pr vis por, NS

SILTSTONE: olv gy, sft-frm, sbblky-blky, sli calc, grd to CLST

CLAYSTONE: lt olv gy-olv gy, v sft-sft, amor-blky, mod-v calc, grd to SLTST

SANDSTONE: trnsp-trnsl qtz, uncons, v hd agg, fL-cL, sbang-sbrnd, pr srt, tr glauc, tr coal, pr-mod inf por, NS

SANDSTONE: trnsp qtz, v lt gy-med dk gy agg, uncons, mnr frm-v hd agg, vfU-cL, sbang-sbrnd, arg mtrx, mod srt, pr - gd por,NS

SILTSTONE: olv gy, sft-frm, sbblky, n calc, grd to CLST

Survey @ 2822.15m
Inc 18.12deg, Azi 136.73deg
TVD 2704.58m

MW 8.6, FV 62, PV/YP 23/19
Gels 7/10/15

SANDSTONE:trnsp-trnsl qtz, uncons, vfL-mU, sbrnd-rnd, mod-wl srt, arg cmt, tr coal, gd inf por,NS

Survey @ 2850.50m
Inc 18.31deg, Azi 135.26deg
TVD 2731.51m

SANDSTONE:trnsp-trnsl qtz, uncons, vfU-mU, sbrnd-rnd, mod-wl srt, NS

SANDSTONE: trnsp-trnsl qtz, uncons, vfU-mU, sbrnd-rnd, mod-wl srt, gd inf por, NS

SILTSTONE: olv gy, frm, sbblky-blky, mod calc

CLAYSTONE: lt olv gy-olv gy, sft-frm, sbblky-blky, n calc

Survey @ 2879.09m
Inc 19.21deg, Azi 130.07deg
TVD2758.56m

LIMESTONE: wh-lt gy, sft-frm, sbblky-blky, aren i/p, mnr-com fU-mU qtz gr, grd to v calc SST, NS

SILTSTONE: olv gy-olv bk, sft-frm, sbblky-blky, sli calc i/p

Survey@2915.6m
Inc21.16deg, Azi 130.18deg
TVD2792.83m


SANDSTONE:trnsp-trnsl qtz, uncons, fL-cL, sbrnd-rnd, mod-wl srt, gd inf por, NS

Survey@2944.18m
Inc 21.73deg, Azi 130.24deg
TVD 2819.43m

SANDSTONE: trnsp-trnsl qtz, uncons, fL-cL, sbrnd-rnd, mod-wl srt, gd inf por, NS

Survey @ 2972.15m
Inc 21.26, Azi 130.94deg
TVD 2845.47m

CLAYSTONE: lt olv gy, v sft-sft, amor



SILTSTONE: 60% grnsh blk-olv blk, sft-frm, blky, com glauc
40% lt olv gy-yel gy, frm, blky, tr vf qtz, tr blk spks

MW 8.65, FV 62, PV/YP 29/21
Gels 8/13/17

SANDSTONE: trnsp-trnsl qtz, wh, uncons, vfU-cL, sbrnd, pr-mod srt, abd rk flr, inf v hd fm, pr-mod inf por, NS

CLAYSTONE:brn-blk, mod-hd, blky, non calc

Survey @ 3000.49m
Inc 20.97deg, Azi 132.92deg
TVD 2871.91m

CLAYSTONE:olv gy, sft-frm, sbblky-blky

SILTSTONE: lt ol gy, lt brnsh gy, sft-frm, blky, tr blk flks, tr vfL qtz, grds to vf silty SST

Survey @ 3029.69m
Inc 21.95deg, Azi 133.21deg
TVD 2899.09m

SANDSTONE:uncons qtz, wh-lt gy, fU-cU, sbang-sbrnd, pr-mod srt, abd rk flr inf v hd, pr inf por, NS

SILTSTONE:lt-dk gy, frm-hd, sbblky-blky, sbang-ang, sli calc

MW 8.7, FV 63, PV/YP 22/19
Gels 7/13/15

CLAYSTONE: dk gy-m dk gy, frm-mod hd, blky, sl calc, tr calc vn
SILTSTONE: olv gy-dk gnsh gy, sft-frm, sbblky-blky, sli calc i/p

SANDSTONE: lt gy, fri - frm, trnsp-trnsl qtz, lse-uncons w/ occ hd agg, vfL-fL, sbrnd-rnd, mod srt, com calc cmt, tr glauc, com-abd rk flr, tr glauc, pr inf por, NS

SILTSTONE:lt-dk gy, frm-hd, sbblky-blky, n calc

SANDSTONE: trnsl-trnsp qtz, lse, occ hd agg, vfU-mU, sbang-ang, mod srt, fr inf por por, NS

CLAYSTONE:md dk gy-olv gy, v sft-frm, blky, sli calc, grd to SLTST

Survey @ 3086.24m
Inc 22.18deg, Azi 135.33deg
TVD 2951.46

CLAYSTONE:lt olv gy, sft-hd, amor, mod calc

CLAYSTONE: olv gy, sft-frm, sbblky-blky, mod calc i/p

SANDSTONE: trnsp-trnsl qtz, lse, vfU-mL, sbang-sbrnd, pr-mod srt, tr coal, fr inf por, NS

Survey @ 3115.05m
Inc 21.89deg, Azi 138.31deg
2978.16m

Survey @ 3143.80m
Inc 21.05deg, Azi 141.58deg
TVD 3004.93m

CLAYSTONE:lt olv gy-olv gy, sft-frm,sbblky-blky, mod calc, grd to SLTST

MW 8.7, FV 68, PV/YP 23/18
Gels 7/12/15

SANDSTONE: trnsp-trnsl qtz, lse, vfL-fU, sbrnd, mod srt, fr inf por, NS

Survey @ 3172.54m
Inc 20.63deg, Azi 144.17deg
TVD 3031.80m

CLAYSTONE: lt olv gy-olv gy, sft-frm, sbblky-blky, sli-mod calc

17 stand wiper trip @ 3182m

MW 8.75. FV 76, PV/YP 27/21
Gels 8/14/19

11/04/2005

3200

WOB 5-13klb
RPM 178-203
GPM 200
2310-2515psi

11/05/2005

3250

WOB 3-14klb
RPM 158-203
GPM 200
SPP 2335-2545psi

F.G. 0.85/0.32% bg

F.G. 0.93/0.42% bg

3300

NB6 Reed DSX413M-A2
6" 4x15 Jets
In 3296m Out 3370m
74m/8.9hrs
1-1-NO-A-X-I-NO-TD

WOB 2-13klb
RPM 33-89
GPM 180-200
SPP 1445-1935psi

11/07/2005

3350

WOB 4-8klb
RPM 76-90
GPM 200
SPP 1880-1910psi

CLAYSTONE: lt olv gy-olv gy, sft-frm, sbblky-blky, sli-mod calc

Survey @ 3201.13m
Inc 19.54deg, Azi 147.86deg
TVD 3058.66m

CLAYSTONE: lt olv gy-olv gy, sft-frm, occ mod hd, sbblky-blky, mod-v calc, i/p grd to arg LST

MW 8.7, FV 75, PV/YP 27/19
Gels 8/14/18

Survey @ 3229.81m
Inc 18.8deg, Azi 151.07deg
TVD 3085.73

SILTSTONE: dk gnsh gy-gnsh bk, sft-frm, sbblky-blky, com glauc, v calc i/p, grd to CLST

SILTSTONE: 90% wh-yelsh gy, sft-frm, sbblky-blky, com glauc, sli calc i/p, grd to SST; 10% dk gnsh gy-gnsh bk, sft-frm, sbblky-blky, v calc i/p

SANDSTONE: lt gy, yel gy, fri, vfL-fL, sbang-sbrnd, mod w srtd,abt slty mtx,tr lse clr-trnsl qtz, p vis por, NS

CLAYSTONE: brnsh gy-brnsh bk, frm-mod hd, blky, n calc

Survey @ 3258.74m
Inc 18.55deg, Azi 152.29deg
TVD 3113.14

COAL: bk, vit, brit-frm, sbblky-blky

SANDSTONE: lt gy, yel gy, fri, blky, tr lse gr, vfL-fL, sbang-rnd, mod srt, abd slty mtx, grd to SLTST, p vis por, NS

SILTSTONE: 20% brn blk, frm-mod hd, sb fis-blky, v carb, i/p w coal laminae, 80% lt olv gy-brn gy, sft-frm, blky, tr vf qtz

COAL: brn blk-blk, brit, hckly frac, sub fis, i/p arg, earthy

CLAYSTONE: lt olv gy-olv gy, frm-mod hd, sbblky-blky, mod calc, com grd to SLTST

CLAYSTONE: olv gy-ol blk, frm, blky, sli-mod calc, tr calc vn

MW 8.8, FV 98, PV/YP 30/20
Gels 9/17/23

Run E-Logs:
1. PEX/AIT/BHC
Depth reached 3370m

CLAYSTONE: dk gy-olv bk, mod hd, sbblky-blky
T.D. 3370m @ 0420hrs 11/07/2005

FORMATION EVALUATION LOG

ROP (reverse logarithmic)
1000 | 100 | 10
m/hr
WOB Avg (linear)
20 | 40 | 60
klbf

MD meters 1:500

SLIDE / ROTATE

Cuttings Lithology

DIRECT FLUORESCENCE

CUT FLUORESCENCE

Interpreted Lithology

CORE

TEST

Total Gas (%)
0.1 | 1 | 10 | 100
Methane (%)
Ethane (%)
Propane (%)
iso-Butane (%)
n-Butane (%)
iso-Pentane (%)
n-Pentane (%)
0.1 | 1 | 10 | 100


REMARKS

BAKER HUGHES INTEQ


Company : Swift Energy
Well : Ahuroa South B1 ST1
Interval : 2387.00 - 3096.62 meters
Created : 1/17/2006 2:43:30 PM

SWIFT ENERGY NEW ZEALAND LTD

DRILLING DATA PLOT



DRILLING DATA PLOT



BAKER HUGHES INTEQ

Company : Swift Energy
Well : Ahuroa South B1
Interval : 629.00 - 3383.86 meters
Created : 1/30/2006 3:04:19 PM

SWIFT ENERGY NEW ZEALAND LTD

DRILLING DATA PLOT

Total Gas (reverse log) 10 | 1 | 0.1 %
ROP (reverse log) 1000 | 100 | 10 m/hr
MD meters 1:2500
Max Pump Pressure 1250 | 2500 | 3750 | 5000 psi
Avg Pump Pressure 1250 | 2500 | 3750 | 5000 psi
Mud Flow In 250 | 500 | 750 | 1000 USgl/min
Bit RPM 75 | 150 | 225 | 300 RPM
WOB Avg 5 | 10 | 15 | 20 klbf
Max Torque 5 | 10 | 15 | 20 kft.lb
Avg Torque 5 | 10 | 15 | 20 kft.lb
DXC 3 unitless
INTERPRETED LITHOLOGY

NB3 Reed DSX104HG
8.5" 5x14 Jets
In 659m Out 2209m
1740m/113.0hrs
Not Grad

650 700 750 800 850 900 950 1000 1050 1100 1150 1200 1250 1300 1350 1400 1450 1500

Torque sensor offline from1120m to 1555m

NB4 Reed DSX516M-BT
6" 5x13 Jets
In 2403m Out 2903m
400m/93.5hrs
3-6-WT-S-X-I-CT-PR

1550
1600
1650
1700
1750
1800
1850
1900
1950
2000
2050
2100
2150
2200
2250
2300
2350
2400
2450
2500
2550
2600

NB5 Reed DSX516M-B1
6" 3x13 2x15 Jets
In 2903m Out 3296
393m/123.8hrs
2-6-WT-S-X-1-WT-FM

NB6 Reed DSX413M-A2
6" 4x15 Jets
In 3296m Out 3370m
74m/8.9hrs
1-1-NO-A-X-I-NO-TD

2650 2700 2750 2800 2850 2900 2950 3000 3050 3100 3150 3200 3250 3300 3350

DRILLING DATA PLOT

Total Gas (reverse log)	MD meters 1:2500	Max Pump Pressure	Bit RPM	Max Torque	DXC	INTERPRETED LITHOLOGY
10 | 1 | 0.1 %		1250 | 2500 | 3750 | 5000 psi	75 | 150 | 225 | 300 RPM	5 | 10 | 15 | 20 kft.lb	3 unitless	
ROP (reverse log)		Avg Pump Pressure	WOB Avg	Avg Torque		
1000 | 100 | 10 m/hr		1250 | 2500 | 3750 | 5000 psi	5 | 10 | 15 | 20 klbf	5 | 10 | 15 | 20 kft.lb		
		Mud Flow In				
		250 | 500 | 750 | 1000 USgl/min				

Composite Log

SWIFT ENERGY NEW ZEALAND LTD

Well: Ahuroa South B-1

SURFACE LOCATIONS

Latitude	38 10' 21.877" S
Longitude	174 25' 29.9" E
Northing	6214865.8
Easting	1719000.0
KB Elevation	201.6 m
DL Elevation	198.3 m

BOTTOM HOLE LOCATIONS

TD Latitude	38 10' 21.877" S
TD Longitude	174 25' 29.9" E
TD Northing	6214865.8
TD Easting	2629224.1
Total Depth MD	3215.0 m
Total Depth TVD	3215.0 m
Total Depth KB	3016.0 m
Max Inc Angle	0.0
Max Rate Build	0.0 / m-S
Max Rate Drift	0.0 / m-S

DATE SUMMARY

Spud	5 Oct, 2005
Reached TD	7 Nov, 2005
Rig Released	28 Nov, 2005

SUMMARY

Operator	Swift Energy New Zealand
Country	New Zealand
Basin	Taranaki
Field	Ahuroa
Rig Name	Parker Drilling Rig 252
TP Well Status	Gas Well

WELL SITE

Depth	Diameter	Depth MD
Surface	508.0 in	0.0 m
8 1/2 in.	2368.0 m	2368.0 m
8 in	3215.0 m	

CASING

Diameter	Depth MD
13 3/8 in	203.0 m
9 5/8 in	653.0 m
7 in	2368.0 m

SHOW SYMBOLS

	Oil	Gas
Good		
Fair		
Poor		
Trace		

LITHOLOGY LEGEND

SANDSTONE	MUDSTONE
LIMESTONE	COAL
SANDY LIMESTONE	
SILTSTONE	

LEGEND

Spot Sidewall Core
FIT Depth
Casing Shoe
Gas Show
Core
Core

Geologists

K. Pawlowski
B. Pini

WELL REMARKS

Datum: NZGD 2000 / NZMG Geodetics, NZ Map Grid
Primary Target: McKee Sandstone. Secondary targets Tikorangi Limestone and Mangahewa Sandstones.
Sidetrack (ST-1) was kicked off below 2453 m MD (see seperate composite log)

SCALE 1:1000 Meters MD/KB

Composite Log

SWIFT ENERGY NEW ZEALAND LTD

Well: Ahuroa South B-1 ST1

SURFACE LOCATIONS

Latitude	: 39 16' 1.196" S
Longitude	: 174 20' 25.375" E
Northing	: 6214665.8
Easting	: 2625724.0
RT Elevation:	201.8 m
GL Elevation:	196.3 m

HOLE SIZE


Diameter	Depth MD
12 1/4 in.	659.0 m
8 1/2 in.	2403.0 m
6 in.	3085.0 m

CASING

Diameter	Depth MD
9 5/8 in.	653.0 m
7 in.	2395.0 m

SHOW SYMBOLS

	Oil	Gas
Good	●	✺
Fair	◑	✺
Poor	◔	✺
Trace	○	✺



BOTTOM HOLE LOCATIONS


TD Latitude	: 39 16' 14.427" S
TD Longitude	: 174 20' 40.987" E
TD Northing	: 6214252.1
TD Easting	: 2626091.8
Total Depth MD	: 3085.0 m
Total Depth TVD	: 2979.5 m
Total Depth SS	: -2777.7 m
Total Depth TWT	:
Max N-S Drift	: 438.9 m S
Max E-W Drift	: 417.6 m E

LEGEND

Test Interval
FIT Depth
Casing Shoe
Sidewall Core
Core

LITHOLOGY LEGEND

SANDSTONE
SHALE
LIMESTONE
COAL
SANDY LIMESTONE
SILTSTONE



DATE SUMMARY

Spud	: 11 Nov, 2005
Reached TD	: 24 Nov, 2005
Completed	:
Rig Released	: 28 Nov, 2005

Geologists

K. Frankiewicz
B. Prin

SUMMARY

Operator	Swift Energy NZ LTD
Country	New Plymouth
State	Taranaki
Field	PML 38139
Rig Name	Parker Drilling Rig 252
TD Driller	3085.0 m


WELL REMARKS

Note: Datum NZ 1949 Geodetic, NZ Map Grid
Primary target McKee Sandstone. Secondary targets Tikorangi Limestone and Mangahewa Sandstones.
A Sidetrack (ST-1) was kicked-off below 2400 m MD (see seperate composite log)

SCALE 1:1000 Meters MD/KB


Date: 24 Nov, 2007

GS SOFTWARE



Structural Cross Section "MCKSND PiakNA-1_PiakNA-1ST1_AhuSB1_WHA-1_STR 806418" :
Equally Spaced Logs - Datum = 0 m Subsea - Vertical Scale = 0.4 mm per 1 m
8 Nov 05





SWIFT ENERGY
NEW ZEALAND LTD

AHUROA FIELD AREA
NEW ZEALAND

CROSS SECTION

PiakauN A-1, st1, A-2, AhuroaS B-1, Wharehuia - MCKEE SAND

GEOLOGY: DAVIS, C
CREATED BY: HUNTER, T
DATE: 8 NOV 2005
Post ASB1 806418

Structural Cross Section "MCKSND PiakNA-1_PiakNA-1ST1_AhuSB1st1_AhuSB1_WHA-1_STR 806418" :
Equally Spaced Logs - Datum = 0 m Subsea - Vertical Scale = 0.4 mm per 1 m
29 Nov 05

Piakau North A-1	16 m	Piakau North A-1 ST1	504 m	Piakau North A-2	2421 m	Ahuroa South B-1 ST1	204 m	Ahuroa South B-1	2488 m	Wharehuia-1
Spud Date=1/06/2005		Spud Date=13/07/2005		Spud Date=12/08/2005		Spud Date=10/11/2005		Spud Date=5/10/2005		Spud Date=31/12/1984
		> (EAST)		> (NORTH EAST)		> (DUE NORTH)		> (SOUTH EAST)		> (DUE SOUTH)

-2400
-2500
-2600
-2700
-2800
-2900
-3000
-3100
-3200

Datum KB=276.7
TD=2960.0 MD

Datum KB=276.7
TD=3012.0 MD

GOC @ 2740m TVDSS (MDT data)
OWC @ 2777 TVDSS (PVT data)


Datum KB=275.4
TD=3460.0 MD

Datum KB=201.8
TD=3085.0 MD

Datum KB=201.8
TD=3370.0 MD

Datum KB=280.2
TD=3595.0 MD

MCKEE
Turust Fault
MANGANUI
MANGAHEWA
U
D



SWIFT ENERGY
NEW ZEALAND LTD

AHUROA FIELD AREA
NEW ZEALAND

CROSS SECTION

PiakauN A-1, st1, A-2, AhuroaS B-1, ASB1ST1

GEOLOGY: DAVIS, C
DATE: 8 NOV 2005

CREATED BY: HUNTER, T
Post ASB1 806418
PWT FINK